Solicitation no. _____

US Army Corps
of Engineers
Afghanistan Engineer District

AFGHAN NATIONAL ARMY REGIONAL MIILITARY TRAINING CENTER (RMTC)

Kandahar, Afghanistan

Appendix B

2010

THIS IS A SINGLE-PHASE REQUEST FOR PROPOSAL

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01 33 00 SUBMITTAL PROCEDURES
01 42 00 SOURCES FOR REFERENCE PUBLICATIONS
01 78 23 OPERATION AND MAINTENANCE DATA

DIVISION 02 - EXISTING CONDITIONS

02 41 00 DEMOLITION

DIVISION 03 - CONCRETE

03 11 13.00 10 STRUCTURAL CONCRETE FORMWORK
03 15 13.00 10 EXPANSION JOINTS, CONTRACTION JOINTS, AND WATERSTOPS
03 20 01.00 10 CONCRETE REINFORCEMENT
03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE

DIVISION 04 - MASONRY

04 20 00 MASONRY
04 57 13 MASONRY WOOD STOVE

DIVISION 05 - METALS

05 12 00 STRUCTURAL STEEL
05 40 00 COLD-FORMED METAL FRAMING
05 50 13 MISCELLANEOUS METAL FABRICATIONS
05 52 00 METAL RAILINGS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00 ROUGH CARPENTRY

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 13 53 ELASTOMERIC SHEET WATERPROOFING
07 21 13 BOARD INSULATION
07 41 13 NON-STRUCTURAL METAL ROOFING
07 60 00 FLASHING AND SHEET METAL
07 84 00 FIRESTOPPING
07 92 00 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 11 13 STEEL DOORS AND FRAMES
08 33 13 METAL ROLLING COUNTER DOORS
08 33 23 OVERHEAD COILING DOORS
08 34 63 HOLLOW METAL FRAMES, DOORS, AND DOOR FRAMES
08 51 13 ALUMINUM WINDOWS
08 53 00 PLASTIC WINDOWS
08 71 00 DOOR HARDWARE
08 81 00 GLAZING

DIVISION 09 - FINISHES

09 22 00 METAL SUPPORT ASSEMBLIES
09 22 37.00 10 LATHING AND PLASTERING

09 24 23 STUCCO
09 30 00 CERAMIC TILE
09 66 16 TERRAZZO TILE
09 90 00 PAINTS AND COATINGS

DIVISION 10 - SPECIALTIES

10 22 26.13 OPERABLE PARTITIONS
10 35 23.13 PROPANE STOVE
10 44 16 FIRE EXTINGUISHERS
10 75 00 FLAGPOLES
10 90 00 MISCELLANEOUS SPECIALTIES

DIVISION 13 - SPECIAL CONSTRUCTION

13 21 26 COLD-STORAGE ROOMS FIELD-FABRICATED
13 48 00 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT

DIVISION 22 - PLUMBING

22 00 00 PLUMBING, GENERAL PURPOSE
22 07 19.00 40 PLUMBING PIPING INSULATION

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING

23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
23 05 93.00 10 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS
23 11 13.00 20 FUEL OIL PIPING

DIVISION 26 - ELECTRICAL

26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS
26 05 00.00 40 COMMON WORK RESULTS FOR ELECTRICAL
26 05 13.00 40 MEDIUM-VOLTAGE CABLES
26 05 19.00 10 INSULATED WIRE AND CABLE
26 05 48.00 10 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT
26 05 70.00 40 HIGH VOLTAGE OVERCURRENT PROTECTIVE DEVICES
26 08 00 APPARATUS INSPECTION AND TESTING
26 12 19.00 40 PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS
26 13 13 MEDIUM VOLTAGE SWITCHGEAR
26 20 00 INTERIOR DISTRIBUTION SYSTEM
26 24 16.00 40 PANELBOARDS
26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION
26 32 15.00 10 DIESEL-GENERATOR SET STATIONARY 100-2500 KW, WITH AUXILIARIES
26 32 33.00 10 UNINTERRUPTIBLE POWER SUPPLY (UPS) SYSTEM ABOVE 15 KVA CAPACITY
26 41 00.00 20 LIGHTNING PROTECTION SYSTEM
26 51 00 INTERIOR LIGHTING
26 52 00.00 40 EMERGENCY LIGHTING
26 53 00.00 40 EXIT SIGNS
26 56 00 EXTERIOR LIGHTING

DIVISION 27 - COMMUNICATIONS

27 51 16 PUBLIC ADDRESS SYSTEM

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 31 64.00 10 FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE

DIVISION 31 - EARTHWORK

31 00 00 EARTHWORK
31 05 19 GEOTEXTILE
31 11 00 CLEARING AND GRUBBING
31 23 00.00 20 EXCAVATION AND BACKFILLING FOR UTILITIES AND STRUCTURES
31 32 11 SOIL SURFACE EROSION CONTROL

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 11 23 GRANULAR FILL AND STONE WATER CAPILLARY BARRIER
32 15 00 AGGREGATE SURFACE COURSE
32 31 00.00 10 CHAIN LINK FENCES AND GATES
32 92 19 SEEDING

DIVISION 33 - UTILITIES

33 56 13 ABOVEGROUND FUEL STORAGE TANKS
33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION

DIVISION 34 - TRANSPORTATION

34 71 13.19 VEHICLE BARRIERS

-- End of Project Table of Contents --

SECTION 01 33 00

SUBMITTAL PROCEDURES
10/06

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Submittal

Contract Clauses "FAR 52.236-5, Material and Workmanship," paragraph (b) and "FAR 52.236-21, Specifications and Drawings for Construction," paragraphs (d), (e), and (f) apply to all "submittals."

1.1.2 Submittal Descriptions (SD)

Submittals requirements are specified in the technical sections. Submittals are identified by SD numbers and titles as follows.

SD-01 Preconstruction Submittals

Submittals which are required prior to a notice to proceed on a new contract. Submittals required prior to the start of the next major phase of the construction on a multi-phase contract. Schedules or tabular list of data or tabular list including location, features, or other pertinent information regarding products, materials, equipment, or components to be used in the work, submitted prior to contract notice to proceed or next major phase of construction.

Certificates of insurance.
Surety bonds.
List of proposed subcontractors.
List of proposed products.
Construction Progress Schedule.
Submittal register.
Schedule of prices.
Health and safety plan.
Work plan.
Quality control plan.
Environmental protection plan.

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and

other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards by which the ensuring work can be judged. Includes assemblies or portions of assemblies which are to be incorporated into the project and those which will be removed at conclusion of the work.

SD-05 Design Data

Design calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. (Testing must have been within three years of date of contract award for the project.)

Report which includes findings of a test required to be performed by the Contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports.

Daily logs and checklists.

Final acceptance test and operational test procedure.

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or subcontractor through Contractor, the purpose of which is

to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

Confined space entry permits.

Text of posted operating instructions.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data sheets concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and must state the test results; and indicate whether the material, product, or system has passed or failed the test.

Factory test reports.

SD-10 Operation and Maintenance Data

Data that is furnished by the manufacturer, or the system provider, to the equipment operating and maintenance personnel. This data is needed by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

This Data is intended to be incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Special requirements necessary to properly close out a construction contract. For example, Record Drawings, manufacturer's help and product lines necessary to maintain and install equipment. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.1.3 Approving Authority

Office or designated person authorized to approve submittal.

1.1.4 Work

As used in this section, on- and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submittal register; G

1.3 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.3.1 Designer of Record Approved

Designer of Record approval is required for extensions of design, critical materials, any deviations from the solicitation, the accepted proposal, or the completed design, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction", they are considered to be "shop drawings". The Contractor shall provide the Government the number of copies designated hereinafter of all Designer of Record approved submittals. The Government may review any or all Designer of Record approved submittals for conformance to the Solicitation and Accepted Proposal. The Government will review all submittals designated as deviating from the Solicitation or Accepted Proposal, as described below. Generally, design submittals should be identified as SD-05 DESIGN DATA submittals.

1.3.2 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Government approval is required for any deviations from the Solicitation or Accepted Proposal and other items as designated by the Contracting Officer.Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

1.3.3 Government Reviewed Design or Extension of Design

The Government will review all (65%) and (75%) design submittals for conformance with the technical requirements of the solicitation. Government review is required for extension of design construction submittals, used to define contract conformity, and for deviation from the completed design. Review will be only for conformance with the contract requirements. Included are only those construction submittals for which the Designer of Record design documents do not include enough detail to ascertain contract compliance. The Government may, but is not required, to review extensions of design such as structural steel or reinforcement shop drawings.

1.3.4 Information Only

All submittals not requiring Government approval will be for information

only.All submittals not requiring Designer of Record or Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.4 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactorydesign, general method of construction, materials, detailing and other information appear to meet the Solicitation and Accepted Proposal. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for design, dimensions, all design extensions, such as the design of adequate connections and details, etc., and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.5 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer, obtain the Designer of Record's approval when applicable, and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. Any "information only" submittal found to contain errors or unapproved deviations from the Solicitation or Accepted Proposal shall be resubmitted as one requiring "approval" action, requiring both Designer of Record and Government approval. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

1.6 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained. No payment for materials incorporated in the work will be made if all required Designer of Record or required Government approvals have not been obtained. No payment will be made for any materials incorporated into the work for any conformance review submittals or information only submittals found to contain errors or deviations from the Solicitation or Accepted Proposal.

1.7 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) System ManagerQuality Control (CQC) System Manager and the Designer of Record, if applicable, and each item shall be stamped, signed, and dated by the CQC System Manager indicating action taken. Proposed deviations from the contract requirements shall be clearly

identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

1.8 SUBMITTAL REGISTER

The Government will provide the initial submittal register in electronic format. Thereafter, the Contractor shall maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file to the Contractor. The Contractor shall track all submittals.

The Designer of Record shall develop a complete list of submittals during design. The Designer of Record shall identify required submittals in the specifications, and use the list to prepare the Submittal Register. The list may not be all inclusive and additional submittals may be required by other parts of the contract. The Contractor is required to complete the submittal register and submit it to the Contracting Officer for approval within 30 calendar days after Notice to Proceed. The approved submittal register will serve as a scheduling document for submittals and will be used to control submittal actions throughout the contract period. The submit dates and need dates used in the submittal register shall be coordinated with dates in the Contractor prepared progress schedule. Updates to the submittal register showing the Contractor action codes and actual dates with Government action codes and actual dates shall be submitted monthly or until all submittals have been satisfactorily completed. When the progress schedule is revised, the submittal register shall also be revised and both submitted for approval.

1.9 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 14 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals. An additional 3 calendar days shall be allowed and shown on the register for review and approval of submittals for food service equipment and refrigeration and HVAC control systems.

1.10 SUBMITTAL PROCEDURES

Submittals shall be made as follows:

1.10.1 Procedures

The Government will further discuss detailed submittal procedures with the Contractor at the Preconstruction Conference.

1.10.2 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

1.11 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

1.12 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and dated. One copy of the submittal will be retained by the Contracting Officer and six copies of the submittal will be returned to the Contractor. If the Government performs a conformance review of other Designer of Record approved submittals, the submittals will be so identified and returned, as described above.

1.13 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe. For design-build construction the Government will retain one copy of information only submittals.

1.14 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR
(Firm Name)
_____ Approved
_____ Approved with corrections as noted on submittal data and/or attached sheets(s).
SIGNATURE: _____
TITLE: _____
DATE: _____

For design-build construction, both the Contractor Quality Control System Manager and the Designer of Record shall stamp and sign to certify that the submittal meets contract requirements.

1.15 PREPARATION

1.15.1 Marking

Prepare, review and stamp with Contractor's approval all specified submittals.

Permanently mark each submittal to identify it by contract number; transmittal date; Contractor's, Subcontractor's, and supplier's name, address(es) and telephone number(s); submittal name; specification or drawing reference; and similar information to distinguish it from other submittals. Submittal identification shall include space to receive the review action by the Contracting Officer.

1.15.2 Drawing Format

Drawing submittals shall be prepared on translucent, reproducible sheets, not less than 210 by 279 millimeter nor larger than 841 by 1189 millimeter in size, except for full size patterns or templates. Drawings shall be prepared to accurate size, with scale indicated, unless other form is required. Drawing reproducibles shall be suitable for microfilming and reproduction on the Diazo or Ozalid machines and shall be of a quality to produce clear, distinct lines and letters. Drawings shall have dark lines on a white background.

Copies of each drawing shall have the following information clearly marked thereon:

a. Job name, which shall be the general title of the contract

drawings.

b. Date of the drawings and revisions.

c. Name of Contractor.

d. Name of Subcontractor.

e. Name of the item, material, or equipment detailed thereon.

f. Submittal number (e.g., first submittal to last submittal) in a uniform location adjacent to the title block.

g. Specification section to which submittal applies.

h. Government contract number shall appear in the margin, immediately below the title block.

Drawings shall be numbered in logical sequence. Contractor may use his own number system. Each drawing shall bear the number of the submittal in a uniform location adjacent to the title block. Government contract number shall appear in the margin, immediately below the title block, for each drawing.

A blank space, no smaller than 100 millimeter shall be reserved on the right hand side of each sheet for the Government disposition stamp.

1.15.3 Data Format

Required data submittals for each specific material, product, unit of work, or system shall be collected into a single submittal and marked for choices, options, and portions applicable to the submittal. Marking of each copy of product data submitted shall be identical. Partial submittals will not be accepted for expedition of construction effort.

1.15.4 Samples

Samples shall be physically identical with the proposed material or product to be incorporated in the work, fully fabricated and finished in the specified manner, and full scale. Where variations in color, finish, pattern, or texture are inherent in the material or product represented by the sample, multiple units of the sample, showing the near-limits of the variations and the "average" of the whole range (not less than 3 units), shall be submitted. Each unit shall be marked to describe its relation to the range of the variation. Where samples are specified for selection of color, finish, pattern, or texture, the full set of available choices shall be submitted for the material or product specified. Sizes and quantities of samples shall represent their respective standard unit.

1.16 SUBMISSION REQUIREMENTS

1.16.1 Schedules

Within 15 calendar days of notice to proceed provide, for approval by the Contracting Officer, the following schedule of submittals:

a. A schedule of shop drawings and technical submittals required by the specifications and drawings. Indicate the specification or drawing reference requiring the submittal; the material, item, or

process for which the submittal is required; the "SD" number and identifying title of the submittal; the Contractor's anticipated submission date and the approval need date.

b. A separate schedule of other submittals required under the contract but not listed in the specifications or drawings. Schedule will indicate the contract requirement reference; the type or title of the submittal; the Contractor's anticipated submission date and the approved need date (if approval is required).

c. Submittals called for by the contract documents will be listed on one of the above schedules. If a submittal is called for but does not pertain to the contract work, the Contractor shall include the submittal in the applicable schedule and annotate it "N/A" with a brief explanation. Approval of the schedules by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but which have been omitted from the schedules or marked "N/A".

d. Re-submit copies of both schedules and annotate monthly by the Contractor with actual submission and approval dates. When all items on a schedule have been fully approved, no further re-submittal of the schedule is required.

1.16.2 Drawings Submittals

Submit one translucent reproducible copy and six blackline or blueline opaque print(s) of each drawing. Six prints, marked with review notations by the Contracting Officer, will be returned to the Contractor. All required installation, fabrication and connection drawings shall be submitted and approved prior to the start of work detailed on these drawings.

1.16.3 Data Submittals

Submit seven complete sets of indexed and bound product data. One set, marked with review notations by the Contracting Officer, will be returned to the Contractor.

1.16.4 Samples

Submit one set of identified samples. A copy of the transmittal form, marked with review notations including selections by the Contracting Officer, will be returned to the Contractor.

Samples that are intended or permitted to be returned and actually incorporated in the work are so indicated in the individual technical sections. These samples will be returned to the Contractor, at his expense, to be clearly labeled, with installation location recorded. Samples shall be in undamaged condition at the time of installation.

Where mockups and similar large samples are required by individual technical sections, it is recognized that these are a special type of sample which cannot be readily "transmitted" as specified for submittal of samples. Otherwise, and except as indicated in the individual technical sections, the requirements for samples shall be complied with and a transmittal form shall be processed for each mockup, to provide a record of the activity.

1.17 GOVERNMENT'S REVIEW

1.17.1 Review Notations

Contracting Officer will review submittals and provide pertinent notation within 17 calendar days after date of submission. Submittals will be returned to the Contractor with the following notations:

a. Submittals marked "approved" authorize the Contractor to proceed with the work covered.

b. Submittals marked "approved as noted" authorize the Contractor to proceed with the work covered provided he takes no exception to the corrections. Notes shall be incorporated prior to submission of the final submittal.

c. Submittals marked "return for correction" require the Contractor to make the necessary corrections and revisions and to re-submit them for approval in the same routine as before, prior to proceeding with any of the work depicted by the submittal.

d. Submittals marked "not approved" or "disapproved" indicate noncompliance with the contract requirements and shall be re-submitted with appropriate changes. No item of requiring a submittal shall be accomplished until the submittals are approved or approved as noted.

e. Contractor shall make corrections required by the Contracting Officer. If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications; notice as required under the clause entitled, "Changes" shall be given to the Contracting Officer. Approval of the submittals by the Contracting Officer shall not be construed as a complete check, but will indicate only that the general method of construction and detailing is satisfactory. Contractor shall be responsible for the dimensions and design of connection details and construction of work. Failure to point out deviations may result in the Government requiring rejection and removal of such work at the Contractor's expense.

f. If changes are necessary to approved submittals, the Contractor shall make such revisions and submission of the submittals in accordance with the procedures above. No item of work requiring a submittal change shall be accomplished until the changed submittals are approved.

1.17.2 Sample Approval

Furnish, for the approval of the Contracting Officer, samples required by the specifications or by the Contracting Officer. Shipping charges shall be paid by the Contractor. Materials or equipment requiring sample approval shall not be delivered to the site or used in the work until approved in writing by the Contracting Officer.

Each sample shall have a label indicating:

a. Name of project

b. Name of Contractor

c. Material or equipment

d. Place of origin

e. Name of producer and brand

f. Specification section to which samples applies

g. Samples of furnished material shall have additional markings that will identify them under the finished schedules.

Contractor shall submit to the Contracting Officer two samples of materials where samples are requested. Transmit to the Contracting Officer with each sample a letter, original and two copies, containing the above information.

Approval of a sample shall be only for the characteristics or use named in such approval and shall not be construed to change or modify any contract requirements. Before submitting samples, the Contractor shall assure that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Materials and equipment incorporated in the work shall match the approved samples. If requested, approved samples, including those which may be damaged in testing, will be returned to the Contractor, at his expense, upon completion of the contract. Samples not approved will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make of that material. Government reserves the right to disapproved any material or equipment which previously has proved unsatisfactory in service.

Variations from contract requirements shall be specifically pointed out in transmittal letters. Failure to point out deviations may result in the Government requiring rejection and removal of such work at no additional cost to the Government.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Contractor shall replace such materials or equipment to meet contract requirements.

Approval of the Contractor's samples by the Contracting Officer shall not relieve the Contractor of his responsibilities under the contract.

1.18 PROGRESS SCHEDULE

1.18.1 Bar Chart

a. Submit the progress chart, for approval by the Contracting Officer, at the Preconstruction Conference in one reproducible and 4 copies.

b. Prepare the progress chart in the form of a bar chart utilizing

form "Construction Progress Chart" or comparable format acceptable to the Contracting Officer.

c. Include no less than the following information on the progress chart:

(1) Break out by major headings for primary work activity.

(2) A line item break out under each major heading sufficient to track the progress of the work.

(3) A line item showing contract finalization task which includes punch list, clean-up and demolition, and final construction drawings.

(4) A materials bar and a separate labor bar for each line item. Both bars will show the scheduled percentage complete for any given date within the contract performance period. Labor bar will also show the number of men (man-load) expected to be working on any given date within the contract performance period.

(5) The estimated cost and percentage weight of total contract cost for each materials and labor bar on the chart.

(6) Separate line items for mobilization and drawing submittal and approval. (These items are to show no associated costs.)

d. Update the progress schedule in one reproduction and 4 copies every 30 calendar days throughout the contract performance period.

1.19 STATUS REPORT ON MATERIALS ORDERS

Within 30 calendar days after notice to proceed, submit, for approval by the Contracting Officer, an initial material status report on all materials orders. This report will be updated and re-submitted every 30 calendar days as the status on material orders changes.

Report shall list, in chronological order by need date, materials orders necessary for completion of the contract. The following information will be required for each material order listed:

a. Material name, supplier, and invoice number.

b. Bar chart line item or CPM activity number affected by the order.

c. Delivery date needed to allow directly and indirectly related work to be completed within the contract performance period.

d. Current delivery date agreed on by supplier.

e. When item d exceeds item c, the effect that delayed delivery date will have on contract completion date.

f. When item d exceeds item c, a summary of efforts made by the Contractor to expedite the delayed delivery date to bring it in line with the needed delivery date, including efforts made to place the order (or subcontract) with other suppliers.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS
05/09

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization, (e.g. ASTM B 564 Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided. Documents listed in the specifications with numbers which were not assigned by the standards producing organization should be ordered from the source by title rather than by number.

ACOUSTICAL SOCIETY OF AMERICA (ASA)
2 Huntington Quadrangle, Suite 1NO1
Melville, NY 11747-4502
Ph: 516-576-2360
Fax: 516-576-2377
E-mail: asa@aip.org
Internet: http://asa.aip.org

ACI INTERNATIONAL (ACI)
38800 Country Club Drive
Farmington Hills, MI 48331
Ph: 248-848-3700
Fax: 248-848-3701
E-mail: bkstore@concrete.org
Internet: http://www.concrete.org

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)
2111 Wilson blvd, Suite 500
Arlington, VA 22201
Ph: 703-524-8800
Fax: 703-528-3816
E-mail: ahri@ahrinet.org
Internet: http://www.ahrinet.org

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)
30 West University Drive
Arlington Heights, IL 60004-1893
Ph: 847-394-0150
Fax: 847-253-0088
E-mail: amca@amca.org

Internet: http://www.amca.org

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)
1827 Walden Office Square
Suite 550
Schaumburg, IL 60173-4268
Ph: 847-303-5664
Fax: 847-303-5774
E-mail: webmaster@aamanet.org
Internet: http://www.aamanet.org

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
444 North Capital Street, NW, Suite 249
Washington, DC 20001
Ph: 202-624-5800
Fax: 202-624-5806
E-Mail: info@aashto.org
Internet: http://www.aashto.org

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)
2025 M Street, NW, Suite 800
Washington, DC 20036
Ph: 202-367-1155
Fax: 202-367-2155
E-mail: info.abma@smithbucklin.com
Internet: http://www.abma-dc.org

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
1330 Kemper Meadow Drive
Cincinnati, OH 45240
Ph: 513-742-2020
Fax: 513-742-3355
E-mail: mail@acgih.org
Internet: http://www.acgih.org

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)
American Wood Council
ATTN: Publications Department
1111 Nineteenth Street NW, Suite 800
Washington, DC 20036
Ph: 800-890-7732 or 202-463-2766
Fax: 202-463-2791
Internet: http://www.awc.org/

AMERICAN HARDBOARD ASSOCIATION (AHA)
c/o Composite Panel Association
18922 Premiere Court
Gaithersburg, MD 20879-1574
Ph: 301-670-0604
Fax: 301-840-1252
Internet: http://www.pbmdf.org

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)
One East Wacker Drive
Chicago, IL 60601-1802
Ph: 312-670-2400
Fax: 312-670-5403
Publications: 800-644-2400

E-mail: pubs@aisc.org
Internet: http://www.aisc.org

AMERICAN IRON AND STEEL INSTITUTE (AISI)
1140 Connecticut Avenue, NW, Suite 705
Washington, DC 20036
Ph: 202-452-7100
Fax: 202-463-6573
Internet: http://www.steel.org

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1819 L Street, NW, 6th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: info@ansi.org
Internet: http://www.ansi.org/

AMERICAN PETROLEUM INSTITUTE (API)
1220 L Street, NW
Washington, DC 20005-4070
Ph: 202-682-8000
Fax: 202-682-8223
Internet: http://www.api.org

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)
1801 Alexander Bell Drive
Reston, VA 20191-4400
Ph: 703-295-6300 - 800-548-2723
Fax: 703-295-6222
E-mail: marketing@asce.org
Internet: http://www.asce.org

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)
1791 Tullie Circle, NE
Atlanta, GA 30329
Ph: 800-527-4723 or 404-636-8400
Fax: 404-321-5478
E-mail: ashrae@ashrae.org
Internet: http://www.ashrae.org

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)
1800 East Oakton Street
Des Plaines, IL 60018-2187
Ph: 847-699-2929
Fax: 847-768-3434
E-mail: customerservice@asse.org
Internet: http://www.asse.org

AMERICAN WATER WORKS ASSOCIATION (AWWA)
6666 West Quincy Avenue
Denver, CO 80235
Ph: 800-926-7337
Fax: 303-347-0804
Internet: http://www.awwa.org

AMERICAN WELDING SOCIETY (AWS)
550 N.W. LeJeune Road

Miami, FL 33126
Ph: 800-443-9353 - 305-443-9353
Fax: 305-443-7559
E-mail: info@aws.org
Internet: http://www.aws.org

APA - THE ENGINEERED WOOD ASSOCIATION (APA)
7011 South 19th
Tacoma, WA 98466
Ph: 253-565-6600
Fax: 253-565-7265
E-mail: help@apawood.org
Internet: http://www.apawood.org

ASME INTERNATIONAL (ASME)
Three Park Avenue, M/S 10E
New York, NY 10016
Ph: 212-591-7722 or 800-843-2763
Fax: 212-591-7674
E-mail: infocentral@asme.org
Internet: http://www.asme.org

ASSOCIATED AIR BALANCE COUNCIL (AABC)
1518 K Street, NW
Washington, DC 20005
Ph: 202-737-0202
Fax: 202-638-4833
E-mail: info@aabc.com
Internet: http://www.aabchq.com

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)
600 North 18th Street
P.O. Box 2641
Birmingham, AL 35291
Ph: 205-257-2530
Fax: 205-257-2540
Internet: http://www.aeic.org

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 610-832-9500
Fax: 610-832-9555
E-mail: service@astm.org
Internet: http://www.astm.org

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
355 Lexington Avenue
17th Floor
New York, NY 10017
Ph: 212-297-2122
Fax: 212-370-9047
E-mail: assocmgmt@aol.com
Internet: http://www.buildershardware.com

CALIFORNIA ENERGY COMMISSION (CEC)
Media and Public Communications Office
1516 Ninth Street, MS-29
Sacramento, CA 95814-5512

Ph: 916-654-4287
Internet: http://www.energy.ca.gov/

CARPET AND RUG INSTITUTE (CRI)
P.O. Box 2048
Dalton, GA 30722-2048
Ph: 800-882-8846 or 706-278-3176
Fax: 706-278-8835
Internet: http://www.carpet-rug.com

CHEMICAL FABRICS & FILM ASSOCIATION (CFFA)
1300 Sumner Avenue
Cleveland OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
E-mail: cffa@chemicalfabricsandfilm.com
Internet: http://www.chemicalfabricsandfilm.com/

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
933 North Plum Grove Road
Schaumburg, IL 60173-4758
Ph: 847-517-1200
Fax: 847-517-1206
Internet: http://www.crsi.org/

ELECTRICAL GENERATING SYSTEMS ASSOCIATION (EGSA)
1650 South Dixie Highway, Suite 500
Boca Raton, FL 33432-7462
Ph: 561-750-5575
Fax: 561-395-8557
E-mail: e-mail@egsa.org
Internet: http://www.egsa.org

ELECTRONIC INDUSTRIES ALLIANCE (EIA)
2500 Wilson Boulevard
Arlington, VA 22201-3834
Ph: 703-907-7500
Fax: 703-907-7501
Internet: http://www.eia.org

U.S. DEPARTMENT OF ENERGY (DOE)
1000 Independance Ave. SW
Washington, DC 20585
Ph: 800-342-5363
Fax: 202-586-4403
E-mail: dmteam@hq.doe.gov
Internet: http://www.eh.doe.gov/

FM GLOBAL (FM)
1301 Atwood Avenue
P.O. Box 7500
Johnston, RI 02919
Ph: 401-275-3000
Fax: 401-275-3029
E-mail: information@fmglobal.com
Internet: http://www.fmglobal.com

GLASS ASSOCIATION OF NORTH AMERICA (GANA)
2945 SW Wanamaker Drive, Suite A

Topeka, KS 66614
Ph: 785-271-0208
Fax: 785-271-0166
E-mail: gana@glasswebsite.com
Internet: http://www.glasswebsite.com

GREEN SEAL (GS)
1001 Connecticut Avenue, NW
Suite 827
Washington, DC 20036-5525
Ph: 202-872-6400
Fax: 202-872-4324
E-mail: greenseal@greenseal.org
Internet: http://www.greenseal.org

ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA)
120 Wall Street, 17th Floor
New York, NY 10005
Ph: 212-248-5000
Fax: 212-248-5018
E-mail: iesna@iesna.org
Internet: http://www.iesna.org

INDUSTRIAL FASTENERS INSTITUTE (IFI)
6363 Oak Tree Boulevard
Independance, OH 44131
Ph: 216-241-1482
Fax: 216-241-5901
E-mail: IFI-orders@indfast.org
Internet: http://www.industrial-fasteners.org

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)
445 Hoes Lane
Piscataway, NJ 08855-1331
Ph: 732-981-0060
Fax: 732-981-1712
E-mail: customer-services@ieee.org
Internet: http://www.ieee.org

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)
P.O. Box 1568
Carrollton, GA 30112
Ph: 770-830-0369
Fax: 770-830-8501
Internet: http://www.icea.net

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)
1500 Bank Street, Suite 300
Ottawa, Ontario CANADA K1H 1B8
Ph: 613-233-1510
Fax: 613-482-9436
E-mail: info@igmaonline.org
Internet: http://www.igmaonline.org

INTERNATIONAL CODE COUNCIL (ICC)
5360 Workman Mill Road
Whittier, CA 90601
Ph: 562-699-0541
Fax: 562-699-9721

E-mail: webmaster@iccsafe.org
Internet: www.iccsafe.org

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)
P.O. Box 687
106 Stone Street
Morrison, CO 80465
Ph: 303-697-8441
Fax: 303-697-8431
E-mail: neta@netaworld.org
Internet: http://www.netaworld.org

INTERNATIONAL WINDOW CLEANING ASSOCIATION (IWCA)
6277 Franconia Rd.
Alexandria, VA 22310
Ph: 800-875-4922 or 703-971-7771
FAX: 703-971-7772
E-mail: IWCA@aol.com
Internet: http://www.iwca.org

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)
127 Park Street, NE
Vienna, VA 22180-4602
Ph: 703-281-6613
Fax: 703-281-6671
E-mail: info@mss-hq.com
Internet: http://www.mss-hq.com

MARBLE INSTITUTE OF AMERICA (MIA)
28901 Clemens Road, Suite 100
Westlake, OH 44145
Ph: 440-250-9222
Fax: 440-250-9223
E-mail: info@marble-institute.com
Internet: http://www.marble-institute.com

MASTER PAINTERS INSTITUTE (MPI)
4090 Graveley Street
Burnaby, BC CANADA V5C 3T6
Ph: 888-674-8937
Fax: 888-211-8708
E-mail: info@paintinfo.com
Internet: http://www.paintinfo.com/mpi

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)
1300 Sumner Avenue
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
E-mail: mbma@mbma.com
Internet: http://www.mbma.com

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)
8oo Roosevelt Road, Bldg C, Suite 312
Glen Ellyn, IL 60137
Ph: 630-942-6591
Fax: 630-790-3095
E-mail: naamm@gss.net

Internet: http://www.naamm.org

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)
1300 North 17th Street, Suite 1752
Rosslyn, VA 22209
Ph: 703-841-3200
Fax: 703-841-5900
E-mail: webmaster@nema.org
Internet: http://www.nema.org/

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)
8575 Grovemont Circle
Gaithersburg, MD 20877
Ph: 301-977-3698
Fax: 301-977-9589
Internet: http://www.nebb.org

NATIONAL FENESTRATION RATING COUNCIL (NFRC)
8484 Georgia Avenue, Suite 320
Silver Spring, MD 20910
Ph: 301-589-1776
Fax: 301-589-3884
E-Mail: info@nfrc.org
Internet: http://www.nfrc.org

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 617-770-3000
Fax: 617-770-0700
E-mail: webmaster@nfpa.org
Internet: http://www.nfpa.org

NATIONAL READY MIXED CONCRETE ASSOCIATION (NRMCA)
900 Spring Street
Silver Spring, MD 20910
Ph: 301-587-1400
Fax: 301-585-4219
Internet: http://www.nrmca.org

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
10255 West Higgins Road, Suite 600
Rosemont, IL 60018
Ph: 847-299-9070
Fax: 847-299-1183
Internet: http://www.nrca.net

NSF INTERNATIONAL (NSF)
789 North Dixboro Road
P.O. Box 130140
Ann Arbor, MI 48113-0140
Ph: 734-769-8010 or 800-NSF-MARK
Fax: 734-769-0109
E-mail: info@nsf.org
Internet: http://www.nsf.org

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)
2200 Powell Street, Suite 725
Emeryville, CA 94608

Ph: 510-452-8000
Fax: 510-452-8001
E-mail: webmaster@scscertified.com
Internet: http://www.scs1.com

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
4201 Lafayette Center Drive
Chantilly, VA 20151-1209
Ph: 703-803-2980
Fax: 703-803-3732
E-mail: info@smacna.org
Internet: http://www.smacna.org

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)
400 Commonwealth Drive
Warrendale, PA 15096-0001
Ph: 724-776-4841
Fax: 724-776-0790
E-mail: customerservice@sae.org
Internet: http://www.sae.org

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)
21865 Copley Drive
Diamond Bar, CA 91765-4182
Ph: 909-396-2000
E-mail: webinquiry@aqmd.gov
Internet: http://www.aqmd.gov

STEEL DOOR INSTITUTE (SDI/DOOR)
c/o Wherry Associates
30200 Detroit Road
Cleveland, OH 44145-1967
Ph: 440-899-0010
Fax: 440-892-1404
E-mail: leh@wherryassoc.com
Internet: http://www.steeldoor.org

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)
40 24th Street, 6th Floor
Pittsburgh, PA 15222-4656
Ph: 412-281-2331
Fax: 412-281-9992
E-mail: info@sspc.org
Internet: http://www.sspc.org

TILE COUNCIL OF AMERICA (TCA)
100 Clemson Research Boulevard
Anderson, SC 29625
Ph: 864-646-8453
Fax: 864-646-2821
E-mail: literature@tileusa.com
Internet: http://www.tileusa.com

UNDERWRITERS LABORATORIES (UL)
333 Pfingsten Road
Northbrook, IL 60062-2096
Ph: 847-272-8800
Fax: 847-272-8129

E-mail: customerexperiencecenter@us.ul.com
Internet: http://www.ul.com/

U.S. ARMY CORPS OF ENGINEERS (USACE)
Order CRD-C DOCUMENTS from:
U.S. Army Engineer Waterways Experiment Station
ATTN: Technical Report Distribution Section, Services Branch, TIC
3909 Halls Ferry Road
Vicksburg, MS 39180-6199
Ph: 601-634-2664
Fax: 601-634-2388
E-mail: mtc-info@erdc.usace.army.mil
Internet: http://www.wes.army.mil/SL/MTC/handbook.htm

Order Other Documents from:
USACE Publications Depot
Attn: CEHEC-IM-PD
2803 52nd Avenue
Hyattsville, MD 20781-1102
Ph: 301-394-0081
Fax: 301-394-0084
E-mail: pubs-army@usace.army.mil
Internet: http://www.usace.army.mil/publications
or http://www.hnd.usace.army.mil/techinfo/engpubs.htm

U.S. DEFENSE LOGISTICS AGENCY (DLA)
Andrew T. McNamara Building
8725 John J. Kingman Road
Fort Belvoir, VA 22060
Ph: 1-877-352-2255
Internet: http://www.dla.mil

U.S. DEPARTMENT OF AGRICULTURE (USDA)
Order AMS Publications from:
AGRICULTURAL MARKETING SERVICE (AMS)
Seed Regulatory and Testing Branch
801 Summit Crossing Place, Suite C
Gastonia, NC 28054-2193
Ph: 704-810-8870
Fax: 704-852-4189
Internet: http://www.ams.usda.gov/lsg/seed.htm
E-mail: seed.ams@usda.gov

Order Other Publications from:
U.S. Department of Agriculture, Rural Utilities Service
14th and Independence Avenue, SW, Room 4028-S
Washington, DC 20250
Ph: 202-720-2791
Fax: 202-720-2166
Internet: http://www.usda.gov/rus

U.S. DEPARTMENT OF DEFENSE (DOD)
Directorate for Public Inquiry and Analysis
Office of the Secretary of Defense (Public Affairs)
Room 3A750 -- The Pentagon
1400 Defense Pentagon
Washington, DC 20301-1400
Ph: 703-428-0711

E-mail: pia@hq.afis.asd.mil
Internet: http://www.dod.gov

Order DOD Documents from:
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Ph: 703-605-6585
FAX: 703-605-6900
E-mail: info@ntis.gov
Internet: http://www.ntis.gov

Order Military Specifications, Standards and Related Publications from:
Department of Defense Single Stock Point for (DODSSP)
Defense Automation and Production Service (DAPS)
Building 4D
700 Robbins Avenue
Philadelphia, PA 19111-5098
Ph: 215-697-2179
Fax: 215-697-1462
Internet: http://www.dodssp.daps.mil
www.daps.dla.mil

- - - - - Detail Series Documents - - - - -

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)
Ariel Rios Building
1200 Pennsylvania Avenue, N.W.
Washington, DC 20460
Ph: 202-272-0167
Internet: http://www.epa.gov

--- Some EPA documents are available only from:
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Ph: 703-605-6585
Fax: 703-605-6900
E-mail: info@ntis.gov
Internet: http://www.ntis.gov

U. S. GREEN BUILDING COUNCIL (USGBC)
1015 18th Street, NW, Suite 508
Washington, D.C. 20036
Ph: 202-828-7422
Fax: 202-828-5110
E-mail: info@usbc.org
Internet: http://www.usgbc.org
AOK: 2/04
LOK: 2/04

U.S. GENERAL SERVICES ADMINISTRATION (GSA)
General Services Administration
1800 F Street, NW
Washington, DC 20405
Ph: 202-501-1021
Internet: www.GSA.gov

Order from:
General Services Administration
Federal Supply Service Bureau
1941 Jefferson Davis Highway
Arlington, VA 22202
Ph: 703-605-5400
Internet: http://apps.fss.gsa.gov/pub/fedspecs/index.cfm

- - - - - Commercial Item Description Documents - - - - -

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Fax: 301-837-0483
Internet: http://www.archives.gov

Order documents from:
Superintendent of Documents
U.S.Government Printing Office (GPO)
732 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: http://www.gpoaccess.gov

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 1971	(1998; R 2005) Stewardship for the Cleaning of Commercial and Institutional Buildings

1.2 SUBMISSION OF OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data specifically applicable to this contract and a complete and concise depiction of the provided equipment, product, or system, stressing and enhancing the importance of system interactions, troubleshooting, and long-term preventative maintenance and operation. The subcontractors shall compile and prepare data and deliver to the Contractor prior to the training of Government personnel. The Contractor shall compile and prepare aggregate O&M data including clarifying and updating the original sequences of operation to as-built conditions. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01 33 00 SUBMITTAL PROCEDURES.

1.2.1 Package Quality

Documents must be fully legible. Poor quality copies and material with hole punches obliterating the text or drawings will not be accepted.

1.2.2 Package Content

Data package content shall be as shown in the paragraph titled "Schedule of Operation and Maintenance Data Packages." Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission, except as follows.

1.2.3 Changes to Submittals

Manufacturer-originated changes or revisions to submitted data shall be furnished by the Contractor if a component of an item is so affected subsequent to acceptance of the O&M Data. Changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data, shall be submitted by the Contractor within 30 calendar days of the notification of this change requirement.

1.3 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

1.3.1 Operating Instructions

Include specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.3.1.1 Safety Precautions

List personnel hazards and equipment or product safety precautions for all operating conditions.

1.3.1.2 Operator Prestart

Include procedures required to install, set up, and prepare each system for use.

1.3.1.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.3.1.4 Normal Operations

Provide narrative description of Normal Operating Procedures. Include Control Diagrams with data to explain operation and control of systems and specific equipment.

1.3.1.5 Emergency Operations

Include Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Include Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of all utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.3.1.6 Operator Service Requirements

Include instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gage readings.

1.3.1.7 Environmental Conditions

Include a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.3.2 Preventive Maintenance

Include the following information for preventive and scheduled maintenance to minimize corrective maintenance and repair for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.3.2.1 Lubrication Data

Include preventative maintenance lubrication data, in addition to instructions for lubrication provided under paragraph titled "Operator Service Requirements":

a. A table showing recommended lubricants for specific temperature ranges and applications.

b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.

c. A Lubrication Schedule showing service interval frequency.

1.3.2.2 Preventive Maintenance Plan and Schedule

Include manufacturer's schedule for routine preventive maintenance, inspections, tests and adjustments required to ensure proper and economical operation and to minimize corrective maintenance. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

1.3.2.3 Cleaning Recommendations

Provide environmentally preferable cleaning recommendations in accordance with ASTM E 1971.

1.3.3 Corrective Maintenance (Repair)

Include manufacturer's recommended procedures and instructions for correcting problems and making repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.3.3.1 Troubleshooting Guides and Diagnostic Techniques

Include step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.3.3.2 Wiring Diagrams and Control Diagrams

Wiring diagrams and control diagrams shall be point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.3.3.3 Maintenance and Repair Procedures

Include instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.3.3.4 Removal and Replacement Instructions

Include step-by-step procedures and a list required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Instructions shall include a combination of text and illustrations.

1.3.3.5 Spare Parts and Supply Lists

Include lists of spare parts and supplies required for maintenance and repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.3.4 Corrective Maintenance Work-Hours

Include manufacturer's projection of corrective maintenance work-hours including requirements by type of craft. Corrective maintenance that requires completion or participation of the equipment manufacturer shall be identified and tabulated separately.

1.3.5 Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.3.5.1 Product Submittal Data

Provide a copy of all SD-03 Product Data submittals required in the applicable technical sections.

1.3.5.2 Manufacturer's Instructions

Provide a copy of all SD-08 Manufacturer's Instructions submittals required in the applicable technical sections.

1.3.5.3 O&M Submittal Data

Provide a copy of all SD-10 Operation and Maintenance Data submittals required in the applicable technical sections.

1.3.5.4 Parts Identification

Provide identification and coverage for all parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing shall show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Parts shown in the listings shall be grouped by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment,

components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog

1.3.5.5 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components such as the compressor of air conditioning system.

1.3.5.6 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.3.5.7 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components.

1.3.5.8 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms.

1.3.5.9 Contractor Information

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

1.4 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Furnish the O&M data packages specified in individual technical sections. The required information for each O&M data package is as follows:

1.4.1 Data Package 1

a. Safety precautions

b. Cleaning recommendations

c. Maintenance and repair procedures

d. Warranty information

e. Contractor information

f. Spare parts and supply list

1.4.2 Data Package 2

a. Safety precautions

b. Normal operations

c. Environmental conditions

d. Lubrication data

e. Preventive maintenance plan and schedule

f. Cleaning recommendations

g. Maintenance and repair procedures

h. Removal and replacement instructions

i. Spare parts and supply list

j. Parts identification

k. Warranty information

l. Contractor information

1.4.3 Data Package 3

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Environmental conditions

g. Lubrication data

h. Preventive maintenance plan and schedule

i. Cleaning recommendations

j. Troubleshooting guides and diagnostic techniques

k. Wiring diagrams and control diagrams

l. Maintenance and repair procedures

m. Removal and replacement instructions

n. Spare parts and supply list

o. Product submittal data

p. O&M submittal data

q. Parts identification

r. Warranty information

s. Testing equipment and special tool information

t. Testing and performance data

u. Contractor information

1.4.4 Data Package 4

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Operator service requirements

g. Environmental conditions

h. Lubrication data

i. Preventive maintenance plan and schedule

j. Cleaning recommendations

k. Troubleshooting guides and diagnostic techniques

l. Wiring diagrams and control diagrams

m. Maintenance and repair procedures

n. Removal and replacement instructions

o. Spare parts and supply list

p. Corrective maintenance man-hours

q. Product submittal data

r. O&M submittal data

s. Parts identification

t. Warranty information

u. Personnel training requirements

v. Testing equipment and special tool information

w. Testing and performance data

x. Contractor information

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 02 41 00

DEMOLITION
10/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

ARI Guideline K	(2005) Guideline for Containers for Recovered Non-Flammable Fluorocarbon Refrigerants

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 145	(1991; R 2004) Classification of Soils and Soil-Aggregate Mixtures for Highway Construction Purposes
AASHTO T 180	(2001; R 2004) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457-mm (18-in) Drop

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.6	(2006) Safety Requirements for Demolition Operations

CARPET AND RUG INSTITUTE (CRI)

CRI 104	(2002) Standard for Installation Specification of Commercial Carpet

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008) Safety and Health Requirements Manual

U.S. DEFENSE LOGISTICS AGENCY (DLA)

DLA 4145.25	(June 2000) Storage and Handling of Liquefied and Gaseous Compressed Gases and Their Full and Empty Cylinders

U.S. DEPARTMENT OF DEFENSE (DOD)

DOD 4000.25-1-M	(2006; Notice 1) Requisitioning and Issue Procedures
MIL-STD-129	(Rev P; Notice 3) Military Marking for

Shipment and Storage

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61	National Emission Standards for Hazardous Air Pollutants
40 CFR 82	Protection of Stratospheric Ozone
49 CFR 173.301	Shipment of Compressed Gases in Cylinders and Spherical Pressure Vessels

1.2 GENERAL REQUIREMENTS

Do not begin demolition until authorization is received from the Contracting Officer. The work of this section is to be performed in a manner that maximizes salvage and recycling of materials. Remove rubbish and debris from the project site; do not allow accumulations inside or outside the building. The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Existing Conditions; G

SD-07 Certificates

Demolition Plan; G
Notifications; G

Proposed salvage, demolition, and removal procedures for approval before work is started.

SD-11 Closeout Submittals

Receipts

Receipts or bills of laden, as specified.

1.4 REGULATORY AND SAFETY REQUIREMENTS

Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSE/SAFE A10.6.

1.4.1 Notifications

1.4.1.1 General Requirements

Furnish timely notification of demolition projects to government authorities in accordance with 40 CFR 61, Subpart M. Notify the government environmental protection organization, local air pollution control district/organization and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M.

If unexpected asbestos/hazardous waste is encountered at the site, the Contracting Officer will investigate the conditions, determine the extent of the affected area, and authorize the Contractor, in writing, to remove and dispose of the asbestos/waste as directed and specified. Payment for such work will be made as specified in Contract. The Contractor will not be required to perform or arrange for this work

1.5 DUST AND DEBRIS CONTROL

Prevent the spread of dust and debris and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

1.6 PROTECTION

1.6.1 Traffic Control Signs

Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Notify the Contracting Officer prior to beginning such work.

1.6.2 Existing Conditions Documentation

Before beginning any demolition work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs sized 100 mm will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document.

1.6.3 Items to Remain in Place

Take necessary precautions to avoid damage to existing items to be the property of the Government. Repair or replace damaged items if/as required by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports if/as required. Do not overload structural elements for government property.

1.6.4 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove snow, dust, dirt, and debris from work areas daily.

1.6.5 Trees

Protect trees within the project site which might be damaged during demolition or deconstruction, and which are indicated to be left in place, by a 1.8 m high fence. Erect and secure fence a minimum of 1.5 m from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.6.6 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition and deconstruction operations. Prior to start of work, utilities serving each area of removal will be shut off by the Government and disconnected and sealed by the Contractor if/as required or directed.

1.6.7 Facilities

If/as required or directed, protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities.

1.6.8 Protection of Personnel

Before, during and after the demolition work the Contractor shall continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.7 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.8 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the work involved. Items to be relocated which are damaged by the Contractor shall be repaired or replaced with new undamaged items as approved by the Contracting Officer.

1.9 REQUIRED DATA

Prepare a Demolition Plan. Include in the plan procedures for careful

removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, as applicable, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Identify components and materials to be salvaged for reuse or recycling with reference to paragraph Existing Facilities to be Removed. Append tracking forms for all removed materials indicating type, quantities, condition, destination, and end use. Coordinate with Waste Management Plan. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan shall be approved by Contracting Officer prior to work beginning.

1.10 ENVIRONMENTAL PROTECTION

Comply with the Environmental Protection Agency requirements specified.

1.11 USE OF EXPLOSIVES

Use of explosives will not be permitted.

1.12 AVAILABILITY OF WORK AREAS

Areas in which the work is to be accomplished will be available at the notice-to-proceed.

PART 2 PRODUCTS

2.1 FILL MATERIAL

Comply with excavating, backfilling, and compacting procedures for soils used as backfill material to fill basements, voids, depressions or excavations resulting from demolition or deconstruction of structures.

Fill material must conform to the definition of satisfactory soil material as defined in AASHTO M 145, Soil Classification Groups A-1, A-2-4, A-2-5 and A-3. In addition, fill material must be free from roots and other organic matter, trash, debris, frozen materials, and stones larger than 50 millimeter in any dimension.

Proposed fill material must be sampled and tested by an approved soil testing laboratory, as follows:

Soil classification	AASHTO M 145
Moisture-density relations	AASHTO T 180, Method B or D

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures on site for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse on site whenever possible.

3.1.1 Structures

a. Remove existing structures indicated to be removed to 1.2 meters

below grade. Break up basement slabs to permit drainage. Remove sidewalks, curbs, gutters and street light bases as indicated.

b. Demolish structures in a systematic manner from the top of the structure to the ground. Complete demolition work above each tier or floor before the supporting members on the lower level are disturbed. Demolish concrete and masonry walls in small sections. Remove structural framing members and lower to ground by means of derricks, platforms hoists, or other suitable methods as approved by the Contracting Officer.

c. Locate demolition and deconstruction equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

d. Building, or the remaining portions thereof, not exceeding 25 m in height may be demolished by the mechanical method of demolition.

3.1.2 Utilities and Related Equipment

3.1.2.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.2.2 Disconnecting Existing Utilities

Remove existing utilities as indicated or directed and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered that are not indicated on the drawings, the Contracting Officer shall be notified prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Contracting Officer.

3.1.3 Chain Link Fencing

Remove chain link fencing, gates and other related salvaged items scheduled for removal and transport to designated areas. Remove gates as whole units. Cut chain link fabric to 7 m lengths and store in rolls off the ground.

3.1.4 Paving and Slabs

If/as directed, remove concrete and asphaltic concrete paving and slabs as indicated or as directed to a depth below existing adjacent or new finish grade. Provide neat sawcuts at limits of pavement removal. Pavement and slabs designated to be recycled and utilized in this project shall be moved, ground and stored if/as directed by the Contracting Officer. Pavement and slabs not to be used in this project shall be removed from the Installation at Contractor's expense.

3.1.5 Roofing

As directed, salvage asphalt roofing materials.

3.1.6 Masonry

Masonry removed in whole blocks shall be salvaged and stored for reuse. Masonry removed in pieces shall be crushed for use as aggregate.

3.1.7 Concrete

Saw concrete along straight lines to a depth of a minimum 50 mm. Make each cut in walls perpendicular to the face and in alignment with the cut in the opposite face. Break out the concrete. Salvage removed concrete.

3.1.8 Structural Steel

Dismantle structural steel at field connections and in a manner that will prevent bending or damage. Salvage for recycle structural steel, steel joists, girders, angles, plates, columns and shapes. Transport steel joists and girders as whole units and not dismantled. Transport structural steel shapes to a designated storage area, recycling facility or area as directed by the Contracting Officer, stacked according to size, type of member and length, and stored off the ground, protected from the weather.

3.1.9 Miscellaneous Metal

Salvage shop-fabricated items such as access doors and frames, steel gratings, metal ladders, wire mesh partitions, metal railings, metal windows and similar items as whole units. Salvage light-gage and cold-formed metal framing, such as steel studs, steel trusses, metal gutters, roofing and siding, metal toilet partitions, toilet accessories and similar items. Recycle scrap metal as part of demolition and deconstruction operations. Provide separate containers to collect scrap metal and transport to a scrap metal collection or recycling facility, in accordance with the Waste Management Plan.

3.1.10 Carpentry

Salvage for recycle lumber, millwork items, and finished boards, and sort by type and size. Chip or shred and recycle salvaged wood unfit for reuse, except stained, painted, or treated wood. Salvage windows, doors, frames, and cabinets, and similar items as whole units, complete with trim and accessories. Salvage hardware attached to units for reuse. Brace the open end of door frames to prevent damage.

3.1.11 Carpet

Remove existing carpet for reclamation in accordance with manufacturer recommendations and as follows. Remove used carpet in large pieces, roll tightly, and pack neatly in a container. Remove adhesive according to recommendations of the Carpet and Rug Institute (CRI). Adhesive removal solvents shall comply with CRI 104. Recycle removed carpet cushion.

3.1.12 Acoustic Ceiling Tile

Remove, neatly stack, and recycle acoustic ceiling tiles. Recycling may be available with manufacturer. Otherwise, priority shall be given to a local recycling organization.

3.1.13 Air Conditioning Equipment

Remove air conditioning, refrigeration, and other equipment containing refrigerants without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990. Recover all refrigerants prior to removing air conditioning, refrigeration, and other equipment containing refrigerants and dispose of in accordance with the paragraph entitled "Disposal of Ozone Depleting Substance (ODS)." Turn in salvaged Class I ODS refrigerants as specified in Paragraph, "Salvaged Materials and Equipment".

3.1.14 Cylinders and Canisters

Remove all fire suppression system cylinders and canisters and dispose of in accordance with the paragraph entitled "Disposal of Ozone Depleting Substance (ODS)."

3.1.15 Locksets on Swinging Doors

The Contractor shall remove all locksets from all swinging doors indicated to be removed and disposed of. Deliver the locksets and related items to a designated location for receipt by the Contracting Officer after removal.

3.1.16 Mechanical Equipment and Fixtures

Disconnect mechanical hardware at the nearest connection to existing services to remain, unless otherwise noted. Mechanical equipment and fixtures must be disconnected at fittings. Remove service valves attached to the unit. Salvage each item of equipment and fixtures as a whole unit; listed, indexed, tagged, and stored. Salvage each unit with its normal operating auxiliary equipment. Transport salvaged equipment and fixtures, including motors and machines, to a designated storage area as directed by the Contracting Officer. Do not remove equipment until approved. Do not offer low-efficiency equipment for reuse; provide to recycling service for disassembly and recycling of parts.

3.1.16.1 Preparation for Storage

Remove water, dirt, dust, and foreign matter from units; tanks, piping and fixtures shall be drained; interiors, if previously used to store flammable, explosive, or other dangerous liquids, must be steam cleaned. Seal openings with caps, plates, or plugs. Secure motors attached by flexible connections to the unit. Change lubricating systems with the proper oil or grease.

3.1.16.2 Piping

Disconnect piping at unions, flanges and valves, and fittings as required to reduce the pipe into straight lengths for practical storage. Store salvaged piping according to size and type. Carefully dismantle piping that previously contained gas, gasoline, oil, or other dangerous fluids, with precautions taken to prevent injury to persons and property. Store piping outdoors until all fumes and residues are removed. Box prefabricated supports, hangers, plates, valves, and specialty items according to size and type. Wrap sprinkler heads individually in plastic bags before boxing. Classify piping not designated for salvage, or not reusable, as scrap metal.

3.1.16.3 Ducts

Classify removed duct work as scrap metal.

3.1.16.4 Fixtures, Motors and Machines

Remove and salvage fixtures, motors and machines associated with plumbing, heating, air conditioning, refrigeration, and other mechanical system installations. Salvage, box and store auxiliary units and accessories with the main motor and machines. Tag salvaged items for identification, storage, and protection from damage. Classify non-porcelain broken, damaged, or otherwise unserviceable units and not caused to be broken, damaged, or otherwise unserviceable as debris and disposed of by the Contractor. Salvage and crush porcelain plumbing fixtures unsuitable for reuse.

3.1.17 Electrical Equipment and Fixtures

Salvage motors, motor controllers, and operating and control equipment that are attached to the driven equipment. Salvage wiring systems and components. Box loose items and tag for identification. Disconnect primary, secondary, control, communication, and signal circuits at the point of attachment to their distribution system.

3.1.17.1 Fixtures

Remove and salvage electrical fixtures. Salvage unprotected glassware from the fixture and salvage separately. Salvage incandescent, mercury-vapor, and fluorescent lamps and fluorescent ballasts manufactured prior to 1978, boxed and tagged for identification, and protected from breakage.

3.1.17.2 Electrical Devices

Remove and salvage switches, switchgear, transformers, conductors including wire and nonmetallic sheated and flexible armored cable, regulators, meters, instruments, plates, circuit breakers, panelboards, outlet boxes, and similar items. Box and tag these items for identification according to type and size.

3.1.17.3 Wiring Ducts or Troughs

Remove and salvage wiring ducts or troughs. Dismantle plug-in ducts and wiring troughs into unit lengths. Remove plug-in or disconnecting devices from the busway and store separately.

3.1.17.4 Conduit and Miscellaneous Items

Salvage conduit except where embedded in concrete or masonry. Consider corroded, bent, or damaged conduit as scrap metal. Sort straight and undamaged lengths of conduit according to size and type. Classify supports, knobs, tubes, cleats, and straps as debris to be removed and disposed.

3.1.18 Elevators and Hoists

Remove elevators, hoists, and similar conveying equipment and salvage as whole units, to the most practical extent. Remove and prepare items for salvage without damage to any of the various parts. Salvage and store rails for structural steel with the equipment as an integral part of the

unit.

3.1.19 Items With Unique/Regulated Disposal Requirements

Remove and dispose of items with unique or regulated disposal requirements in the manner dictated by law or in the most environmentally responsible manner.

3.2 CONCURRENT EARTH-MOVING OPERATIONS

Do not begin excavation, filling, and other earth-moving operations that are sequential to demolition work in areas occupied by structures to be demolished until all demolition in the area has been completed and debris removed. Fill holes, open basements and other hazardous openings.

3.3 DISPOSITION OF MATERIAL

3.3.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, and removal procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.3.2 Salvaged Materials and Equipment

Remove materials and equipment that are listed in the Demolition Plan to be removed by the Contractor and that are to remain the property of the Government, and deliver to a storage site, as directed within 10 km of the work site.

a. Salvage items and material to the maximum extent possible.

b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. Material salvaged for the Contractor shall not be sold on the site.

c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing items. Properly identify the contents of containers. Deliver items reserved as property of the Government to the areas designated as directed.

d. Remove as directed any items reserved as property of the using service prior to commencement of work under this contract.

e. Remove historical items in a manner to prevent damage. Deliver the following historical items to the Government for disposition: Corner stones, contents of corner stones, and document boxes wherever located

on the site.

3.3.3 Disposal of Ozone Depleting Substance (ODS)

Class I and Class II ODS are defined in Section, 602(a) and (b), of The Clean Air Act. Prevent discharge of Class I and Class II ODS to the atmosphere. Place recovered ODS in cylinders meeting ARI Guideline K suitable for the type ODS (filled to no more than 80 percent capacity) and provide appropriate labeling. Recovered ODS shall be removed from Government property and disposed of in accordance with 40 CFR 82. Products, equipment and appliances containing ODS in a sealed, self-contained system (e.g. residential refrigerators and window air conditioners) shall be disposed of in accordance with 40 CFR 82.

3.3.3.1 Special Instructions

No more than one type of ODS is permitted in each container. A warning/hazardous label shall be applied to the containers in accordance with Department of Transportation regulations. All cylinders including but not limited to fire extinguishers, spheres, or canisters containing an ODS shall have a tag with the following information:

a. Activity name and unit identification code

b. Activity point of contact and phone number

c. Type of ODS and pounds of ODS contained

d. Date of shipment

e. Naval stock number (for information, call (804) 279-4525).

3.3.3.2 Fire Suppression Containers

Deactivate fire suppression system cylinders and canisters with electrical charges or initiators prior to shipment. Also, safety caps must be used to cover exposed actuation mechanisms and discharge ports on these special cylinders.

3.3.4 Transportation Guidance

Ship all ODS containers in accordance with MIL-STD-129, DLA 4145.25 (also referenced one of the following: Army Regulation 700-68, Naval Supply Instruction 4440.128C, Marine Corps Order 10330.2C, and Air Force Regulation 67-12), 49 CFR 173.301, and DOD 4000.25-1-M.

3.3.5 Unsalvageable and Non-Recyclable Material

Dispose of unsalvageable and non-recyclable noncombustible material in an approved disposal area off-site. The fill in the disposal area must remain below grade and after disposal is completed, the disposal area must be uniformly graded to drain.

3.4 CLEANUP

Remove debris and rubbish from excavations. Remove and transport the in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.5 DISPOSAL OF REMOVED MATERIALS

3.5.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable government regulations as contractually specified off-site in the Waste Management Plan. Storage of removed materials on the project site is prohibited.

3.5.2 Removal from Government Property

Transport waste materials removed from demolished structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

-- End of Section --

SECTION 03 11 13.00 10

STRUCTURAL CONCRETE FORMWORK
05/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 347	(2004) Guide to Formwork for Concrete

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA PS 1	(1995) Voluntary Product Standard for Construction and Industrial Plywood

ASTM INTERNATIONAL (ASTM)

ASTM C 1077	(2009b) Standard Practice for Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation
ASTM C 31/C 31M	(2009) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C 39/C 39M	(2005e1e2) Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C 578	(2009e1) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation

1.2 SYSTEM DESCRIPTION

The design, engineering, and construction of the formwork is the responsibility of the Contractor. Design formwork in accordance with methodology of ACI 347 for anticipated loads, lateral pressures, and stresses, and capable of withstanding the pressures resulting from placement and vibration of concrete. Comply with the tolerances specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE, paragraph CONSTRUCTION TOLERANCES. However, for surfaces with an ACI Class A surface designation, limit the allowable deflection for facing material between studs, for studs between walers and walers between bracing to 0.0025 times the span. Design the formwork as a complete system with consideration given to the effects of cementitious materials and mixture additives such as fly ash, cement type, plasticizers, accelerators, retarders, air entrainment, and others. Monitor the adequacy of formwork design and construction prior to and during concrete placement as part of the Contractor's approved Quality Control Plan.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Formwork; G

Drawings showing details of formwork, including dimensions of fiber voids, joints, supports, studding and shoring, and sequence of form and shoring removal.

SD-03 Product Data

Design

Design analysis and calculations for form design and methodology used in the design.

Form Materials

Manufacturer's data including literature describing form materials, accessories, and form releasing agents.

Form Releasing Agents

Manufacturer's recommendation on method and rate of application of form releasing agents.

SD-04 Samples

Sample Panels

After shop drawings have been reviewed, sample panels for Class A finish with applied architectural treatment shall be built on the project site where directed.

Fiber Voids

One sample unit of fiber voids prior to installation of the voids.

SD-06 Test Reports

Inspection

Field inspection reports for concrete forms and embedded items.

SD-07 Certificates

Fiber Voids

Certificates attesting that fiber voids conform to the specified requirements.

1.4 QUALITY ASSURANCE

Sample Panels shall be of sufficient size to contain joints and shall be not less than 2 meters long and 1.5 meters wide. The panels shall be of typical wall thickness and constructed containing the full allocation of reinforcing steel that will be used in the structure, with the forming system that duplicates in every detail the one that will be used in construction of the structure. Use the same concrete mixture proportion and materials, the same placement techniques and equipment, and the same finishing techniques and timing that are planned for the structure. Construction of Class A finish will not be permitted until sample panels have been approved. Protect sample panels from construction operations in a manner to protect approved finish, and are not to be removed until all Class A finish concrete has been accepted.

1.5 DELIVERY, STORAGE, AND HANDLING

Store fiber voids above ground level in a dry location. Fiber voids shall be kept dry until installed and overlaid with concrete.

PART 2 PRODUCTS

2.1 FORM MATERIALS

2.1.1 Forms For Class A Finish

Forms for Class A finished surfaces shall be plywood panels conforming to APA PS 1, Grade B-B concrete form panels, Class I or II. Other form materials or liners may be used provided the smoothness and appearance of concrete produced will be equivalent to that produced by the plywood concrete form panels.

2.1.2 Forms For Class B Finish

This class of finish shall apply to all surfaces except those specified to receive Class A. Forms for Class B finished surfaces shall be plywood panels conforming to APA PS 1, Grade B-B concrete form panels, Class I or II. Other form materials or liners may be used provided the smoothness and appearance of concrete produced will be equivalent to that produced by the plywood concrete form panels. Steel lining on wood sheathing will not be permitted.

2.1.3 Form Ties

Form ties shall be factory-fabricated metal ties, shall be of the removable or internal disconnecting or snap-off type, and shall be of a design that will not permit form deflection and will not spall concrete upon removal. Provide solid backing for each tie. Except where removable tie rods are used, ties shall not leave holes in the concrete surface less than 6 mm nor more than 25 mm deep and not more than 25 mm in diameter. Terminate the embedded portion of metal ties not less that 50 mm from any concrete surface exposed to water. Removable tie rods shall be not more than 38 mm in diameter. Plastic snap ties may be used in locations where the surface will not be exposed to view.

2.1.4 Form Releasing Agents

Form releasing agents shall be commercial formulations that will not bond with, stain or adversely affect concrete surfaces. Agents shall not impair

subsequent treatment of concrete surfaces depending upon bond or adhesion nor impede the wetting of surfaces to be cured with water or curing compounds. If special form liners are to be used, the Contractor shall follow the recommendation of the form coating manufacturer.

2.1.5 Fiber Voids

Fiber voids shall be the product of a reputable manufacturer regularly engaged in the commercial production of fiber voids. The voids shall be constructed of double faced, corrugated fiberboard. The corrugated fiberboard shall be fabricated of wet strength paper liners, impregnated with paraffin, and laminated with moisture resistant adhesive, and shall have a board strength of 20 kg/square centimeter. Voids which are impregnated with paraffin after construction, in lieu of being constructed with paraffin impregnated fiberboard, are acceptable. Voids shall be designed to support not less than 4900 kg/square meter. To prevent separation during concrete placement fiber voids shall be assembled with steel or plastic banding at 1.22 m on center maximum, or by adequate stapling or gluing as recommended by the manufacturer. Fiber voids placed under concrete slabs and that are 200 mm in depth may be heavy duty "waffle box" type, constructed of paraffin impregnated corrugated fiberboard.

2.2 FIBER VOID RETAINERS

2.2.1 Polystyrene Rigid Insulation

Polystyrene rigid insulation shall conform to ASTM C 578, Type V, VI, or VII, square edged. Size shall be 38 mm thick by 400 mm in height by 1 m in length, unless otherwise indicated.

2.2.2 Precast Concrete

Precast concrete units shall have a compressive strength of not less than 17 MPa, reinforced with 150 mm by 150 mm by W1.4 WWF wire mesh, and 300 mm (height) by 1 m (length) by 40 mm (thickness) in size unless indicated.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Formwork

Forms shall be constructed true to the structural design and required alignment. Forms shall be mortar tight, properly aligned and adequately supported to produce concrete surfaces meeting the surface requirements specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE and conforming to construction tolerance given in TABLE 1. Continuously monitor the alignment and stability of the forms during all phases to assure the finished product will meet the required surface class or classes specified. Failure of any supporting surface either due to surface texture, deflection or form collapse shall be the responsibility of the Contractor as will the replacement or correction of unsatisfactory surfaces. Where concrete surfaces are to have a Class A or Class B finish, joints in form panels shall be arranged as approved. When forms for continuous surfaces are placed in successive units, care shall be taken to fit the forms over the completed surface to obtain accurate alignment of the surface and to prevent leakage of mortar. Forms shall not be re-used if there is any evidence of defects which would impair the quality of the resulting concrete surface. All surfaces of used forms shall be cleaned of

mortar and any other foreign material before reuse. Form ties that are to be completely withdrawn shall be coated with a nonstaining bond breaker.

3.1.2 Fiber Voids

Voids shall be placed on a smooth firm dry bed of suitable material, to avoid being displaced vertically, and shall be set tight, with no buckled cartons, in order that horizontal displacement cannot take place. Each section of void shall have its ends sealed by dipping in paraffin, with any additional cutting of voids at the jobsite to be field dipped in the same type of sealer, unless liners and flutes are completely impregnated with paraffin. Prior to placing reinforcement, the entire formed area for slabs shall be covered with a 1.22 x 2.44 m minimum flat sheets of fiber void corrugated fiberboard. Joints shall be sealed with a moisture resistant tape having a minimum width of 75 mm. If voids are destroyed or damaged and are not capable of supporting the design load, they shall be replaced prior to placing of concrete.

3.1.3 Fiber Void Retainers

Fiber void retainers shall be installed, continuously, on both sides of fiber voids placed under grade beams in order to retain the cavity after the fiber voids biodegrade.

3.2 CHAMFERING

All exposed joints, edges and external corners shall be chamfered by molding placed in the forms unless the drawings specifically state that chamfering is to be omitted or as otherwise specified. Chamfered joints shall not be permitted where earth or rockfill is placed in contact with concrete surfaces. Chamfered joints shall be terminated 300 mm outside the limit of the earth or rockfill so that the end of the chamfers will be clearly visible.

3.3 COATING

Forms for Class A and Class B finished surfaces shall be coated with a form releasing agent before the form or reinforcement is placed in final position. The coating shall be used as recommended in the manufacturer's printed or written instructions. Surplus coating on form surfaces and coating on reinforcing steel and construction joints shall be removed before placing concrete.

3.4 FORM REMOVAL

Forms shall not be removed without approval. The minimal time required for concrete to reach a strength adequate for removal of formwork without risking the safety of workers or the quality of the concrete depends on a number of factors including, but not limited to, ambient temperature, concrete lift heights, type and amount of concrete admixture, and type and amount of cementitious material in the concrete. It is the responsibility of the Contractor to consider all applicable factors and leave the forms in place until it is safe to remove them. In any case forms shall not be removed unless the minimum compressive strength or minimum time, minimum ambient temperature, and minimum compressive strength requirements below are met, except as otherwise directed or specifically authorized. When conditions are such as to justify the requirement, forms will be required to remain in place for a longer period. All removal shall be accomplished in a manner which will prevent damage to the concrete and ensure the

complete safety of the structure. Where forms support more than one element, the forms shall not be removed until the form removal criteria are met by all supported elements. Form removal shall be scheduled so that all necessary repairs can be performed as specified in Section 03 31 00.00 10, paragraph 3.10.1. Evidence that concrete has gained sufficient strength to permit removal of forms shall be determined by tests on control cylinders. All control cylinders shall be stored in the structure or as near the structure as possible so they receive the same curing conditions and protection methods as given those portions of the structure they represent. Control cylinders shall be removed from the molds at an age of no more than 24 hours. All control cylinders shall be prepared and tested in accordance with ASTM C 31/C 31M and ASTM C 39/C 39M at the expense of the Contractor by an independent laboratory that complies with ASTM C 1077 and shall be tested within 4 hours after removal from the site.

3.4.1 Formwork Not Supporting Weight of Concrete

Formwork for walls, columns, sides of beams, gravity structures, and other vertical type formwork not supporting the weight of concrete shall not be removed in less than 24 hours after concrete placement is completed. Form removal before 24 hours will be allowed for simple floor slab on-grade, sidewalks, and driveways provided the ambient temperature during this period has not fallen below 10 degrees C at any time since placement and evidence from compressive tests on field-cured concrete control cylinders or maturity instrumentation indicates that the concrete has attained a compressive strength of at least 3.5 MPa. Control cylinders shall be prepared for each set of forms to be removed before 24 hours. The stability of the concrete shall be evaluated by a structural engineer prior to removal of the forms.

3.4.2 Formwork Supporting Weight of Concrete

Formwork supporting weight of concrete and shoring shall not be removed until structural members have acquired sufficient strength to safely support their own weight and any construction or other superimposed loads to which the supported concrete may be subjected. As a minimum, forms shall be left in place until control concrete test cylinders indicate evidence the concrete has attained at least 70 percent of the compressive strength required for the structure in accordance with the quality and location requirements.

3.5 INSPECTION

Forms and embedded items shall be inspected in sufficient time prior to each concrete placement in order to certify to the Contracting Officer that they are ready to receive concrete. The results of each inspection shall be reported in writing.

TABLE 1 TOLERANCES FOR FORMED SURFACES	
1. Variations from the plumb:	
a. In the lines and surfaces of columns, piers, walls and in arises	6 mm in any 3 m of length Maximum for entire length -- 25 mm

TABLE 1 TOLERANCES FOR FORMED SURFACES	
b. For exposed corner columns, control-joint grooves, and other conspicuous lines	6 mm in any 6 m of length Maximum for entire length -- 13 mm
2. Variation for the level or from the grades indicated on the drawings:	
a. In slab soffits, ceilings beam soffits, and in arises,measured before removal of supporting shores	6 mm in any 3 m of length 10 mm in any bay or in any 6 m of length Maximum for entire length -- 20 mm
b. In exposed lintels, sills, parapets, horizontal grooves, and other conspicuous lines	6 mm in any bay or in any 6 m of length Maximum for entire length -- 13 mm
3. Variation of the linear building lines from established position in plan	13 mm in any 6 m 25 mm maximum
4. Variation of distance between walls, columns, partitions	6 mm per 3 m of distance, but not more than 13 mm in any one bay, and not more than 25 mm total variation
5. Variation in the sizes and locations of sleeves, floor openings, and wall opening	Minus 6 mm, Plus 13 mm
6. Variation in cross-sectional dimensions of columns and beams and in the thickness of slabs and walls	Minus 6 mm, Plus 13 mm
7. Footings:	
a. Variation of dimensions in plan	Minus 13 mm, plus 50 mm when formed or plus 75 mm when placed against unformed excavation
b. Misplacement of eccentricity	2 percent of the footing width in the direction of misplacement but not more than 50 mm
c. Reduction in thickness	Minus 5 percent of the specified thickness
8. Variation in steps:	

TABLE 1 TOLERANCES FOR FORMED SURFACES	
a. In a flight of stairs	Riser -- 3 mm Tread -- 6 mm
b. In consecutive steps	Riser -- 2 mm Tread -- 3 mm

-- End of Section --

SECTION 03 15 13.00 10

EXPANSION JOINTS, CONTRACTION JOINTS, AND WATERSTOPS
11/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 111	(2009) Inorganic Matter or Ash in Bituminous Materials

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA A135.4	(2004) Basic Hardboard

ASTM INTERNATIONAL (ASTM)

ASTM A 1011/A 1011M	(2009a) Standard Specification for Steel, Sheet, and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability
ASTM A 109/A 109M	(2008) Standard Specification for Steel, Strip, Carbon (0.25 Maximum Percent), Cold-Rolled
ASTM A 167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 480/A 480M	(2009) Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip
ASTM B 152/B 152M	(2006ae1) Standard Specification for Copper Sheet, Strip, Plate, and Rolled Bar
ASTM B 370	(2009) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM C 919	(2008) Use of Sealants in Acoustical Applications
ASTM C 920	(2008) Standard Specification for Elastomeric Joint Sealants

ASTM D 1751	(2004; R 2008) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D 1752	(2004a; R 2008) Standard Specification for Preformed Sponge Rubber Cork and Recycled PVC Expansion
ASTM D 2628	(1991; R 2005) Standard Specification for Preformed Polychloroprene Elastomeric Joint Seals for Concrete Pavements
ASTM D 2835	(1989; R 2007) Lubricant for Installation of Preformed Compression Seals in Concrete Pavements
ASTM D 4	(1986; R 2004) Bitumen Content
ASTM D 412	(2006ae1e2) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D 471	(2006; R 2008) Standard Test Method for Rubber Property - Effect of Liquids
ASTM D 5249	(1995; R 2006) Backer Material for Use with Cold-and Hot-Applied Joint Sealants in Portland-Cement Concrete and Asphalt Joints
ASTM D 6	(1995; R 2006) Loss on Heating of Oil and Asphaltic Compounds
ASTM D 7116	(2005) Standard Specification for Joint Sealants, Hot Applied, Jet Fuel Resistant Types, for Portland Cement Concrete

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 513	(1974) Specifications for Rubber Waterstops
COE CRD-C 572	(1974) Specifications for Polyvinylchloride Waterstops

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Waterstops; G

Shop drawings and fabrication drawings provided by the

manufacturer or prepared by the Contractor.

SD-03 Product Data

Preformed Expansion Joint Filler
Sealant
Waterstops

Manufacturer's literature, including safety data sheets, for preformed fillers and the lubricants used in their installation; field-molded sealants and primers (when required by sealant manufacturer); preformed compression seals; and waterstops. Manufacturer's recommended instructions for installing preformed fillers, field-molded sealants; preformed compression seals; and waterstops; and for splicing non-metallic waterstops.

SD-04 Samples

Lubricant for Preformed Compression Seals

Specimens identified to indicate the manufacturer, type of material, size and quantity of material, and shipment or lot represented. Each sample shall be a piece not less than 3 m of 25 mm nominal width or wider seal or a piece not less than 4 m of compression seal less than 25 mm nominal width. Provide one L of lubricant.

Field-Molded Type

Four liters of field-molded sealant and one L of primer (when primer is recommended by the sealant manufacturer) identified to indicate manufacturer, type of material, quantity, and shipment or lot represented.

Non-metallic Materials

Specimens identified to indicate manufacturer, type of material, size, quantity of material, and shipment or lot represented. Each sample shall be a piece not less than 300 mm long cut from each 61 m of finished waterstop furnished, but not less than a total of 1 m of each type, size, and lot furnished. One splice sample of each size and type for every 50 splices made in the factory and every 10 splices made at the job site. The splice samples shall be made using straight run pieces with the splice located at the mid-length of the sample and finished as required for the installed waterstop. The total length of each splice shall be not less than 300 mm long.

SD-07 Certificates

Preformed Expansion Joint Filler
Sealant
Waterstops

Certificates of compliance stating that the joint filler and sealant materials and waterstops conform to the requirements specified.

1.3 DELIVERY, STORAGE, AND HANDLING

Protect material delivered and placed in storage off the ground from moisture, dirt, and other contaminants. Deliver sealants in the manufacturer's original unopened containers. Sealants whose shelf life has expired shall be removed from the site.

PART 2 PRODUCTS

2.1 CONTRACTION JOINT STRIPS

Contraction joint strips shall be 3 mm thick tempered hardboard conforming to AHA A135.4, Class 1. In lieu of hardboard strips, rigid polyvinylchloride (PVC) or high impact polystyrene (HIPS) insert strips specifically designed to induce controlled cracking in slabs on grade may be used. Such insert strips shall have removable top section.

2.2 PREFORMED EXPANSION JOINT FILLER

Expansion joint filler shall be preformed material conforming to ASTM D 1751 or ASTM D 1752. Unless otherwise indicated, filler material shall be 10 mm thick and of a width applicable for the joint formed. Backer material, when required, shall conform to ASTM D 5249.

2.3 SEALS/SEALANT

Joint sealant shall conform to the following:

2.3.1 Preformed Polychloroprene Elastomeric Type

ASTM D 2628.

2.3.2 Lubricant for Preformed Compression Seals

ASTM D 2835.

2.3.3 Field-Molded Type

ASTM C 920, Type M, Grade P or NS, Class 25, Use T for horizontal joints. Type M, Grade NS, Class 25, Use NT for vertical joints. Bond breaker material shall be polyethylene tape, coated paper, metal foil or similar type materials. The back-up material shall be compressible, non-shrink, nonreactive with sealant, and non-absorptive material type such as extruded butyl or polychloroprene rubber.

2.3.4 Hot-Applied Jet-Fuel Resistant Type

ASTM D 7116, Type I

2.4 WATERSTOPS

Intersection and change of direction waterstops shall be shop fabricated.

2.4.1 Flexible Metal

Copper waterstops shall conform to ASTM B 152/B 152M and ASTM B 370, O60 soft anneal temper and 0.686 mm sheet thickness. Stainless steel waterstops shall conform to ASTM A 167 and ASTM A 480/A 480M, UNS S30453 (Type 304L), and 0.9525 mm thick strip.

2.4.2 Rigid Metal

Flat steel waterstops shall conform to ASTM A 109/A 109M, No. 2 (half hard) temper, No. 2 edge, No. 1 (matte or dull) finish or ASTM A 1011/A 1011M, Grade 40.

2.4.3 Non-Metallic Materials`

Non-metallic waterstops shall be manufactured from a prime virgin resin; reclaimed material is not acceptable. The compound shall contain plasticizers, stabilizers, and other additives to meet specified requirements. Rubber waterstops shall conform to COE CRD-C 513. Polyvinylchloride waterstops shall conform to COE CRD-C 572. Thermoplastic elastomeric rubber waterstops shall conform to ASTM D 471.

2.4.4 Non-Metallic Hydrophilic

Swellable strip type compound of polymer modified chloroprene rubber that swells upon contact with water shall conform to ASTM D 412 as follows: Tensile strength 2.9 MPa minimum; ultimate elongation 600 percent minimum. Hardness shall be 50 minimum on the type A durometer and the volumetric expansion ratio in distilled water at 20 degrees C shall be 3 to 1 minimum.

2.4.5 Preformed Elastic Adhesive

Preformed plastic adhesive waterstops shall be produced from blends of refined hydrocarbon resins and plasticizing compounds reinforced with inert mineral filler, and shall contain no solvents, asbestos, irritating fumes or obnoxious odors. The compound shall not depend on oxidizing, evaporating, or chemical action for its adhesive or cohesive strength.

2.4.5.1 Chemical Composition

The chemical composition of the sealing compound shall meet the requirements shown below:

	PERCENT BY WEIGHT		
COMPONENT	MIN.	MAX.	TEST
Bitumen (Hydrocarbon plastic)	50	70	ASTM D 4
Inert Mineral Filler	30	50	AASHTO T 111
Volatile Matter		2	ASTM D 6

2.4.5.2 Adhesion Under Hydrostatic Pressure

The sealing compound shall not leak at the joints for a period of 24 hours under a vertical 2 m head pressure. In a separate test, the sealing compound shall not leak under a horizontal pressure of 65 kPa which is reached by slowly applying increments of 13 kPa every minute.

2.4.5.3 Sag of Flow Resistance

Sagging shall not be detected when tested as follows: Fill a wooden form 25 mm wide and 150 mm long flush with sealing compound and place in an oven at 58 degrees C in a vertical position for 5 days.

2.4.5.4 Chemical Resistance

The sealing compound when immersed separately in a 5% solution of caustic potash, a 5% solution of hydrochloric acid, 5% solution of sulfuric acid and a saturated hydrogen sulfide solution for 30 days at ambient room temperature shall show no visible deterioration.

PART 3 EXECUTION

3.1 JOINTS

Install joints at locations indicated and as authorized.

3.1.1 Contraction Joints

Contraction joints may be constructed by inserting tempered hardboard strips or rigid PVC or HIPS insert strips into the plastic concrete using a steel parting bar, when necessary, or by cutting the concrete with a saw after concrete has set. Joints shall be approximately 3 mm wide and shall extend into the slab one-fourth the slab thickness, minimum, but not less than 25 mm.

3.1.1.1 Sawed Joints

Joint sawing shall be early enough to prevent uncontrolled cracking in the slab, but late enough that this can be accomplished without appreciable spalling. Use concrete sawing machines that are adequate in number and power, and with sufficient replacement blades to complete the sawing at the required rate. Cut joints to true alignment and in sequence of concrete placement. Remove sludge and cutting debris.

3.1.2 Expansion Joints

Use preformed expansion joint filler in expansion and isolation joints in slabs around columns and between slabs on grade and vertical surfaces where indicated. The filler shall extend the full slab depth, unless otherwise indicated. The edges of the joint shall be neatly finished with an edging tool of 3 mm radius, except where a resilient floor surface will be applied. Where the joint is to receive a sealant, the filler strips shall be installed at the proper level below the finished floor with a slightly tapered, dressed and oiled wood strip temporarily secured to the top to form a recess to the size shown on the drawings. The wood strip shall be removed after the concrete has set. Contractor may opt to use a removable expansion filler cap designed and fabricated for this purpose in lieu of the wood strip. The groove shall be thoroughly cleaned of laitance, curing compound, foreign materials, protrusions of hardened concrete, and any dust which shall be blown out of the groove with oil-free compressed air.

3.1.3 Joint Sealant

Sawed contraction joints and expansion joints in slabs shall be filled with joint sealant, unless otherwise shown. Joint surfaces shall be clean, dry, and free of oil or other foreign material which would adversely affect the bond between sealant and concrete. Joint sealant shall be applied as recommended by the manufacturer of the sealant.

3.1.3.1 Joints With Preformed Compression Seals

Install compression seals with equipment capable of installing joint seals

to the prescribed depth without cutting, nicking, twisting, or otherwise distorting or damaging the seal or concrete and with no more than 5 percent stretching of the seal. The sides of the joint and, if necessary, the sides of the compression seal shall be covered with a coating of lubricant. Butt joints shall be coated with liberal applications of lubricant.

3.1.3.2 Joints With Field-Molded Sealant

Joints shall not be sealed when the sealant material, ambient air, or concrete temperature is less than 4 degrees C. When the sealants are meant to reduce the sound transmission characteristics of interior walls, ceilings, and floors the guidance provided in ASTM C 919 shall be followed. Joints requiring a bond breaker shall be coated with curing compound or with bituminous paint. Bond breaker and back-up material shall be installed where required. Joints shall be primed and filled flush with joint sealant in accordance with the manufacturer's recommendations.

3.2 WATERSTOPS, INSTALLATION AND SPLICES

Install waterstops at the locations shown to form a continuous water-tight diaphragm. Make adequate provision to support and completely protect the waterstops during the progress of the work. Any waterstop punctured or damaged shall be repaired or replaced. Protect exposed waterstops during application of form release agents to avoid being coated. Provide suitable guards to protect exposed projecting edges and ends of partially embedded waterstops from damage when concrete placement has been discontinued. Splices shall be made by certified trained personnel using approved equipment and procedures.

3.2.1 Copper And Stainless Steel

Splices in copper waterstops shall be lap joints made by brazing. Splices in stainless steel waterstops shall be welded using a TIG or MIG process utilizing a weld rod to match the stainless. All welds shall not be annealed to maintain physical properties. Carbon flame shall not be used in the annealing process. Damaged waterstops shall be repaired by removing damaged portions and patching. Patches shall overlap a minimum of 25 mm onto undamaged portion of the waterstop.

3.2.2 Flat Steel

Splices in flat steel waterstops shall be properly aligned, butt welded, and cleaned of excessive material.

3.2.3 Non-Metallic

Fittings shall be shop made using a machine specifically designed to mechanically weld the waterstop. A miter guide, proper fixturing (profile dependant), and portable power saw shall be used to miter cut the ends to be joined to ensure good alignment and contact between joined surfaces. The splicing of straight lengths shall be done by squaring the ends to be joined. Continuity of the characteristic features of the cross section of the waterstop (ribs, tabular center axis, protrusions, etc.) shall be maintained across the splice.

3.2.3.1 Rubber Waterstop

Splices shall be vulcanized or shall be made using cold bond adhesive as

recommended by the manufacturer. Splices for TPE-R shall be as specified for PVC.

3.2.3.2 Polyvinyl Chloride Waterstop

Make splices by heat sealing the adjacent waterstop edges together using a thermoplastic splicing iron utilizing a non-stick surface specifically designed for waterstop welding. The correct temperature shall be used to sufficiently melt without charring the plastic. The spliced area, when cooled, shall show no signs of separation, holes, or other imperfections when bent by hand in as sharp an angle as possible.

3.2.3.3 Quality Assurance

Edge welding will not be permitted. Centerbulbs shall be compressed or closed when welding to non-centerbulb type. Waterstop splicing defects which are unacceptable include, but are not limited to the following: 1) Tensile strength less than 80 percent of parent section. 2) Free lap joints. 3) Misalignment of centerbulb, ribs, and end bulbs greater than 2 mm. 4) Misalignment which reduces waterstop cross section more than 15 percent. 5) Bond failure at joint deeper than 2 mm or 15 percent of material thickness. 6) Misalignment of waterstop splice resulting in misalignment of waterstop in excess of 13 mm in 3 m. 7) Visible porosity in the weld area, including pin holes. 8) Charred or burnt material. 9) Bubbles or inadequate bonding. 10) Visible signs of splice separation when cooled splice is bent by hand at a sharp angle.

3.2.4 Non-Metallic Hydrophilic Waterstop Installation

Ends to be joined shall be miter cut with sharp knife or shears. The ends shall be adhered with cyanacryiate (super glue) adhesive. When joining hydrophilic type waterstop to PVC waterstop, the hydrophilic waterstop shall be positioned as shown on the drawings. A liberal amount of a single component hydrophilic sealant shall be applied to the junction to complete the transition.

3.2.5 Preformed Plastic Adhesive Installation

The installation of preformed plastic adhesive waterstops shall be a prime, peel, place and pour procedure. Joint surfaces shall be clean and dry before priming and just prior to placing the sealing strips. The end of each strip shall be spliced to the next strip with a 25 mm overlap; the overlap shall be pressed firmly to release trapped air. During damp or cold conditions the joint surface shall be flashed with a safe, direct flame to warm and dry the surface adequately; the sealing strips shall be dipped in warm water to soften the material to achieve maximum bond to the concrete surface.

3.3 CONSTRUCTION JOINTS

Construction joints are specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE except that construction joints coinciding with expansion and contraction joints shall be treated as expansion or contraction joints as applicable.

-- End of Section --

SECTION 03 20 01.00 10

CONCRETE REINFORCEMENT
10/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 318M	(2008; Errata 2008; Errata 2009) Metric Building Code Requirements for Structural Concrete and Commentary

ASTM INTERNATIONAL (ASTM)

ASTM A 184/A 184M	(2006) Standard Specification for Fabricated Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A 185/A 185M	(2007) Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete
ASTM A 615/A 615M	(2009) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A 884/A 884M	(2006) Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

CRSI 10MSP	(2001; 27Ed) Manual of Standard Practice

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Reinforcement; G

Detail drawings showing reinforcing steel placement, schedules, sizes, grades, and splicing and bending details. Drawings shall show support details including types, sizes and spacing.

SD-07 Certificates

Reinforcing Steel

Certified copies of mill reports attesting that the reinforcing steel furnished contains no less than 25 percent recycled scrap steel and meets the requirements specified herein, prior to the installation of reinforcing steel.

1.3 DELIVERY, STORAGE, AND HANDLING

Reinforcement and accessories shall be stored off the ground on platforms, skids, or other supports.

PART 2 PRODUCTS

2.1 DOWELS

Dowels shall match the size and number of main reinforcement unless indicated otherwise.

2.2 FABRICATED BAR MATS

Fabricated bar mats shall conform to ASTM A 184/A 184M.

2.3 REINFORCING STEEL

Reinforcing steel shall be deformed bars conforming to ASTM A 615/A 615M , grades and sizes as indicated.

2.4 WELDED WIRE FABRIC

Welded wire fabric shall conform to ASTM A 185/A 185M. When directed by the Contracting Officer for special applications, welded wire fabric shall conform to ASTM A 884/A 884M.

2.5 WIRE TIES

Wire ties shall be 16 gauge or heavier black annealed steel wire.

2.6 SUPPORTS

Bar supports for formed surfaces shall be designed and fabricated in accordance with CRSI 10MSP and shall be steel or precast concrete blocks. Precast concrete blocks shall have wire ties and shall be not less than 100 by 100 mm when supporting reinforcement on ground. Precast concrete block shall have compressive strength equal to that of the surrounding concrete. Where concrete formed surfaces will be exposed to weather or where surfaces are to be painted, steel supports within 13 mm of concrete surface shall be galvanized, plastic protected or of stainless steel. Concrete supports used in concrete exposed to view shall have the same color and texture as the finish surface. For slabs on grade, supports shall be precast concrete blocks or plastic coated steel fabricated with bearing plates.

PART 3 EXECUTION

3.1 REINFORCEMENT

Reinforcement shall be fabricated to shapes and dimensions shown and shall

conform to the requirements of ACI 318M. Reinforcement shall be cold bent unless otherwise authorized. Bending may be accomplished in the field or at the mill. Bars shall not be bent after embedment in concrete. Safety caps shall be placed on all exposed ends of vertical concrete reinforcement bars that pose a danger to life safety. Wire tie ends shall face away from the forms.

3.1.1 Placement

Reinforcement shall be free from loose rust and scale, dirt, oil, or other deleterious coating that could reduce bond with the concrete. Reinforcement shall be placed in accordance with ACI 318M at locations shown plus or minus one bar diameter. Reinforcement shall not be continuous through expansion joints and shall be as indicated through construction or contraction joints. Concrete coverage shall be as indicated or as required by ACI 318M. If bars are moved more than one bar diameter to avoid interference with other reinforcement, conduits or embedded items, the resulting arrangement of bars, including additional bars required to meet structural requirements, shall be approved before concrete is placed.

3.1.2 Splicing

Splices of reinforcement shall conform to ACI 318M and shall be made only as required or indicated. Splicing shall be by lapping or by mechanical connection; except that lap splices shall not be used for bars larger than No. 11 unless otherwise indicated. Lapped bars shall be placed in contact and securely tied or spaced transversely apart to permit the embedment of the entire surface of each bar in concrete. Lapped bars shall not be spaced farther apart than one-fifth the required length of lap or 150 mm. Mechanical butt splices shall be in accordance with the recommendation of the manufacturer of the mechanical splicing device. Butt splices shall develop 125 percent of the specified minimum yield tensile strength of the spliced bars or of the smaller bar in transition splices. Bars shall be flame dried before butt splicing. Adequate jigs and clamps or other devices shall be provided to support, align, and hold the longitudinal centerline of the bars to be butt spliced in a straight line.

3.2 WELDED-WIRE FABRIC PLACEMENT

Welded-wire fabric shall be placed in slabs as indicated. Fabric placed in slabs on grade shall be continuous between expansion, construction, and contraction joints. Fabric placement at joints shall be as indicated. Lap splices shall be made in such a way that the overlapped area equals the distance between the outermost crosswires plus 50 mm. Laps shall be staggered to avoid continuous laps in either direction. Fabric shall be wired or clipped together at laps at intervals not to exceed 1.2 m. Fabric shall be positioned by the use of supports.

3.3 DOWEL INSTALLATION

Dowels shall be installed in slabs on grade at locations indicated and at right angles to joint being doweled. Dowels shall be accurately positioned and aligned parallel to the finished concrete surface before concrete placement. Dowels shall be rigidly supported during concrete placement. One end of dowels shall be coated with a bond breaker.

-- End of Section --

SECTION 03 31 00.00 10

CAST-IN-PLACE STRUCTURAL CONCRETE
11/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 117	(2006) Standard Specifications for Tolerances for Concrete Construction and Materials
ACI 211.1	(1991; R 2009) Standard Practice for Selecting Proportions for Normal, Heavyweight, and Mass Concrete
ACI 214R	(2002) Recommended Practice for Evaluation of Strength Test Results of Concrete
ACI 305R	(1999; Errata 2006) Hot Weather Concreting
ACI 318M	(2008; Errata 2008; Errata 2009) Metric Building Code Requirements for Structural Concrete and Commentary

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 182	(2005) Standard Specification for Burlap Cloth Made from Jute or Kenaf and Cotton Mats

ASTM INTERNATIONAL (ASTM)

ASTM C 1017/C 1017M	(2007) Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C 1059/C 1059M	(1999; R 2008) Standard Specification for Latex Agents for Bonding Fresh to Hardened Concrete
ASTM C 1064/C 1064M	(2008) Standard Test Method for Temperature of Freshly Mixed Hydraulic-Cement Concrete
ASTM C 1077	(2009b) Standard Practice for Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation

ASTM C 1107/C 1107M	(2008) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM C 1260	(2007) Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C 143/C 143M	(2009) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C 150/C 150M	(2009) Standard Specification for Portland Cement
ASTM C 1567	(2008) Standard Test Method for Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C 171	(2007) Standard Specification for Sheet Materials for Curing Concrete
ASTM C 172	(2008) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C 173/C 173M	(2009) Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method
ASTM C 192/C 192M	(2007) Standard Practice for Making and Curing Concrete Test Specimens in the Laboratory
ASTM C 231	(2009a) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C 260	(2006) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C 309	(2007) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C 31/C 31M	(2009) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C 33/C 33M	(2008) Standard Specification for Concrete Aggregates
ASTM C 39/C 39M	(2005e1e2) Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C 42/C 42M	(2004) Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams

	of Concrete
ASTM C 494/C 494M	(2008a) Standard Specification for Chemical Admixtures for Concrete
ASTM C 618	(2008a) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C 78	(2009) Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C 881/C 881M	(2002) Standard Specification for Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C 937	(2002) Grout Fluidifier for Preplaced-Aggregate Concrete
ASTM C 94/C 94M	(2009) Standard Specification for Ready-Mixed Concrete
ASTM D 1751	(2004; R 2008) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D 75/D 75M	(2009) Standard Practice for Sampling Aggregates
ASTM E 96/E 96M	(2005) Standard Test Methods for Water Vapor Transmission of Materials

NATIONAL READY MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA QC 3	(2002) Quality Control Manual: Section 3, Plant Certifications Checklist: Certification of Ready Mixed Concrete Production Facilities
NRMCA TMMB 100	(2001) Truck Mixer, Agitator and Front Discharge Concrete Carrier Standards

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 104	(1980) Method of Calculation of the Fineness Modulus of Aggregate
COE CRD-C 400	(1963) Requirements for Water for Use in Mixing or Curing Concrete
COE CRD-C 521	(1981) Standard Test Method for Frequency and Amplitude of Vibrators for Concrete
COE CRD-C 540	(2001) Standard Specification for Nonbituminous Inserts for Contraction Joints in Portland Cement Concrete

	Airfield Pavements, Sawable Type
COE CRD-C 572	(1974) Specifications for Polyvinylchloride Waterstops
COE CRD-C 94	(1995) Specification for Surface Retarders

1.2 SYSTEM DESCRIPTION

Provide concrete composed of portland cement, other cementitious and pozzolanic materials as specified, aggregates, water and admixtures as specified.

1.2.1 Proportioning Studies-Normal Weight Conc

Trial design batches, mixture proportions studies, and testing requirements for various classes and types of concrete specified are the responsibility of the Contractor. Mixture proportions shall be based on compressive strength as determined by test specimens fabricated in accordance with ASTM C 192/C 192M and tested in accordance with ASTM C 39/C 39M.

a. Samples of all materials used in mixture proportioning studies shall be representative of those proposed for use in the project and be accompanied by the manufacturer's or producer's test reports indicating compliance with these specifications.

b. Make trial mixtures having proportions, consistencies, and air content suitable for the work based on methodology described in ACI 211.1, using at least three different water-cement ratios for each type of mixture, which will produce a range of strength encompassing those required for each class and type of concrete required on the project.

c. The maximum water-cement ratios required in subparagraph Water-Cement Ratio below will be the equivalent water-cement ratio as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag (GGBF slag) by the weight equivalency method as described in ACI 211.1. In the case where silica fume or GGBF slag is used, the weight of the silica fume and GGBF slag shall be included in the equations in ACI 211.1 for the term P, which is used to denote the weight of pozzolan. If pozzolan is used in the concrete mixture, the minimum pozzolan content shall be 15 percent by weight of the total cementitious material, and the maximum shall be 35 percent.

d. Design laboratory trial mixtures for maximum permitted slump and air content. Make separate sets of trial mixture studies for each combination of cementitious materials and each combination of admixtures proposed for use. No combination of either shall be used until proven by such studies, except that, if approved in writing and otherwise permitted by these specifications, an accelerator or a retarder may be used without separate trial mixture study. Separate trial mixture studies shall also be made for concrete for any conveying or placing method proposed which requires special properties and for concrete to be placed in unusually difficult placing locations.

e. Report the temperature of concrete in each trial batch. For each water-cement ratio, at least three test cylinders for each test age shall be made, cured in accordance with ASTM C 192/C 192M and tested at

7 and 28 days in accordance with ASTM C 39/C 39M. From these test results, plot a curve showing the relationship between water-cement ratio and strength for each set of trial mix studies. In addition, a curve shall be plotted showing the relationship between 7 day and 28 day strengths. Design each mixture to promote easy and suitable concrete placement, consolidation and finishing, and to prevent segregation and excessive bleeding.

1.2.2 Average Compressive Strength

The mixture proportions selected during mixture design studies shall produce a required average compressive strength (f'cr) exceeding the specified compressive strength (f'c) by the amount indicated below. This required average compressive strength, f'cr, will not be a required acceptance criteria during concrete production. However, whenever the daily average compressive strength at 28 days drops below f'cr during concrete production, or daily average 7-day strength drops below a strength correlated with the 28-day f'cr, adjust the mixture, as approved, to bring the daily average back up to f'cr. During production, the required f'cr shall be adjusted, as appropriate, based on the standard deviation being attained on the job.

1.2.3 Computations from Test Records

Where a concrete production facility has test records, establish a standard deviation in accordance with the applicable provisions of ACI 214R. Test records from which a standard deviation is calculated shall represent materials, quality control procedures, and conditions similar to those expected; shall represent concrete produced to meet a specified strength or strengths (f'c) within 7 MPa of that specified for proposed work; and shall consist of at least 30 consecutive tests. A strength test shall be the average of the strengths of two cylinders made from the same sample of concrete and tested at 28 days. Required average compressive strength f'cr used as the basis for selection of concrete proportions shall be the larger of the equations that follow using the standard deviation as determined above:

f'cr = f'c + 1.34S where units are in MPa

f'cr = f'c + 2.33S - 3.45 where units are in MPa

Where S = standard deviation

Where a concrete production facility does not have test records meeting the requirements above but does have a record based on 15 to 29 consecutive tests, a standard deviation shall be established as the product of the calculated standard deviation and a modification factor from the following table:

NUMBER OF TESTS	MODIFICATION FACTOR FOR STANDARD DEVIATION
15	1.16
20	1.08
25	1.03
30 or more	1.00

1.2.4 Computations without Previous Test Records

When a concrete production facility does not have sufficient field strength test records for calculation of the standard deviation, the required average strength f'cr shall be determined as follows:

a. If the specified compressive strength f'c is less than 20 MPa,

f'cr = f'c + 6.9 MPa

b. If the specified compressive strength f'c is 20 to 35 MPa,

f'cr = f'c + 8.3 MPa

c. If the specified compressive strength f'c is over 35 MPa,

f'cr = f'c + 9.7 MPa

1.2.5 Tolerances

Except as otherwise specified herein, tolerances for concrete batching, mixture properties, and construction as well as definition of terms and application practices shall be in accordance with ACI 117. Take level and grade tolerance measurements of slabs as soon as possible after finishing; when forms or shoring are used, the measurements shall be made prior to removal.

1.2.6 Floor Finish

For the purpose of this Section the following terminology correlation between ACI 117 and this Section shall apply:

Floor Profile Quality Classification From ACI 117	This Section
Conventional Bullfloated	Same
Conventional Straightedged	Same
Flat	Float Finish or Trowel Finish

Levelness tolerance shall not apply where design requires floors to be sloped to drains or sloped for other reasons.

1.2.6.1 Floors by the Straightedge System

The flatness of the floors shall be carefully controlled and the tolerances shall be measured by the straightedge system as specified in paragraph 4.5.7 of ACI 117, using a 3 m straightedge, within 72 hours after floor slab installation and before shores and/or forms are removed. The listed tolerances shall be met at any and every location at which the straightedge can be placed.

Float Finish Latrines, Laundry, POL, DFAC (Preparation Area) Trowel Finish HQ, Administration Buildings, Classroom Buildings, DFCA (Dining Area), PX/Finance Building.

1.2.7 Strength Requirements

Specified compressive strength (f'c) shall be as follows:

COMPRESSIVE STRENGTH	STRUCTURE OR PORTION OF STRUCTURE
28 MPa at 28 days	All

Concrete slabs on-grade shall have a 28-day flexural strength of 28 MPa. Concrete made with high-early strength cement shall have a 7-day strength equal to the specified 28-day strength for concrete made with Type I or II portland cement. Compressive strength shall be determined in accordance with ASTM C 39/C 39M. Flexural strength shall be determined in accordance with ASTM C 78.

a. Evaluation of Concrete Compressive Strength. Fabricate compressive strength specimens (152 by 305 mm cylinders), laboratory cure them in accordance with ASTM C 31/C 31M and test them in accordance with ASTM C 39/C 39M. The strength of the concrete will be considered satisfactory so long as the average of all sets of three consecutive test results equals or exceeds the specified compressive strength f'c and no individual test result falls below the specified strength f'c by more than 3.5 MPa. A "test" is defined as the average of two companion cylinders, or if only one cylinder is tested, the results of the single cylinder test. Additional analysis or testing, including taking cores and/or load tests may be required at the Contractor's expense when the strength of the concrete in the structure is considered potentially deficient.

b. Investigation of Low-Strength Compressive Test Results. When any strength test of standard-cured test cylinders falls below the specified strength requirement by more than 3.5 MPa or if tests of field-cured cylinders indicate deficiencies in protection and curing, take steps to assure that the load-carrying capacity of the structure is not jeopardized. When the strength of concrete in place is considered potentially deficient, cores shall be obtained and tested in accordance with ASTM C 42/C 42M. At least three representative cores shall be taken from each member or area of concrete in place that is considered potentially deficient. The location of cores will be determined by the Contracting Officer to least impair the strength of the structure. Concrete in the area represented by the core testing will be considered adequate if the average strength of the cores is equal to at least 85 percent of the specified strength requirement and if no single core is less than 75 percent of the specified strength requirement. Non-destructive tests (tests other than test cylinders or cores) shall not be used as a basis for acceptance or rejection. Perform the coring and repair the holes; cores will be tested by the Government.

c. Load Tests. If the core tests are inconclusive or impractical to obtain or if structural analysis does not confirm the safety of the structure, load tests may be directed by the Contracting Officer in accordance with the requirements of ACI 318M. Concrete work evaluated by structural analysis or by results of a load test as being understrength shall be corrected in a manner satisfactory to the Contracting Officer. All investigations, testing, load tests, and correction of deficiencies shall be performed by and at the expense of the Contractor and approved by the Contracting Officer, except that if all concrete is found to be in compliance with the drawings and specifications, the cost of investigations,

testing, and load tests will be at the expense of the Government.

1.2.8 Water-Cement Ratio

Maximum water-cement ratio (w/c) for normal weight concrete shall be as follows:

WATER-CEMENT RATIO, BY WEIGHT	STRUCTURE OR PORTION OF STRUCTURE
0.45	All

These w/c's may cause higher strengths than that required above for compressive or flexural strength. The maximum w/c required will be the equivalent w/c as determined by conversion from the weight ratio of water to cement plus pozzolan, silica fume, and ground granulated blast furnace slag (GGBF slag) by the weight equivalency method as described in ACI 211.1. In the case where silica fume or GGBF slag is used, the weight of the silica fume and GGBF slag shall be included in the equations of ACI 211.1 for the term P which is used to denote the weight of pozzolan.

1.2.9 Air Entrainment

All normal weight concrete shall be air entrained to contain between 4 and 7 percent total air, except that when the nominal maximum size coarse aggregate is 19 mm or smaller it shall be between 4.5 and 7.5 percent. Concrete with specified strength over 35 MPa may have 1.0 percent less air than specified above. Specified air content shall be attained at point of placement into the forms. Air content for normal weight concrete shall be determined in accordance with ASTM C 231.

1.2.10 Slump

Slump of the concrete, as delivered to the point of placement into the forms, shall be within the following limits. Slump shall be determined in accordance with ASTM C 143/C 143M.

Structural Element	Slump Minimum	Slump Maximum
Walls, columns and beams	50 mm	100 mm
Foundation walls, substructure walls, footings, slabs	25 mm	75 mm
Any structural concrete approved for placement by pumping:		
At pump	50 mm	150 mm
At discharge of line	25 mm	100 mm

When use of a plasticizing admixture conforming to ASTM C 1017/C 1017M or when a Type F or G high range water reducing admixture conforming to ASTM C 494/C 494M is permitted to increase the slump of concrete, concrete shall have a slump of 50 to 100 mm before the admixture is added and a maximum slump of 200 mm at the point of delivery after the admixture is added.

1.2.11 Concrete Temperature

The temperature of the concrete as delivered shall not exceed 32 degrees C. When the ambient temperature during placing is 5 degrees C or less, or is expected to be at any time within 6 hours after placing, the temperature of the concrete as delivered shall be between 12 and 25 degrees C.

1.2.12 Size of Coarse Aggregate

Use the largest feasible nominal maximum size aggregate (NMSA), specified in paragraph AGGREGATES PART 2, in each placement. However, nominal maximum size of aggregate shall not exceed any of the following: three-fourths of the minimum cover for reinforcing bars, three-fourths of the minimum clear spacing between reinforcing bars, one-fifth of the narrowest dimension between sides of forms, or one-third of the thickness of slabs or toppings.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Curing Materials
Joint fillers
Recycled Content Products
Portland Cement
Ready-Mixed Concrete
Vapor Barrier
Latex Bonding Agent
Floor Finish
Waterstops
Chemical Admixtures
Epoxy-Resin

Manufacturer's product data, indicating VOC content. Manufacturer's catalog data for the items above, including printed instructions. Products included in other referenced Section (Ex: 07 92 00 JOINT SEALANTS) shall follow the submittals requirements for that Section.

SD-04 Samples

Surface Retarder

Sample of surface retarder material with manufacturer's instructions for application in conjunction with air-water cutting.

SD-05 Design Data

Mixture Proportions; G

The results of trial mixture design studies along with a statement giving the maximum nominal coarse aggregate size and the proportions of ingredients that will be used in the manufacture of

each strength or class of concrete, at least 14 days prior to commencing concrete placing operations. Aggregate weights shall be based on the saturated surface dry condition. Accompany the statement with test results from an approved independent commercial testing laboratory, showing that mixture design studies have been made with materials proposed for the project and that the proportions selected will produce concrete of the qualities indicated. No substitutions shall be made in the materials used in the mixture design studies without additional tests to show that the quality of the concrete is satisfactory.

SD-06 Test Reports

Testing and Inspection for CQC

Certified copies of laboratory test reports, including mill tests and all other test data, for portland cement, blended cement, pozzolan, ground granulated blast furnace slag, silica fume, aggregate, admixtures, and curing compound proposed for use on this project.

SD-07 Certificates

Qualifications

Written documentation for Contractor Quality Control personnel.

1.4 QUALITY ASSURANCE

Submit qualifications for Contractor Quality Control personnel assigned to concrete construction as American Concrete Institute (ACI) Certified Workmen in one of the following grades or show written evidence of having completed similar qualification programs:

Concrete Field Testing Technician, Grade I
Concrete Laboratory Testing Technician, Grade I or II
Concrete Construction Inspector, Level II

Concrete Transportation Construction Inspector or Reinforced Concrete Special Inspector, Jointly certified by American Concrete Institute (ACI), Building Official and Code Administrators International (BOCA), International Code Council (ICC), and Southern Building Code Congress International (SBCCI).

The foreman or lead journeyman of the flatwork finishing crew shall have similar qualification for ACI Concrete Flatwork Technician/Finisher or equal, with written documentation.

1.4.1 Field Test Panels

Construct field test panels prior to beginning of work using the materials and procedures proposed for use on the job, to demonstrate the results to be attained. The quality and appearance of each panel shall be subject to the approval of the Contracting Officer, and, if not judged satisfactory, construct additional panels until approval is attained. Formed or finished surfaces in the completed structure shall match the quality and appearance of the approved field example.

1.4.1.1 Sample Wall Panels

One sample panel at least 1220 mm by 1525 mm and 150 mm thick shall be constructed to demonstrate Class A formed finish and a similar one for Class B formed finish. Panels shall be located as per Contracting Officer's directions. Each panel shall include a full length and full width joint line and shall have at least two voids each at least 300 mm by 300 mm by 75 mm deep either impressed in the concrete as placed or chipped in the hardened concrete. After the concrete is 7 days old, the voids shall be patched to demonstrate the effectiveness and the appearance of the Contractor's repair procedures.

1.4.2 Special Properties and Products

Concrete may contain admixtures other than air entraining agents, such as water reducers, superplasticizers, or set retarding agents to provide special properties to the concrete, if specified or approved. Any of these materials to be used on the project shall be used in the mix design studies.

1.4.3 Government Assurance Inspection and Testing

Day-to day inspection and testing shall be the responsibility of the Contractor Quality Control (CQC) staff. However, representatives of the Contracting Officer can and will inspect construction as considered appropriate and will monitor operations of the Contractor's CQC staff. Government inspection or testing will not relieve the Contractor of any CQC responsibilities.

1.4.3.1 Materials

The Government will sample and test aggregates, cementitious materials, other materials, and concrete to determine compliance with the specifications as considered appropriate. Provide facilities and labor as may be necessary for procurement of representative test samples. Samples of aggregates will be obtained at the point of batching in accordance with ASTM D 75/D 75M. Other materials will be sampled from storage at the jobsite or from other locations as considered appropriate. Samples may be placed in storage for later testing when appropriate.

1.4.3.2 Fresh Concrete

Fresh concrete will be sampled as delivered in accordance with ASTM C 172 and tested in accordance with these specifications, as considered necessary.

1.4.3.3 Hardened Concrete

Tests on hardened concrete will be performed by the Government when such tests are considered necessary.

1.4.3.4 Inspection

Concrete operations may be tested and inspected by the Government as the project progresses. Failure to detect defective work or material will not prevent rejection later when a defect is discovered nor will it obligate the Government for final acceptance.

1.5 DELIVERY, STORAGE, AND HANDLING

Store cement and other cementitious materials in weathertight buildings, bins, or silos which will exclude moisture and contaminants and keep each material completely separated. Aggregate stockpiles shall be arranged and used in a manner to avoid excessive segregation and to prevent contamination with other materials or with other sizes of aggregates. Aggregate shall not be stored directly on ground unless a sacrificial layer is left undisturbed. Store reinforcing bars and accessories above the ground on platforms, skids or other supports. Other materials shall be stored in such a manner as to avoid contamination and deterioration. Admixtures which have been in storage at the project site for longer than 6 months or which have been subjected to freezing shall not be used unless retested and proven to meet the specified requirements. Materials shall be capable of being accurately identified after bundles or containers are opened.

PART 2 PRODUCTS

2.1 CEMENTITIOUS MATERIALS

Cementitious Materials shall be portland cement, portland-pozzolan cement or portland cement in combination with pozzolan conforming to appropriate specifications listed below. Restrict usage of cementitious materials in concrete that will have surfaces exposed in the completed structure so there is no change in color, source, or type of cementitious material.

2.1.1 Portland Cement

ASTM C 150/C 150M, Type I, IA low alkali with a maximum 15 percent amount of tricalcium aluminate, or Type II, IIA low alkali. White portland cement shall meet the above requirements except that it may be Type I, Type IA, Type II or Type IIA low alkali.

2.1.2 Pozzolan (Fly Ash)

Pozzolan shall conform to ASTM C 618, Class C or F, including low alkali multiple factor, drying shrinkage, uniformity, and moderate sulfate resistance requirements in Table 3 of ASTM C 618. If pozzolan is used, it shall never be less than 15 percent nor more than 35 percent by weight of the total cementitious material.

2.2 AGGREGATES

Fine and coarse aggregates shall "be tested and evaluated for alkali-aggregate reactivity in accordance with ASTM C 1260. The fine and coarse aggregates shall be evaluated separately and in combination, which matches the Contractor's proposed mix design proportioning. All results of the separate and combination testing shall have a measured expansion less than 0.10 (0.08) percent at 16 days after casting. Should the test data indicate an expansion of 0.10 (0.08) percent or greater, the aggregate(s) shall be rejected or additional testing using ASTM C 1260 and ASTM C 1567 shall be performed. The additional testing using ASTM C 1260 and ASTM C 1567 shall be performed using the low alkali portland cement in combination with ground granulated blast furnace (GGBF) slag, or Class F fly ash. GGBF slag shall be used in the range of 40 to 50 percent of the total cementitious material by mass. Class F fly ash shall be used in the range of 25 to 40 percent of the total cementitious material by mass."

2.2.1 Fine Aggregate

Fine aggregate shall conform to the quality and gradation requirements of ASTM C 33/C 33M.

2.2.2 Coarse Aggregate

Coarse aggregate shall conform to ASTM C 33/C 33M, Class 5S, size designation 467 (reinforced slabs on ground) or 67 (reinforced walls, columns, beams and other formed sections.

2.3 CHEMICAL ADMIXTURES

Chemical admixtures, when required or permitted, shall conform to the appropriate specification listed. Admixtures shall be furnished in liquid form and of suitable concentration for easy, accurate control of dispensing.

2.3.1 Air-Entraining Admixture

ASTM C 260 and shall consistently entrain the air content in the specified ranges under field conditions.

2.3.2 Accelerating Admixture

ASTM C 494/C 494M, Type C or E, except that calcium chloride or admixtures containing calcium chloride shall not be used.

2.3.3 Water-Reducing or Retarding Admixture

ASTM C 494/C 494M, Type A, B, or D, except that the 6-month and 1-year compressive and flexural strength tests are waived.

2.3.4 High-Range Water Reducer

ASTM C 494/C 494M, Type F or G, except that the 6-month and 1-year strength requirements are waived. The admixture shall be used only when approved in writing, such approval being contingent upon particular mixture control as described in the Contractor's Quality Control Plan and upon performance of separate mixture design studies.

2.3.5 Surface Retarder

COE CRD-C 94.

2.3.6 Expanding Admixture

Aluminum powder type expanding admixture conforming to ASTM C 937.

2.3.7 Other Chemical Admixtures

Chemical admixtures for use in producing flowing concrete shall comply with ASTM C 1017/C 1017M, Type I or II. These admixtures shall be used only when approved in writing, such approval being contingent upon particular mixture control as described in the Contractor's Quality Control Plan and upon performance of separate mixture design studies.

2.4 CURING MATERIALS

2.4.1 Impervious-Sheet

Impervious-sheet materials shall conform to ASTM C 171, type optional, except, that polyethylene sheet shall not be used.

2.4.2 Membrane-Forming Compound

Membrane-Forming curing compound shall conform to ASTM C 309, Type 1-D or 2, except that only a styrene acrylate or chlorinated rubber compound meeting Class B requirements shall be used for surfaces that are to be painted or are to receive bituminous roofing, or waterproofing, or floors that are to receive adhesive applications of resilient flooring. The curing compound selected shall be compatible with any subsequent paint, roofing, waterproofing, or flooring specified. Nonpigmented compound shall contain a fugitive dye, and shall have the reflective requirements in ASTM C 309 waived.

2.4.3 Burlap and Cotton Mat

Burlap and cotton mat used for curing shall conform to AASHTO M 182.

2.5 WATER

Water for mixing and curing shall be fresh, clean, potable, and free of injurious amounts of oil, acid, salt, or alkali, except that non-potable water may be used if it meets the requirements of COE CRD-C 400.

2.6 NONSHRINK GROUT

Nonshrink grout shall conform to ASTM C 1107/C 1107M, and shall be a commercial formulation suitable for the proposed application.

2.7 LATEX BONDING AGENT

Latex agents for bonding fresh to hardened concrete shall conform to ASTM C 1059/C 1059M.

2.8 EPOXY RESIN

Epoxy resins for use in repairs shall conform to ASTM C 881/C 881M, Type V, Grade 2. Class as appropriate to the existing ambient and surface temperatures.

2.9 EMBEDDED ITEMS

Embedded items shall be of the size and type indicated or as needed for the application. Dovetail slots shall be galvanized steel. Inserts for shelf angles and bolt hangers shall be of malleable iron or cast or wrought steel.

2.10 VAPOR BARRIER

Vapor barrier shall be polyethylene sheeting with a minimum thickness of 0.25 mm or other equivalent material having a vapor permeance rating not exceeding 30 nanograms per Pascal per second per square meter as determined in accordance with ASTM E 96/E 96M.

2.11 JOINT MATERIALS

2.11.1 Joint Fillers, Sealers, and Waterstops

Expansion joint fillers shall be preformed materials conforming to ASTM D 1751. Materials for waterstops shall be in accordance with Section 03 15 13.00 10 EXPANSION JOINTS, CONTRACTION JOINTS, AND WATERSTOPS. Materials for and sealing of joints shall conform to the requirements of Section 07 92 00 JOINT SEALANTS.

2.11.2 Contraction Joints in Slabs

Sawable type contraction joint inserts shall conform to COE CRD-C 540. Nonsawable joint inserts shall have sufficient stiffness to permit placement in plastic concrete without undue deviation from a straight line and shall conform to the physical requirements of COE CRD-C 540, with the exception of Section 3.4 "Resistance to Sawing". Plastic inserts shall be polyvinyl chloride conforming to the materials requirements of COE CRD-C 572.

PART 3 EXECUTION

3.1 PREPARATION FOR PLACING

Before commencing concrete placement, perform the following: Surfaces to receive concrete shall be clean and free from frost, ice, mud, and water. Forms shall be in place, cleaned, coated, and adequately supported, in accordance with Section 03 11 13.00 10 STRUCTURAL CONCRETE FORMWORK. Reinforcing steel shall be in place, cleaned, tied, and adequately supported, in accordance with Section 03 20 01.00 10 CONCRETE REINFORCEMENT. Transporting and conveying equipment shall be in-place, ready for use, clean, and free of hardened concrete and foreign material. Equipment for consolidating concrete shall be at the placing site and in proper working order. Equipment and material for curing and for protecting concrete from weather or mechanical damage shall be at the placing site, in proper working condition and in sufficient amount for the entire placement. When hot, windy conditions during concreting appear probable, equipment and material shall be at the placing site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.1.1 Foundations

3.1.1.1 Concrete on Earth Foundations

Earth (subgrade, base, or subbase courses) surfaces upon which concrete is to be placed shall be clean, damp, and free from debris, frost, ice, and standing or running water. Prior to placement of concrete, the foundation shall be well drained and shall be satisfactorily graded and uniformly compacted.

3.1.1.2 Preparation of Rock

Rock surfaces upon which concrete is to be placed shall be free from oil, standing or running water, ice, mud, drummy rock, coating, debris, and loose, semidetached or unsound fragments. Joints in rock shall be cleaned to a satisfactory depth, as determined by the Contracting Officer, and to firm rock on the sides. Immediately before the concrete is placed, rock surfaces shall be cleaned thoroughly by the use of air-water jets or sandblasting as specified below for Previously Placed Concrete. Keep rock

surfaces continuously moist for at least 24 hours immediately prior to placing concrete thereon. All horizontal and approximately horizontal surfaces shall be covered, immediately before the concrete is placed, with a layer of mortar proportioned similar to that in the concrete mixture. Place concrete before the mortar stiffens.

3.1.2 Vapor Barrier

Provide vapor barrier beneath the interior on-grade concrete floor slabs. Use the greatest widths and lengths practicable to eliminate joints wherever possible. Joints shall be lapped a minimum of 300 mm. Torn, punctured, or damaged vapor barrier material shall be removed and new vapor barrier shall be provided prior to placing concrete. For minor repairs, patches may be made using laps of at least 300 mm. Lapped joints shall be sealed and edges patched with pressure-sensitive adhesive or tape not less than 50 mm wide and compatible with the membrane. Place vapor barrier directly on underlying subgrade, base course, or capillary water barrier, unless it consists of crushed material or large granular material which could puncture the vapor barrier. In this case, a thin layer of approximately 13 mm of fine graded material should be rolled or compacted over the fill before installation of the vapor barrier to reduce the possibility of puncture. Control concrete placement so as to prevent damage to the vapor barrier.

3.1.3 Embedded Items

Before placement of concrete, determine that all embedded items are firmly and securely fastened in place as indicated on the drawings, or required. Conduit and other embedded items shall be clean and free of oil and other foreign matter such as loose coatings or rust, paint, and scale. The embedding of wood in concrete will be permitted only when specifically authorized or directed. Voids in sleeves, inserts, and anchor slots shall be filled temporarily with readily removable materials to prevent the entry of concrete into voids. Welding shall not be performed on embedded metals within 300 mm of the surface of the concrete. Tack welding shall not be performed on or to embedded items.

3.2 CONCRETE PRODUCTION

3.2.1 General Requirements

Concrete shall be furnished from a ready-mixed concrete plant. Ready-mixed concrete shall be batched, mixed, and transported in accordance with ASTM C 94/C 94M, except as otherwise specified. Truck mixers, agitators, and nonagitating transporting units shall comply with NRMCA TMMB 100. Ready-mix plant equipment and facilities shall be certified in accordance with NRMCA QC 3. Approved batch tickets shall be furnished for each load of ready-mixed concrete.

3.3 TRANSPORTING CONCRETE TO PROJECT SITE

Transport concrete to the placing site in truck mixers.

3.4 CONVEYING CONCRETE ONSITE

Convey concrete from mixer or transporting unit to forms as rapidly as possible and within the time interval specified by methods which will prevent segregation or loss of ingredients using following equipment. Conveying equipment shall be cleaned before each placement.

Equipment shall ensure continuous delivery/flow of concrete at delivery end and shall be as approved. If/as necessary, runways for wheeled concrete-conveying equipment shall be provided from concrete delivery point to locations of final deposit. Interior surfaces of concrete conveying equipment shall be free of hardened concrete, debris, water, snow, ice, and other deleterious substances.

3.5 PLACING CONCRETE

Discharge mixed concrete within 1.5 hours or before the mixer drum has revolved 300 revolutions, whichever comes first after the introduction of the mixing water to the cement and aggregates. When the concrete temperature exceeds 30 degrees C, reduce the time to 45 minutes. Place concrete within 15 minutes after it has been discharged from the transporting unit. Concrete shall be handled from mixer or transporting unit to forms in a continuous manner until the approved unit of operation is completed. Provide adequate scaffolding, ramps and walkways so that personnel and equipment are not supported by in-place reinforcement. Placing will not be permitted when the sun, heat, wind, or limitations of facilities prevent proper consolidation, finishing and curing. Provide sufficient placing capacity so that concrete can be kept free of cold joints.

3.5.1 Depositing Concrete

Deposit concrete as close as possible to its final position in the forms, and with no vertical drop greater than 1.5 meters except where suitable equipment is provided to prevent segregation and where specifically authorized. Depositing of the concrete shall be so regulated that it will be effectively consolidated in horizontal layers not more than 300 mm thick, except that all slabs shall be placed in a single lift. Concrete to receive other construction shall be screeded to the proper level. Concrete shall be deposited continuously in one layer or in layers so that fresh concrete is deposited on in-place concrete that is still plastic. Fresh concrete shall not be deposited on concrete that has hardened sufficiently to cause formation of seams or planes of weakness within the section. Concrete that has surface dried, partially hardened, or contains foreign material shall not be used. When temporary spreaders are used in the forms, the spreaders shall be removed as their service becomes unnecessary. Concrete shall not be placed in slabs over columns and walls until concrete in columns and walls has been in-place at least two hours or until the concrete begins to lose its plasticity. Place concrete for beams, girders, brackets, column capitals, haunches, and drop panels at the same time as concrete for adjoining slabs.

3.5.2 Consolidation

Immediately after placing, consolidate each layer of concrete by internal vibrators, except for slabs 100 mm thick or less. The vibrators shall at all times be adequate in effectiveness and number to properly consolidate the concrete; keep a spare vibrator at the jobsite during all concrete placing operations. The vibrators shall have a frequency of not less than 10,000 vibrations per minute, an amplitude of at least 0.6 mm, and the head diameter shall be appropriate for the structural member and the concrete mixture being placed. Insert vibrators vertically at uniform spacing over the area of placement. The distance between insertions shall be approximately 1.5 times the radius of action of the vibrator so that the area being vibrated will overlap the adjacent just-vibrated area by a

reasonable amount. The vibrator shall penetrate rapidly to the bottom of the layer and at least 150 mm into the preceding layer if there is such. Vibrator shall be held stationary until the concrete is consolidated and then vertically withdrawn slowly while operating. Form vibrators shall not be used unless specifically approved and unless forms are constructed to withstand their use. Vibrators shall not be used to move concrete within the forms. Slabs 100 mm and less in thickness shall be consolidated by properly designed vibrating screeds or other approved technique. Frequency and amplitude of vibrators shall be determined in accordance with COE CRD-C 521. Grate tampers ("jitterbugs") shall not be used.

3.5.3 Cold Weather Requirements

Submit a cold weather concreting plan if concrete is to be placed during winter months. Use special protection measures, approved by the Contracting Officer including ACI 306 Cold Weather Concreting requirements, if freezing temperatures are anticipated before the expiration of the specified curing period. The ambient temperature of the air where concrete is to be placed and the temperature of surfaces to receive concrete shall be not less than 5 degrees C. The temperature of the concrete when placed shall be not less than 10 degrees C nor more than 25 degrees C. Heating of the mixing water or aggregates will be required to regulate the concrete placing temperature. Materials entering the mixer shall be free from ice, snow, or frozen lumps. Salt, chemicals or other materials shall not be incorporated in the concrete to prevent freezing. Upon written approval, an accelerating admixture conforming to ASTM C 494/C 494M, Type C or E may be used, provided it contains no calcium chloride. Calcium chloride shall not be used.

3.5.4 Hot Weather Requirements

When the ambient temperature during concrete placing is expected to exceed 30 degrees C, the concrete shall be placed and finished with procedures previously submitted and as specified herein. The concrete temperature at time of delivery to the forms shall not exceed the temperature shown in the table below when measured in accordance with ASTM C 1064/C 1064M. Cooling of the mixing water or aggregates or placing concrete in the cooler part of the day may be required to obtain an adequate placing temperature. A retarder may be used, as approved, to facilitate placing and finishing. Steel forms and reinforcements shall be cooled as approved prior to concrete placement when steel temperatures are greater than 49 degrees C. Conveying and placing equipment shall be cooled if necessary to maintain proper concrete-placing temperature.

Maximum Allowable Concrete Placing Temperature

Relative Humidity, Percent, During Time of Concrete Placement	Maximum Allowable Concrete Temperature Degrees
Greater than 60	33 C
40-60	30 C
Less than 40	27 C

3.5.5 Prevention of Plastic Shrinkage Cracking

During hot weather with low humidity, and particularly with appreciable wind, as well as interior placements when space heaters produce low humidity, the Contractor shall be alert to the tendency for plastic

shrinkage cracks to develop and shall institute measures to prevent this. Take particular care if plastic shrinkage cracking is potentially imminent and especially if it has developed during a previous placement. Periods of high potential for plastic shrinkage cracking can be anticipated by use of Fig. 2.1.5 of ACI 305R. In addition the concrete placement shall be further protected by erecting shades and windbreaks and by applying fog sprays of water, sprinkling, ponding or wet covering. Plastic shrinkage cracks that occur shall be filled by injection of epoxy resin as directed, after the concrete hardens. Plastic shrinkage cracks shall never be troweled over or filled with slurry.

3.5.6 Placing Concrete in Congested Areas

Use special care to ensure complete filling of the forms, elimination of all voids, and complete consolidation of the concrete when placing concrete in areas congested with reinforcing bars, embedded items, waterstops and other tight spacing. An appropriate concrete mixture shall be used, and the nominal maximum size of aggregate (NMSA) shall meet the specified criteria when evaluated for the congested area. Vibrators with heads of a size appropriate for the clearances available shall be used, and the consolidation operation shall be closely supervised to ensure complete and thorough consolidation at all points. Where necessary, splices of reinforcing bars shall be alternated to reduce congestion. Where two mats of closely spaced reinforcing are required, the bars in each mat shall be placed in matching alignment to reduce congestion.

3.6 JOINTS

3.6.1 Construction Joints

For concrete other than slabs on grade, locate construction joints as per drawings.

3.6.2 Contraction Joints in Slabs on Grade

Contraction joints shall be located and detailed as shown on the drawings. Produce contraction joints by forming a weakened plane in the concrete slab Regardless of method used to produce the weakened plane, it shall be 1/4 the depth of the slab thickness and between 3 and 5 mm wide. For saw-cut joints, cutting shall be timed properly with the set of the concrete. Cutting shall be started as soon as the concrete has hardened sufficiently to prevent ravelling of the edges of the saw cut. Cutting shall be completed before shrinkage stresses become sufficient to produce cracking. Form reservoir for joint sealant as per drawings.

3.6.3 Expansion Joints

Installation of expansion joints and sealing of these joints shall conform to the requirements of Section 03 15 13.00 10 EXPANSION JOINTS, CONTRACTION JOINTS, AND WATERSTOPS and Section 07 92 00 JOINT SEALANTS.

3.6.4 Waterstops

Install waterstops in conformance with the locations and details shown on the drawings using materials and procedures specified in Section 03 15 13.00 10 EXPANSION JOINTS, CONTRACTION JOINTS, AND WATERSTOPS.

3.6.5 Dowels and Tie Bars

Install dowels and tie bars at the locations shown on the drawings and to the details shown, using materials and procedures specified in Section 03 20 01.00 10 CONCRETE REINFORCEMENT and herein. Conventional smooth "paving" dowels shall be installed in slabs using approved methods to hold the dowel in place during concreting within a maximum alignment tolerance of 1 mm in 100 mm. "Structural" type deformed bar dowels, or tie bars, shall be installed as indicated to meet the specified tolerances. Care shall be taken during placing adjacent to and around dowels and tie bars to ensure there is no displacement of the dowel or tie bar and that the concrete completely embeds the dowel or tie bar and is thoroughly consolidated.

3.7 FINISHING FORMED SURFACES

Forms, form materials, and form construction are specified in Section 03 11 13.00 10 STRUCTURAL CONCRETE FORMWORK. Finishing of formed surfaces shall be as specified herein. Unless another type of architectural or special finish is specified, surfaces shall be left with the texture imparted by the forms except that defective surfaces shall be repaired. Unless painting of surfaces is required, maintain uniform color of the concrete by use of only one mixture without changes in materials or proportions for any structure or portion of structure that requires a Class A or B finish. Except for major defects, as defined hereinafter, repair surface defects as specified herein within 24 hours after forms are removed. Repairs of the so-called "plaster-type" will not be permitted in any location. Tolerances of formed surfaces shall conform to the requirements of ACI 117. These tolerances apply to the finished concrete surface, not to the forms themselves; forms shall be set true to line and grade. Form tie holes requiring repair and other defects whose depth is at least as great as their surface diameter shall be repaired as specified in paragraph Damp-Pack Mortar Repair below. Defects whose surface diameter is greater than their depth shall be repaired as specified in paragraph Repair of Major Defects below. Repairs shall be finished flush with adjacent surfaces and with the same surface texture. The cement used for all repairs shall be a blend of job cement with white cement proportioned so that the final color after curing and aging will be the same as the adjacent concrete. Concrete with excessive honeycomb, or other defects which affect the strength of the member, will be rejected. Repairs shall be demonstrated to be acceptable and free from cracks or loose or drummy areas at the completion of the contract and, for Class A and B Finishes, shall be inconspicuous. Repairs not meeting these requirements will be rejected and shall be replaced.

3.7.1 Class A Finish and Class B Finish

Class A finish is required where indicated on the drawings. Class B finish is required where indicated on the drawings. Remove fins, ravelings, and loose material, all surface defects over 12 mm in diameter or more than 12 mm deep, shall be repaired and, except as otherwise indicated or as specified in Section 03 11 13.00 10 STRUCTURAL CONCRETE FORMWORK, holes left by removal of form ties shall be reamed and filled. Defects more than 12 mm in diameter shall be cut back to sound concrete, but in all cases at least 25 mm deep. Prepare a sample panel for approval (as specified in PART 1) before commencing repair, showing that the surface texture and color match will be attained. Metal tools shall not be used to finish repairs in Class A surfaces.

3.8 REPAIRS

3.8.1 Damp-Pack Mortar Repair

Form tie holes requiring repair and other defects, whose depth is at least as great as their surface diameter but not over 100 mm, shall be repaired by the damp-pack mortar method. Form tie holes shall be reamed and other similar defects shall be cut out to sound concrete. The void shall then be thoroughly cleaned, thoroughly wetted, brush-coated with a thin coat of neat cement grout and filled with mortar. Mortar shall be a stiff mix of 1 part portland cement to 2 parts fine aggregate passing the 1.18 mm sieve, and minimum amount of water. Use only sufficient water to produce a mortar which, when used, will stick together on being molded into a ball by a slight pressure of the hands and will not exude water but will leave the hands damp. Mortar shall be mixed and allowed to stand for 30 to 45 minutes before use with remixing performed immediately prior to use. Mortar shall be thoroughly tamped in place in thin layers using a hammer and hardwood block. Holes passing entirely through walls shall be completely filled from the inside face by forcing mortar through to the outside face. All holes shall be packed full. Damp-pack repairs shall be moist cured for at least 48 hours.

3.8.2 Repair of Major Defects

Major defects will be considered to be those more than 12 mm deep or, for Class A and B finishes, more than 12 mm in diameter.

3.8.2.1 Surface Application of Mortar Repair

Defective concrete shall be removed, and removal shall extend into completely sound concrete. Use approved equipment and procedures which will not cause cracking or microcracking of the sound concrete. If reinforcement is encountered, remove concrete so as to expose the reinforcement for at least 50 mm on all sides. All such defective areas greater than 7800 square mm shall be outlined by saw cuts at least 25 mm deep. Defective areas less than 7800 square mm shall be outlined by a 25 mm deep cut with a core drill in lieu of sawing. All saw cuts shall be straight lines in a rectangular pattern in line with the formwork panels. After concrete removal, the surface shall be thoroughly cleaned by high pressure washing to remove all loose material. Keep surfaces continually saturated for the first 12 of the 24 hours immediately before placing mortar and shall be damp but not wet at the time of commencing mortar placement. The Contractor, as an option, may use either hand-placed mortar or mortar placed with a mortar gun. If hand-placed mortar is used, the edges of the cut shall be perpendicular to the surface of the concrete. The prepared area shall be brush-coated with a thin coat of neat cement grout. The repair shall then be made using a stiff mortar, preshrunk by allowing the mixed mortar to stand for 30 to 45 minutes and then remixed, thoroughly tamped into place in thin layers. If hand-placed mortar is used, test each repair area for drumminess by firm tapping with a hammer and inspecting for cracks, both in the presence of the Contracting Officer, immediately before completion of the contract, and replacing any showing drumminess or cracking. If mortar placed with a mortar gun is used, the gun shall be a small compressed air-operated gun to which the mortar is slowly hand fed and which applies the mortar to the surface as a high-pressure stream, as approved. Repairs made using shotcrete equipment will not be accepted. The mortar used shall be the same mortar as specified for damp-pack mortar repair. If gun-placed mortar is used, the edges of the cut shall be beveled toward the center at a slope of 1:1. All

surface applied mortar repairs shall be continuously moist cured for at least 7 days. Moist curing shall consist of several layers of saturated burlap applied to the surface immediately after placement is complete and covered with polyethylene sheeting, all held closely in place by a sheet of plywood or similar material rigidly braced against it. Keep burlap continually wet.

3.9 FINISHING UNFORMED SURFACES

The finish of all unformed surfaces shall meet the requirements of paragraph Tolerances in PART 1, when tested as specified herein.

3.9.1 General

The ambient temperature of spaces adjacent to unformed surfaces being finished and of the base on which concrete will be placed shall be not less than 10 degrees C. In hot weather all requirements of paragraphs Hot Weather Requirements and Prevention of Plastic Shrinkage Cracking above shall be met. Unformed surfaces that are not to be covered by additional concrete or backfill shall have a float finish, with additional finishing as specified below, and shall be true to the elevation shown on the drawings. Surfaces to receive additional concrete or backfill shall be brought to the elevation shown on the drawings, properly consolidated, and left true and regular. Unless otherwise shown on the drawings, exterior surfaces shall be sloped for drainage, as directed. Where drains are provided, interior floors shall be evenly sloped to the drains. Joints shall be carefully made with a jointing or edging tool. The finished surfaces shall be protected from stains or abrasions. Grate tampers or "jitterbugs" shall not be used for any surfaces. The dusting of surfaces with dry cement or other materials or the addition of any water during finishing shall not be permitted. If bleedwater is present prior to finishing, the excess water shall be carefully dragged off or removed by absorption with porous materials such as burlap. During finishing operations, extreme care shall be taken to prevent over finishing or working water into the surface; this can cause "crazing" (surface shrinkage cracks which appear after hardening) of the surface. Any slabs with surfaces which exhibit significant crazing shall be removed and replaced. During finishing operations, surfaces shall be checked with a 10 foot straightedge, applied in both directions at regular intervals while the concrete is still plastic, to detect high or low areas.

3.9.2 Rough Slab Finish

As a first finishing operation for unformed surfaces e.g. slab on grade, the surface shall receive a rough slab finish prepared as follows. The concrete shall be uniformly placed across the slab area, consolidated as previously specified, and then screeded with straightedge strikeoffs immediately after consolidation to bring the surface to the required finish level with no coarse aggregate visible. Side forms and screed rails shall be provided, rigidly supported, and set to exact line and grade. Allowable tolerances for finished surfaces apply only to the hardened concrete, not to forms or screed rails. Forms and screed rails shall be set true to line and grade. "Wet screeds" shall not be used.

3.9.3 Floated Finish

Slabs to receive more than a rough slab finish shall next be given a wood float finish. Latrine and laundry floors shall be given only a float finish. The screeding shall be followed immediately by darbying or bull

floating before bleeding water is present, to bring the surface to a true, even plane. Then, after the concrete has stiffened so that it will withstand a man's weight without imprint of more than 6 mm and the water sheen has disappeared, it shall be floated to a true and even plane free of ridges. Perform floating by use of suitable hand floats or power driven equipment. Use sufficient pressure on the floats to bring a film of moisture to the surface. Hand floats shall be made of wood, magnesium, or aluminum. Lightweight concrete or concrete that exhibits stickiness shall be floated with a magnesium float. Care shall be taken to prevent over-finishing or incorporating water into the surface.

3.9.4 Troweled Finish

All interior slab on grade except in latrines and laundry building shall be given a trowel finish. After floating is complete and after the surface moisture has disappeared, unformed surfaces shall be steel-troweled to a smooth, even, dense finish, free from blemishes including trowel marks. In lieu of hand finishing, an approved power finishing machine may be used in accordance with the directions of the machine manufacturer. Additional trowelings shall be performed, either by hand or machine until the surface has been troweled 2 times, with waiting period between each. Care shall be taken to prevent blistering and if such occurs, troweling shall immediately be stopped and operations and surfaces corrected. A final hard steel troweling shall be done by hand, with the trowel tipped, and using hard pressure, when the surface is at a point that the trowel will produce a ringing sound. The finished surface shall be thoroughly consolidated and shall be essentially free of trowel marks and be uniform in texture and appearance. The concrete mixture used for troweled finished areas shall be adjusted, if necessary, in order to provide sufficient fines (cementitious material and fine sand) to finish properly.

3.10 EXTERIOR SLAB AND RELATED ITEMS

3.10.1 Pavements

Construct pavements where and as shown on the drawings. After forms are set and underlying material prepared as specified, place the concrete uniformly throughout the area and thoroughly vibrated. As soon as placed and vibrated, the concrete shall be struck off and screeded to the crown and cross section and to such elevation above grade that when consolidated and finished, the surface of the pavement will be at the required elevation. The entire surface shall be tamped with the strike off, or consolidated with a vibrating screed, and this operation continued until the required compaction and reduction of internal and surface voids are accomplished. Take care to prevent bringing excess paste to the surface. Immediately following the final consolidation of the surface, the pavement shall be floated longitudinally from bridges resting on the side forms and spanning but not touching the concrete. If necessary, additional concrete shall be placed and screeded, and the float operated until a satisfactory surface has been produced. The floating operation shall be advanced not more than half the length of the float and then continued over the new and previously floated surfaces. After finishing is completed but while the concrete is still plastic, eliminate minor irregularities and score marks in the pavement surface by means of long-handled cutting straightedges. Straightedges shall be 3.75 m in length and shall be operated from the sides of the pavement and from bridges. A straightedge operated from the side of the pavement shall be equipped with a handle 1 m longer than one-half the width of the pavement. The surface shall then be tested for trueness with a 3.75 straightedge held in successive positions parallel and

at right angles to the center line of the pavement, and the whole area covered as necessary to detect variations. The straightedge shall be advanced along the pavement in successive stages of not more than one-half the length of the straightedge. Depressions shall be immediately filled with freshly mixed concrete, struck off, consolidated, and refinished. Projections above the required elevation shall also be struck off and refinished. Continue the straightedge testing and finishing until the entire surface of the concrete is true. Before the surface sheen has disappeared and well before the concrete becomes nonplastic, the surface of the pavement shall be given a nonslip sandy surface texture by belting with approved "belt" and procedures, use of a burlap drag or broom finish as indicated. A strip of clean, wet burlap from 1.0 to 1.5 m wide and 0.7 m longer than the pavement width shall be carefully pulled across the surface. Round edges and joints with an edger having a radius of 3 mm. Curing shall be as specified.

3.10.2 Sidewalks

Concrete shall be 100 mm minimum thickness. Provide contraction joints at 1.75 m spaces unless otherwise indicated. Contraction joints shall be cut 25 mm deep with a jointing tool after the surface has been finished. Provide transverse expansion joints 12 mm thick at changes in direction and where sidewalk abuts curbs, steps, rigid pavement, or other similar structures. Sidewalks shall be given a lightly broomed finish. A transverse slope of 1 mm per 50 mm shall be provided, unless otherwise indicated. Variations in cross section shall be limited to 1 mm per 250 mm.

3.10.3 Curbs and Gutters

Concrete shall be formed, placed, and finished by hand using a properly shaped "mule" or constructed using a slipform machine suitable for this work. Contraction joints shall be cut 75 mm deep with a jointing tool after the surface has been finished. Expansion joints (12 mm wide) shall be provided at 35 m maximum spacing unless otherwise indicated. Finish exposed surfaces using a stiff bristled brush.

3.10.4 Pits and Trenches

Construct pits and trenches as indicated on the drawings. Bottoms and walls shall be placed monolithically or waterstops and keys, shall be provided as approved.

3.11 CURING AND PROTECTION

3.11.1 General

Concrete shall be cured by an approved method for the period of time given below:

All concrete	7 days

Immediately after placement, protect concrete from premature drying, extremes in temperatures, rapid temperature change, mechanical injury and damage from rain and flowing water for the duration of the curing period. Maintain air and forms in contact with concrete at a temperature above 10 degrees C for the first 3 days and at a temperature above 0 degrees C for the remainder of the specified curing period. Exhaust fumes from combustion heating units shall be vented to the outside of the enclosure, and heaters and ducts shall be placed and directed so as not to cause areas

of overheating and drying of concrete surfaces or to create fire hazards. Materials and equipment needed for adequate curing and protection shall be available and at the site prior to placing concrete. No fire or excessive heat, including welding, shall be permitted near or in direct contact with the concrete at any time. Except as otherwise permitted by paragraph Membrane Forming Curing Compounds in PART 2, moist curing shall be provided for any areas to receive any paint or other applied coating, or to which other cementitious material and tile is to be bonded.

3.11.2 Moist Curing

Maintain concrete, to be moist-cured, continuously wet for the entire curing period, commencing immediately after finishing. If water or curing materials used stain or discolor concrete surfaces which are to be permanently exposed, the concrete surfaces shall be cleaned as approved. When wooden forms are left in place during curing, they shall be kept wet at all times. If steel forms are used in hot weather, nonsupporting vertical forms shall be broken loose from the concrete soon after the concrete hardens and curing water continually applied in this void. If the forms are removed before the end of the curing period, curing shall be carried out as on unformed surfaces, using suitable materials. Surfaces shall be cured by ponding, by continuous sprinkling, by continuously saturated burlap or cotton mats, or by continuously saturated plastic coated burlap. Burlap and mats shall be clean and free from any contamination and shall be completely saturated before being placed on the concrete. Provide an approved work system to ensure that moist curing is continuous 24 hours per day.

3.11.3 Membrane Forming Curing Compounds

Membrane curing shall not be used on surfaces that are to receive any subsequent treatment depending on adhesion or bonding to the concrete, including surfaces to which a smooth finish is to be applied or other material is to be bonded. However, a styrene acrylate or chlorinated rubber compound meeting ASTM C 309, Class B requirements, may be used for surfaces which are to be painted or are to receive bituminous roofing or waterproofing, or floors that are to receive adhesive applications of resilient flooring. The curing compound selected shall be compatible with any subsequent paint, roofing, waterproofing or flooring specified. Membrane curing compound shall not be used on surfaces that are maintained at curing temperatures with free steam. Apply curing compound to formed surfaces immediately after the forms are removed and prior to any patching or other surface treatment except the cleaning of loose sand, mortar, and debris from the surface. All surfaces shall be thoroughly moistened with water. Curing compound shall be applied to slab surfaces as soon as the bleeding water has disappeared, with the tops of joints being temporarily sealed to prevent entry of the compound and to prevent moisture loss during the curing period. The curing compound shall be applied in a two-coat continuous operation by approved motorized power-spraying equipment operating at a minimum pressure of 500 kPa, at a uniform coverage of not more than 10 cubic meters/L for each coat, and the second coat shall be applied perpendicular to the first coat. Concrete surfaces which have been subjected to rainfall within 3 hours after curing compound has been applied shall be resprayed by the method and at the coverage specified. Shade surfaces, on which clear compound is used, from direct rays of the sun for the first 3 days. Keep surfaces coated with curing compound free of foot and vehicular traffic, and from other sources of abrasion and contamination during the curing period.

3.11.4 Impervious Sheeting

Except for plastic coated burlap, impervious sheeting alone shall not be used for curing. Use impervious-sheet curing only on horizontal or nearly horizontal surfaces. Surfaces shall be thoroughly wetted and be completely covered with the sheeting. Sheeting shall be at least 450 mm wider than the concrete surface to be covered. Covering shall be laid with light-colored side up. Covering shall be lapped not less than 300 mm and securely weighted down or shall be lapped not less than 100 mm and taped to form a continuous cover with completely closed joints. The sheet shall be weighted to prevent displacement so that it remains in contact with the concrete during the specified length of curing. Coverings shall be folded down over exposed edges of slabs and secured by approved means. Sheets shall be immediately repaired or replaced if tears or holes appear during the curing period.

3.11.5 Cold Weather Curing and Protection

When the daily ambient low temperature is less than 0 degrees Cmaintain the temperature of the concrete above 5 degrees C for the first seven days after placing. During the period of protection removal, control the air temperature adjacent to the concrete surfaces so that concrete near the surface will not be subjected to a temperature differential of more than 13 degrees C as determined by suitable temperature measuring devices furnished by the Contractor, as required, and installed adjacent to the concrete surface and 50 mm inside the surface of the concrete. Perform the installation of the thermometers as directed.

3.12 SETTING FOR BASE PLATES AND BEARING PLATES, NONSHRINK GROUT SURFACING

After being properly positioned, column base plates, bearing plates for beams and similar structural members, and machinery and equipment base plates shall be set to the proper line and elevation with damp-pack bedding mortar, except where nonshrink grout is indicated. The thickness of the mortar or grout shall be approximately 1/24 the width of the plate, but not less than 19 mm. Concrete and metal surfaces in contact with grout shall be clean and free of oil and grease, and concrete surfaces in contact with grout shall be damp and free of laitance when grout is placed. Use nonshrink grout as indicated.

3.12.1 Damp-Pack Bedding Mortar

Damp-pack bedding mortar shall consist of 1 part cement and 2-1/2 parts fine aggregate having water content such that a mass of mortar tightly squeezed in the hand will retain its shape but will crumble when disturbed. The space between the top of the concrete and bottom of the bearing plate or base shall be packed with the bedding mortar by tamping or ramming with a bar or rod until it is completely filled.

3.12.2 Nonshrink Grout

Nonshrink grout shall be a ready-mixed material requiring only the addition of water. Water content shall be the minimum that will provide a flowable mixture and completely fill the space/cover the surface to be grouted without segregation, bleeding, or reduction of strength.

3.12.2.1 Mixing and Placing of Nonshrink Grout

Mixing and placing shall be in conformance with the material manufacturer's

instructions and as specified therein. Ingredients shall be thoroughly dry-mixed before adding water. After adding water, mix the batch for 3 minutes. Batches shall be of size to allow continuous placement of freshly mixed grout. Discard grout not used within 30 minutes after mixing. If/as applicable, the space between the top of the concrete or machinery-bearing surface and the plate shall be filled solid with the grout. If/as applicable, forms shall be of wood or other equally suitable material for completely retaining the grout on all sides and on top and shall be removed after the grout has set. The placed grout shall be carefully worked by rodding, floating or other means to eliminate voids; however, overworking and breakdown of the initial set shall be avoided. Grout shall not be retempered or subjected to vibration from any source. Where clearances are unusually small, placement shall be under pressure with a grout pump. Temperature of the grout, and of surfaces receiving the grout, shall be maintained at 18 to 30 degrees C until after setting.

3.12.2.2 Treatment of Exposed Surfaces

For metal-oxidizing nonshrink grout, exposed surfaces shall be cut back 25 mm and immediately covered with a parge coat of mortar consisting of 1 part portland cement and 2-1/2 parts fine aggregate by weight, with sufficient water to make a plastic mixture. The parge coat shall have a smooth finish. For other mortars or grouts, exposed surfaces shall have a smooth-dense finish and be left untreated. Curing shall comply with paragraph CURING AND PROTECTION above.

3.13 TESTING AND INSPECTION FOR CQC

Perform the inspection and tests described below and, based upon the results of these inspections and tests, take the action required and submit specified reports. When, in the opinion of the Contracting Officer, the concreting operation is out of control, cease concrete placement and correct the operation. The laboratory performing the tests shall be onsite and shall conform with ASTM C 1077. Materials may be subjected to check testing by the Government from samples obtained at the manufacturer, at transfer points, or at the project site. The Government will inspect the laboratory, equipment, and test procedures prior to start of concreting operations and and may reinspect same thereafter for conformance with ASTM C 1077.

3.13.1 Grading and Corrective Action

3.13.1.1 Fine Aggregate

At least once during each shift when the concrete plant is operating, there shall be one sieve analysis and fineness modulus determination in accordance with ASTM C 136 and COE CRD-C 104 for the fine aggregate or for each fine aggregate if it is batched in more than one size or classification. The location at which samples are taken may be selected by the Contractor as the most advantageous for control. However, the Contractor is responsible for delivering fine aggregate to the mixer within specification limits. When the amount passing on any sieve is outside the specification limits, the fine aggregate shall be immediately resampled and retested. If there is another failure on any sieve, the fact shall be immediately reported to the Contracting Officer, concreting shall be stopped, and immediate steps taken to correct the grading.

3.13.1.2 Coarse Aggregate

At least once during each shift in which the concrete plant is operating, there shall be a sieve analysis in accordance with ASTM C 136 for each size of coarse aggregate. The location at which samples are taken may be selected by the Contractor as the most advantageous for production control. However, the Contractor shall be responsible for delivering the aggregate to the mixer within specification limits. A test record of samples of aggregate taken at the same locations shall show the results of the current test as well as the average results of the five most recent tests including the current test. The Contractor may adopt limits for control coarser than the specification limits for samples taken other than as delivered to the mixer to allow for degradation during handling. When the amount passing any sieve is outside the specification limits, the coarse aggregate shall be immediately resampled and retested. If the second sample fails on any sieve, that fact shall be reported to the Contracting Officer. Where two consecutive averages of 5 tests are outside specification limits, the operation shall be considered out of control and reported to the Contracting Officer. Concreting shall be stopped and immediate steps shall be taken to correct the grading.

3.13.2 Quality of Aggregates

Thirty days prior to the start of concrete placement, perform all tests for aggregate quality required by ASTM C 33/C 33M. In addition, after the start of concrete placement, perform tests for aggregate quality at least every three months, and when the source of aggregate or aggregate quality changes. Samples tested after the start of concrete placement shall be taken immediately prior to entering the concrete mixer.

3.13.3 Scales, Batching and Recording

Check the accuracy of the scales by test weights prior to start of concrete operations and at least once every three months. Such tests shall also be made as directed whenever there are variations in properties of the fresh concrete that could result from batching errors. Once a week the accuracy of each batching and recording device shall be checked during a weighing operation by noting and recording the required weight, recorded weight, and the actual weight batched. At the same time, test and ensure that the devices for dispensing admixtures are operating properly and accurately. When either the weighing accuracy or batching accuracy does not comply with specification requirements, the plant shall not be operated until necessary adjustments or repairs have been made. Discrepancies in recording accuracies shall be corrected immediately.

3.13.4 Batch-Plant Control

Continuously control the measurement of concrete materials, including cementitious materials, each size of aggregate, water, and admixtures. Adjust the aggregate weights and amount of added water as necessary to compensate for free moisture in the aggregates. The amount of air-entraining agent shall be adjusted to control air content within specified limits. Prepare a report indicating type and source of cement used, type and source of pozzolan or slag used, amount and source of admixtures used, aggregate source, the required aggregate and water weights per cubic meter amount of water as free moisture in each size of aggregate, and the batch aggregate and water weights per cubic meter for each class of concrete batched during each day's plant operation.

3.13.5 Concrete Mixture

a. Air Content Testing. Perform air content tests when test specimens are fabricated. In addition, at least two tests for air content shall be made on randomly selected batches of each separate concrete mixture produced during each 8-hour period of concrete production. Perform additional tests when excessive variation in workability is reported by the placing foreman or Government inspector. Tests shall be made in accordance with ASTM C 231 for normal weight concrete and ASTM C 173/C 173M for lightweight concrete. Plot test results on control charts which shall at all times be readily available to the Government and submitted weekly. Keep copies of the current control charts in the field by testing crews and results plotted as tests are made. When a single test result reaches either the upper or lower action limit, perform a second test immediately. The results of the two tests shall be averaged and this average used as the air content of the batch to plot on both the air content and the control chart for range, and for determining need for any remedial action. The result of each test, or average as noted in the previous sentence, shall be plotted on a separate control chart for each mixture on which an "average line" is set at the midpoint of the specified air content range from paragraph Air Entrainment in PART 1. Set an upper warning limit and a lower warning limit line 1.0 percentage point above and below the average line, respectively. An upper action limit and a lower action limit line shall be set 1.5 percentage points above and below the average line, respectively. The range between each two consecutive tests shall be plotted on a secondary control chart for range where an upper warning limit is set at 2.0 percentage points and an upper action limit is set at 3.0 percentage points. Samples for air content may be taken at the mixer, however, the Contractor is responsible for delivering the concrete to the placement site at the stipulated air content. If the Contractor's materials or transportation methods cause air content loss between the mixer and the placement, correlation samples shall be taken at the placement site as required by the Contracting Officer, and the air content at the mixer controlled as directed.

b. Air Content Corrective Action. Whenever points on the control chart for percent air reach either warning limit, an adjustment shall immediately be made in the amount of air-entraining admixture batched. As soon as practical after each adjustment, another test shall be made to verify the result of the adjustment. Whenever a point on the secondary control chart for range reaches the warning limit, the admixture dispenser shall be recalibrated to ensure that it is operating accurately and with good reproducibility. Whenever a point on either control chart reaches an action limit line, the air content shall be considered out of control and the concreting operation shall immediately be halted until the air content is under control. Additional air content tests shall be made when concreting is restarted.

c. Slump Testing. In addition to slump tests which are made when test specimens are fabricated, at least four slump tests shall be made on randomly selected batches in accordance with ASTM C 143/C 143M for each separate concrete mixture produced during each 8-hour or less period of concrete production each day. Also, additional tests shall be made when excessive

variation in workability is reported by the placing foreman or Government inspector. Plot test results on control charts which shall at all times be readily available to the Government and submitted weekly. Keep copies of the current control charts in the field by testing crews and results plotted as tests are made. When a single slump test reaches or goes beyond either the upper or lower action limit, immediately perform a second test. The results of the two tests shall be averaged and this average used as the slump of the batch to plot on both the control charts for slump and the chart for range, and for determining need for any remedial action. Set limits on separate control charts for slump for each type of mixture. The upper warning limit shall be set at 12.5 mm below the maximum allowable slump specified in paragraph Slump in PART 1 for each type of concrete and an upper action limit line and lower action limit line shall be set at the maximum and minimum allowable slumps, respectively, as specified in the same paragraph. The range between each consecutive slump test for each type of mixture shall be plotted on a single control chart for range on which an upper action limit is set at 50 mm. Take samples for slump at the mixer. However, the Contractor is responsible for delivering the concrete to the placement site at the stipulated slump. If the Contractor's materials or transportation methods cause slump loss between the mixer and the placement, take correlation samples at the placement site as required by the Contracting Officer, and the slump at the mixer controlled as directed.

d. Slump Corrective Action. Whenever points on the control charts for slump reach the upper warning limit, make an adjustment immediately in the batch weights of water and fine aggregate. The adjustments are to be made so that the total water content does not exceed that amount allowed by the maximum w/c ratio specified, based on aggregates which are in a saturated surface dry condition. When a single slump reaches the upper or lower action limit, no further concrete shall be delivered to the placing site until proper adjustments have been made. Immediately after each adjustment, another test shall be made to verify the correctness of the adjustment. Whenever two consecutive individual slump tests, made during a period when there was no adjustment of batch weights, produce a point on the control chart for range at or above the upper action limit, halt the concreting operation immediately, and take appropriate steps to bring the slump under control. Additional slump tests shall be made as directed.

e. Temperature. Measure the temperature of the concrete when compressive strength specimens are fabricated in accordance with ASTM C 1064/C 1064M. Report the temperature along with the compressive strength data.

f. Strength Specimens. Perform at least one set of test specimens, for compressive strength, on each different concrete mixture placed during the day for each 380 cubic meters or portion thereof of that concrete mixture placed each day. Perform additional sets of test specimens, as directed by the Contracting Officer, when the mixture proportions are changed or when low strengths have been detected. Develop a truly random (not haphazard) sampling plan for approval by the Contracting Officer prior to the start of construction. The plan shall ensure that sampling is done in a completely random and unbiased manner. A set of test specimens

for concrete with a 28-day specified strength in accordance with paragraph Strength Requirements in PART 1 shall consist of four specimens, two to be tested at 7 days and two at 28 days. Test specimens shall be molded and cured in accordance with ASTM C 31/C 31M and tested in accordance with ASTM C 39/C 39M for test cylinders and ASTM C 78 for test beams. Results of all strength tests shall be reported immediately to the Contracting Officer. Quality control charts shall be kept for individual strength "tests", ("test" as defined in paragraph Strength Requirements in PART 1) moving average of last 3 "tests" for strength, and moving average for range for the last 3 "tests" for each mixture. The charts shall be similar to those found in ACI 214R.

3.13.6 Inspection Before Placing

Inspect foundations, construction joints, forms, and embedded items in sufficient time prior to each concrete placement in order to certify to the Contracting Officer that they are ready to receive concrete. Report the results of each inspection in writing.

3.13.7 Placing

The placing foreman shall supervise placing operations, shall determine that the correct quality of concrete or grout is placed in each location as specified and as directed by the Contracting Officer, and shall be responsible for measuring and recording concrete temperatures and ambient temperature hourly during placing operations, weather conditions, time of placement, volume placed, and method of placement. The placing foreman shall not permit batching and placing to begin until it has been verified that an adequate number of vibrators in working order and with competent operators are available. Placing shall not be continued if any pile of concrete is inadequately consolidated. If any batch of concrete fails to meet the temperature requirements, immediate steps shall be taken to improve temperature controls.

3.13.8 Vibrators

Determine the frequency and amplitude of each vibrator in accordance with COE CRD-C 521 prior to initial use and at least once a month when concrete is being placed. Perform additional tests as directed when a vibrator does not appear to be adequately consolidating the concrete. The frequency shall be determined while the vibrator is operating in concrete with the tachometer being held against the upper end of the vibrator head while almost submerged and just before the vibrator is withdrawn from the concrete. Determine the amplitude with the head vibrating in air. Take two measurements, one near the tip and another near the upper end of the vibrator head, and these results averaged. Report the make, model, type, and size of the vibrator and frequency and amplitude results in writing. Any vibrator not meeting the requirements of paragraph Consolidation above, shall be immediately removed from service and repaired or replaced.

3.13.9 Curing Inspection

a. Moist Curing Inspections. At least once each shift, and not less than twice per day on both work and non-work days, an inspection shall be made of all areas subject to moist curing. The surface moisture condition shall be noted and recorded.

b. Moist Curing Corrective Action. When a daily inspection report lists an area of inadequate curing, immediate corrective action shall be taken, and the required curing period for those areas shall be extended by 1 day.

c. Membrane Curing Inspection. No curing compound shall be applied until the Contractor has verified that the compound is properly mixed and ready for spraying. At the end of each operation, estimate the quantity of compound used by measurement of the container and the area of concrete surface covered, compute the rate of coverage in square meters/L, and note whether or not coverage is uniform.

d. Membrane Curing Corrective Action. When the coverage rate of the curing compound is less than that specified or when the coverage is not uniform, the entire surface shall be sprayed again.

e. Sheet Curing Inspection. At least once each shift and once per day on non-work days, an inspection shall be made of all areas being cured using impervious sheets. The condition of the covering and the tightness of the laps and tapes shall be noted and recorded.

f. Sheet Curing Corrective Action. When a daily inspection report lists any tears, holes, or laps or joints that are not completely closed, the tears and holes shall promptly be repaired or the sheets replaced, the joints closed, and the required curing period for those areas shall be extended by 1 day.

3.13.10 Cold-Weather Protection

At least once each shift and once per day on non-work days, an inspection shall be made of all areas subject to cold-weather protection. Any deficiencies shall be noted, corrected, and reported.

3.13.11 Mixer Uniformity

a. Stationary Mixers. Prior to the start of concrete placing and once every 6 months when concrete is being placed, or once for every 60,000 cubic meters of concrete placed, whichever results in the shortest time interval, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M.

b. Truck Mixers. Prior to the start of concrete placing and at least once every 6 months when concrete is being placed, uniformity of concrete mixing shall be determined in accordance with ASTM C 94/C 94M. Select the truck mixers randomly for testing. When satisfactory performance is found in one truck mixer, the performance of mixers of substantially the same design and condition of the blades may be regarded as satisfactory.

c. Mixer Uniformity Corrective Action. When a mixer fails to meet mixer uniformity requirements, either the mixing time shall be increased, batching sequence changed, batch size reduced, or adjustments shall be made to the mixer until compliance is achieved.

3.13.12 Reports

Report all results of tests or inspections conducted, informally as they are completed and in writing daily. Prepare a weekly report for the updating of control charts covering the entire period from the start of the construction season through the current week. During periods of cold-weather protection, reports of pertinent temperatures shall be made daily. These requirements do not relieve the Contractor of the obligation to report certain failures immediately as required in preceding paragraphs. Such reports of failures and the action taken shall be confirmed in writing in the routine reports. The Contracting Officer has the right to examine all contractor quality control records.

-- End of Section --

SECTION 04 20 00

MASONRY
10/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 530	(2005) Building Code Requirements for Masonry Structures Commentaries
ACI 530.1	(2005) Specification for Masonry Structures
ACI SP-66	(2004) ACI Detailing Manual

ASTM INTERNATIONAL (ASTM)

ASTM A 167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 615/A 615M	(2009) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM B 370	(2009) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM C 1019	(2005) Standard Test Method for Sampling and Testing Grout
ASTM C 1072	(2006) Standard Test Method for Measurement of Masonry Flexural Bond Strength
ASTM C 144	(2004) Standard Specification for Aggregate for Masonry Mortar
ASTM C 150	(2007) Standard Specification for Portland Cement
ASTM C 207	(2006) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C 270	(2006) Standard Specification for Mortar for Unit Masonry
ASTM C 315	(2002) Clay Flue Linings

ASTM C 476	(2002) Standard Specification for Grout for Masonry
ASTM C 494/C 494M	(2008a) Standard Specification for Chemical Admixtures for Concrete
ASTM C 641	(2007) Staining Materials in Lightweight Concrete Aggregates
ASTM C 593	(1985; R 2000) Fly Ash and Other Pozzolans for Use with Lime
ASTM C 780	(2006) Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
ASTM C 90	(2006a) Loadbearing Concrete Masonry Units
ASTM C 91	(2005) Masonry Cement
ASTM C 989	(2009a) Standard Specification for Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars
ASTM C 94/C 94M	(2009) Standard Specification for Ready-Mixed Concrete
ASTM D 2000	(2006a) Standard Classification System for Rubber Products in Automotive Applications
ASTM D 2240	(2005) Standard Test Method for Rubber Property - Durometer Hardness
ASTM D 2287	(1996; R 2001) Nonrigid Vinyl Chloride Polymer and Copolymer Molding and Extrusion Compounds

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2006) International Building Code

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Structural Masonry; G

Drawings including plans, elevations, and details of wall reinforcement; details of reinforcing bars at corners and wall intersections; offsets; tops, bottoms, and ends of walls; control and expansion joints; lintels; and wall openings. Bar splice locations shall be shown. If the Contractor opts to furnish inch-pound CMU products, drawings showing elevation of walls

exposed to view and indicating the location of all cut CMU products shall be submitted for approval. Bent bars shall be identified on a bending diagram and shall be referenced and located on the drawings. Wall dimensions, bar clearances, and wall openings greater than one masonry unit in area shall be shown. No approval will be given to the shop drawings until the Contractor certifies that all openings, including those for mechanical and electrical service, are shown. If, during construction, additional masonry openings are required, the approved shop drawings shall be resubmitted with the additional openings shown along with the proposed changes. Location of these additional openings shall be clearly highlighted. The minimum scale for wall elevations shall be 1 to 50. Reinforcement bending details shall conform to the requirements of ACI SP-66.

SD-03 Product Data

Cold Weather Installation; G

Cold weather construction procedures.

SD-04 Samples

Concrete Masonry Units (CMU)

Color samples of three stretcher units and one unit for each type of special shape. Units shall show the full range of color and texture. Submit sample of colored mortar with applicable masonry unit.

Anchors, Ties, and Bar Positioners;

Two of each type used.

Expansion-Joint Materials;

One piece of each type used.

SD-05 Design Data

Pre-mixed Mortar; G

Unit Strength Method; G

Pre-mixed mortar composition. Calculations and certifications of masonry unit and mortar strength.

SD-07 Certificates

Concrete Masonry Units (CMU)
Control Joint Keys
Anchors, Ties, and Bar Positioners
Expansion-Joint Materials
Reinforcing Steel Bars and Rods
Masonry Cement
Admixtures for Masonry Mortar
Admixtures for Grout

Certificates of compliance stating that the materials meet the

specified requirements.

Contamination

SD-08 Manufacturer's Instructions

Masonry Cement

When masonry cement is used, submit the manufacturer's printed instructions on proportions of water and aggregates and on mixing to obtain the type of mortar required.

1.3 DELIVERY, HANDLING, AND STORAGE

Materials shall be delivered, handled, stored, and protected to avoid chipping, breakage, and contact with soil or contaminating material. Store and prepare materials in already disturbed areas to minimize project site disturbance and size of project site.

1.3.1 Masonry Units

Cover and protect moisture-controlled concrete masonry units and cementitious materials from precipitation. Conform to all handling and storage requirements of ASTM C 90. Prefabricated lintels shall be marked on top sides to show either the lintel schedule number or the number and size of top and bottom bars.

1.3.2 Reinforcement

Steel reinforcing bars shall be stored above the ground. Steel reinforcing bars shall be free of loose mill scale and rust.

1.3.3 Cementitious Materials, Sand and Aggregates

Cementitious and other packaged materials shall be delivered in unopened containers, plainly marked and labeled with manufacturers' names and brands. Cementitious material shall be stored in dry, weathertight enclosures or be completely covered. Cement shall be handled in a manner that will prevent the inclusion of foreign materials and damage by water or dampness. Sand and aggregates shall be stored in a manner to prevent contamination or segregation.

1.4 STRUCTURAL MASONRY

1.4.1 Special Inspection

A qualified masonry inspector approved by the Contracting Officer shall perform inspection of the masonry work. Minimum qualifications for the masonry inspector shall be 5 years of reinforced masonry inspection experience or acceptance by a State, municipality, or other governmental body having a program of examining and certifying inspectors for reinforced masonry construction. The masonry inspector shall be present during preparation of masonry prisms, sampling and placing of masonry units, placement of reinforcement (including placement of dowels in footings and foundation walls), inspection of grout space, immediately prior to closing of cleanouts, and during grouting operations. The masonry inspector shall assure Contractor compliance with the drawings and specifications. The masonry inspector shall keep a complete record of all inspections and shall submit daily written reports to the Quality Control Supervisory

Representative reporting the quality of masonry construction.

1.4.2 Unit Strength Method

Compute compressive strength of masonry system "Unit Strength Method," ACI 530. Submit calculations and certifications of unit and mortar strength.

1.4.3 Seismic Requirement

In addition to design requirements of ICC IBC, the Contractor shall provide additional seismic reinforcement as detailed on the drawings

Bond beams are required at the top of footings, at the bottom and top of openings at roof and floor levels, and at the top of parapet walls and additional locations where indicated.

1.5 QUALITY ASSURANCE

1.5.1 Testing

Masonry strength shall be determined in accordance with ACI 530; submit test reports on three prisms as specified in ACI 530.1. The cost of testing shall be paid by the Contractor.

1.5.2 Spare Vibrator

Maintain at least one spare vibrator on site at all times.

1.5.3 Bracing and Scaffolding

Provide bracing and scaffolding necessary for masonry work. Design bracing to resist wind pressure as required by local code.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

The source of materials which will affect the appearance of the finished work shall not be changed after the work has started except with Contracting Officer's approval. The Contractor has the option to use either hard metric or substitute inch-pound (soft-metric) CMU products. If the Contractor decides to substitute inch-pound CMU products, the following additional requirements shall be met:

a. The metric dimensions indicated on the drawings shall not be altered to accommodate inch-pound CMU products either horizontally or vertically. The 100 mm building module shall be maintained, except for the CMU products themselves.

b. Mortar joint widths shall be maintained as specified.

c. Rebars shall not be cut, bent or eliminated to fit into the inch-pound CMU products module.

d. Inch-pound CMU products shall not be reduced in size by more than one-third (1/3) in height and one-half (1/2) in length. Cut CMU products shall not be located at ends of walls, corners, and other openings.

e. Cut, exposed CMU products shall be held to a minimum and located where they would have the least impact on the architectural aesthetic goals of the facility.

f. Other building components, built into the CMU products, such as window frames, door frames, louvers, grilles, fire dampers, etc., that are required to be metric, shall remain metric.

2.2 CONCRETE MASONRY UNITS (CMU)

Cement shall have a low alkali content and be of one brand. Surfaces of units which are to be plastered or stuccoed shall be sufficiently rough to provide bond elsewhere.

a. Hollow Load-Bearing Units: ASTM C 90, made with normal weight aggregate. Provide load-bearing units for exterior walls, foundation walls, load-bearing walls, and shear walls.

2.2.1 Aggregates

Lightweight aggregates and blends of lightweight and heavier aggregates in proportions used in producing the units, shall comply with the following requirements when tested for stain-producing iron compounds in accordance with ASTM C 641: by visual classification method, the iron stain deposited on the filter paper shall not exceed the "light stain" classification. Use industrial waste by-products (air-cooled slag, cinders, or bottom ash), ground waste glass and concrete, granulated slag, and expanded slag in aggregates. Slag shall comply with ASTM C 989; Grade 80.

2.2.2 Flue Linings and Thimbles

ASTM C 315, free from fractures. Sizes and shapes shall be as indicated.

2.3 MORTAR FOR STRUCTURAL MASONRY

ASTM C 270, Type S. Strength (f'm) as indicated. Test in accordance with ASTM C 780. Do not use admixtures containing chlorides. When structural reinforcement is incorporated, maximum air-content shall be 12 percent in cement-lime mortar and 18 percent in masonry cement mortar. Use up to 40 percent Class F fly ash with type IP cement in cement-lime mortar. Fly ash shall comply with ASTM C 593.

2.4 MASONRY MORTAR

Mortar Type S shall conform to the proportion specification of ASTM C 270 except Type S cement-lime mortar proportions shall be 1 part cement, 1/2 part lime and 4-1/2 parts aggregate. Type S mortar shall be used for non-load-bearing, non-shear-wall interior masonry; and Type S for remaining masonry work; except where higher compressive strength is indicated on structural drawings. When masonry cement ASTM C 91 is used the maximum air content shall be limited to 12 percent and performance equal to cement-lime mortar shall be verified. Verification of masonry cement performance shall be based on ASTM C 780 and ASTM C 1072. Pointing mortar in showers and kitchens shall contain ammonium stearate, or aluminum tri-stearate, or calcium stearate in an amount equal to 3 percent by weight of cement used. Cement shall have a low alkali content and be of one brand. Aggregates shall be from one source.

2.4.1 Admixtures for Masonry Mortar

In cold weather, a non-chloride based accelerating admixture may be used subject to approval. Accelerating admixture shall be non-corrosive, shall contain less than 0.2 percent chlorides, and shall conform to ASTM C 494/C 494M, Type C.

2.4.2 Hydrated Lime and Alternates

Hydrated lime shall conform to ASTM C 207, Type S. Lime alternates which have a current ICBO, ICBO UBC, Evaluation Report number whose findings state it may be used as an alternate to lime for Type M, S, N, and O mortars will be deemed acceptable provided the user follows the manufacturer's proportions and mixing instructions as set forth in ICBO report.

2.4.3 Cement

Portland cement shall conform to ASTM C 150, Type I. Masonry cement shall conform to ASTM C 91, Type S M. Containers shall bear complete instructions for proportioning and mixing to obtain the required types of mortar. Incorporate to the maximum extent, without conflicting with other requirements of this section, up to 40 percent fly ash, up to 70 percent slag, up to 10 percent cenospheres, and up to 10 percent silica fume. Additives shall conform to requirements in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

2.4.4 Sand and Water

Sand shall conform to ASTM C 144. Water shall be clean, potable, and free from substances which could adversely affect the mortar.

2.5 GROUT AND READY-MIXED GROUT

Grout shall conform to ASTM C 476, fine. Cement used in grout shall have a low alkali content. Grout slump shall be between 200 and 250 mm. Minimum grout strength shall be 14 MPa in 28 days, as tested by ASTM C 1019. Grout shall be used subject to the limitations of Table III. Proportions shall not be changed and materials with different physical or chemical characteristics shall not be used in grout for the work unless additional evidence is furnished that the grout meets the specified requirements. Ready-Mixed grout shall conform to ASTM C 94/C 94M.

2.5.1 Admixtures for Grout

In cold weather, a non-chloride based accelerating admixture may be used subject to approval; accelerating admixture shall be non-corrosive, shall contain less than 0.2 percent chlorides, and shall conform to ASTM C 494/C 494M, Type C. In general, air-entrainment, anti-freeze or chloride admixtures shall not be used except as approved by the Contracting Officer.

2.5.2 Grout Barriers

Grout barriers for vertical cores shall consist of fine mesh wire, fiberglass, or expanded metal.

2.6 BAR POSITIONERS

Bar positioners, used to prevent displacement of reinforcing bars during the course of construction, shall be factory fabricated from 9 gauge steel wire or equivalent, and coated with a hot-dip galvanized finish. Not more than one wire shall cross the cell.

2.7 REINFORCING STEEL BARS AND RODS

Reinforcing steel bars and rods shall conform to ASTM A 615/A 615M, Grade 420 MPa (60).

2.8 CONTROL JOINT KEYS

Control joint keys shall be a factory fabricated solid section of natural or synthetic rubber (or combination thereof) conforming to ASTM D 2000or polyvinyl chloride conforming to ASTM D 2287. The material shall be resistant to oils and solvents. The control joint key shall be provided with a solid shear section not less than 16 mm thick and 10 mm thick flanges, with a tolerance of plus or minus 2 mm. The control joint key shall fit neatly, but without forcing, in masonry unit jamb sash grooves. The control joint key shall be flexible at a temperature of minus 34 degrees C after five hours exposure, and shall have a durometer hardness of not less than 70 when tested in accordance with ASTM D 2240.

2.9 EXPANSION-JOINT MATERIALS

Backer rod and sealant shall be adequate to accommodate joint compression equal to 50 percent of the width of the joint. The backer rod shall be compressible rod stock of polyethylene foam, polyurethane foam, butyl rubber foam, or other flexible, nonabsorptive material as recommended by the sealant manufacturer. Sealant shall conform to Section 07 92 00 JOINT SEALANTS, and shall be penetrating with a maximum volatile organic compound (VOC) content of 600 grams/liter.

2.10 FLASHING

Flashing shall be as specified in Section 07 60 00 FLASHING AND SHEET METAL. Provide one of the following types except that flashing indicated to terminate in reglets shall be metal or coated-metal flashing and except that the material shall be one which is not adversely affected by dampproofing material.

Stainless Steel Flashing: Copper, ASTM B 370, minimum 450 kg weight; stainless steel, ASTM A 167, Type 301, 302, 304, or 316, 4 mm thick, No. 2D finish. Provide with factory-fabricated deformations that mechanically bond flashing against horizontal movement in all directions. Deformations shall consist of dimples, diagonal corrugations, or a combination of dimples and transverse corrugations.

PART 3 EXECUTION

3.1 PREPARATION

Prior to start of work, masonry inspector shall verify the applicable conditions as set forth in ACI 530.1, inspection. The Contracting Officer will serve as inspector or will select a masonry inspector.

3.1.1 Hot Weather Installation

The following precautions shall be taken if masonry is erected when the ambient air temperature is more than 37 degrees C in the shade and the relative humidity is less than 50 percent or the ambient air temperature exceeds 32 degrees C and the wind velocity is more than 13 km/h. All masonry materials shall be shaded from direct sunlight; mortar beds shall be spread no more than 1.2 m ahead of masonry; masonry units shall be set within one minute of spreading mortar; and after erection, masonry shall be protected from direct exposure to wind and sun for 48 hours.

3.1.2 Cold Weather Installation

Before erecting masonry when ambient temperature or mean daily air temperature falls below 4 degrees C or temperature of masonry units is below 4 degrees C, a written statement of proposed cold weather construction procedures shall be submitted for approval. The following precautions shall be taken during all cold weather erection. Conform to ACI 530.1 for hot and cold weather masonry erection.

3.1.2.1 Protection

Ice or snow formed on the masonry bed shall be thawed by the application of heat. Heat shall be applied carefully until the top surface of the masonry is dry to the touch. Sections of masonry deemed frozen and damaged shall be removed before continuing construction of those sections.

a. Air Temperature 4 to 0 degrees C. Sand or mixing water shall be heated to produce mortar temperatures between 4 and 49 degrees C

b. Air Temperature 0 to minus 4 degrees C. Sand and mixing water shall be heated to produce mortar temperatures between 4 and 49 degrees C. Temperature of mortar on boards shall be maintained above freezing.

c. Air Temperature minus 4 to minus 7 degrees C. Sand and mixing water shall be heated to provide mortar temperatures between 4 and 49 degrees C. Temperature of mortar on boards shall be maintained above freezing. Sources of heat shall be used on both sides of walls under construction. Windbreaks shall be employed when wind is in excess of 24 km/hour.

d. Air Temperature minus 7 degrees C and below. Sand and mixing water shall be heated to provide mortar temperatures between 4 and 49 degrees C. Enclosure and auxiliary heat shall be provided to maintain air temperature above 0 degrees C. Temperature of units when laid shall not be less than minus 7 degrees C.

3.1.2.2 Completed Masonry and Masonry Not Being Worked On

a. Mean daily air temperature 4 to 0 degrees C. Masonry shall be protected from rain or snow for 24 hours by covering with weather-resistive membrane.

b. Mean daily air temperature 0 to minus 4 degrees C. Masonry shall be completely covered with weather-resistant membrane for 24 hours.

c. Mean Daily Air Temperature minus 4 to minus 7 degrees C. Masonry shall be completely covered with insulating blankets or equally protected for 24 hours.

d. Mean Daily Temperature minus 7 degrees C and Below. Masonry temperature shall be maintained above 0 degrees C for 24 hours by enclosure and supplementary heat, by electric heating blankets, infrared heat lamps, or other approved methods.

3.1.3 Stains

Protect exposed surfaces from mortar and other stains. When mortar joints are tooled, remove mortar from exposed surfaces with fiber brushes and wooden paddles. Protect base of walls from splash stains by covering adjacent ground with sand, sawdust, or polyethylene.

3.1.4 Loads

Do not apply uniform loads for at least 12 hours or concentrated loads for at least 72 hours after masonry is constructed. Provide temporary bracing as required.

3.1.5 Surfaces

Surfaces on which masonry is to be placed shall be cleaned of laitance, dust, dirt, oil, organic matter, or other foreign materials and shall be slightly roughened to provide a surface texture with a depth of at least 3 mm. Sandblasting shall be used, if necessary, to remove laitance from pores and to expose the aggregate.

3.2 LAYING MASONRY UNITS

Coordinate masonry work with the work of other trades to accommodate built-in items and to avoid cutting and patching. Masonry units shall be laid in running bond pattern. Each unit shall be adjusted to its final position while mortar is still soft and plastic. Units that have been disturbed after the mortar has stiffened shall be removed, cleaned, and relaid with fresh mortar. Air spaces, cavities, chases, expansion joints, and spaces to be grouted shall be kept free from mortar and other debris. Units used in exposed masonry surfaces shall be selected from those having the least amount of chipped edges or other imperfections detracting from the appearance of the finished work. Vertical joints shall be kept plumb. Units being laid and surfaces to receive units shall be free of water film and frost. Solid units shall be laid in a nonfurrowed full bed of mortar. Units shall be shoved into place so that the vertical joints are tight. Vertical masonry joints except where indicated at control, expansion, and isolation joints, shall be completely filled with mortar. Mortar will be permitted to protrude up to 13 mm into the space or cells to be grouted. Means shall be provided to prevent mortar from dropping into the space below.

3.2.1 Forms and Shores

Provide bracing and scaffolding as required. Design bracing to resist wind pressure as required by local codes. Forms and shores shall be sufficiently rigid to prevent deflections which may result in cracking or other damage to supported masonry and sufficiently tight to prevent leakage of mortar and grout. Supporting forms and shores shall not be removed in less than 10 days.

3.2.2 Reinforced Concrete Masonry Units Walls

Where vertical reinforcement occurs and as noted for exterior and shearwalls, fill cores solid with grout. Lay units in such a manner as to preserve the unobstructed vertical continuity of cores to be filled. Embed the adjacent webs in mortar to prevent leakage of grout. Remove mortar fins protruding from joints before placing grout. Minimum clear dimensions of vertical cores shall be 50 by 75 mm. Position reinforcing accurately as indicated before placing grout. As masonry work progresses, secure vertical reinforcing in place at vertical intervals not to exceed 160 bar diameters. Use puddling rod or vibrator to consolidate the grout. Minimum clear distance between masonry and vertical reinforcement shall be not less than 13 mm. Unless indicated or specified otherwise, form splices by lapping bars not less than 40 bar diameters and wire tying them together.

3.2.3 Concrete Masonry Units

Units in piers, pilasters, columns, starting courses on footings, solid foundation walls, lintels, and beams, and where cells are to be filled with grout shall be full bedded in mortar under both face shells and webs. Other units shall be full bedded under both face shells. Head joints shall be filled solidly with mortar for a distance in from the face of the unit not less than the thickness of the face shell. Foundation walls below grade shall be grouted solid. Jamb units shall be of the shapes and sizes to conform with wall units. Solid units may be incorporated in the masonry work where necessary to fill out at corners, gable slopes, and elsewhere as approved. Double walls shall be stiffened at wall-mounted plumbing fixtures by use of strap anchors, two above each fixture and two below each fixture, located to avoid pipe runs, and extending from center to center of the double wall. Walls and partitions shall be adequately reinforced for support of other work if/as shown.

3.2.4 Tolerances

Masonry shall be laid plumb, true to line, with courses level. Bond pattern shall be kept plumb throughout. Corners shall be square unless noted otherwise. Except for walls constructed of prefaced concrete masonry units, masonry shall be laid within the following tolerances (plus or minus unless otherwise noted):

TABLE II

TOLERANCES

Variation from the plumb in the lines and surfaces of columns, walls and arises	
In adjacent masonry units	3 mm
In 3 m	6 mm
In 6 m	10 mm
In 12 m or more	13 mm

Variations from the plumb for external corners, expansion joints, and other conspicuous lines	
In 6 m	6 mm
In 12 m or more	13 mm

TOLERANCES

Variations from the level for exposed lintels, sills, parapets, horizontal grooves, and other conspicuous lines	
In 6 m	6 mm
In 12 m or more	13 mm

Variation from level for bed joints and top surfaces of bearing walls	
In 3 m	6 mm
In 12 m or more	13 mm

Variations from horizontal lines	
In 3 m	6 mm
In 6 m	10 mm
In 12 m or more	13 mm

Variations in cross sectional dimensions of columns and in thickness of walls	
Minus	6 mm
Plus	13 mm

3.2.5 Cutting and Fitting

Full units of the proper size shall be used wherever possible, in lieu of cut units. Cutting and fitting, including that required to accommodate the work of others, shall be done by masonry mechanics using power masonry saws. Concrete masonry units may be wet or dry cut. Wet cut units, before being placed in the work, shall be dried to the same surface-dry appearance as uncut units being laid in the wall. Cut edges shall be clean, true and sharp. Openings in the masonry shall be made carefully so that wall plates, cover plates or escutcheons required by the installation will completely conceal the openings and will have bottoms parallel with the masonry bed joints. Reinforced masonry lintels shall be provided above openings over 300 mm wide for pipes, ducts, cable trays, and other wall penetrations, unless steel sleeves are used.

3.2.6 Jointing

Joints shall be tooled when the mortar is thumbprint hard. Horizontal joints shall be tooled last. Joints shall be brushed to remove all loose and excess mortar. Mortar joints shall be finished as follows:

3.2.6.1 Flush Joints

Joints in concealed masonry surfaces and joints at electrical outlet boxes in wet areas shall be flush cut. Flush cut joints shall be made by cutting off the mortar flush with the face of the wall. Joints in unparged masonry walls below grade shall be pointed tight. Flush joints for architectural

units, such as fluted units, shall completely fill both the head and bed joints.

3.2.6.2 Tooled Joints

Joints in exposed exterior and interior masonry surfaces shall be tooled slightly concave. Joints shall be tooled with a jointer slightly larger than the joint width so that complete contact is made along the edges of the unit. Tooling shall be performed so that the mortar is compressed and the joint surface is sealed. Jointer of sufficient length shall be used to obtain a straight and true mortar joint.

3.2.6.3 Door and Window Frame Joints

On the exposed interior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 10 mm. On the exterior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 10 mm.

3.2.7 Joint Widths

Joint widths shall be as follows:

3.2.7.1 Concrete Masonry Units

Concrete masonry units shall have 10 mm joints, except for prefaced concrete masonry units.

3.2.8 Embedded Items

Spaces around built-in items shall be filled with mortar. Openings around flush-mount electrical outlet boxes in wet locations shall be pointed with mortar. Anchors, ties, wall plugs, accessories, flashing, pipe sleeves and other items required to be built-in shall be embedded as the masonry work progresses. Anchors shall be fully embedded in the mortar. Cells receiving anchor bolts and cells of the first course below bearing plates shall be filled with grout.

3.2.9 Unfinished Work

Unfinished work shall be stepped back for joining with new work. Toothing may be resorted to only when specifically approved. Loose mortar shall be removed and the exposed joints shall be thoroughly cleaned before laying new work.

3.2.10 Masonry Wall Intersections

Each course shall be masonry bonded at corners and elsewhere as shown. Masonry walls shall be anchored or tied together at corners and intersections with bond beam reinforcement if/as shown.

3.2.11 Partitions

Partitions shall be continuous from floor to underside of floor or roof deck where shown. Openings in firewalls around joists or other structural members shall be filled as indicated or approved. Where suspended ceilings on both sides of partitions are indicated, the partitions other than those shown to be continuous may be stopped approximately 100 mm above the ceiling level. An isolation joint shall be placed in the intersection

between partitions and structural or exterior walls as shown. Interior partitions having 100 mm nominal thick units shall be tied to intersecting partitions of 100 mm units, 125 mm into partitions of 150 mm units, and 175 into partitions of 200 mm or thicker units. Cells within vertical plane of ties shall be filled solid with grout for full height of partition or solid masonry units may be used.

3.3 MORTAR

Mortar shall be mixed in a mechanically operated mortar mixer for at least 3 minutes, but not more than 5 minutes. Measurement of ingredients for mortar shall be by volume. Ingredients not in containers, such as sand, shall be accurately measured by the use of measuring boxes. Water shall be mixed with the dry ingredients in sufficient amount to provide a workable mixture which will adhere to the vertical surfaces of masonry units. Mortar that has stiffened because of loss of water through evaporation shall be retempered by adding water to restore the proper consistency and workability. Mortar that has reached its initial set or that has not been used within 2.5 hours after mixing shall be discarded.

3.4 REINFORCING STEEL

Reinforcement shall be cleaned of loose, flaky rust, scale, grease, mortar, grout, or other coating which might destroy or reduce its bond prior to placing grout. Bars with kinks or bends not shown on the drawings shall not be used. Reinforcement shall be placed prior to grouting. Unless otherwise indicated, vertical wall reinforcement shall extend to within 50 mm of tops of walls.

3.4.1 Positioning Bars

Vertical bars shall be accurately placed within the cells at the positions indicated on the drawings. A minimum clearance of 13 mm shall be maintained between the bars and masonry units. Minimum clearance between parallel bars shall be one diameter of the reinforcement. Vertical reinforcing may be held in place using bar positioners located near the ends of each bar and at intermediate intervals of not more than 192 diameters of the reinforcement. Column and pilaster ties shall be wired in position around the vertical steel. Ties shall be in contact with the vertical reinforcement and shall not be placed in horizontal bed joints.

3.4.2 Splices

Bars shall be lapped a minimum of 48 diameters of the reinforcement. Welded or mechanical connections shall develop at least 125 percent of the specified yield strength of the reinforcement.

3.5 PLACING GROUT

Cells containing reinforcing bars shall be filled with grout. Hollow masonry units in walls or partitions supporting plumbing, heating, or other mechanical fixtures, voids at door and window jambs, and other indicated spaces shall be filled solid with grout. Cells under lintel bearings on each side of openings shall be filled solid with grout for full height of openings. Walls below grade, lintels, and bond beams shall be filled solid with grout. Units other than open end units may require grouting each course to preclude voids in the units. Grout not in place within 1-1/2 hours after water is first added to the batch shall be discarded. Sufficient time shall be allowed between grout lifts to preclude

displacement or cracking of face shells of masonry units. If blowouts, flowouts, misalignment, or cracking of face shells should occur during construction, the wall shall be torn down and rebuilt.

3.5.1 Vertical Grout Barriers for Fully Grouted Walls

Grout barriers shall be provided not more than 10 m apart, or as required, to limit the horizontal flow of grout for each pour.

3.5.2 Horizontal Grout Barriers

Grout barriers shall be embedded in mortar below cells of hollow units receiving grout.

3.5.3 Grout Holes and Cleanouts

3.5.3.1 Grout Holes

Grouting holes shall be provided in slabs, spandrel beams, and other in-place overhead construction. Holes shall be located over vertical reinforcing bars or as required to facilitate grout fill in bond beams. Additional openings spaced not more than 400 mm on centers shall be provided where grouting of all hollow unit masonry is indicated. Openings shall not be less than 100 mm in diameter or 75 by 100 mm in horizontal dimensions. Upon completion of grouting operations, grouting holes shall be plugged and finished to match surrounding surfaces.

3.5.3.2 Cleanouts for Hollow Unit Masonry Construction

Cleanout holes shall be provided at the bottom of every pour in cores containing vertical reinforcement when the height of the grout pour exceeds 1.5 m. Where all cells are to be grouted, cleanout courses shall be constructed using bond beam units in an inverted position to permit cleaning of all cells. Cleanout holes shall be provided at a maximum spacing of 800 mm where all cells are to be filled with grout. A new series of cleanouts shall be established if grouting operations are stopped for more than 4 hours. Cleanouts shall not be less than 75 by 100 mm openings cut from one face shell. Manufacturer's standard cutout units may be used at the Contractor's option. Cleanout holes shall not be closed until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, cleanout holes shall be closed in an approved manner to match surrounding masonry.

3.5.4 Grouting Equipment

3.5.4.1 Grout Pumps

Pumping through aluminum tubes will not be permitted. Pumps shall be operated to produce a continuous stream of grout without air pockets, segregation, or contamination. Upon completion of each day's pumping, waste materials and debris shall be removed from the equipment, and disposed of outside the masonry.

3.5.4.2 Vibrators

Internal vibrators shall maintain a speed of not less than 5,000 impulses per minute when submerged in the grout. At least one spare vibrator shall be maintained at the site at all times. Vibrators shall be applied at

uniformly spaced points not further apart than the visible effectiveness of the machine. Duration of vibration shall be limited to time necessary to produce satisfactory consolidation without causing segregation.

3.5.5 Grout Placement

Masonry shall be laid to the top of a pour before placing grout. Grout shall not be placed in hollow unit masonry until mortar joints have set for at least 24 hours. Grout shall be placed using a hand bucket, concrete hopper, or grout pump to completely fill the grout spaces without segregation of the aggregates. Vibrators shall not be inserted into lower pours that are in a semi-solidified state. The height of grout pours and type of grout used shall be limited by the dimensions of grout spaces as indicated in Table III. Low-lift grout methods may be used on pours up to and including 1.5 m in height. High-lift grout methods shall be used on pours exceeding 1.5 m in height.

3.5.5.1 Low-Lift Method

Grout shall be placed at a rate that will not cause displacement of the masonry due to hydrostatic pressure of the grout. Mortar protruding more than 13 mm into the grout space shall be removed before beginning the grouting operation. Grout pours 300 mm or less in height shall be consolidated by mechanical vibration or by puddling. Grout pours over 300 mm in height shall be consolidated by mechanical vibration and reconsolidated by mechanical vibration after initial water loss and settlement has occurred. Vibrators shall not be inserted into lower pours that are in a semi-solidified state. Low-lift grout shall be used subject to the limitations of Table III.

TABLE III

POUR HEIGHT AND TYPE OF GROUT FOR VARIOUS GROUT SPACE DIMENSIONS

Maximum Grout Pour Height (m) (3)	Grout Type	Grouting Procedure	Minimum Dimensions of the Total Clear Areas Within Grout Spaces and Cells (mm) (1,2) Hollow-unit Masonry
0.3	Fine	Low Lift	40 x 50
1.5	Fine	Low Lift	50 x 75
0.3	Coarse	Low Lift	40 x 75
1.5	Coarse	Low Lift	65 x 75

Notes:

(1) The actual grout space or cell dimension must be larger than the sum of the following items:

a) The required minimum dimensions of total clear areas given in the table above;

b) The width of any mortar projections within the space;

c) The horizontal projections of the diameters of the horizontal reinforcing bars within a cross section of the grout space or cell.

(2) The minimum dimensions of the total clear areas shall be made up of one or more open areas, with at least one area being 20 mm or greater in width.

(3) Where only cells of hollow masonry units containing reinforcement are grouted, the maximum height of the pour shall not exceed the distance between horizontal bond beams.

3.6 BOND BEAMS

Bond beams shall be filled with grout and reinforced as indicated on the drawings. Grout barriers shall be installed under bond beam units to retain the grout as required. Reinforcement shall be continuous, including around corners, except through control joints or expansion joints, unless otherwise indicated on the drawings. Where splices are required for continuity, reinforcement shall be lapped 48 bar diameters. A minimum clearance of 13 mm shall be maintained between reinforcement and interior faces of units.

3.7 CONTROL JOINTS

Control joints shall be provided as indicated in accordance with the details shown on the drawings. Sash jamb units shall have a 19 by 19 mm groove near the center at end of each unit. The vertical mortar joint at control joint locations shall be continuous, including through all bond beams. This shall be accomplished by utilizing half blocks in alternating courses on each side of the joint. The control joint key shall be interrupted in courses containing continuous bond beam steel. In exterior masonry walls, the exterior control joints shall be raked to a depth of 19 mm; backer rod and sealant shall be installed in accordance with Section 07 92 00 JOINT SEALANTS. Exposed interior control joints shall be raked to a depth of 6 mm. Concealed control joints shall be flush cut.

3.8 SHELF ANGLES

Shelf angles shall be adjusted as required to keep the masonry level and at the proper elevation. Shelf angles shall be galvanized. Shelf angles shall be provided in sections not longer than 3 m and installed with a 6 mm gap between sections. Shelf angles shall be mitered and welded at building corners with each angle not shorter than 1.2 m, unless limited by wall configuration.

3.9 LINTELS

3.9.1 Lintels

All lintels shall be constructed as cast-in-place concrete as shown and reinforced with a minimum of two No. 13 bars in the bottom course unless otherwise indicated on the drawings. Lintel reinforcement shall extend beyond each side of masonry opening 40 bar diameters or 600 mm, whichever is greater. Reinforcing bars shall be supported in place and shall be located 1/2 inch above the bottom inside surface of the lintel unit.

3.10 SILLS AND COPINGS

Sills and copings shall be set in a full bed of mortar with faces plumb and true.

3.11 ANCHORAGE TO CONCRETE AND STRUCTURAL STEEL

3.11.1 Anchorage to Concrete

Anchorage of CMU wall bond beam to the reinforced concrete shear walls shall be as indicated.

3.12 POINTING AND CLEANING

After mortar joints have attained their initial set, but prior to hardening, mortar and grout daubs or splashings shall be completely removed from masonry-unit surfaces that will be exposed or painted. Before completion of the work, defects in joints of masonry to be exposed or painted shall be raked out as necessary, filled with mortar, and tooled to match existing joints. Immediately after grout work is completed, scum and stains which have percolated through the masonry work shall be removed using a high pressure stream of water and a stiff bristled brush. Masonry surfaces shall not be cleaned, other than removing excess surface mortar, until mortar in joints has hardened. Masonry surfaces shall be left clean, free of mortar daubs, dirt, stain, and discoloration, including scum from cleaning operations, and with tight mortar joints throughout. Metal tools and metal brushes shall not be used for cleaning.

3.12.1 Concrete Masonry Unit

Exposed concrete masonry unit surfaces shall be dry-brushed at the end of each day's work and after any required pointing, using stiff-fiber bristled brushes.

3.13 BEARING PLATES

Bearing plates for beams, joists, joist girders and similar structural members shall be set to the proper line and elevation with damp-pack bedding mortar, except where non-shrink grout is indicated. Bedding mortar and non-shrink grout shall be as specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.14 PROTECTION

Facing materials shall be protected against staining. Top of walls shall be covered with nonstaining waterproof covering or membrane when work is not in progress. Covering of the top of the unfinished walls shall continue until the wall is waterproofed with a complete roof or parapet system. Covering shall extend a minimum of 600 mm down on each side of the wall and shall be held securely in place. Before starting or resuming, top surface of masonry in place shall be cleaned of loose mortar and foreign material.

3.15 TEST REPORTS

3.15.1 Field Testing of Mortar

At least three specimens of mortar shall be taken each day. A layer of mortar 13 to 16 mm thick shall be spread on the masonry units and allowed to stand for one minute. The specimens shall then be prepared and tested for compressive strength in accordance with ASTM C 780.

3.15.2 Field Testing of Grout

Field sampling and testing of grout shall be in accordance with the applicable provisions of ASTM C 1019. A minimum of three specimens of grout per day shall be sampled and tested. Each specimen shall have a minimum ultimate compressive strength of 13.8 MPa at 28 days.

3.15.3 Prism Tests

At least one prism test sample shall be made for each 465 square meters of wall but not less than three such samples shall be made for any building. Three prisms shall be used in each sample. Prisms shall be tested in accordance with ACI 530.1. Seven-day tests may be used provided the relationship between the 7- and 28-day strengths of the masonry is established by the tests of the materials used. Compressive strength shall not be less than 10.3 MPa at 28 days. If the compressive strength of any prism falls below the specified value by more than 3.5 MPa, steps shall be taken to assure that the load-carrying capacity of the structure is not jeopardized. If the likelihood of low-strength masonry is confirmed and computations indicate that the load-carrying capacity may have been significantly reduced, tests of cores drilled, or prisms sawed, from the area in question may be required. In such case, three specimens shall be taken for each prism test more than 3.5 MPa below the specified value. Masonry in the area in question shall be considered structurally adequate if the average compressive strength of three specimens is equal to at least 85 percent of the specified value, and if the compressive strength of no single specimen is less than 75 percent of the specified value. Additional testing of specimens extracted from locations represented by erratic core or prism strength test results shall be permitted.

3.16 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

Special inspections and testing for seismic-resisting systems and components shall be done in accordance with IBC.

-- End of Section --

SECTION 04 57 13

MASONRY WOOD STOVE
10/09

PART 1 GENERAL

1.1 RELATED REQUIREMENTS

As applicable, Sections 03 31 00.00 10 CAST-IN-PLACE CONCRETE, 04 20 00 MASONRY, 05 12 00 STRUCTURAL STEEL, 05 50 00 METAL: MISCELLANEOUS AND FABRICATIONS apply to this section, with additions and modifications specified herein.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI SP-66	(2004) ACI Detailing Manual

ASTM INTERNATIONAL (ASTM)

ASTM C 27	(1998; R 2002) Fireclay and High-Alumina Refractory Brick
ASTM C 62	(2005) Building Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C 67	(2009) Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile
ASTM C 90	(2009) Loadbearing Concrete Masonry Units

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Wood Burning Stove; G

Drawings including plans, elevations, and details of wall reinforcement; details of brick work and wall intersections; offsets; tops, bottoms, and ends of walls; and wall openings. Iron and steel work shall be shown as well as flue and vent work. No approval will be given to the shop drawings until the Contractor certifies that all openings, including those for ash tray, loading, etc., are shown. If, during construction, additional masonry openings are required, the approved shop drawings shall be resubmitted with the additional openings shown

along with the proposed changes. Location of these additional openings shall be clearly highlighted. The minimum scale for wall elevations shall be 1 to 20. Reinforcement bending details shall conform to the requirements of ACI SP-66.

SD-03 Product Data

Cold Weather Installation; G

Cold weather construction procedures.

SD-04 Samples

Brick - Shale/Clay and Refractory

Concrete Masonry Units (CMU)

Color samples of three stretcher units and one unit for each type of special shape. Units shall show the full range of color and texture. Submit sample of colored mortar with applicable masonry unit.

Anchors and Ties

Two of each type used.

Expansion-Joint Materials

One piece of each type used.

SD-05 Design Data

Pre-mixed Mortar

Pre-mixed mortar composition. Calculations and certifications of masonry unit and mortar strength.

SD-07 Certificates

Clay or Shale Brick/Refractory Brick
Anchors and Ties
Expansion-Joint Materials
Masonry Cement
Admixtures for Masonry Mortar
Admixtures for Grout

Certificates of compliance stating that the materials meet the specified requirements.

Insulation

Certificate attesting that the insulation furnished for the project contains recovered material, and showing an estimated percent of such recovered material.

Contamination

SD-08 Manufacturer's Instructions

Masonry Cement

Submit the manufacturer's printed instructions on proportions of water and aggregates and on mixing to obtain the type of mortar required.

1.4 DELIVERY, HANDLING, AND STORAGE

Materials shall be delivered, handled, stored, and protected to avoid chipping, breakage, and contact with soil or contaminating material. Store and prepare materials in already disturbed areas to minimize project site disturbance and size of project site.

1.4.1 Brick

Cover and protect brick units and cementitious materials from precipitation. Conform to all handling and storage requirements of ASTM C 90. Prefabricated lintels shall be marked on top sides to show either the lintel schedule number or the number and size of top and bottom bars.

1.4.2 Anchors and Ties

Steel coated anchors and ties shall be stored above the ground. Uncoated ties shall be free of loose mill scale and rust.

1.4.3 Cementitious Materials, Sand and Aggregates

Cementitious and other packaged materials shall be delivered in unopened containers, plainly marked and labeled with manufacturers' names and brands. Cementitious material shall be stored in dry, weathertight enclosures or be completely covered. Cement shall be handled in a manner that will prevent the inclusion of foreign materials and damage by water or dampness. Sand and aggregates shall be stored in a manner to prevent contamination or segregation.

1.5 QUALITY ASSURANCE

1.5.1 Appearance

Blocks and bricks shall be manufactured at one time and from the same batch.

1.5.2 Contamination

When using bricks containing contaminated soil, supplier shall certify that the hazardous waste is neutralized by the manufacturing process and that no additional pollutants will be released, or that the product is free from hazardous contaminants.

1.5.3 Testing

Masonry strength shall be determined in accordance with ACI 530; submit test reports on three prisms as specified in ACI 530.1. The cost of testing shall be paid by the Contractor.

PART 2 PRODUCTS

2.1 MASONRY WOOD STOVE

2.1.1 Stove

Construction as follows:

- CMU walls
- Concrete housekeeping pad
- Steel support angle and channel
- Brick facing
- Firebrick lining
- Mineral wool insulation
- Steel flue box
- Cast iron stove top
- Cast iron door with hinge and latch
- Cast iron door with hinge and latch and adjustable vent
- Cast iron open grate
- stainless steel vent

2.1.2 Materials

2.1.2.1 General

Except as herein specified, provide materials for wood stove as per this Section and Sections 04 20 00 (masonry, mortar, grout, CMU), 03 31 00.00 10 (CIP concrete), 05 12 00 (support angles and channels), 05 50 00 (cast iron stove top, doors and grate and steel flue box, steel ash tray and vent), and 09 66 16 (terrazzo tile). Provide quantities, physical dimensions, colors, and characteristics as specified and indicated.

2.1.2.2 Clay or Shale Brick

Color range and texture of clay or shale brick shall be as indicated and shall conform to the approved sample. Brick shall conform to ASTM C 62; Grade SW shall be used for brick in contact with earth or grade and for all exterior work and for all nonvertical surfaces. Grade SW or MW shall be used in other brickwork. Average dimensions of brick shall be 90 mm thick, 57 mm high, and 190 mm long (standard), subject to the tolerances specified in ASTM C 62. Brick shall be tested for efflorescence. Clay or shale brick units shall be delivered factory-blended to provide a uniform appearance and color range in the completed wall.

2.1.2.3 Refractory Brick

ASTM C 27, low-duty type.

2.1.2.4 Mineral Wool Board Insulation

Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Fibrex Insulations Inc.
2. Isolatek International.
3. Owens Corning.
4. Roxul Inc.
5. Thermafiber.

Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 5 percent.

Unfaced, Mineral-Wool Board Insulation: ASTM C 612; with maximum flame-spread and smoke-developed indexes of 15 and zero, respectively, per ASTM E 84; passing ASTM E 136 for combustion characteristics.

1. Nominal density of 4 lb/cu. ft. (64 kg/cu. m), Types IA and IB, thermal resistivity of 4 deg F x h x sq. ft./Btu x in. at 75 deg F (27.7 K x m/W at 24 deg C).
2. Nominal density of 6 lb/cu. ft. (96 kg/cu. m), Type II, thermal resistivity of 4.16 deg F x h x sq. ft./Btu x in. at 75 deg F (28.8 K x m/W at 24 deg C).
3. Nominal density of 8 lb/cu. ft. (128 kg/cu. m), Type III, thermal resistivity of 4.35 deg F x h x sq. ft./Btu x in. at 75 deg F (30.2 K x m/W at 24 deg C).
4. Fiber Color: Darkened, where indicated.

2.1.2.5 Masonry Mortar

Clay/Shale Brick: See Section 04 20 00.

Fire Brick: See Section 04 20 00 except as follows: Approved commercial fire clay mortar (air setting refractory mortar such as "Sairset" from RHI Refractories) or refractory cement (calcium-aluminate) mortar for fire brick.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 General

Construct wood stove encasement and chimney (Sections 04 20 00 Masonry, 05 50 00 Metal: Miscellaneous and Fabrications) on concrete housekeeping pad (Section 03 31 00.00 10 Cast-in-place Structural Concrete) as per specifications and manufacturer's instructions. Field verify actual stove dimensions prior to fabrication of cast iron stove top, grate and doors.

3.1.2 Brick/Fire Brick

Section 04 20 00, as applicable and as follows. Brick facing shall be laid with the better face exposed. Brick shall be laid in running bond with each course bonded at corners, unless otherwise indicated. Molded brick shall be laid with the frog side down. Brick that is cored, recessed, or has other deformations may be used in sills, treads, soldier courses, except where deformations will be exposed to view. Lay fire brick by dipping each brick in a soft mixture of fire clay and water and then rubbing the brick into place with joints as thin as practicable or provide refractory mortar with joints not more than 10 mm thick.

3.1.2.1 Wetting of Units

Wetting of clay or shale brick units having an initial rate of absorption of more than 0.155 gm per minute per square cm of bed surface shall be in conformance with ASTM C 67. The method of wetting shall ensure that each unit is nearly saturated but surface dry when laid. Test clay or shale brick daily on the job, prior to laying, as follows: Using a wax pencil, draw a circle the size of a quarter on five randomly selected bricks.

Apply 20 drops of water with a medicine dropper to the surface within the circle on each brick. If the average time that the water is completely absorbed in the five bricks is less than 1-1/2 minutes, wet bricks represented by the five bricks tested.

3.1.2.2 Brick

Brick joint widths shall be the difference between the actual and nominal dimensions of the brick in either height or length. Brick expansion joint widths shall be as shown.

3.1.3 Mineral Wool

Clean substrates of substances that are harmful to insulation or that interfere with insulation attachment or placement.

Comply with insulation manufacturer's written instructions applicable to products and applications indicated.

Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.

Provide sizes to fit applications indicated and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units to produce thickness indicated unless multiple layers are otherwise shown or required to make up total thickness.

On vertical surfaces, set insulation units loosely laid according to manufacturer's written instructions.

3.2 FIELD QUALITY CONTROL

Conduct inspection and testing in the presence of the Contracting Officer to certify compliance with specified requirements, NFPA 96 and NSF 2. Affect repairs and retest until no deficiencies exist.

3.2.1 Field Inspection

Before and after installation, inspect wood stove and ancillary work for compliance with specified requirements.

3.2.2 Operation Tests

Upon completion but before final acceptance, perform wood stove operation tests to determine that components, including adjustable components, operate properly and in accordance with specified requirements.

3.3 PROTECTION

Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

3.4 CLAY OR SHALE BRICK SURFACES

Exposed clay or shale brick masonry surfaces shall be cleaned as necessary to obtain surfaces free of stain, dirt, mortar and grout daubs, efflorescence, and discoloration or scum from cleaning operations. The

exposed masonry surfaces shall be water-soaked and then cleaned with a solution proportioned 30 mL trisodium phosphate and 30 mL laundry detergent to 1 L of water or cleaned with a proprietary masonry cleaning agent specifically recommended for the color and texture by the clay products manufacturer. The solution shall be applied with stiff fiber brushes, followed immediately by thorough rinsing with clean water. Proprietary cleaning agents shall be used in conformance with the cleaning product manufacturer's printed recommendations. Efflorescence shall be removed in conformance with the brick manufacturer's recommendations.

-- End of Section --

SECTION 05 12 00

STRUCTURAL STEEL
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2005) Code of Standard Practice for Steel Buildings and Bridges
AISC 316	(1989) ASD Manual of Steel Construction
AISC 317	(1992; Reprint 1999) ASD Manual of Steel Construction, Vol II: Connections
AISC 326	(2002) Detailing for Steel Construction
AISC 348	(2000) Structural Joints Using ASTM A325 or A490 Bolts
AISC 360	(2005) Specification for Structural Steel Buildings, with Commentary
AISC FCD	(1995a) Quality Certification Program Description

AMERICAN WELDING SOCIETY (AWS)

AWS A2.4	(1998) Standard Symbols for Welding, Brazing and Nondestructive Examination
AWS D1.1/D1.1M	(2008; Errata 2009) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B46.1	(2002) Surface Texture (Surface Roughness, Waviness and Lay)

ASTM INTERNATIONAL (ASTM)

ASTM A 123/A 123M	(2009) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 325	(2009) Standard Specification for

	Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel
ASTM A 501	(2007) Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing
ASTM A 500	(2003a) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A 514/A 514M	(2005) Standard Specification for High-Yield-Strength, Quenched and Tempered Alloy Steel Plate, Suitable for Welding
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 563	(2004a) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A 563M	(2006) Standard Specification for Carbon and Alloy Steel Nuts (Metric)
ASTM A 6/A 6M	(2006a) Standard Specification for General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling
ASTM A 992/A 992M	(2006a) Standard Specification for Structural Steel Shapes
ASTM C 827	(2001a; R 2005) Change in Height at Early Ages of Cylindrical Specimens from Cementitious Mixtures
ASTM F 436	(2009) Hardened Steel Washers
ASTM C 1107/C 1107M	(2008) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM F 844	(2004) Washers, Steel, Plain (Flat), Unhardened for General Use

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1	(2000; E 2004) Shop, Field, and Maintenance Painting
SSPC Paint 25	(1997; E 2004) Paint Specification No. 25 Zinc Oxide, Alkyd,

	Linseed Oil Primer for Use Over Hand Cleaned Steel Type I and Type II
SSPC SP 3	(2004; E 2004) Power Tool Cleaning
SSPC SP 6	(2007) Commercial Blast Cleaning

1.2 SYSTEM DESCRIPTION

Provide the structural steel system, including shop primer, complete and ready for use. Structural steel systems including materials, installation, workmanship, fabrication, assembly, erection, inspection, quality control, and testing shall be provided in accordance with AISC 316 and AISC 317 except as modified in this contract.

1.3 MODIFICATIONS TO REFERENCES

Conform to AISC 316, AISC 317, AISC 360, AISC 303, and AISC 348, except as modified in this section.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Erection Plan, including description of temporary supports; G

Fabrication drawings including description of connections; G

SD-03 Product Data

Shop primer

Welding electrodes and rods

Non-Shrink Grout

Include test report for Class B primer.

SD-06 Test Reports

Class B coating

Bolts, nuts, and washers

Supply the certified manufacturer's mill reports which clearly show the applicable ASTM mechanical and chemical requirements together with the actual test results for the supplied fasteners.

SD-07 Certificates

Steel

Bolts, nuts, and washers

Galvanizing

AISC Quality Certification

Welding procedures and qualifications

1.5 AISC QUALITY CERTIFICATION

Work shall be fabricated in an AISC certified Category STD fabrication plant.

1.6 QUALITY ASSURANCE

1.6.1 Drawing Requirements

Submit fabrication drawings for approval prior to fabrication. Prepare in accordance with AISC 326, AISC 316 and AISC 317. Fabrication drawings shall not be reproductions of contract drawings. Sign and seal fabrication drawings by a professional engineer registered in the State where the project is located. Include complete information for the fabrication and erection of the structure's components, including the location, type, and size of bolts, welds, member sizes and lengths, connection details with structural analysis as to compliance to specified design loads, if/as directed, blocks, copes, and cuts. Use AWS A2.4 standard welding symbols. Shoring and temporary bracing shall be designed and sealed by a registered professional engineer and submitted for record purposes, with calculations, as part of the drawings. Member substitutions of details shown on the contract drawings shall be clearly highlighted on the fabrication drawings. Explain the reasons for any deviations from the contract drawings.

1.6.2 Certifications

1.6.2.1 Erection Plan

Submit for record purposes. Indicate the sequence of erection, temporary shoring and bracing, and a detailed sequence of welding, including each welding procedure required.

1.6.2.2 Welding Procedures and Qualifications

Prior to welding, submit certification for each welder stating the type of welding and positions qualified for, the code and procedure qualified under, date qualified, and the firm and individual certifying the qualification tests. If the qualification date of the welding operator is more than one-year old, the welding operator's qualification certificate shall be accompanied by a current certificate by the welder attesting to the fact that he has been engaged in welding since the date of certification, with no break in welding service greater than 6 months.

Conform to all requirements specified in AWS D1.1/D1.1M.

PART 2 PRODUCTS

2.1 STEEL

2.1.1 Structural Steel

ASTM A 36/A 36M.

2.1.2 Structural Shapes for Use in Building Framing

Wide flange shapes, ASTM A 992/A 992M.

2.1.3 Structural Steel Tubing

ASTM A 500, Grade B; ASTM A 501.

2.1.4 Steel Pipe

ASTM A 53/A 53M, Type E or S, Grade B, weight class STD (Standard).

2.2 BOLTS, NUTS, AND WASHERS

Provide the following unless indicated otherwise.

2.2.1 Structural Steel, Steel Pipe

2.2.1.1 Bolts

ASTM A 325, Type 1. The bolt heads and the nuts of the supplied fasteners must be marked with the manufacturer's identification mark, the strength grade and type specified by ASTM specifications.

2.2.1.2 Nuts

ASTM A 563M, Grade A, heavy hex style, except nuts under M36 may be provided in hex style.

2.2.1.3 Washers

ASTM F 436 washers for ASTM A 325 bolts.

2.2.2 Foundation Anchorage

2.2.2.1 Anchor Bolts

ASTM A 307.

2.2.2.2 Anchor Nuts

ASTM A 563, Grade A, hex style.

2.2.2.3 Anchor Washers

ASTM F 844.

2.3 STRUCTURAL STEEL ACCESSORIES

2.3.1 Welding Electrodes and Rods

AWS D1.1/D1.1M.

2.3.2 Non-Shrink Grout

ASTM C 1107/C 1107M, with no ASTM C 827 shrinkage.

2.4 SHOP PRIMER

SSPC Paint 25, (alkyd primer). Primer shall conform to Federal, State, and local VOC regulations. If flash rusting occurs, re-clean the surface prior to application of primer.

2.5 GALVANIZING

ASTM A 123/A 123M or ASTM A 153/A 153M, as indicated and applicable, unless specified otherwise galvanize after fabrication where practicable.

2.6 FABRICATION

2.6.1 Markings

Prior to erection, members shall be identified by a painted erection mark. Connecting parts assembled in the shop for reaming holes in field connections shall be match marked with scratch and notch marks. Do not locate erection markings on areas to be welded. Do not locate match markings in areas that will decrease member strength or cause stress concentrations.

2.6.2 Shop Primer

Shop prime structural steel, except as modified herein, in accordance with SSPC PA 1. Do not prime steel surfaces embedded in concrete, or surfaces within 13 mm of the toe of the welds prior to welding (except surfaces on which metal decking is to be welded). Prior to assembly, prime surfaces which will be concealed or inaccessible after assembly. Do not apply primer in foggy or rainy weather; when the ambient temperature is below 7 degrees C or over 35 degrees C; or when the primer may be exposed to temperatures below 4 degrees C within 48 hours after application, unless approved otherwise by the Contracting Officer.

2.6.2.1 Cleaning

SSPC SP 6, except steel exposed in spaces above ceilings, attic spaces, furred spaces, and chases that will be hidden to view in finished construction may be cleaned to SSPC SP 3 when recommended by the shop primer manufacturer. Maintain steel surfaces free from rust, dirt, oil, grease, and other contaminants through final assembly.

2.6.2.2 Primer

Apply primer to a minimum dry film thickness of 0.05 mm except provide the Class B coating for slip critical joints in accordance with the coating manufacturer's recommendations. Repair damaged primed surfaces with an additional coat of primer.

2.7 DRAINAGE HOLES

Adequate drainage holes shall be drilled to eliminate water traps. Hole diameter shall be 13 mm and location shall be indicated on the detail drawings. Hole size and location shall not affect the structural integrity.

PART 3 EXECUTION

3.1 FABRICATION

Fabrication shall be in accordance with the applicable provisions of AISC 316. Fabrication and assembly shall be done in the shop to the greatest extent possible. The fabricating plant shall be certified under the AISC FCD for Category STD structural steelwork.

Compression joints depending on contact bearing shall have a surface roughness not in excess of 13 micrometer as determined by ASME B46.1, and ends shall be square within the tolerances for milled ends specified in ASTM A 6/A 6M.

Shop splices of members between field splices will be permitted only where indicated on the Contract Drawings. Splices not indicated require the approval of the Contracting Officer.

3.2 ERECTION

Erection of structural steel shall be in accordance with the applicable provisions of AISC 316 or endorsement F of AISC FCD. Erection plan shall be reviewed, stamped and sealed by a licensed structural engineer.

Provide for drainage in structural steel. After final positioning of steel members, provide full bearing under base plates and bearing plates using nonshrink grout. Place nonshrink grout in accordance with the manufacturer's instructions.

3.2.1 STORAGE

Material shall be stored out of contact with the ground in such manner and location as will minimize deterioration.

3.3 CONNECTIONS

Except as modified in this section, connections not detailed shall be designed in accordance with AISC 360. Build connections into existing work. Do not tighten anchor bolts set in concrete with impact torque wrenches. Punch, subpunch and ream, or drill bolt holes perpendicular to the surface of the member. Holes shall not be cut or enlarged by burning. Bolts, nuts, and washers shall be clean of dirt and rust, and lubricated immediately prior to installation.

3.3.1 Common Grade Bolts

ASTM A 307 bolts shall be tightened to a "snug tight" fit. "Snug tight" is the tightness that exists when plies in a joint are in firm contact. If firm contact of joint plies cannot be obtained with a few impacts of an impact wrench, or the full effort of a man using a spud wrench, contact the Contracting Officer for further instructions.

3.3.2 High-Strength Bolts

ASTM A 325 bolts shall be fully tensiored to 70 percent of their minimum tensile strength. Provide load indicator bolts or washers in all ASTM A 325M bolted connections. Direct tensiion indicator tichtening, shall be the only acceptable tighentening methods. Bolts shall be installed in connection holes andn initially brought to a snug tight fit. After the

initial tightening procedure, bolts shall be fully tensioned, progressing from the most rigid part of a connection to the free edges.

3.4 GAS CUTTING

Use of gas-cutting torch in the field for correcting fabrication errors will not be permitted on any major member in the structural framing. Use of a gas cutting torch will be permitted on minor members not under stress only after approval has been obtained from the Contracting Officers.

3.5 WELDING

AWS D1.1/D1.1M, except use only shielded metal arc welding and low hydrogen electrodes for ASTM A 514/A 514M steel. Do not stress relieve ASTM A 514/A 514M steel by heat treatment. Grind exposed welds smooth as indicated. Provide AWS D1.1/D1.1M qualified welders, welding operators, and tackers.

The Contractor shall develop and submit the Welding Procedure Specifications (WPS) for all welding, including welding done using prequalified procedures. Prequalified procedures may be submitted for information only; however, procedures that are not prequalified shall be submitted for approval.

3.5.1 Removal of Temporary Welds, Run-Off Plates, and Backing Strips

Remove only from finished areas.

3.6 SHOP PRIMER REPAIR

Repair shop primer in accordance with the paint manufacturer's recommendation for surfaces damaged by handling, transporting, cutting, welding, or bolting.

3.6.1 Field Priming

Field priming of steel exposed to the weather, or located in building areas without HVAC for control of relative humidity. After erection, the field bolt heads and nuts, field welds, and any abrasions in the shop coat shall be cleaned and primed with paint of the same quality as that used for the shop coat.

3.7 FIELD QUALITY CONTROL

Perform field tests, and provide labor, equipment, and incidentals required for testing, except that electric power for field tests will be furnished as set forth in Division 1. The Contracting Officer shall be notified in writing of defective welds, bolts, nuts, and washers within 7 working days of the date of weld inspection.

3.7.1 Welds

3.7.1.1 Visual Inspection

AWS D1.1/D1.1M. Furnish the services of AWS-certified welding inspectors for fabrication and erection inspection and testing and verification inspections. Welding inspectors shall visually inspect and mark welds, including fillet weld end returns.

3.7.2 Testing

The Government has the option to perform nondestructive tests on 5 percent of the installed bolts to verify compliance with pre-load bolt tension requirements. The nondestructive testing will be done in-place using an ultrasonic measuring device or any other device capable of determining in-place pre-load bolt tension. The test locations shall be selected by the Contracting Officer. If more than 10 percent of the bolts tested contain defects identified by testing, then all bolts used from the batch from which the tested bolts were taken, shall be tested. Retest new bolts after installation.

-- End of Section --

SECTION 05 40 00

COLD-FORMED METAL FRAMING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG-973	(2002) Cold-Formed Steel Design Manual
AISI SG02-1	(2001) North American Specification for the Design of Cold-Formed Steel Structural Members

AMERICAN WELDING SOCIETY (AWS)

AWS D1.3	(1998) Structural Welding Code - Sheet Steel

ASTM INTERNATIONAL (ASTM)

ASTM A 1008/A 1008M	(2006a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardened
ASTM A 123/A 123M	(2009) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 370	(2006) Standard Test Methods and Definitions for Mechanical Testing of Steel Products
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B 633	(1998e1) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM C 955	(2006) Load-Bearing (Transverse and Axial) Steel Studs, Runners (Tracks), and Bracing or Bridging for Screw Application of

	Gypsum Panel Products and Metal Plaster Bases
ASTM E 329	(2005b) Standard Specification for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J78	(1998) Steel Self Drilling Tapping Screws

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 25	(1997; E 2004) Paint Specification No. 25 Zinc Oxide, Alkyd, Linseed Oil Primer for Use Over Hand Cleaned Steel Type I and Type II

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Framing Components; G

a. Cross sections, plans, and/or elevations showing component types and locations for each framing application; including shop coatings and material thicknesses for each framing component.

b. Connection details showing fastener type, quantity, location, and other information to assure proper installation.

c. Drawings depicting panel configuration, dimensions, components, locations, and construction sequence if the Contractor elects to install prefabricated/prefinished frames.

SD-03 Product Data

Steel studs,joists, tracks, bracing, bridging and accessories

SD-05 Design Data

Metal framing calculations; G

SD-07 Certificates

Load-bearing cold-formed metal framing

Mill certificates or test reports from independent testing agency, qualified in accordance with ASTM E 329, showing that the steel sheet used in the manufacture of each cold-formed component complies with the minimum yield strengths and uncoated steel

thickness specified. Test reports shall be based on the results of three coupon tests in accordance with ASTM A 370.

Welds

Certified copies of welder qualifications test records showing qualification in accordance with AWS D1.3.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials to job site and store in adequately ventilated, dry locations. Storage area shall permit easy access for inspection and handling. If necessary to store materials outside, stack off the ground, support on a level platform, and protect from the weather as approved. Handle materials to prevent damage. Finish of the framing members shall be maintained at all times, using an approved high zinc dust content, galvanizing repair paint whenever necessary to prevent the formation of rust. Replace damaged items with new, as directed by the Contracting Officer.

1.4 LOAD-BEARING COLD-FORMED METAL FRAMING

Include top and bottom tracks as applicable and as indicated, bracing, fastenings, and other accessories necessary for complete installation. Framing members shall have the structural properties indicated. Where physical structural properties are not indicated, they shall be as necessary to withstand all imposed loads. Design framing in accordance with AISI SG-973. Non-load-bearing metal framing, furring, and ceiling suspension systems are specified in Section 09 22 00 METAL SUPPORT ASSEMBLIES.

1.5 MAXIMUM DEFLECTION

a. Exterior Studs:

Deflection Criteria	Exterior Finish
L/240 or L/360	Synthetic Plaster, Metal Panels
L/360	Cement Plaster, Wood Veneer
L/600	Brick Veneer, Stone Panels

Wall deflections shall be computed on the basis that studs withstand all lateral forces independent of any composite action from sheathing materials. Studs abutting windows or louvers shall also be designed not to exceed 6 mm maximum deflection.

b. Floor Joists:

L/360 - Live load only
L/240 - Total load

c. Roof Rafters:

L/240 - Live load only

1.6 QUALITY ASSURANCE

1.6.1 Drawing Requirements

Submit framing components to show sizes, thicknesses, layout, material designations, methods of installation, and accessories.

1.6.2 Design Data Required

Submit metal framing calculations to verify sizes, gages, and spacing of members and connections. Show methods and practices used in installation.

PART 2 PRODUCTS

2.1 STEEL STUDS, JOISTS, TRACKS, BRACING, BRIDGING AND ACCESSORIES

Framing components shall comply with ASTM C 955 and the following.

2.1.1 Studs and Joists of 1.5 mm and Heavier

Galvanized steel, ASTM A 653/A 653M, SS Grade 50.

2.1.2 Studs and Joists of 1.2 mm and Lighter

Studs and Joists of 1.2 mm and Lighter, Track, and Accessories (All Gages): Galvanized steel, ASTM A 653/A 653M, SS, Grade 345 230 MPa Z180; or carbon steel, ASTM A 1008/A 1008M, Grade C, painted.

2.1.3 Sizes, Gages, Section Modulus, and Other Structural Properties

Size and gage as indicated. Steel stud deflection shall be limited to L/600 for exterior wall brick veneer construction.

2.2 MARKINGS

Studs and track shall have product markings stamped on the web of the section. The markings shall be repeated throughout the length of the member at a maximum spacing of 1200 mm on center and shall be legible and easily read. The product marking shall include the following:

a. An ICBO number.

b. Manufacturer's identification.

c. Minimum delivered uncoated steel thickness.

d. Protective coating designator.

e. Minimum yield strength.

2.3 CONNECTIONS

Screws for steel-to-steel connections shall be self-drilling tapping in compliance with SAE J78 of the type, size, and location as shown on the drawings. Electroplated screws shall have a Type II coating in accordance with ASTM B 633. Screws, bolts, and anchors shall be hot-dipped galvanized in accordance with ASTM A 123/A 123M or ASTM A 153/A 153M as appropriate. Screws bolts, and anchors shall be hot dipped galvanized in accordance with ASTM A 123/A 123M or ASTM A 153/A 153M as appropriate.

2.4 PAINT

Ungalvanized steel, if used, shall be thoroughly cleaned, phosphate treated, and coated with corrosion-inhibiting primer, SSPC Paint 25.

2.5 PLASTIC GROMMETS

Supply plastic grommets, recommended by stud manufacturer, to protect electrical wires. Prevent metal to metal contact for plumbing pipes.

PART 3 EXECUTION

3.1 FASTENING

Fasten framing members together by welding or by using self-drilling or self-tapping screws. Electrodes and screw connections shall be as required and indicated in the design calculations.

3.1.1 Welds

All welding shall be performed in accordance with AWS D1.3, as modified by AISI SG02-1. All welders, welding operations, and welding procedures shall be qualified according to AWS D1.3. All welds shall be cleaned and coated with rust inhibitive galvanizing paint. Do not field weld materials lighter than 1.2 mm.

3.1.2 Screws

Screws shall be of the self-drilling self-tapping type, size, and location shown on the drawings. Screw penetration through joined materials shall not be less than three exposed threads. Minimum spacings and edge distances for screws shall be as specified in AISI SG02-1. Screws covered by sheathing materials shall have low profile heads.

3.1.3 Anchors

Anchors shall be of the type, size, and location shown on the drawings.

3.2 INSTALLATION

3.2.1 Tracks

Provide accurately aligned runners at top and bottom of partitions. Anchor tracks as indicated in design calculations. Butt weld joints in tracks or splice with stud inserts. Fasteners shall be at least 75 mm from the edge of concrete slabs.

3.2.2 Studs

Cut studs square and set with firm bearing against webs of top and bottom tracks. Position studs vertically in tracks and space as indicated in design. Do not splice studs. Provide at least two studs at jambs of doors and other openings 600 mm wide or larger. Provide jack studs over openings, as necessary, to maintain indicated stud spacing. Provide tripled studs at corners, positioned to receive interior and exterior finishes. Fasten studs to top and bottom tracks by welding or screwing both flanges to the tracks. Framed wall openings shall include headers and supporting components as shown on the drawings. Headers shall be installed

in all openings that are larger than the stud spacing in a wall. In curtain wall construction, provide for vertical movement where studs connect to the structural frame. Provide horizontal bracing in accordance with the design calculations and AISI SG-973, consisting of, as a minimum, runner channel cut to fit between and welded to the studs or hot- or cold-rolled steel channels inserted through cutouts in web of each stud and secured to studs with welded clip angles. Bracing shall be not less than the following:

LOAD	HEIGHT	BRACING
Wind load only	Up to 3000 mm	One row at mid-height
	Over 3000 mm	Rows 1500 mm o.c. maximum
Axial load	Up to 3000 mm	Two rows at 1/3 points
	Over 3000 mm	Rows 900 mm o.c. maximum

3.2.3 Joists and Trusses

Locate each joist or truss directly above a stud. Provide doubled joists under parallel partitions wherever partition length exceeds 1/2 of joist span. Joists shall have at least 60 mm of bearing on steel, 100 mm on masonry, and shall be reinforced over bearings where required to prevent web crippling. Splice joists over bearings only. Lap and weld splices as indicated. Provide manufacturer's standard bridging which shall not be less than the following:

CLEAR SPAN	BRIDGING
Up to 4200 mm	One row near center
4200 mm to 6000 mm	Two rows at 1/3 points
6000 mm to 7800 mm	Three rows at 1/4 points
7800 mm to 10600 mm	Four rows at 1/5 points

Temporary bracing shall be provided and remain in place until work is permanently stabilized.

3.2.4 Erection Tolerances

a. Framing members which will be covered by finishes such as wallboard, plaster, or ceramic tile set in a mortar setting bed, shall be within the following limits:

(1) Layout of walls and partitions: 6 mm from intended position;

(2) Plates and runners: 6 mm in 2400 mm from a straight line;

(3) Studs: 6 mm in 2400 mm out of plumb, not cumulative; and

(4) Face of framing members: 6 mm in 2400 mm from a true plane.

b. Framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive shall be within the following limits:

(1) Layout of walls and partitions: 6 mm from intended position;

(2) Plates and runners: 3 mm in 2400 mm from a straight line;

(3) Studs: 3 mm in 2400 mm out of plumb, not cumulative; and

(4) Face of framing members: 3 mm in 2400 mm from a true plane.

-- End of Section --

SECTION 05 50 13

MISCELLANEOUS METAL FABRICATIONS
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2005) Code of Standard Practice for Steel Buildings and Bridges

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.3	(2006) Operations - Safety Requirements for Powder Actuated Fastening Systems

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2008; Errata 2009) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(1996; Addenda A 1999; Errata 2003; R 2005) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(1987; R 2005) Standard for Square and Hex Nuts
ASME B18.21.2M	(1999; R 2005) Lock Washers (Metric Series)
ASME B18.22M	(1981; R 2005) Metric Plain Washers
ASME B18.6.2	(1998; R 2005) Slotted Head Cap Screws, Square Head Set Screws, and Slotted Headless Set Screws: Inch Series
ASME B18.6.3	(2003; R 2008) Machine Screws and Machine Screw Nuts

ASTM INTERNATIONAL (ASTM)

ASTM A 123/A 123M	(2009) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 319	(1971; R 2006) Standard Specification for Gray Iron Castings for Elevated Temperatures for Non-Pressure Containing Parts
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel
ASTM A 47/A 47M	(1999; R 2009) Standard Specification for Steel Sheet, Aluminum-Coated, by the Hot-Dip Process
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A 687	(1993) Standard Specification for High-Strength Nonheaded Steel Bolts and Studs
ASTM A 780/A 780M	(2001; R 2006) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A 786/A 786M	(2005) Standard Specification for Hot-Rolled Carbon, Low-Alloy, High-Strength Low-Alloy, and Alloy Steel Floor Plates
ASTM A 924/A 924M	(2009) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM D 1187	(1997; R 2002e1) Asphalt-Base Emulsions for Use as Protective Coatings for Metal

MASTER PAINTERS INSTITUTE (MPI)

MPI 79	(Oct 2009) Alkyd Anti-Corrosive Metal Primer

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 211	(2006) Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 3	(2004; E 2004) Power Tool Cleaning

SSPC SP 6 (2007) Commercial Blast Cleaning

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication drawings of structural steel door frames;

Access doors and panels, installation drawings;

Cover plates and frames, installation drawings;

Expansion joint covers, installation drawings;

Floor gratings and exterior stair trends, and landings installation drawings;

Handrails, installation drawings; G

Ladders, installation drawings; G

Embedded angles and plates, installation drawings;

Metal Window Sills, Installation Drawings;

Steel Corner Guards, Installation Drawings;

Stainless Steel Back Splash, Installation Drawings;

Submit fabrication drawings showing layout(s), connections to structural system, and anchoring details as specified in AISC 303.

Submit templates, erection and installation drawings indicating thickness, type, grade, class of metal, and dimensions. Show construction details, reinforcement, anchorage, and installation with relation to the building construction.

SD-03 Product Data

Access doors and panels;

Cover plates and frames;

Control-joint covers;

Expansion joint covers;

Handrails;

Ladders;

Steel stairs;

Window sub sill;

Cast iron plate for wood stove top;

Cast iron grid plate for wood stove fire box;

Cast iron insert for wood stove;

Cast iron hinged cleanout door for wood stove;

Cast iron sliding fire box door for wood stove;

Structural steel door frames;

Window and door guards;

Roof hatch

Floor hatch

Steel corner guard

Stainless steel back splash

SD-04 Samples

Expansion joint covers

Control-joint covers

Steel corner guards

Stainless steel back splash

Provide full size samples, taken from manufacturer's stock, and be complete as required for installation in the structure. Samples may be installed in the work, provided each sample is clearly identified and its location recorded.

1.3 QUALIFICATION OF WELDERS

Qualify welders in accordance with AWS D1.1/D1.1M. Use procedures, materials, and equipment of the type required for the work.

1.4 DELIVERY, STORAGE, AND PROTECTION

Protect from corrosion, deformation, and other types of damage. Store items in an enclosed area free from contact with soil and weather. Remove and replace damaged items with new items.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Structural Carbon Steel

ASTM A 36/A 36M.

2.1.2 Steel Pipe

ASTM A 53/A 53M, Type E or S, Grade B.

2.1.3 Fittings for Steel Pipe

Standard malleable iron fittings ASTM A 47/A 47M.

2.1.4 Floor Plates, Patterned

Floor plate ASTM A 786/A 786M. Steel plate shall not be less than 1.9 mm.

2.1.5 Anchor Bolts

ASTM A 307. Where exposed, shall be of the same material, color, and finish as the metal to which applied.

2.1.5.1 Expansion Anchors, Sleeve Anchors, Adhesive Anchors, and Toggle Anchors

Provide anchors as required for adequate embedment, pullout strength and shear strength.

For anchors in CMU (solid and/or hollow wall) use shield type bolt/caulking anchors, ASTM B 633 (Machine screws or bolts); or super plastic anchors (sheet metal screwa or lag screws); or heavy duty toggle anchors (CMU hollow wall applications only), ASTM B 633 from IBS, Inc., 1-800-628-1906 or equivalent.

2.1.5.2 Lag Screws and Bolts

ASME B18.2.1, type and grade best suited for the purpose.

2.1.5.3 Toggle Bolts

ASME B18.2.1.

2.1.5.4 Bolts, Nuts, Studs and Rivets

ASME B18.2.2 and ASTM A 687 or ASTM A 307.

2.1.5.5 Powder Driven Fasteners

Follow safety provisions of ASSE/SAFE A10.3.

2.1.5.6 Screws

ASME B18.2.1, ASME B18.6.2, and ASME B18.6.3.

2.1.5.7 Washers

Provide plain washers to conform toASME B18.22M. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers to conform to ASME B18.21.2M.

2.1.6 Stainless Steel Backsplash

Conform to ASTM A 319.

2.1.7 Cast Iron

Conform to ASTM A 319.

2.2 FABRICATION FINISHES

2.2.1 Galvanizing

Hot-dip galvanize items specified to be zinc-coated, after fabrication where practicable. Galvanizing: ASTM A 123/A 123M, ASTM A 153/A 153M, ASTM A 653/A 653M or ASTM A 924/A 924M, Z275, as applicable.

2.2.2 Galvanize

Anchor bolts, grating fasteners, washers, and parts or devices necessary for proper installation, unless indicated otherwise.

2.2.3 Repair of Zinc-Coated Surfaces

Repair damaged surfaces with galvanizing repair method and paint conforming to ASTM A 780/A 780M or by application of stick or thick paste material specifically designed for repair of galvanizing, as approved by Contracting Officer. Clean areas to be repaired and remove slag from welds. Heat surfaces to which stick or paste material is applied, with a torch to a temperature sufficient to melt the metallics in stick or paste; spread molten material uniformly over surfaces to be coated and wipe off excess material.

2.2.4 Shop Cleaning and Painting

2.2.4.1 Surface Preparation

Blast clean surfaces in accordance with SSPC SP 6. Surfaces that will be exposed in spaces above ceiling or in attic spaces, crawl spaces, furred spaces, and chases may be cleaned in accordance with SSPC SP 3 in lieu of being blast cleaned. Wash cleaned surfaces which become contaminated with rust, dirt, oil, grease, or other contaminants with solvents until thoroughly clean. Steel to be embedded in concrete shall be free of dirt and grease. Do not paint or galvanize bearing surfaces, including contact surfaces within slip critical joints, but coat with rust preventative applied in the shop.

2.2.4.2 Pretreatment, Priming and Painting

Apply pretreatment, primer, and paint in accordance with manufacturer's printed instructions. On surfaces concealed in the finished construction or not accessible for finish painting, apply an additional prime coat to a minimum dry film thickness of 0.03 mm. Tint additional prime coat with a small amount of tinting pigment.

2.3 ACCESS DOORS AND PANELS

Provide flush type access doors and panels unless otherwise indicated. Fabricate frames for access doors of steel not lighter than 1.9 mm with welded joints and anchorage for securing into construction. Provide access doors with a minimum of 350 by 500 mm and of not lighter than 1.9 mm steel, with stiffened edges and welded attachments. Provide access doors hinged to frame and with a flush-face, turn-screw-operated latch. Provide exposed metal surfaces with a shop applied prime coat.

2.4 CONTROL-JOINT COVERS

Provide indicated control-joint covers to be located on surfaces of concrete, masonry indicated and tile work. Provide protective coating on the surface in contact with concrete, masonry or tile.

2.5 EXPANSION JOINT COVERS

Provide expansion joint covers constructed of extruded aluminum with anodized satin aluminum finish for walls and ceilings and with standard mill finish for floor covers and exterior covers. Furnish plates, backup angles, expansion filler strip and anchors as indicated. Provide a 2-hour fire rating expansion joint system.

2.6 GUARD POSTS (BOLLARDS/PIPE GUARDS)

Provide 200 mm prime coated extra strong weight steel pipe as specified in ASTM A 53/A 53M. Anchor posts in concrete as indicated, fill solidly with concrete with minimum compressive strength of 17 MPa and paint as indicated.

2.7 MISCELLANEOUS PLATES AND SHAPES

Provide for items that do not form a part of the structural steel framework.

Provide angles and plates, ASTM A 36/A 36M, for embedment as indicated. Galvanize embedded items exposed to the elements according to ASTM A 123/A 123M.

2.8 CHIMNEYS, VENTS, AND SMOKESTACKS

Design and construct chimneys and vents in accordance with NFPA 211. Form chimney connectors of not lighter than 1.01 mm (20 gauge) galvanized steel. Design and construct stacks to withstand a wind velocity as indicated on structural drawings. Weld seams and joints, except provide an angle flange for connection to equipment, and stack support.

2.9 CLEANOUT DOORS

Provide cast iron cleanout doors with frames, and unless otherwise indicated sized to match flues. Provide a continuous flange and anchors for securing frames into masonry. The doors shall be smokeproof, hinged, and have fastening devices to hold the door closed.

2.10 WINDOW SUB-SILL

If/as indicated, provide window sub-sill of extruded aluminum alloy with size and design indicated. Provide not less than two anchors per window section for securing into mortar joints of masonry sill course. Provide sills for banks of windows with standard mill finish with a protective coating, prior to shipment, of two coats of a clear, colorless, methacrylate lacquer applied to all surfaces of the sills.

2.11 ALUMINUM SILL

Aluminum sill enclosures shall be extruded at 20 gage and dimensions and profile as required and indicated.

2.12 STAINLESS STEEL BACK SPLASH

Stainless steel back splash at propane stove shall be 18' gage with #4 brushed finish, and dimensions and profile as required and indicated.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Install items at locations indicated, according to notes and manufacturer's instructions. Verify all measurements and take all field measurements necessary before fabrication. Exposed fastenings shall be compatible materials, shall generally match in color and finish, and harmonize with the material to which fastenings are applied. Include materials and parts necessary to complete each item, even though such work is not definitely shown or specified. Poor matching of holes for fasteners shall be cause for rejection. Conceal fastenings where practicable. Thickness of metal and details of assembly and supports shall provide strength and stiffness. Form joints exposed to the weather shall be formed to exclude water. Items listed below require additional procedures.

3.2 WORKMANSHIP

Provide miscellaneous metalwork that is well formed to shape and size, with sharp lines and angles and true curves. Drilling and punching shall produce clean true lines and surfaces. Provide continuous welding along the entire area of contact except where tack welding is permitted. Do not tack weld exposed connections of work in place and ground smooth. Provide a smooth finish on exposed surfaces of work in place and unless otherwise approved, flush exposed riveting. Mill joints where tight fits are required. Corner joints shall be coped or mitered, well formed, and in true alignment. Accurately set work to established lines and elevations and securely fastened in place. Install in accordance with manufacturer's installation instructions and approved drawings, cuts, and details.

3.3 ANCHORAGE, FASTENINGS, AND CONNECTIONS

Provide anchorage where necessary for fastening miscellaneous metal items securely in place. Include for anchorage not otherwise specified or indicated slotted inserts, expansion shields, and powder-driven fasteners, when approved for concrete; toggle bolts and through bolts for masonry; machine and carriage bolts for steel; through bolts, lag bolts, and screws for wood. Do not use wood plugs in any material. Provide non-ferrous attachments for non-ferrous metal. Make exposed fastenings of compatible materials, generally matching in color and finish, to which fastenings are applied. Conceal fastenings where practicable.

3.4 BUILT-IN WORK

Form for anchorage metal work built-in with concrete or masonry, or provide with suitable anchoring devices as indicated or as required. Furnish metal work in ample time for securing in place as the work progresses.

3.5 WELDING

Perform welding, welding inspection, and corrective welding, in accordance with AWS D1.1/D1.1M. Use continuous welds on all exposed connections. Grind visible welds smooth in the finished installation.

3.6 FINISHES

3.6.1 Dissimilar Materials

Where dissimilar metals are in contact, protect surfaces with a coat conforming to MPI 79 to prevent galvanic or corrosive action. Where aluminum is in contact with concrete, plaster, mortar, masonry, wood, or absorptive materials subject to wetting, protect with ASTM D 1187, asphalt-base emulsion.

3.7 ACCESS PANELS

Install removable access panels where indicated including in CMU construction at lavatories. Fasten access panel and frame using the specified anchors that permit re-use if and when removing screws and access panel and frame. Install as per manufacturer's instructions.

3.8 CONTROL-JOINT COVERS

Provide covers over control-joints and fasten on one side only with fasteners spaced to give positive contact with wall surfaces on both sides of joint throughout the entire length of cover.

3.9 COVER PLATES AND FRAMES

Install the tops of cover plates and frames flush with floor.

3.10 HANDRAILS

Toeboards and brackets shall be installed where indicated. Splices, where required, shall be made at expansion joints. Removable sections shall be installed as indicated.

3.10.1 Steel Handrail

Install in pipe sleeves embedded in concrete and filled with non-shrink grout or quick setting anchoring cement with anchorage covered with standard pipe collar pinned to post or by means of pipe sleeves secured to masonry with expansion shields and bolts or toggle bolts or by means of base plates bolted to stringers or structural steel frame work. Secure rail ends by steel pipe flanges anchored by expansion shields and bolts.

3.11 LADDERS

Secure to the adjacent construction with the clip angles attached to the stringer. Secure to masonry or concrete with not less than two 12 mm diameter expansion bolts. Install intermediate clip angles not over 1200 mm on center. Install brackets as required for securing of ladders welded or bolted to structural steel or built into the masonry or concrete. In no case shall ends of ladders rest upon floor.

3.12 STEEL STAIRS

Provide anchor bolts, grating fasteners, washers, and all parts or devices necessary for proper installation. Provide lock washers under nuts.

3.13 INSTALLATION OF CHIMNEYS, VENTS, AND SMOKESTACKS

Install chimneys and vents in accordance with NFPA 211. Provide a cleanout opening with a tight-fitting, hinged, cast-iron door and frame at the base of each smokestack. Provide a top band on stacks for attachment of painter's rigging. Provide roof housing, rain cap, downdraft diverter, fire damper, and other accessories required for a complete installation. Join sections of prefabricated lined stacks with acid-resisting high-temperature cement and steel draw bands. Provide means to prevent accumulation of water in the smokestack.

3.14 INSTALLATION OF GUARD POSTS (BOLLARDS/PIPE GUARDS)

Set pipe guards vertically in concrete piers. Construct piers of, and the hollow cores of the pipe filled with, concrete having a compressive strength of 21 MPa.

3.15 INSTALLATION OF SAFETY NOSINGS

Nosing shall be completely embedded in concrete before the initial set of the concrete occurs and shall finish flush with the top of the concrete surface.

3.16 INSTALLATION OF METAL WINDOW SUB-SILL

Extend the metal window sill a minimum of 20 mm under the bottom of the aluminum windows. Install masonry mortar under the metal sub-sill as required for a smooth surface under the window sills. Sills shall slope a minimum of 6 mm to the exterior and not allow water to puddle.

3.17 INSTALLATION OF STAINLESS STEEL BACK SPLASH

Attach to surface with stainless steel screws.

3.18 INSTALLATION OF PROPANE STOVE STEEL CORNER GUARDS

Weld miter corners, attach to surface with 6 mm anchors, 300 mm or center, minimum 2 anchors per angle, as indicated.

-- End of Section --

SECTION 05 52 00

METAL RAILINGS
04/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 314	(1990; R 2004) Standard Specification for Steel Anchor Bolts

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISC/AISI 121	(2004) Standard Definitions for Use in the Design of Steel Structures

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI B18.22M	(1981; R 2005) Metric Plain Washers

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2008; Errata 2009) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B18.2.3.8M	(1981; R 2005) Metric Hex Lag Screws
ASME B18.6.7M	(1999; R 2005) Metric Machine Screws

ASTM INTERNATIONAL (ASTM)

ASTM A 108	(2007) Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished
ASTM A 123/A 123M	(2009) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 283/A 283M	(2003; R 2007) Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel

ASTM A 500/A 500M	(2007) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A 512	(2006) Standard Specification for Cold-Drawn Buttweld Carbon Steel Mechanical Tubing
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 575	(1996; R 2007) Standard Specification for Steel Bars, Carbon, Merchant Quality, M-Grades
ASTM C 514	(2004) Standard Specification for Nails for the Application of Gypsum Board
ASTM E 488	(1996; R 2003) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements
ASTM F 568M	(2007) Standard Specification for Carbon and Alloy Steel Externally Threaded Metric Fasteners

INDUSTRIAL FASTENERS INSTITUTE (IFI)

IFI 502	(1982) Metric Tapping Screws

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 521	(2001) Pipe Railing Manual

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Submit fabrication drawings for the following items in accordance with the paragraph entitled, "General Requirements," of this section.

Iron and Steel Hardware

Steel Shapes, Plates, Bars and Strips

Steel Railings and Handrails

SD-03 Product Data

Submit manufacturer's catalog data including two copies of manufacturers specifications, load tables, dimension diagrams, and anchor details for the following items:

Structural Steel Plates, Shapes, and Bars

Structural Steel Tubing

Cold Finished Steel Bars

Hot-Rolled Carbon Steel Bars

Cold-Drawn Steel Tubing

Concrete Inserts

Masonry Anchorage Devices

Protective Coating

Steel Railings and Handrails

SD-07 Certificates

Submit Welding Procedures in accordance with AWS D1.1/D1.1M.

Submit certificates for Welder Qualification in accordance with the paragraph entitled, "Qualifications for Welding Work," of this section.

SD-08 Manufacturer's Instructions

Submit manufacturer's installation instructions for the following products to be used in the fabrication of steel stair work.

Structural Steel Plates, Shapes, and Bars

Structural Steel Tubing

Cold Finished Steel Bars

Hot-Rolled Carbon Steel Bars

Cold-Drawn Steel Tubing

Protective Coating

Masonry Anchorage Devices

Steel Railings and Handrails

1.3 QUALIFICATIONS FOR WELDING WORK

Provide Welding Procedures testing in accordance with AWS D1.1/D1.1M made in the presence of the Contracting Officer and by an approved testing laboratory at the Contractor's expense.

Provide certified Welder Qualification by tests in accordance with AWS D1.1/D1.1M, or under an equivalent approved qualification test. In

addition be performed on test pieces in positions and with clearances equivalent to those actually encountered. If a test weld fails to meet requirements, make an immediate retest of two test welds and each test weld must pass. Failure in the immediate retest will require that the welder be retested after further practice or training and make a complete set of test welds.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

Provide complete and detailed fabrication drawings for all Iron and Steel Hardware, and for all Steel Shapes, Plates, Bars and Strips used in accordance with the design specifications referenced in this section.

Preassemble items in the shop to the greatest extent possible. Disassemble units only to the extent necessary for shipping and handling. Clearly mark units for reassembly and coordinated installation.

For the fabrication of work exposed to view, use only materials that are smooth and free of surface blemishes, including pitting, seam marks, roller marks, rolled trade names, and roughness. Remove blemishes by grinding, or by welding and grinding, prior to cleaning, treating, and application of surface finishes, including zinc coatings.

2.2 STRUCTURAL STEEL PLATES, SHAPES AND BARS

Structural-size shapes and plates, except plates to be bent or cold-formed, must conform to ASTM A 36/A 36M, unless otherwise noted.

Steel plates to be bent or cold-formed must conform to ASTM A 283/A 283M, Grade C.

Steel bars and bar-size shapes must conform to ASTM A 36/A 36M, unless otherwise noted.

2.3 STRUCTURAL STEEL TUBING

Structural steel tubing, hot-formed, welded or seamless, must conform to ASTM A 500/A 500M, Grade B, unless otherwise noted.

2.4 HOT-ROLLED CARBON STEEL BARS

Bars and bar-size shapes must conform to ASTM A 575, grade as selected by the fabricator.

2.5 COLD-FINISHED STEEL BARS

Bars must conform to ASTM A 108, grade as selected by the fabricator.

2.6 COLD-DRAWN STEEL TUBING

Tubing must conform to ASTM A 512, sunk drawn, butt-welded, cold-finished, and stress-relieved.

2.7 STEEL PIPE

Pipe must conform to ASTM A 53/A 53M, type as selected, Grade B; primed finish, unless galvanizing is required; standard weight (Schedule 40).

2.8 CONCRETE INSERTS

Provide carbon steel bolts having special wedge-shaped heads, nuts, washers, and shims, galvanized in accordance with ASTM A 153/A 153M. Provide slotted-type concrete inserts consisting of galvanized 3 millimeter thick pressed steel plate conforming to ASTM A 283/A 283M; they must be of box-type welded construction with slot designed to receive M20 diameter square-head bolt with knockout cover; and hot-dip galvanized in accordance with ASTM A 123/A 123M.

2.9 MASONRY ANCHORAGE DEVICES

Provide masonry anchorage devices consisting of expansion shields complying with AASHTO M 314, ASTM E 488 and ASTM C 514 as follows:

Provide lead expansion shields for machine screws and bolts 6 millimeter and smaller; head-out embedded nut type, single unit class, Group I, Type 1, Class 1.

Provide lead expansion shields for machine screws and bolts larger than 6 millimeter in size; head-out embedded nut type, multiple unit class, Group I, Type 1, Class 2.

Provide bolt anchor expansion shields for lag bolts; zinc-alloy, long shield anchors class, Group II, Type 1, Class 1.

Provide bolt anchor expansion shields for bolts; closed-end bottom bearing class, Group II, Type 2, Class 1.

2.10 FASTENERS

Galvanize zinc-coated fasteners in accordance with ASTM A 153/A 153M and used for exterior applications or where built into exterior walls or floor systems. Select fasteners for the type, grade, and class required for the installation of steel stair items.

Standard bolts and nuts must be regular hexagon-head conforming to ASTM F 568M.

Lag bolts must be square-head conforming to ASME B18.2.3.8M.

Machine screws cadmium-plated steel conforming to ASME B18.6.7M.

Wood screws must be flat-head carbon steel conforming to IFI 502.

Plain washers must be round, general-assembly-grade, carbon steel conforming to ANSI B18.22M.

Lockwashers must be helical spring, carbon steel conforming to ASME B18.2.3.8M.

2.11 GENERAL FABRICATION

Provide Railings and Handrails detail plans and elevations at not less than 1 to 12 scale. Provide details of sections and connections at not less than 1 to 4 scale. Also detail setting drawings, diagrams, templates for installation of anchorages, including concrete inserts, anchor bolts, and miscellaneous metal items having integral anchors.

Use materials of size and thicknesses indicated or, if not indicated, of required size and thickness to produce adequate strength and durability in finished product for intended use. Work materials to dimensions indicated on approved detail drawings, using proven details of fabrication and support. Use type of materials indicated or specified for the various components of work.

Form exposed work true to line and level with accurate angles and surfaces and straight sharp edges. Exposed edges must be eased to a radius of approximately 0.8 millimeter. Bend metal corners to the smallest radius possible without causing grain separation or otherwise impairing the work.

Weld corners and seams continuously and in accordance with the recommendations of AWS D1.1/D1.1M. Grid exposed welds smooth and flush to match and blend with adjoining surfaces.

Form exposed connections with hairline joints that are flush and smooth, using concealed fasteners wherever possible. Use exposed fasteners of the type indicated or, if not indicated, use Phillips flathead (countersunk) screws or bolts.

Provide anchorage of the type indicated and coordinated with the supporting structure. Fabricate anchoring devices and space as indicated and as required to provide adequate support for the intended use of the work.

Use hot-rolled steel bars for work fabricated from bar stock unless work is indicated or specified to be fabricated from cold-finished or cold-rolled stock.

2.12 PROTECTIVE COATING

Shop prime steelwork as indicated in accordance with AISC/AISI 121 except surfaces of steel to be encased in concrete, surfaces to be welded, contact surfaces to be high-strength bolt connected, and surfaces of crane rails.

Provide hot dipped galvanized steelwork as indicated in accordance with ASTM A 123/A 123M. Touch up abraded surfaces and cut ends of galvanized members with zinc-dust, zinc-oxide primer, or an approved galvanizing repair compound.

2.13 STEEL RAILINGS AND HANDRAILS

Design handrails to resist a concentrated load of 490 N in any direction at any point of the top of the rail or 290 N/m applied horizontally to top of the rail, whichever is more severe. NAAMM AMP 521, provide the same size rail and post. Provide pipe collars of the same material and finish as the handrail and posts.

2.13.1 Steel Handrails

Provide steel handrails, including inserts in concrete, steel pipe conforming to ASTM A 53/A 53M or structural tubing conforming to ASTM A 500/A 500M, Grade A or B of equivalent strength. Provide steel railings of 40 mm nominal size. Railings to be hot-dip galvanized and shop painted.

Fabrication: Joint posts, rail, and corners by one of the following methods:

(1) Flush-type rail fittings of commercial standard, welded and ground smooth with railing splice locks secured with 10 mm hexagonal-recessed-head setscrews.

(2) Mitered and welded joints made by fitting post to top rail and intermediate rail to post, mitering corners, groove welding joints, and grinding smooth. Butt railing splices and reinforce them by a tight fitting interior sleeve not less than 150 mm long.

(3) Railings may be bent at corners in lieu of jointing, provided bends are made in suitable jigs and the pipe is not crushed.

Provide kickplates between railing posts where indicated, and consist of 4 millimeter steel flat bars not less than 150 millimeter high. Secure kickplates as indicated.

Galvanize exterior railings, including pipe, fittings, brackets, fasteners, and other ferrous metal components. Provide black steel pipe for interior railings.

PART 3 EXECUTION

3.1 STAIR RAILINGS AND HANDRAILS

Adjust railings prior to securing in place to ensure proper matching at butting joints and correct alignment throughout their length. Space posts not more than 2440 millimeter on center. Plumb posts in each direction. Secure posts and rail ends to building construction as follows:

Anchor posts in concrete by means of pipe sleeves set and anchored into concrete. Provide sleeves of galvanized, standard weight, steel pipe, not less than 150 millimeter long, and having an inside diameter not less than 13 millimeter greater than the outside diameter of the inserted pipe post. Provide steel plate closure secured to the bottom of the sleeved; closure must be of width and length not less than 25 millimeter greater than the outside diameter of the sleeve. After posts have been inserted into sleeves, the annular space between post and sleeve must be filled with molten lead, sulfur, or a quick-setting hydraulic cement. Cover anchorage joint with a round steel flange welded to the post.

Anchor posts to steel with steel oval flanges, angle type or floor type as required by conditions, welded to posts and bolted to the steel supporting members.

Anchor rail ends into concrete and masonry with steel round flanges welded to rail ends and anchored into the wall construction with lead expansion shields and bolts.

Anchor rail ends to steel with steel oval or round flanges welded to tail ends and bolted to the structural steel members.

Secure handrails to walls by means of wall brackets and wall return fitting at handrail ends. Provide brackets of malleable iron castings, with not less than 75 millimeter projection from the finish wall surface to the center of the pipe drilled to receive one M10 bolt. Locate brackets not more than 1525 millimeter on center. Provide wall return fittings of cast iron castings, flush-type, with the same projection as that specified for

wall brackets. Secure wall brackets and wall return fittings to building construction as follows:

For concrete and solid masonry anchorage, use bolt anchor expansion shields and lag bolts.

For hollow masonry and stud partition anchorage, use toggle bolts having square heads.

Install toeboards and brackets where indicated. Make splices, where required, at expansion joints. Install removable sections as indicated.

3.2 STEEL HANDRAIL

Install in pipe sleeves embedded in concrete and filled with non-shrink grout or quick setting anchoring cement with anchorage covered with standard pipe collar pinned to post. Secure rail ends by steel pipe flanges anchored by expansion shields and bolts.

3.3 FIELD WELDING

Procedures of manual shielded metal arc welding, appearance and quality of welds made, and methods used in correcting welding work must comply with AWS D1.1/D1.1M.

3.4 TOUCHUP PAINTING

Immediately after installation, clean field welds, bolted connections, and abraded areas of the shop paint and exposed areas painted with the paint used for shop painting. Apply paint by brush or spray to provide a minimum dry-film thickness of 0.051 millimeter.

-- End of Section --

SECTION 06 10 00

ROUGH CARPENTRY
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)

AF&PA T10	(2001) Wood Frame Construction Manual for One- and Two-Family Dwellings
AF&PA T101	(2001) National Design Specification (NDS)for Wood Construction

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA E30	(2005) Engineered Wood Construction Guide
APA E445S	(2001; R 2002) Performance Standards and Qualification Policy for Structural-Use Panels (APA PRP-108)
APA F405L	(1999) Performance Rated Panels
APA PS 1	(1995) Voluntary Product Standard for Construction and Industrial Plywood
APA PS 2	(2004) Voluntary Product Standard for Wood-Based Structural-Use Panels

ASME INTERNATIONAL (ASME)

ASME B18.2.2	(1987; R 2005) Standard for Square and Hex Nuts
ASME B18.5.2.1M	(2006) Metric Round Head Short Square Neck Bolts
ASME B18.5.2.2M	(1982; R 2005) Metric Round Head Square Neck Bolts
ASME B18.52.1	(1996; R 2005) Square and Hex Bolts and Screws Inch Series
ASME B18.6.1	(1981; R 2008) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength

ASTM A 687	(1993) Standard Specification for High-Strength Nonheaded Steel Bolts and Studs
ASTM F 1667	(2003) Driven Fasteners: Nails, Spikes, and Staples
ASTM F 547	(2001) Nails for Use with Wood and Wood-Base Materials

FM GLOBAL (FM)

FM DS 1-49	(2000) Perimeter Flashing

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2006) International Building Code

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1923	(Rev A; Notice 1) Shield, Expansion (Lag, Machine and Externally Threaded Wedge Bolt Anchors)
CID A-A-1924	(Rev A; Notice 1) Shield, Expansion (Self Drilling Tubular Expansion Shell Bolt Anchors
CID A-A-1925	(Rev A; Notice 1) Shield Expansion (Nail Anchors)
FS FF-B-588	(Rev E) Bolt, Toggle: and Expansion Sleeve, Screw
FS FF-T-1813	(Basic) Tack
FS UU-B-790	(Rev A) Building Paper, Vegetable Fiber: (Kraft, Waterproofed, Water Repellent and Fire Resistant)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Nailers and Nailing Strips

Drawings of field erection details, including materials and methods of fastening nailers in conformance with Factory Mutual wind uplift rated systems specified in other Sections of these specifications.

SD-03 Product Data

Adhesives

Submit manufacturer's product data, indicating VOC content.

SD-07 Certificates

Certificates of grade

Manufacturer's certificates (approved by an American Lumber Standards approved agency) attesting that lumber and material not normally grade marked meet the specified requirements. Certificate of Inspection for grade marked material by an American Lumber Standards Committee (ALSC) recognized inspection agency prior to shipment.

Preservative treatment

1.3 DELIVERY AND STORAGE

Deliver materials to the site in an undamaged condition. Store, protect, handle, and install prefabricated structural elements in accordance with manufacturer's instructions and as specified. Store materials off the ground to provide proper ventilation, with drainage to avoid standing water, and protection against ground moisture and dampness. Store materials with a moisture barrier at both the ground level and as a cover forming a well ventilated enclosure. Store wood I-beams and glue-laminated beams and joists on edge. Adhere to requirements for stacking, lifting, bracing, cutting, notching, and special fastening requirements. Remove defective and damaged materials and provide new materials. Store separated reusable wood waste convenient to cutting station and area of work.

1.4 GRADING AND MARKING

1.4.1 Lumber

Mark each piece of framing and board lumber or each bundle of small pieces of lumber with the grade mark of a recognized association or independent inspection agency. Such association or agency shall be certified by the Board of Review, American Lumber Standards Committee, to grade the species used. Surfaces that are to be exposed to view shall not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

1.4.2 Plywood

Mark each sheet with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood. The mark shall identify the plywood by species group or span rating, exposure durability classification, grade, and compliance with APA PS 1.Surfaces that are to be exposed to view shall not bear grademarks or other types of identifying marks.

1.5 SIZES AND SURFACING

APA PS 20 for dressed sizes of yard and structural lumber. Lumber shall be surfaced four sides. Size references, unless otherwise specified, are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced. Other

measurements are IP or SI standard.

1.6 MOISTURE CONTENT

Air-dry or kiln-dry lumber. Kiln-dry treated lumber after treatment. Maximum moisture content of wood products shall be as follows at the time of delivery to the job site:

a. Framing lumber and boards - 19 percent maximum

b. Timbers 125 mm and thicker - 25 percent maximum

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Virgin Lumber

Lumber fabricated from old growth timber is not permitted. Avoid companies who buy, sell, or use old growth timber in their operations, when possible.

2.1.2 Recovered Lumber

Use recovered lumber where practical. Unless otherwise noted, recovered lumber shall be delivered clean and free of contamination. Provide grading certificates for any recovered wood materials used in structural applications.

2.2 PLYWOOD PANELS

APA PS 1, APA PS 2, APA E445S, and APA F405L respectively.

2.2.1 Exposed Exterior Canopy Ceiling Sheathing

2.2.1.1 Plywood

C-D Grade, Exposure 1, with an Identification Index of not less than 24/0.

2.3 OTHER MATERIALS

2.3.1 Building Paper

FS UU-B-790, Type I, Grade D, Style 1.

2.4 ROUGH HARDWARE

Unless otherwise indicated or specified, rough hardware shall be of the type and size necessary for the project requirements. Sizes, types, and spacing of fastenings of manufactured building materials shall be as recommended by the product manufacturer unless otherwise indicated or specified. Rough hardware exposed to the weather or embedded in or in contact with preservative treated wood, exterior masonry, or concrete walls or slabs shall be zinc-coated.

2.4.1 Bolts, Nuts, Studs, and Rivets

ASME B18.52.1, ASME B18.5.2.1M, ASME B18.5.2.2M, ASME B18.2.2, and ASTM A 687.

2.4.2 Anchor Bolts

ASTM A 307, size as indicated, complete with nuts and washers.

2.4.3 Expansion Shields

CID A-A-1923, CID A-A-1924, and CID A-A-1925. Except as shown otherwise, maximum size of devices shall be 10 mm.

2.4.4 Lag Screws and Lag Bolts

ASME B18.52.1.

2.4.5 Toggle Bolts

FS FF-B-588.

2.4.6 Wood Screws

ASME B18.6.1.

2.4.7 Nails and Staples

ASTM F 547, size and type best suited for purpose; staples shall be as recommended by the manufacturer of the materials to be joined. For sheathing and subflooring, length of nails shall be sufficient to extend 25 mm into supports. In general, 8-penny or larger nails shall be used for nailing through 25 mm thick lumber and for toe nailing 50 mm thick lumber; 16-penny or larger nails shall be used for nailing through 50 mm thick lumber. Nails used with treated lumber and sheathing shall be galvanized. Nailing shall be in accordance with the recommended nailing schedule contained in AF&PA T10. Where detailed nailing requirements are not specified, nail size and spacing shall be sufficient to develop an adequate strength for the connection. The connection's strength shall be verified against the nail capacity tables in AF&PA T101. Reasonable judgment backed by experience shall ensure that the designed connection will not cause the wood to split. If a load situation exceeds a reasonable limit for nails, a specialized connector shall be used.

2.4.8 Wire Nails

ASTM F 1667.

2.4.9 Tacks

FS FF-T-1813.

2.4.10 Clip Angles

Steel, 5 mm thick, size best suited for intended use; or zinc-coated steel or iron commercial clips designed for connecting wood members.

PART 3 EXECUTION

3.1 INSTALLATION

Conform to AF&PA T10 and install in accordance with the National Association of Home Builders (NAHB) Advanced Framing Techniques: Optimum Value Engineering, unless otherwise indicated or specified. Select lumber

sizes to minimize waste. Fit rough carpentry, set accurately to the required lines and levels, and secure in place in a rigid manner. Do not splice framing members between bearing points. Provide adequate support as appropriate to the application, climate, and modulus of elasticity of the product. Provide as necessary for the proper completion of the work all framing members not indicated or specified. Spiking and nailing not indicated or specified otherwise shall be in accordance with the Nailing Schedule contained in ICC IBC; perform bolting in an approved manner. Spikes, nails, and bolts shall be drawn up tight. Provide 50 mm minimum clearance between chimneys and wood framing; provide 100 mm minimum clearance at fireplaces. Fill the spaces with strips of approved noncombustible material.

3.1.1 Plywood and Structural-Use Panel Sheathing

Install with the grain of the outer plies or long dimension at right angles to supports. Stagger end joints and locate over the centerlines of supports. Allow 3 mm spacing at panel ends and 6 mm at panel edges. Nail panels with 8-penny common nails or 6-penny annular rings or screw-type nails spaced 150 mm o.c. at supported edges and 300 mm o.c. at intermediate bearings. Where the support spacing exceeds the maximum span for an unsupported edge, provide adequate blocking, tongue-and-groove edges, or panel edge clips, in accordance with APA E30.

3.2 MISCELLANEOUS

3.2.1 Wood Roof Nailers, Edge Strips, Crickets, Curbs, and Cants

Provide sizes and configurations indicated or specified and anchored securely to continuous construction.

3.2.1.1 Roof Edge Strips and Nailers

Provide at perimeter of roof, around openings through roof, and where roofs abut walls, curbs, and other vertical surfaces. Except where indicated otherwise, nailers shall be 150 mm wide and the same thickness as the insulation. Anchor nailers securely to underlying construction. Anchor perimeter nailers in accordance with FM DS 1-49. Strips shall be grooved as indicated for edge venting; install at walls, curbs, and other vertical surfaces with a 6 to 12 mm air space.

3.2.1.2 Crickets, Cants, and Curbs

Provide wood saddles or crickets, cant strips, curbs for scuttles and ventilators, and wood nailers bolted to tops of concrete or masonry curbs and at expansion joints, as necessary and of lumber or 19 mm thick exterior plywood.

3.2.2 Rough Wood Bucks

Size as indicated. Set wood bucks true and plumb. Anchor bucks to concrete or masonry with steel straps extending into the wall 200 mm minimum. Place anchors near the top and bottom of the buck and space uniformly at 600 mm maximum intervals.

3.2.3 Wood Blocking

Provide proper sizes and shapes at proper locations for the installation and attachment of wood and other finish materials, fixtures, equipment, and

items indicated or specified.

3.2.4 Wood Grounds

Provide for fastening wood trim, finish materials, and other items to plastered walls and ceilings. Install grounds in proper alignment and true with an 2400 mm straightedge.

3.2.5 Temporary Closures

Provide with hinged doors and padlocks and install during construction at exterior doorways and other ground level openings that are not otherwise closed. Cover windows and other unprotected openings with polyethylene or other approved material, stretched on wood frames. Provide dustproof barrier partitions to isolate areas as directed.

3.2.6 Temporary Centering, Bracing, and Shoring

Provide for the support and protection of masonry work during construction as specified in Section 04 20 00, "MASONRY". Forms and centering for cast-in-place concrete work are specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

-- End of Section --

SECTION 07 13 53

ELASTOMERIC SHEET WATERPROOFING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 1004	(2003) Initial Tear Resistance of Plastic Film and Sheeting
ASTM D 1149	(1999) Standard Test Method for Rubber Deterioration - Surface Ozone Cracking in a Chamber
ASTM D 1204	(2002) Linear Dimensional Changes of Nonrigid Thermoplastic Sheeting or Film at Elevated Temperature
ASTM D 146	(2004) Sampling and Testing Bitumen-Saturated Felts and Woven Fabrics for Roofing and Waterproofing
ASTM D 2136	(2002e1) Coated Fabrics - Low-Temperature Bend Test
ASTM D 2240	(2005) Standard Test Method for Rubber Property - Durometer Hardness
ASTM D 297	(1993; R 2006) Rubber Products - Chemical Analysis
ASTM D 3045	(1992; R 2003) Practice for Heat Aging of Plastics Without Load
ASTM D 41	(2005) Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D 412	(2006ae1e2) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D 429	(2003e1) Rubber Property-Adhesion to Rigid Substrates
ASTM D 471	(2006; R 2008) Standard Test Method for Rubber Property - Effect of Liquids

ASTM D 5385	(1993; R 2000e1) Hydrostatic Pressure Resistance of Waterproofing Membranes
ASTM D 570	(1998; R 2005) Standard Test Method for Water Absorption of Plastics
ASTM D 573	(2004) Standard Test Method for Rubber - Deterioration in an Air Oven
ASTM D 624	(2000e2) Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D 638	(2003) Standard Test Method for Tensile Properties of Plastics
ASTM D 746	(2007) Standard Test Method for Brittleness Temperature of Plastics and Elastomers by Impact
ASTM D 751	(2006) Coated Fabrics
ASTM D 903	(1998; R 2004) Peel or Stripping Strength of Adhesive Bonds
ASTM E 154	(1999) Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover
ASTM E 96	(2005) Standard Test Methods for Water Vapor Transmission of Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Elastomeric waterproofing sheet material

Protection board

Primers, adhesives, and mastics

SD-04 Samples

Materials

Submit material samples shwoing resolution of corner and field conditions.

SD-06 Test Reports

Elastomeric waterproofing sheet material

Certify compliance with performance requirements specified herein.

SD-08 Manufacturer's Instructions

Submit Manufacturer's material safety data sheets for primers, adhesives and mastics.

1.3 QUALITY ASSURANCE

1.3.1 Shop Drawing Requirements

Include description and physical properties; termination details; application details; recommendations regarding shelf life, application procedures; requirements for protective covering; and precautions for flammability and toxicity.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver and store materials out of the weather, in manufacturer's original packaging with brand name and product identification clearly marked. Do not permit uncertified materials in the work area.

1.5 ENVIRONMENTAL CONDITIONS

Do not apply waterproofing during inclement weather or when there is ice, frost, surface moisture, or visible dampness on the surface to receive waterproofing and when ambient and surface temperatures are 4 degrees C or below. The restriction on the application of waterproofing materials when ambient and surface temperatures are below 4 degrees C will be waived if the Contractor devises a means, approved by the Contracting Officer, of maintaining the surface and ambient temperatures above 4 degrees C.

PART 2 PRODUCTS

2.1 MATERIALS

Provide one of the types of elastomeric waterproofing sheet materialand related primers, adhesives, and mastics as specified herein. Ensure compatibility of waterproofing materials within a specific type, with each other, and with the materials on which they will be applied. Materials shall conform to the applicable performance requirements cited below when tested in accordance with the referenced ASTM publications.

2.2 BUTYL RUBBER SHEETING

Not less than 1.5 mm minimum thickness.

2.2.1 Butyl Rubber Sheeting Performance Requirements

a. Thickness Tolerance, ASTM D 412: Plus or minus 10 percent;

b. Specific Gravity, ASTM D 297: 1.20, plus or minus 0.05;

c. Tensile Strength, ASTM D 412: 7.7 MP aminimum;

d. Tensile Stress at 300 percent elongation, ASTM D 412: 3.85 MPa minimum;

e. Elongation, ASTM D 412: 300 percent minimum;

f. Tear Resistance, Die C, ASTM D 624: 26.3 newtons per millimeter (N/mm)minimum;

g. Shore A Hardness, ASTM D 2240: Five-second interval before reading; 60 plus or minus 10;

h. Ozone Resistance, ASTM D 1149: No cracks, 7 days - 50 pphm - 37.8 degrees C, 20 percent elongation;

i. Heating Aging-Accelerated, ASTM D 573: Tensile retention, 60 percent of minimum original elongation retention; 60 percent of minimum original requirement; 7 days, 115.6 degrees C;

j. Butyl Identification, ASTM D 471, Tricresyl Phosphate Immersion: Maximum volume swell 10 percent, 70 hrs, 100 degrees C;

k. Low Temperature Flexibility, ASTM D 746: No failure at -40 degrees C ;

l. Water Absorption, ASTM D 471: +1 percent maximum. 7 days, 70 degrees C;

m. Exposure to Fungi and Bacteria in Soil, ASTM E 154, Minimum 16 Weeks: Unaffected; and

n. Water Vapor Transmission, 26.7 Degrees C Permeance, ASTM E 96, Procedure B or BW: 8.58 x 10-7 g/Pa.s.m2 maximum.

2.2.2 Adhesive, Cement, and Tape for Use with Butyl Rubber

As recommended by the butyl rubber waterproofing membrane manufacturer.

2.3 THERMOPLASTIC MEMBRANE: POLYVINYL CHLORIDE (PVC)

Polyvinyl chloride (PVC) flexible sheets with non-woven fiberglass reinforcing not less than 1.5 mm minimum thickness.

2.3.1 Thermoplastic Membrane Performance Requirements

a. Overall thickness, ASTM D 751:, 1.50 mm min.;

b. Tensile strength ASTM D 638:, 11.03 MPa, min.;

c. Elongation at break, ASTM D 638:, 250 percent minimum;

d. Seam strength, ASTM D 638:, 90 percent minimum of tensile strength;

e. Retention of properties after heat aging, ASTM D 3045;

f. Tensile strength, ASTM D 638:, 95 percent of original;

g. Elongation, ASTM D 638:, 95 percent of original;

h. Tear resistance, ASTM D 1004:, 7.7 Kilogram Force;

i. Low Temperature Bend , ASTM D 2136:, -40 C;

j. Liner Dimensional Change, ASTM D 1204: 0.002 percent; and

k. Weight Change After Immersion in Water, ASTM D 570:, 2.0 percent maximum.

2.3.2 Adhesives

a. Adhesive for thermoplastic flashings as recommended by manufacturer.

b. Adhesive for Sub-Membrane Grid: 100% solids, two-part urethane, with minimum tensile strength of 1.04 MPa, in accordance with ASTM D 412 and adhesion to concrete of 12 ply in accordance with ASTM D 429 as recommended by manufacture.

2.3.3 Accessories

a. Securement Strip: 14 gauge stainless steel metal bar, 2.54 cm wide, pre-punched 2.54 cm on center for securement.

2.4 COMPOSITE, SELF-ADHERING MEMBRANE SHEETING

Cold applied composite sheet consisting of rubberized asphalt and cross laminated, high density polyethylene film. Not less than 1.5 mm minimum thickness is required.

2.4.1 Composite, Self-Adhering Sheeting Performance Requirements

a. Tensile Strength, ASTM D 412, Die C: 1.6 MPa minimum;

b. Ultimate Elongation, ASTM D 412, Die C: 200 percent minimum;

c. Water Vapor Transmission,ASTM E 96 26.7 Degrees CPermeance, Procedure B: 5.72 x 10-7 g/Pa.s.m2 maximum;

d. Pliability Degrees F, ASTM D 146: (180 Degrees Bend Over 25 mm Mandrel): No cracks at minus -32 degrees C;

e. Cycling Over Crack at Minus -26 degrees C: Membrane is applied and rolled across two primed concrete blocks with no separation between blocks. Crack opened and closed from zero to 6 mm. No effect at 100 cycles;

f. Puncture Resistance, ASTM E 154: 18 kg minimum;

g. Lap Adhesion at Minimum Application Temperature, ASTM D1876 Modified, 880 N/m (5 lbs/in.);

h. Peel Strength, ASTM D 903: Modified, 1576 N/m;

i. Resistance to Hydrostatic Head, ASTM D 5385:, 70 m, of water

j. Water Absorption, ASTM D 570; 0.1% maximum.

2.4.2 Primer

Asphalt composition, ASTM D 41, or synthetic polymer in solvent as recommended by the membrane manufacturer.

2.4.3 Mastic

Polymer modified asphalt in suitable solvent of trowel-grade consistency and as recommended by the membrane manufacturer.

PART 3 EXECUTION

3.1 VERIFICATION OF CONDITIONS

Before starting the work, verify that surfaces to be waterproofed are in satisfactory condition. Notify the Contracting Officer of defects or conditions that will prevent a satisfactory application. Do not start application until defects and conditions have been corrected.

3.2 SURFACE PREPARATION

Ensure surfaces to be treated are clean, dry, smooth, and free from deleterious materials and projections. Thoroughly wet holes, joints, cracks, and voids in concrete with water and fill with Portland cement mortar, strike flush, and permit to dry. Cut off high spots or grind smooth. Finish top surfaces of projecting masonry or concrete ledges below grade, except footings, to a steep bevel with Portland cement mortar. Sweep surfaces to be covered before applying waterproofing to remove dust and foreign matter. Cure concrete by a method compatible with the waterproofing system.

3.3 APPLICATION

Follow manufacturer's printed installation instructions. When using solvent welding liquid, avoid prolonged contact with skin and breathing of vapor. Provide adequate ventilation. Carry waterproofing of horizontal surfaces up abutting vertical surfaces as indicated and adhere solid to the substrate. Avoid wrinkles and buckles in applying membrane and joint reinforcement.

a. Non-Self-Adhering Membrane: Unroll membrane and allow to remain flat for at least one-half hour before application. Apply an asphalt concrete primer prior to application of asphaltic adhesive. Where solvent adhesive is applied, allow major portion of solvent to evaporate so that bonding adhesive does not stick to a dry finger touching it. Apply elastomeric waterproofing membrane in a full bed of adhesive at a uniform coverage rate in accordance with the recommendations in the membrane manufacturer's printed instructions. Where membrane on horizontal surfaces are to receive concrete fill, apply adhesive in 100 mm wide strips at 600 mm on center. Pull membrane tight without stretching. As soon as adhesive is fully set and dry, recheck lap splices. Where openings or fishmouths appear, reseal and reroll lap splices.

b. Self-Adhering Membrane: Apply composite, self-adhering membrane on surfaces primed at a uniform coverage rate in accordance with membrane manufacturer's printed instructions. Remove release sheet and apply with tacky surface in contact with dried primer.

c. Protection: Protect membrane over horizontal surfaces from abnormal traffic during installation. Use only equipment with rubber tires. Provide walkway protection where heavy traffic from other trades is expected. Do not store material on membrane.

3.3.1 Butyl Rubber

Lap sheets at sides and ends a minimum of 150 mm over the preceding sheet. Apply lap splicing cement over entire 150 mm splice area prior to application of sealant. Sealant shall be continious along the entire length of the splice. Maintain a continuous bead of sealant at all membrane splices or as required by the manufacturer. When membrane will be below water table, provide a tongue and groove cemented splice a minimum of 150 mm with factory made heat vulcanized seam not less than 50 mm or as required by the manufacturer.

3.3.2 Thermoplastic Membrane (PVC)

Deck shall be clean, smooth and dry without surface irregularities. Consult with membrane manufacturer prior to grid application. Install 30.48 cm wide sub-membrane containment grid as required by manufacturer. Provide and install the containment grid at intervals across the width and length of the substrate, at the base of all transitions, walls, curbs, penetrations, and at the perimeter of each deck/substrate section. Fully adhere strips to the deck in a full bedding of two-part urethane adhesive medium. Adjacent sheets shall be welded in accordance with manufacturer's instructions. All side and end lap joints shall be hot-air welded. Lap area shall be a minimum of 7.62 cm wide when machine welding, and a minimum of 10.16 cm wide when hand welding but not less than recommended by the manufacturer. Overlaps shall be with the flow of water.

3.4 Composite, Self-Adhering Membrane

Lap sheets at edges and ends a minimum of 65 mm over the preceding sheet. All side laps shall be minimum 65 mm and end laps shall be 127 mm. Laps shall be self adhesive, mastic as per manufacturer's recommendation. Roll or firmly press to adhere membrane to substrate. Cover corners and joints with two layers of reinforcement by first applying a 300 mm width of membrane centered along the axis. Flash drains and projections with a second ply of membrane for a distance of 150 mm from the drain or projection. Finish exposed, terminated edges of membrane on horizontal or vertical surfaces with a trowelled bead of mastic. Apply mastic around edges of membrane, and drains and projections. Apply mastic at end of each work day.

3.5 FLASHING

Flash penetrations through membrane. Ensure that where reinforcing bars penetrate a waterproofing membrane, each of those penetrations be sealed with the appropriate sealant or mastic flashing component. Embed elastomeric membrane in a heavy coat of adhesive, except for self-adhering membrane. Continuous metal reglets shall be installed, horizontally on footing and vertically on intersecting and connecting walls, and as specified in Section 07 60 00 FLASHING AND SHEET METAL. Metal reglets shall receive exposed edges of membrane waterproofing. Secure membrane into reglets by lead wedges and fill with cement as recommended by manufacturer of waterproofing materials. Counterflash upper edge of membrane waterproofing and protective covering as specified in Section 07 60 00 FLASHING AND SHEET METAL.

3.6 FIELD QUALITY CONTROL

Notify the Contracting Officer one day prior to date of performing tests. Before concealment, cover elastomeric waterproofing on horizontal surfaces

over finished spaces with 75 mm of ponded water for 24 hours. Do not add water after start of 24 hour period. Carefully measure water level at beginning and end of 24 hour period. If water level falls, remove water and inspect waterproofing membrane. Make repairs or replacement as directed, and repeat test. Do not proceed with work that conceals membrane waterproofing before receiving approval and acceptance of Contracting Officer.

-- End of Section --

SECTION 07 21 13

BOARD INSULATION
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 553	(2008) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
ASTM C 578	(2009e1) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C 930	(2005) Potential Health and Safety Concerns Associated with Thermal Insulation Materials and Accessories
ASTM D 1621	(2004a) Compressive Properties of Rigid Cellular Plastics
ASTM D 3833/D 3833M	(1996; R 2006) Water Vapor Transmission of Pressure-Sensitive Tapes
ASTM D 4397	(2002) Standard Specification for Polyethylene Sheeting for Construction, Industrial, and Agricultural Applications
ASTM E 136	(2009) Behavior of Materials in a Vertical Tube Furnace at 750 Degrees C
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E 96	(2005) Standard Test Methods for Water Vapor Transmission of Materials

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 211	(2006) Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances
NFPA 31	(2006; Errata 2006) Installation of Oil Burning Equipment
NFPA 54	(2006) National Fuel Gas Code
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.134 Respiratory Protection

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Board insulation; G

Vapor retarder

Pressure sensitive tape

Protection board or coating

Accessories

SD-08 Manufacturer's Instructions

Board Insulation

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery

Deliver materials to the site in original sealed wrapping bearing manufacturer's name and brand designation, specification number, type, grade, R-value, and class. Store and handle to protect from damage. Do not allow insulation materials to become wet, soiled, crushed, or covered with ice or snow. Comply with manufacturer's recommendations for handling, storing, and protecting of materials before and during installation.

1.3.2 Storage

Inspect materials delivered to the site for damage; unload and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling.

1.4 SAFETY PRECAUTIONS

1.4.1 Respirators

Provide installers with dust/mist respirators, training in their use, and protective clothing, all approved by National Institute for Occupational Safety and Health (NIOSH)/Mine Safety and Health Administration (MSHA) in accordance with 29 CFR 1910.134.

1.4.2 Other Safety Considerations

Consider safety concerns and measures as outlined in ASTM C 930.

PART 2 PRODUCTS

2.1 BOARD INSULATION

Provide only thermal insulating materials recommended by manufacturer for type of application indicated. Provide board thermal insulation conforming to the following standards and the physical properties listed below:

a. Extruded Preformed Cellular Polystyrene: ASTM C 578

2.1.1 Thermal Resistance

As indicated.

2.1.2 Fire Protection Requirement

a. Flame spread index of 75 or less when tested in accordance with ASTM E 84.

b. Smoke developed index of 200 or less when tested in accordance with ASTM E 84.

2.1.3 Other Material Properties

Provide thermal insulating materials with the following properties:

a. Rigid cellular plastics: Compressive Resistance at Yield: Not less than 170 kilopascals (kPa) when measured according to ASTM D 1621.

b. Water Vapor Permeance: Not more than 6.3 x 10-8 g/Pa.s.m2 or less when measured according to ASTM E 96, desiccant method, in the thickness required to provide the specified thermal resistance, including facings, if any.

c. Water Adsorption: Not more than 1 percent by volume when measured in accordance with paragraph 14 of ASTM C 553.

2.1.4 Prohibited Materials

Do not provide materials containing more than one percent of asbestos.

2.2 VAPOR RETARDER AND DAMPPROOFING

2.2.1 Vapor Retarder in Frame Walls and Roofs

a. 0.15 mm thick polyethylene sheeting conforming to ASTM D 4397 and having a water vapor permeance of 5.72 x 10-8g/Pa.s.m2 or less when tested in accordance with ASTM E 96.

2.3 PRESSURE SENSITIVE TAPE

As recommended by manufacturer of vapor retarder and having a water vapor permeance rating of 5.72 x 10-8 g/Pa.s.m2 or less when tested in accordance with ASTM D 3833/D 3833M.

2.4 PROTECTION BOARD OR COATING

As recommended by insulation manufacturer.

2.5 ACCESSORIES

2.5.1 Adhesive

As recommended by insulation manufacturer.

2.5.2 Mechanical Fasteners

Corrosion resistant fasteners as recommended by the insulation manufacturer.

PART 3 EXECUTION

3.1 EXISTING CONDITIONS

Before installing insulation, ensure that all areas that will be in contact with the insulation are dry and free of projections which could cause voids, compressed insulation, or punctured vapor retarders. If installing perimeter or under slab insulation, check that the fill is flat, smooth, dry, and well tamped. If moisture or other conditions are found that do not allow the proper installation of the insulation, do not proceed but notify the Contracting Officer of such conditions.

3.2 PREPARATION

3.2.1 Blocking Around Heat Producing Devices

Unless using insulation board that passes ASTM E 136 in addition to the requirements in Part 2, install non-combustible blocking around heat producing devices to provide the following clearances:

a. Recessed electrical fixtures, including wiring compartments, ballasts, and other heat producing devices, unless certified for installation surrounded by insulation: 75 mm from outside face of fixtures and devices or as required by NFPA 70and, if insulation is to be placed above fixture or device, 600 mm above fixture.

b. Masonry chimneys or masonry enclosing a flue: 50 mm from outside face of masonry. Masonry chimneys for medium and high heat operating appliances: Minimum clearances required by NFPA 211.

c. Vents and vent connectors used for venting products of combustion, flues, and chimneys other than masonry chimneys: minimum clearances as required by NFPA 211.

f. Gas Fired Appliances: Clearances as required in NFPA 54.

g. Oil Fired Appliances: Clearances as required in NFPA 31.

Blocking is not required if chimneys or flues are certified by the Manufacturer for use in contact with insulating materials.

3.3 INSTALLATION

3.3.1 Insulation Board

Install and handle insulation in accordance with the manufacturer's installation instructions. Keep material dry and free of extraneous materials. Observe safe work practices.

3.3.2 Electrical Wiring

Do not install insulation in a manner that would sandwich electrical wiring between two layers of insulation.

3.3.3 Cold Climate Requirement

Place insulation to the outside of pipes.

3.3.4 Continuity of Insulation

Butt tightly against adjoining boards, studs, rafters, joists, sill plates, headers and obstructions. Provide continuity and integrity of insulation at corners, wall to ceiling joint, roof, and floor. Avoid creating any thermal bridges or voids.

3.4 INSTALLATION ON WALLS

3.4.1 Installation using Furring Strips

Install insulation between members as recommended by insulation manufacturer.

3.4.2 Installation on Masonry Walls

Apply board directly to masonry with adhesive or fasteners as recommended by the insulation manufacturer. Fit between obstructions without impaling board on ties or anchors. Apply in parallel courses with joints breaking midway over course below. Put ends in moderate contact with adjoining insulation without forcing. Cut and shape as required to fit around wall penetrations, projections or openings to accommodate conduit or other services. Seal around cut-outs with sealant. Install board in wall cavities so that it leaves at least a nominal 25 mm free air space outside of the insulation to allow for cavity drainage.

3.4.3 Mechanical Attachment on Concrete and Masonry Walls

Cut insulation to cover walls. Apply adhesive to wall and set clip or other mechanical fastener in adhesive as recommended by manufacturer. After curing of adhesive, install insulation over fasteners, bend split prongs flush with insulation. Butt all edges of insulation and seal with tape.

3.4.4 Protection Board or Coating

Install protection board or coating in accordance with manufacturer's instructions. Install protection over all exterior exposed insulation board and down to 300 mm below grade.

3.5 VAPOR RETARDER

Apply a continuous vapor retarder as indicated. Overlap all joints at least 150 mm and seal with pressure sensitive tape. Seal at sill, header, windows, doors and utility penetrations. Repair punctures or tears with pressure sensitive tape.

3.6 ACCESS PANELS AND DOORS

Affix insulation to all access panels greater than 0.1 square meter and all access doors in insulated floors and ceilings. Use insulation with same R-Value as that for floor or ceiling.

-- End of Section --

SECTION 07 41 13

NON-STRUCTURAL METAL ROOFING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 463/A 463M	(2006) Standard Specification for Steel Sheet, Aluminum-Coated
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A 755/A 755M	(2006) Standard Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products
ASTM A 792/A 792M	(2006a) Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process
ASTM D 1308	(2002e1) Effect of Household Chemicals on Clear and Pigmented Organic Finishes
ASTM D 1654	(2008) Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments
ASTM D 1970	(2001) Self-Adhering Polymer Modified Bituminous Sheet Materials Used as Steep Roofing Underlayment for Ice Dam Protection
ASTM D 2224	(1978; R 1983) Standard Test Method for Mean Molecular Weight of Mineral Insulating Oils by the Cryoscopic Method
ASTM D 2247	(2002) Testing Water Resistance of Coatings in 100% Relative Humidity
ASTM D 2794	(1993; R 2004) Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D 3359	(2009) Measuring Adhesion by Tape Test
ASTM D 4214	(1998) Evaluating the Degree of Chalking

	of Exterior Paint Films
ASTM D 4587	(2001) Standard Practice for Fluorescent UV-Condensation Exposures of Paint and Related Coatings
ASTM D 522	(1993a; R 2001) Mandrel Bend Test of Attached Organic Coatings
ASTM D 523	(1989; R 1999) Standard Test Method for Specular Gloss
ASTM D 5894	(1996) Cyclic Salt Fog/UV Exposure of Painted Metal, (Alternating Exposures in a Fog/Dry Cabinet and a UV/Condensation Cabinet)
ASTM D 610	(2001) Evaluating Degree of Rusting on Painted Steel Surfaces
ASTM D 714	(2002e1) Evaluating Degree of Blistering of Paints
ASTM D 968	(2005e1) Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM G 154	(2000ae1) Operating Fluorescent Light Apparatus for UV Exposure of Nonmetallic Materials

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)

MBMA RSDM	(2000) Metal Roofing Systems Design Manual

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

NRCA 0405	(2001; R 2003, 5th Ed) Roofing and Waterproofing Manual

1.2 DESCRIPTION OF METAL ROOF SYSTEM

Galvanized metal panel roof system with exposed fastener attachment through to deck substrate. Roof panel profile shall be corrugated except where indicated otherwise.

1.2.1 Design Requirements

1.2.2 Wind Uplift Resistance

Metal roof panel assembly shall resist wind loads as indicated.

1.2.2.1 Performance Requirements

The installed roof assembly shall be watertight, conform to the roof slope, and resist the uplift pressures calculated or indicated. The Contractor shall furnish a commercially available roofing system which satisfies all specified requirements.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Metal Roofing; G

Drawings consisting of catalog cuts, panel configuration, system assembly, attachment details, roof curb details, flashing details, erection drawings, and other data as necessary to clearly describe layouts, construction details, fasteners, and erection. Drawings shall be approved by the metal roofing manufacturer prior to submission.

SD-03 Product Data

Roof panels; G

Accessories; G

Fasteners; G

Underlayments; G

Gaskets and Insulating Compounds

Roof curbs

SD-04 Samples

Roof Panels; G

One piece of each type and finish to be used, 9 inches long, full width.

Factory-applied Color Finish Charts; G

Provide standard color charts for roof panel and accessory color selection.

Accessories; G

One sample of each type of roof curb, flashing, trim, fascia, closure, cap and similar items. Size shall be sufficient to show construction and configuration.

Fasteners; G

Two samples of each type to be used with statement regarding intended use.

Gaskets and Insulating Compounds

Two samples of each type to be used and descriptive data.

Sealant; G

SD-05 Design Data

Wind Uplift Resistance; G

Engineering calculations validating the wind resistance of non-tested roof system. Calculations shall be prepared, signed, and sealed by a registered structural engineer.

SD-06 Test Reports

Roof Assembly; G,

Factory Color Finish Performance Requirements

SD-07 Certificates

Roof Panels; G,

Certificates from the roof panel manufacturer attesting that the panels and accessories conform to the specified requirements and are suitable for the installation environment at the indicated design slope.

Coil stock compatibility; G,

Provide certification of coil compatibility with roll forming machinery to be used in the field.

Self-Adhering Modified Bitumen Underlayment

Certify underlayment compatibility with service conditions of the roof installation.

Qualification of Manufacturer; G,

Certify that the manufacturer of the roof membrane meets requirements specified under paragraph entitled "Qualification of Manufacturer."

Qualification of Applicator; G,

Certify that the applicator meets requirements specified under paragraph entitled "Qualification of Applicator."

SD-08 Manufacturer's Instructions

INSULATION

INSTALLATION

Roof panel installation manual; G

Submit manufacturer's printed installation manual and instructions.

SD-09 Manufacturer's Field Reports

Copy of manufacturer's field inspection reports, submitted within 48 hours of each site visit.

SD-11 Closeout Submittals

Warranties

Information card

1.4 QUALITY ASSURANCE

1.4.1 Qualification of Manufacturer

Metal roof panel manufacturer shall have been in the business of manufacturing metal roof panels for a period of not less than 5 years.

1.4.2 Qualification of Applicator

Metal roof system applicator shall be approved, authorized, or licensed in writing by the roof panel manufacturer and shall have a minimum of three years experience as an approved, authorized, or licensed applicator with that manufacturer and be approved at a level capable of providing the specified warranty. The applicator shall supply the names, locations and client contact information of 5 projects of similar size and scope that the applicator has constructed using the manufacturer's roofing products submitted for this project within the previous three years.

1.4.3 Preroofing Conference

After approval of submittals and before performing roofing system installation work, hold a preroofing conference to review the following:

a. Drawings and specifications and submittals related to the roof work;

b. Roof system components installation;

c. Procedure for the roof manufacturer's technical representative's onsite inspection and acceptance of the roofing substrate, the name of the manufacturer's technical representatives, the frequency of the onsite visits, distribution of copies of the inspection reports from the manufacturer's technical representative;

d. Contractor's plan for coordination of the work of the various trades involved in providing the roofing system and other components secured to the roofing; and

e. Quality control plan for the roof system installation;

f. Safety requirements.

Preroofing conference scheduling shall be coordinated with the Contracting Officer. The conference shall be attended by the Contractor, the Contracting Officer's designated personnel, personnel directly responsible for the installation of metal roof system, flashing and sheet metal work, mechanical and electrical work, other trades interfacing with the roof work, and representative of the metal roofing manufacturer. Before beginning roofing work, provide a copy of meeting notes and action items to

all attending parties. Note action items requiring resolution prior to start of roof work.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver, store, and handle panel materials, bulk roofing products, accessories, and other manufactured items in a manner to prevent damage and deformation, as recommended by the manufacturer, and as specified.

1.5.1 Delivery

Deliver materials to the site in undamaged condition. Provide adequate packaging to protect materials during shipment. Crated materials shall not be uncrated until ready for use, except for inspection. Immediately upon arrival of materials at jobsite, inspect materials for damage, deformation, dampness, and staining. Remove affected materials from the site. Remove moisture from wet materials not otherwise affected, restack and protect from further moisture exposure.

1.5.2 Storage

Stack materials stored on site on platforms or pallets, and cover with tarpaulins or other weathertight covering which prevents trapping of water or condensation under the covering. Store roof panels so that water which may have accumulated during transit or storage will drain off. Do not store panels in contact with materials that might cause staining. Secure coverings and stored items to protect from wind displacement.

1.5.3 Handling

Handle materials in a manner to avoid damage. Select and operate material handling equipment so as not to damage materials or applied roofing.

1.6 WARRANTIES

Provide metal roof system material and workmanship warranties meeting specified requirements. Revision or amendment to manufacturer's standard warranty shall be provided as required to comply with the specified requirements.

1.6.1 Metal Roof Panel Manufacturer Warranty

Furnish the metal roof panel manufacturer's 10-year no dollar limit roof system materials and installation workmanship warranty, including flashing, insulation, components, trim, and accessories necessary for a watertight roof system construction. The warranty shall run directly to the Government and commence at time of Government's acceptance of the roof work. The warranty shall state that:

a. If within the warranty period the metal roof system, as installed for its intended use in the normal climatic and environmental conditions of the facility, becomes non-watertight, shows evidence of moisture intrusion within the assembly, displaces, corrodes, perforates, separates at the seams, or shows evidence of excessive weathering due to defective materials or installation workmanship, the repair or replacement of the defective and damaged materials of the metal roof system and correction of defective workmanship shall be the responsibility of the metal roof panel manufacturer. All costs associated with the

repair or replacement work shall be the responsibility of the metal roof panel manufacturer.

b. When the manufacturer or his approved applicator fail to perform the repairs within 72 hours of notification, emergency temporary repairs performed by others shall not void the warranty.

1.6.2 Manufacturer's Finish Warranty

Provide a manufacturer's 20 year exterior material finish warranty warranting that the factory color finish, under normal atmospheric conditions at the site, will not crack, peel, or delaminate; chalk in excess of a numerical rating of 8 when measured in accordance with ASTM D 4214; or fade or change colors in excess of 5 NBS units as measured in accordance with ASTM D 2224.

1.6.3 Metal Roof System Installer Warranty

Provide the "Contractors Five (5) Year No Penal Sum Warranty for Non-Structural Metal Roof System" attached at the end of this section.

1.6.4 Continuance of Warranty

Repair or replacement work that becomes necessary within the warranty period shall be approved, as required, and accomplished in a manner so as to restore the integrity of the roof system assembly and validity of the metal roof system manufacturer warranty for the remainder of the manufacturer warranty period.

1.7 CONFORMANCE AND COMPATIBILITY

The entire metal roofing and flashing system shall be in accordance with specified and indicated requirements, including wind resistance requirements. Work not specifically addressed and any deviation from specified requirements shall be in general accordance with recommendations of the MBMA RSDM, NRCA 0405, the metal panel manufacturer's published recommendations and details, and compatible with surrounding components and construction. Any deviation from specified or indicated requirements shall be submitted to the Contracting Officer for approval prior to installation.

PART 2 PRODUCTS

2.1 ROOF PANELS

Roof panels shall be steel with a factory-applied color finish. Panel attachment shall be with exposed fasteners. Panel profile shall be corrugated unless indicated otherwise. Roof panels shall provide nominal 300 mm (12 inches) of coverage in place. Minimum height of corrugations at overlap of adjacent roof sheets shall be the panel manufacturer's standard for the indicated roof slope. Individual panels shall be of continuous length sufficient to cover the entire length of any unbroken roof slope with no joints or seams, except where indicated or approved otherwise by the Contracting Officer. Panels shall be formed without warping, waviness, or ripples that are not a part of the panel profile and shall be free of damage to the finish coating system. Provisions shall be made for thermal expansion and contraction consistent with the type of system to be used. All sheets shall be either square-cut or miter-cut.

2.1.1 Steel Panels

Zinc-coated steel conforming to ASTM A 653/A 653M, Structural Grade 40 and minimum G90 galvanized smooth metallic coating; aluminum-zinc alloy coated steel conforming to ASTM A 792/A 792M, AZ 50 coating; or aluminum-coated steel conforming to ASTM A 463/A 463M, Type 2, coating designation T2 65. Prepainted steel sheet shall also comply with ASTM A 755/A 755M. Roof panel material shall be minimum 0.76 mm (22 gage) thick prior to coating application, and as required to meet wind uplift requirements. Panels shall be within 95 percent of the nominal thickness. Prior to shipment, mill finish panels shall be treated with a passivating chemical and oiled to inhibit the formation of oxide corrosion products. Panels that have become wet during shipment and have started to oxidize shall be rejected.

2.1.2 Texture

Stucco embossed.

2.2 ROOF PANEL FACTORY COLOR FINISH

Provide factory-applied, thermally cured coating system on roof panel surfaces. Provide exterior coat of primer and color finish coat on the exposed side. Prime coat shall be not less than 0.005 mm (0.2 mil). Color finish coat shall be not less than 0.02 mm (0.8 mil). Total color coating system thickness shall be not less than 0.030 mm and with any additional primer and finish coat thickness required to meet the color finish performance requirements specified. Provide manufacturer's standard factory-applied clear coat system over color finish coat. Underside coating shall consist of roof panel manufacturer recommended protective backer coat suitable for the application conditions, not less than 0.008 mm (0.3 mil) thick unless approved otherwise by the Contracting Officer. Finish coat color shall be as selected by Contracting Officer from manufacturer standard color charts. The exterior color finish shall meet the performance requirements specified.

2.2.1 Factory Color Finish Performance Requirements

2.2.1.1 Cyclic Salt Fog/UV Test

A sample of the sheets shall withstand a cyclic corrosion test for a minimum of 2014 hours in accordance with ASTM D 5894, including the scribe requirement in the test. Immediately upon removal of the panel from the test, the coating shall receive a rating of not less than 10, no blistering, as determined by ASTM D 714; no rusting, as determined by ASTM D 610; and a rating of 7, less than 1.5 mm (1/16 inch) creepage from scribe as determined by ASTM D 1654.

2.2.1.2 Formability Test

When subjected to testing in accordance with ASTM D 522 Method B, 3 mm (1/8 inch) diameter mandrel, the coating film shall show no evidence of fracturing to the naked eye.

2.2.1.3 Accelerated Weathering, Chalking Resistance and Color Change

Coating sample shall withstand weathering test of 5000 hours , in accordance with ASTM D 4587 and ASTM G 154, Type D, without cracking, peeling, blistering, loss of adhesion of the protective coating, or corrosion of the base metal. Protective coating with an adhesion rating of

less than 4B when tested in accordance with ASTM D 3359, Test Method B, shall be considered as an area indicating loss of adhesion. Following the accelerated weathering test, the coating shall have a chalk rating not less than No. 8 in accordance with ASTM D 4214 test procedures, and the color change shall not exceed 5 CIE or Hunter Lab color difference (delta E) units in accordance with ASTM D 2224.

2.2.1.4 Humidity Test

When subjected to a humidity cabinet test in accordance with ASTM D 2247 for 1000 hours, a scored panel shall show no signs of blistering, cracking, creepage or corrosion.

2.2.1.5 Impact Resistance

Factory-painted sheet shall withstand direct and reverse impact in accordance with ASTM D 2794 13 mm (0.50 inch) diameter hemispherical head indenter, equal to 1.5 times the metal thickness in mils, expressed in inch-pounds, with no cracking.

2.2.1.6 Abrasion Resistance Test

When subjected to the falling sand test in accordance with ASTM D 968, Method A, the coating system shall withstand a minimum of 80 liters of sand before the appearance of the base metal. The term "appearance of base metal" refers to the metallic coating on steel or the aluminum base metal.

2.2.1.7 Specular Gloss

Finished roof surfaces for shall have a specular gloss value of 10 or less at an angle of 85 degrees when measured in accordance with ASTM D 523.

2.2.1.8 Pollution Resistance

Coating shall show no visual effects when covered spot tested in a 10 percent hydrochloric acid solution for 24 hours in accordance with ASTM D 1308.

2.3 ACCESSORIES

Accessories shall be compatible with the metal roof panels. Sheet metal flashing, trim, metal closure strips, caps, and similar metal accessories shall be not less than the minimum thicknesses specified for roof panels. Exposed metal accessories shall be finished to match the panels furnished. Molded foam rib, ridge and other closure strips shall be closed-cell or solid-cell synthetic rubber or neoprene premolded to match configuration of the panels and shall not absorb or retain water.

2.3.1 Pre-manufactured Accessories

Pre-manufactured accessories shall be manufacturer's standard for intended purpose, comply with applicable specification section, compatible with the metal roof system and approved for use by the metal roof panel manufacturer. Curbs shall be constructed to match roof slope and configuration.

2.3.2 Miscellaneous Metal Framing

Miscellaneous Metal Framing, General: ASTM C 645, cold-formed

metallic-coated steel sheet, ASTM A 653/A 653M, G40 (Z120) hot-dip galvanized or coating with equivalent corrosion resistance unless otherwise indicated.

Hat-Shaped, Rigid Furring Channels:

1. Nominal Thickness: As required to meet performance requirements.
2. Depth: As indicated.

2.4 FASTENERS

Fasteners for roof panels shall be corrosion resistant coated steel, aluminum, stainless steel, or nylon capped steel, compatible with the sheet panel or flashing material and of type and size recommended by the manufacturer to meet the performance requirements. Fasteners for accessories shall be the manufacturer's standard. Exposed fasteners shall have integral metal washer head and compressible sealing EPDM washer. Sealing washer shall be approximately 2.4 mm (3/32 inch) thick. Exposed portion of fasteners shall match color of attached material. Exposed fasteners to metal hot channels shall be high-domed gasketed type.

2.4.1 Screws

Not smaller than 6 mm (No. 14) diameter self-tapping type and not less than 4 mm (No. 12) diameter self-drilling type. Connections e.g. hat channel to metal framing shall be ASTM A153M with head as indicated.

2.4.2 Rivets

Closed-end type where watertight connections are required.

2.5 UNDERLAYMENTS

2.5.1 Self-Adhering Modified Bitumen Underlayment

Self-adhering modified bitumen membrane underlayment material in compliance with ASTM D 1970, and suitable for use as underlayment for metal roofing. Membrane resistant to cyclical elevated temperatures for extended period of time shall be used in high heat service conditions. Membrane shall have integral non-tacking top surface of polyethylene film or other surface material to serve as separator between bituminous material and metal products to be applied above.

2.5.2 Slip Sheet

Slip Sheet shall be 0.24 kg per square meter (5 pounds per 100 sf) rosin sized unsaturated building paper.

2.6 SEALANT

Sealant shall be an elastomeric type containing no oil or asphalt, as recommended by the roof panel manufacturer. Silicone based sealants are prohibited, unless approved otherwise by the roof panel manufacturer and the Contracting Officer. Exposed sealant shall be high quality polyurethane and shall be colored to match adjacent components and shall cure to a rubberlike consistency. Concealed sealant shall be non-hardening type. Sealant placed in the roof panel standing seam ribs shall be provided in accordance with the manufacturer's recommendations.

2.7 GASKETS AND INSULATING COMPOUNDS

Gaskets and insulating compounds shall be nonabsorptive and suitable for insulating contact points of incompatible materials. Insulating compounds shall be nonrunning after drying.

PART 3 EXECUTION

3.1 EXAMINATION

Examine surfaces to receive metal roof panel and flashing installation. Ensure surfaces are suitable, dry and fee of defects and projections which might affect the installation.

3.2 INSTALLATION

Installation shall meet specified requirements and be in accordance with the manufacturer's installation instructions and approved shop drawings. Correct defects or errors in materials and installation. Do not install damaged materials. Dissimilar materials which are not compatible when contacting each other shall be insulated by means of gaskets or insulating compounds. Exposed surfaces and edges shall be kept clean and free from sealant, metal cuttings, hazardous burrs, and other foreign material. Stained, discolored, or damaged materials shall be removed from the site.

3.2.1 Underlayment

Install underlayment parallel to roof slope and in a watershedding fashion. Install self-adhering underlayment in accordance with manufacturer's instructions. Self-adhering underlayment may be installed parallel to roof slope with the approval of the Contracting Officer. Provide a minimum 1 meter (36 inch) wide sheet of self-adhering modified bitumen membrane underlayment at all penetrations, eaves, rakes, hips, ridges, valleys, slope transitions, and side wall and head wall transitions. Ice dam protection shall extend minimum 36 inches inside of building wall line and as otherwise necessary to provide effective protection from water intrusion due to ice daming. Turn underlayment up minimum 4 inches at vertical transitions, except as otherwise indicated. Underlayment shall be concealed by finished flashing and cladding construction. Ensure underlayment is attached in a manner to hold in place until metal roof panels are installed. The underlayment shall ensure that any water that penetrates below the metal roofing panels will drain outside of the building envelope.

3.2.1.1 Slip Sheet

Apply specified slip sheet at time of roof panel installation when felt or other underlayment is used that may be in direct contact with and adhere to or adversely impact the underside of roof panels, and as otherwise recommended by the roof panel manufacturer.

3.2.2 Roofing

Apply roofing panels with longitudinal configurations in the direction of the roof slope. Provide roofing panels in unbroken lengths from peak to low point with no transverse joints except at junction of ventilators, curbs, skylights, chimneys, and similar openings, unless otherwise indicated or approved by the Contracting Officer. Where panel end laps are required, form and install to shed water and seal in a watertight manner as

recommended by the panel manufacturer's installation instructions. Attach roof panels in the manner, type and frequency required by the roof panel manufacturer and to resist required wind uplift pressures. Close panel ribs or side laps as required by the manufacturer to meet specified requirements. Lay side laps away from prevailing wind. Side and end lap distances, joint sealing, and fastening and spacing of fasteners shall be in accordance with manufacturer's instructions. Flash seal roof at ridge, eaves, rakes, and at projections through roof. All sheet metal laps, including but not limited to panel side laps end laps, flashing laps and junctures at accessories and penetrations flashings, shall be sealed watertight within the lap area. Closure strips, flashing, and sealing material shall be provided as indicated and where otherwise necessary to provide complete weathertight construction.

3.2.2.1 Field Forming of Roof Panels

Roll forming equipment shall be maintained in proper working order and operated by a factory trained technician. Field formed panels shall meet all specified requirements. Where UL 580 classified materials are required, rollformer equipment certification shall be provided. In cold weather conditions, warming of the steel coils to be field formed shall be performed as necessary just prior to the rolling operations.

3.2.3 Accessories

Provide all metal hot channel, roof curb, flashings, related closures, and accessories necessary for a complete, watertight installation. Minimize exposed fastening of flashings. On sloped planes, form flashing lap joints to shed water and provide sealant within the lap area. Laps joints shall have minimum 100 mm (4 inch) overlap except where greater overlap is indicated, or otherwise required by the roof panel manufacturer. For butt joints of flashings, provide joint splice and cover plates supplemented by waterproof sealants and sealant tapes to form a watertight joint condition. Ensure firm underlying support for joints greater than 200 mm (8 inches) wide and where otherwise indicated or required by the roof panel manufacturer. Installation shall allow for expansion and contraction of flashing without impacting watertight integrity. Set roof curbs so top surface of roof curb is level. Fasten metal hot channel to metal support framing as per Section 05 40 00 and drawings.

3.2.4 Exposed Fastener Installation

Where exposed fastening is required, provide fastener spacings in accordance with manufacturer's recommendations, in straight lines and to present a uniform appearance. Drive fasteners normal to surface and to uniform depth to seat washers with gaskets without tearing or cracking gasketing material. Exercise extreme care when drilling pilot hole for fastenings to keep drills perpendicular and centered. After drilling, remove metal filings and burrs from holes prior to installing fasteners and washers. Torque used when applying fasteners shall not exceed that recommended by manufacturer. Remove metal shavings and filings from roofs upon completion to prevent rusting and discoloration of panels.

3.3 PROTECTION OF APPLIED ROOFING

Do not permit storing, walking, wheeling, and trucking directly on applied roofing materials. Provide temporary walkways, runways, and platforms of smooth clean boards or planks as necessary to avoid damage to applied roofing materials, and to distribute weight to conform to indicated live

load limits of roof construction.

3.4 CLEAN UP AND FINISH TOUCH-UP

Clean exposed sheet metal work at completion of installation. Remove metal shavings, filings, nails, bolts, and wires from roofs. Remove grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces shall be free of dents, creases, waves, scratch marks, solder or weld marks, and damage to the finish coating. Touch up scratches in panel finish with manufacturer supplied touch-up paint system to match panel finish. Treat exposed cut edges with manufacturer supplied clear coat.

3.5 CORRECTION OF DEFICIENCIES

Where any form of deficiency is found, additional measures shall be taken as deemed necessary by the Contracting Officer to determine the extent of the deficiency and corrective actions shall be as directed by the Contracting Officer.

3.6 FIELD QUALITY CONTROL

3.6.1 Construction Monitoring

During progress of the roof work, Contractor shall make visual inspections as necessary to ensure compliance with specified requirements. Additionally, verify the following:

Materials comply with the specified requirements.

All materials are properly stored, handled and protected from damage. Damaged materials are removed from the site.

Substrates are in acceptable condition, in compliance with specification, prior to application of underlayment, roof panel, and flashing materials.

Nailers and blocking are provided where and as needed.

Underlayment is installed as required and of type required.

Slip sheet, if required, is installed as roof panels are installed.

Panels are installed without buckles, ripples, or waves and in uniform alignment and modulus.

Side laps are formed, sealed, fastened or seam locked as required.

The proper number, type, and spacing of attachment clips and fasteners are installed.

Installer adheres to specified and detailed application parameters.

Associated flashings and sheet metal are installed in a timely manner in accord with the specified requirements.

3.6.2 Manufacturer's Inspection

Manufacturer's technical representative shall visit the site a minimum of

three times during the installation for purposes of reviewing materials installation practices and adequacy of work in place. Inspections shall occur during the first 20 squares of roof panel installation, at mid-point of the installation, and at substantial completion, at a minimum. Additional inspections shall not exceed one for each 100 squares of total roof area with the exception that follow-up inspections of previously noted deficiencies or application errors shall be performed as requested by the Contracting Officer. After each inspection, a report, signed by the manufacturer's technical representative shall be submitted to the Contracting Officer within 3 working days. The report shall note overall quality of work, deficiencies and any other concerns, and recommended corrective action.

3.7 INFORMATION CARD

For each roof, furnish a typewritten information card for facility records and a card laminated in plastic and framed for interior display at roof access point, or a photoengraved 1 mm (0.032) inch thick aluminum card for exterior display. Card shall be 215 mm by 275 mm (8 1/2 by 11 inches) minimum. Information card shall identify facility name and number; location; contract number; approximate roof area; detailed roof system description, including deck type, roof panel manufacturer and product name, type underlayment(s), date of completion; installing contractor identification and contact information; manufacturer warranty expiration, warranty reference number, and contact information. The card shall be a minimum size of 215 mm by 275 mm (8 1/2 by 11 inches). Install card at roof top or access location as directed by the Contracting Officer and provide a paper copy to the Contracting Officer.

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
NON-STRUCTURAL METAL ROOF SYSTEM

FACILITY DESCRIPTION_____

BUILDING NUMBER:_____

CORPS OF ENGINEERS CONTRACT NUMBER:_____

CONTRACTOR

CONTRACTOR:_____

ADDRESS:_____

POINT OF CONTACT:_____

TELEPHONE NUMBER:_____

OWNER

OWNER:_____

ADDRESS:_____

POINT OF CONTACT:_____

TELEPHONE NUMBER:_____

CONSTRUCTION AGENT

CONSTRUCTION AGENT:_____

ADDRESS:_____

POINT OF CONTACT:_____

TELEPHONE NUMBER:_____

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
NON-STRUCTURAL METAL ROOF SYSTEM
(continued)

THE NON-STRUCTURAL METAL ROOF SYSTEM INSTALLED ON THE ABOVE NAMED BUILDING IS WARRANTED BY _____ FOR A PERIOD OF FIVE (5) YEARS AGAINST WORKMANSHIP AND MATERIAL DEFICIENCES, WIND DAMAGE, STRUCTURAL FAILURE, AND LEAKAGE. THE NON-STRUCTURAL METAL ROOFING SYSTEM COVERED UNDER THIS WARRANTY SHALL INCLUDE, BUT SHALL NOT BE LIMITED TO, THE FOLLOWING: THE ENTIRE ROOFING SYSTEM, MANUFACTURER SUPPLIED FRAMING AND STRUCTURAL MEMBERS, METAL ROOF PANELS, FASTENERS, CONNECTORS, ROOF SECUREMENT COMPONENTS, AND ASSEMBLIES TESTED AND APPROVED IN ACCORDANCE WITH UL 580. IN ADDITION, THE SYSTEM PANEL FINISHES, SLIP SHEET, INSULATION, VAPOR RETARDER, ALL ACCESSORIES, COMPONENTS, AND TRIM AND ALL CONNECTIONS ARE INCLUDED. THIS INCLUDES ROOF PENETRATION ITEMS SUCH AS VENTS, CURBS, SKYLIGHTS; INTERIOR OR EXTERIOR GUTTERS AND DOWNSPOUTS; EAVES, RIDGE, HIP, VALLEY, RAKE, GABLE, WALL, OR OTHER ROOF SYSTEM FLASHINGS INSTALLED AND ANY OTHER COMPONENTS SPECIFIED WITHIN THIS CONTRACT TO PROVIDE A WEATHERTIGHT ROOF SYSTEM; AND ITEMS SPECIFIED IN OTHER SECTIONS OF THE SPECIFICATIONS THAT ARE PART OF THE NON-STRUCTURAL METAL ROOFING SYSTEM.

ALL MATERIAL DEFICIENCIES, WIND DAMAGE, STRUCTURAL FAILURE, AND LEAKAGE ASSOCIATED WITH THE NON-STRUCTURAL METAL ROOF SYSTEM COVERED UNDER THIS WARRANTY SHALL BE REPAIRED AS APPROVED BY THE CONTRACTING OFFICER. THIS WARRANTY SHALL COVER THE ENTIRE COST OF REPAIR OR REPLACEMENT, INCLUDING ALL MATERIAL, LABOR, AND RELATED MARKUPS. THE ABOVE REFERENCED WARRANTY COMMENCED ON THE DATE OF FINAL ACCEPTANCE ON _____ AND WILL REMAIN IN EFFECT FOR STATED DURATION FROM THIS DATE.

SIGNED, DATED, AND NOTARIZED (BY COMPANY PRESIDENT)

_____

(Company President) (Date)

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
NON-STRUCTURAL METAL ROOFING SYSTEM
(continued)

THE CONTRACTOR SHALL SUPPLEMENT THIS WARRANTY WITH WRITTEN WARRANTIES FROM THE MANUFACTURER AND/OR INSTALLER OF THE NON-STRUCTURAL METAL ROOFING SYSTEM, WHICH SHALL BE SUBMITTED ALONG WITH THE CONTRACTOR'S WARRANTY. HOWEVER, THE CONTRACTOR WILL BE ULTIMATELY RESPONSIBLE FOR THIS WARRANTY AS OUTLINED IN THE SPECIFICATIONS AND AS INDICATED IN THIS WARRANTY EXAMPLE.

EXCLUSIONS FROM COVERAGE

1. NATURAL DISASTERS, ACTS OF GOD (LIGHTNING, FIRE, EXPLOSIONS, SUSTAINED WIND FORCES IN EXCESS OF THE DESIGN CRITERIA, EARTHQUAKES, AND HAIL).

2. ACTS OF NEGLIGENCE OR ABUSE OR MISUSE BY GOVERNMENT OR OTHER PERSONNEL, INCLUDING ACCIDENTS, VANDALISM, CIVIL DISOBEDIENCE, WAR, OR DAMAGE CAUSED BY FALLING OBJECTS.

3. DAMAGE BY STRUCTURAL FAILURE, SETTLEMENT, MOVEMENT, DISTORTION, WARPAGE, OR DISPLACEMENT OF THE BUILDING STRUCTURE OR ALTERATIONS MADE TO THE BUILDING.

4. CORROSION CAUSED BY EXPOSURE TO CORROSIVE CHEMICALS, ASH OR FUMES GENERATED OR RELEASED INSIDE OR OUTSIDE THE BUILDING FROM CHEMICAL PLANTS, FOUNDRIES, PLATING WORKS, KILNS, FERTILIZER FACTORIES, PAPER PLANTS, AND THE LIKE.

5. FAILURE OF ANY PART OF THE NON-STRUCTURAL METAL ROOF DUE TO ACTIONS BY THE OWNER TO INHIBIT FREE DRAINAGE OF WATER FROM THE ROOF AND GUTTERS AND DOWNSPOUTS OR ALLOW PONDING WATER TO COLLECT ON THE ROOF SURFACE. CONTRACTOR'S DESIGN SHALL INSURE FREE DRAINAGE FROM THE ROOF AND NOT ALLOW PONDING WATER.

6. THIS WARRANTY APPLIES TO THE NON-STRUCTURAL METAL ROOFING SYSTEM. IT DOES NOT INCLUDE ANY CONSEQUENTIAL DAMAGE TO THE BUILDING INTERIOR OR CONTENTS WHICH IS COVERED BY THE WARRANTY OF CONSTRUCTION CLAUSE INCLUDED IN THIS CONTRACT.

7. THIS WARRANTY CANNOT BE TRANSFERRED TO ANOTHER OWNER WITHOUT WRITTEN CONSENT OF THE CONTRACTOR; AND THIS WARRANTY AND THE CONTRACT PROVISIONS WILL TAKE PRECEDENCE OVER ANY CONFLICTS WITH STATE STATUTES.

**

CONTRACTOR'S FIVE (5) YEAR NO PENAL SUM WARRANTY
FOR
NON-STRUCTURAL METAL ROOF SYSTEM
(continued)

**REPORTS OF LEAKS AND ROOF SYSTEM DEFICIENCIES SHALL BE RESPONDED TO WITHIN 48 HOURS OF RECEIPT OF NOTICE, BY TELEPHONE OR IN WRITING, FROM EITHER THE OWNER OR CONTRACTING OFFICER. EMERGENCY REPAIRS TO PREVENT FURTHER ROOF LEAKS SHALL BE INITIATED IMMEDIATELY; A WRITTEN PLAN SHALL BE SUBMITTED FOR APPROVAL TO REPAIR OR REPLACE THIS ROOF SYSTEM WITHIN SEVEN (7) CALENDAR DAYS. ACTUAL WORK FOR PERMANENT REPAIRS OR REPLACEMENT SHALL BE STARTED WITHIN 30 DAYS AFTER RECEIPT OF NOTICE, AND COMPLETED WITHIN A REASONABLE TIME FRAME. IF THE CONTRACTOR FAILS TO ADEQUATELY RESPOND TO THE WARRANTY PROVISIONS, AS STATED IN THE CONTRACT AND AS CONTAINED HEREIN, THE CONTRACTING OFFICER MAY HAVE THE NON-STRUCTURAL METAL ROOF SYSTEM REPAIRED OR REPLACED BY OTHERS AND CHARGE THE COST TO THE CONTRACTOR.

IN THE EVENT THE CONTRACTOR DISPUTES THE EXISTENCE OF A WARRANTABLE DEFECT, THE CONTRACTOR MAY CHALLENGE THE OWNER'S DEMAND FOR REPAIRS AND/OR REPLACEMENT DIRECTED BY THE OWNER OR CONTRACTING OFFICER EITHER BY REQUESTING A CONTRACTING OFFICER'S DECISION UNDER THE CONTRACT DISPUTES ACT, OR BY REQUESTING THAT AN ARBITRATOR RESOLVE THE ISSUE. THE REQUEST FOR AN ARBITRATOR MUST BE MADE WITHIN 48 HOURS OF BEING NOTIFIED OF THE DISPUTED DEFECTS. UPON BEING INVOKED, THE PARTIES SHALL, WITHIN TEN (10) DAYS, JOINTLY REQUEST A LIST OF FIVE (5) ARBITRATORS FROM THE FEDERAL MEDIATION AND CONCILIATION SERVICE. THE PARTIES SHALL CONFER WITHIN TEN (10) DAYS AFTER RECEIPT OF THE LIST TO SEEK AGREEMENT ON AN ARBITRATOR. IF THE PARTIES CANNOT AGREE ON AN ARBITRATOR, THE CONTRACTING OFFICER AND THE PRESIDENT OF THE CONTRACTOR'S COMPANY WILL STRIKE ONE (1) NAME FROM THE LIST ALTERNATIVELY UNTIL ONE (1) NAME REMAINS. THE REMAINING PERSON SHALL BE THE DULY SELECTED ARBITRATOR. THE COSTS OF THE ARBITRATION, INCLUDING THE ARBITRATOR'S FEE AND EXPENSES, COURT REPORTER, COURTROOM OR SITE SELECTED, ETC., SHALL BE BORNE EQUALLY BETWEEN THE PARTIES. EITHER PARTY DESIRING A COPY OF THE TRANSCRIPT SHALL PAY FOR THE TRANSCRIPT. A HEARING WILL BE HELD AS SOON AS THE PARTIES CAN MUTUALLY AGREE. A WRITTEN ARBITRATOR'S DECISION WILL BE REQUESTED NOT LATER THAN 30 DAYS FOLLOWING THE HEARING. THE DECISION OF THE ARBITRATOR WILL NOT BE BINDING; HOWEVER, IT WILL BE ADMISSIBLE IN ANY SUBSEQUENT APPEAL UNDER THE CONTRACT DISPUTES ACT.

A FRAMED COPY OF THIS WARRANTY SHALL BE POSTED IN THE MECHANICAL ROOM OR OTHER APPROVED LOCATION DURING THE ENTIRE WARRANTY PERIOD.

-- End of Section --

SECTION 07 60 00

FLASHING AND SHEET METAL
01/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.2/D1.2M	(2003; Errata 2004) Structural Welding Code - Aluminum

ASTM INTERNATIONAL (ASTM)

ASTM A 167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 308/A 308M	(2003) Standard Specification for Steel Sheet, Terne (Lead-Tin Alloy) Coated by the Hot Dip Process
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B 209M	(2007) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM B 221M	(2007) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM B 32	(2004) Standard Specification for Solder Metal
ASTM B 69	(2001a; R 2005) Standard Specification for Rolled Zinc
ASTM D 226	(2006) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 41	(2005) Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D 4586	(2000; R 2006) Asphalt Roof Cement, Asbestos-Free

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA Arch. Manual (2003, 6th Ed) Architectural Sheet Metal Manual

1.2 General Requirements

Finished sheet metalwork will form a weathertight construction without waves, warps, buckles, fastening stresses or distortion, which allows for expansion and contraction. Sheet metal mechanic is repsonsible for cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades. Coordinate installation of sheet metal items used in conjunction with roofing with roofing work to permit continuous roofing operations.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Covering on flat, sloped, or curved surfaces

Gutters

Downspouts

Expansion joints

Gravel stops and fascias

Splash pans

Flashing for roof drains

Base flashing

Counterflashing

Flashing at roof penetrations

Reglets

Scuppers

Copings

Drip edge

Conductor heads

Open valley flashing

Eave flashing

Indicate thicknesses, dimensions, fastenings and anchoring methods, expansion joints, and other provisions necessary for thermal expansion and contraction. Scaled manufacturer's catalog data may be submitted for factory fabricated items.

SD-11 Closeout Submittals

Quality Control Plan

Submit for sheet metal work in accordance with paragraph entitled "Field Quality Control."

1.4 DELIVERY, HANDLING, AND STORAGE

Package and protect materials during shipment. Uncrate and inspect materials for damage, dampness, and wet-storage stains upon delivery to the job site. Remove from the site and replace damaged materials that cannot be restored to like-new condition. Handle sheet metal items to avoid damage to surfaces, edges, and ends. Store materials in dry, weather-tight, ventilated areas until immediately before installation.

PART 2 PRODUCTS

2.1 MATERIALS

Do not use lead, lead-coated metal, or galvanized steel. Use any metal listed by SMACNA Arch. Manual for a particular item, unless otherwise specified or indicated. Conform to the requirements specified and to the thicknesses and configurations established in SMACNA Arch. Manual for the materials. Different items need not be of the same metal, except that if copper is selected for any exposed item, all exposed items must be copper.

Furnish sheet metal items in 2400 to 3000 mm lengths. Single pieces less than 2400 mm long may be used to connect to factory-fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 300 mm legs. Provide accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied. Fabricate sheet metal items of the materials specified below and to the gage, thickness, or weight shown in Table I at the end of this section. Provide sheet metal items with mill finish unless specified otherwise. Where more than one material is listed for a particular item in Table I, each is acceptable and may be used except as follows:

2.1.1 Exposed Sheet Metal Items

Must be of the same material. Consider the following as exposed sheet metal: gutters, including hangers; downspouts; gravel stops and fascias; cap, valley, steeped, base, and eave flashings and related accessories.

2.1.2 Drainage

Do not use copper for an exposed item if drainage from that item will pass over exposed masonry, stonework or other metal surfaces. In addition to the metals listed in Table I, lead-coated copper may be used for such items.

2.1.3 Steel Sheet, Zinc-Coated (Galvanized)

ASTM A 653/A 653M.

2.1.3.1 Finish

Exposed exterior items of zinc-coated steel sheet must have a baked-on, factory-applied color coating of polyvinylidene fluoride or other equivalent fluorocarbon coating applied after metal substrates have been cleaned and pretreated. Provide finish coating dry-film thickness of 0.020 to 0.033 mm and color as approved by Contracting Officer from manufacturers standard list submitted by the contractor.

2.1.4 Zinc Sheet and Strip

ASTM B 69, Type I, a minimum of 0.61 mm thick.

2.1.5 Stainless Steel

ASTM A 167, Type 302 or 304, 2D Finish, fully annealed, dead-soft temper.

2.1.6 Terne-Coated Steel

Minimum of 350 by 500 mm with minimum of 18 kilogram coating per double base box. ASTM A 308/A 308M.

2.1.7 Aluminum Alloy Sheet and Plate

ASTM B 209M, color as approved by Contracting Officer from manufacturers standard list submitted by the contractor.

2.1.7.1 Alclad

When fabricated of aluminum, fabricate the items Alclad 3003, Alclad 3004, Alclad 3005, clad on both sides unless otherwise indicated.

a. Gutters, downspouts, and hangers

b. Fascias

c. Flashing

2.1.7.2 Finish

Exposed exterior sheet metal items of aluminum must have a baked-on, factory-applied color coating of polyvinylidene fluoride (PVF2) or other equivalent fluorocarbon coating applied after metal substrates have been cleaned and pretreated. Provide finish coating dry-film thickness of 0.020 to 0.033 mm, and color as selected by Contracting Officer from manufacturers standard list submitted by the contractor.

2.1.8 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes

ASTM B 221M.

2.1.9 Solder

ASTM B 32, 95-5 tin-antimony.

2.1.10 Bituminous Plastic Cement

ASTM D 4586, Type I.

2.1.11 Roofing Felt

ASTM D 226 Type I.

2.1.12 Asphalt Primer

ASTM D 41.

2.1.13 Fasteners

Use the same metal or a metal compatible with the item fastened. Use stainless steel fasteners to fasten dissimilar materials.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Workmanship

Make lines and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 13 mm hem on the concealed side. Make sheet metal exposed to the weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA Arch. Manual, Architectural Sheet Metal Manual. Provide sheet metal flashing in the angles formed where roof decks abut walls, curbs, ventilators, pipes, or other vertical surfaces and wherever indicated and necessary to make the work watertight. Join sheet metal items together as shown in Table II.

3.1.2 Nailing

Confine nailing of sheet metal generally to sheet metal having a maximum width of 450 mm. Confine nailing of flashing to one edge only. Space nails evenly not over 75 mm on center and approximately 13 mm from edge unless otherwise specified or indicated. Face nailing will not be permitted. Where sheet metal is applied to other than wood surfaces, include in shop drawings, the locations for sleepers and nailing strips required to secure the work.

3.1.3 Cleats

Provide cleats for sheet metal 450 mm and over in width. Space cleats evenly not over 300 mm on center unless otherwise specified or indicated. Unless otherwise specified, provide cleats of 50 mm wide by 75 mm long and of the same material and thickness as the sheet metal being installed. Secure one end of the cleat with two nails and the cleat folded back over the nailheads. Lock the other end into the seam. Where the fastening is to be made to concrete or masonry, use screws and drive in expansion shields set in concrete or masonry. Pretin cleats for soldered seams.

3.1.4 Bolts, Rivets, and Screws

Install bolts, rivets, and screws where indicated or required. Provide compatible washers where required to protect surface of sheet metal and to provide a watertight connection. Provide mechanically formed joints in aluminum sheets 1.0 mm or less in thickness.

3.1.5 Seams

Straight and uniform in width and height with no solder showing on the face.

3.1.5.1 Flat-lock Seams

Finish not less than 20 mm wide.

3.1.5.2 Lap Seams

Finish soldered seams not less than 25 mm wide. Overlap seams not soldered, not less than 75 mm.

3.1.5.3 Loose-Lock Expansion Seams

Not less than 75 mm wide; provide minimum 25 mm movement within the joint. Completely fill the joints with the specified sealant, applied at not less than 3 mm thick bed.

3.1.5.4 Standing Seams

Not less than 25 mm high, double locked without solder.

3.1.5.5 Flat Seams

Make seams in the direction of the flow.

3.1.6 Soldering

Where soldering is specified, apply to copper, terne-coated stainless steel, zinc-coated steel, and stainless steel items. Pretin edges of sheet metal before soldering is begun. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.6.1 Edges

Scrape or wire-brush the edges of lead-coated material to be soldered to produce a bright surface. Flux brush the seams in before soldering. Treat with soldering acid flux the edges of stainless steel to be pretinned. Seal the joints in aluminum sheets of one mm or less in thickness with specified sealants. Do not solder aluminum.

3.1.7 Welding and Mechanical Fastening

Use welding for aluminum of thickness greater than one mm. Aluminum one mm or less in thickness must be butted and the space backed with formed flashing plate; or lock joined, mechanically fastened, and filled with sealant as recommended by the aluminum manufacturer.

3.1.7.1 Welding of Aluminum

Use welding of the inert gas, shield-arc type. For procedures, appearance and quality of welds, and the methods used in correcting welding work, conform to AWS D1.2/D1.2M.

3.1.7.2 Mechanical Fastening of Aluminum

Use No. 12, aluminum alloy, sheet metal screws or other suitable aluminum alloy or stainless steel fasteners. Drive fasteners in holes made with a No. 26 drill in securing side laps, end laps, and flashings. Space fasteners 300 mm maximum on center. Where end lap fasteners are required to improve closure, locate the end lap fasteners not more than 50 mm from the end of the overlapping sheet.

3.1.8 Protection from Contact with Dissimilar Materials

3.1.8.1 Copper or Copper-bearing Alloys

Paint with heavy-bodied bituminous paint surfaces in contact with dissimilar metal, or separate the surfaces by means of moistureproof building felts.

3.1.8.2 Aluminum

Do not allow aluminum surfaces in direct contact with other metals except stainless steel, zinc, or zinc coating. Where aluminum contacts another metal, paint the dissimilar metal with a primer followed by two coats of aluminum paint. Where drainage from a dissimilar metal passes over aluminum, paint the dissimilar metal with a non-lead pigmented paint.

3.1.8.3 Metal Surfaces

Paint surfaces in contact with mortar, concrete, or other masonry materials with alkali-resistant coatings such as heavy-bodied bituminous paint.

3.1.8.4 Wood or Other Absorptive Materials

Paint surfaces that may become repeatedly wet and in contact with metal with two coats of aluminum paint or a coat of heavy-bodied bituminous paint.

3.1.9 Expansion and Contraction

Provide expansion and contraction joints at not more than 9750 mm intervals for aluminum and at not more than 12 meter intervals for other metals. Provide an additional joint where the distance between the last expansion joint and the end of the continuous run is more than half the required interval. Space joints evenly. Join extruded aluminum gravel stops and fascias by expansion and contraction joints spaced not more than 3600 mm apart.

3.1.10 Base Flashing

Extend up vertical surfaces of the flashing not less than 200 mm and not less than 100 mm under the roof covering. Where finish wall coverings form a counterflashing, extend the vertical leg of the flashing up behind the applied wall covering not less than 150 mm. Overlap the flashing strips with the previously laid flashing not less than 75 mm. Fasten the strips at their upper edge to the deck. Horizontal flashing at vertical surfaces

must extend vertically above the roof surface and fastened at their upper edge to the deck a minimum of 6 inch on center with hex headed, galvanized shielded screws a minimum of 2-inch lap of any surface. Solder end laps and provide for expansion and contraction. Extend the metal flashing over crickets at the up-slope side of chimneys, curbs, and similar vertical surfaces extending through sloping roofs, the metal flashings. Extend the metal flashings onto the roof covering not less than 115 mm at the lower side of chimneys, and similar vertical surfaces extending through the roof decks. Install and fit the flashings so as to be completely weathertight. Provide factory-fabricated base flashing for interior and exterior corners. Do not use metal base flashing on built-up roofing.

3.1.11 Counterflashing

Except where indicated or specified otherwise, insert counterflashing in reglets located from 230 to 250 mm above roof decks, extend down vertical surfaces over upturned vertical leg of base flashings not less than 75 mm. Fold the exposed edges of counterflashings 13 mm. Where stepped counterflashings are required, they may be installed in short lengths a minimum 8 inch by 8 inch or may be of the preformed one-piece type. Provide end laps in counterflashings not less than 75 mm and make it weathertight with plastic cement. Do not make lengths of metal counterflashings exceed 3000 mm. Form the flashings to the required shapes before installation. Factory-form the corners not less than 300 mm from the angle. Secure the flashings in the reglets with lead wedges and space not more than450 mm apart; on chimneys and short runs, place wedges closer together. Fill caulked-type reglets or raked joints which receive counterflashing with caulking compound. Turn up the concealed edge of counterflashings built into masonry or concrete walls not less than 6 mm and extend not less than 50 mm into the walls. Install counterflashing to provide a spring action against base flashing. Where bituminous base flashings are provided, extend down the counter flashing as close as practicable to the top of the cant strip. Factory form counter flashing to provide spring action against the base flashing.

3.1.12 Metal Reglets

Provide factory fabricated caulked type or friction type reglets with a minimum opening of 6 mm and a depth of 30 mm, as approved.

3.1.12.1 Caulked Reglets

Provide with rounded edges and metal strap brackets or other anchors for securing to the concrete forms. Provide reglets with a core to protect them from injury during the installation. Provide built-up mitered corner pieces for internal and external angles. Wedge the flashing in the reglets with lead wedges every 450 mm, caulked full and solid with an approved compound.

3.1.12.2 Friction Reglets

Provide with flashing receiving slots not less than 16 mm deep, 25 mm jointing tongues, and upper and lower anchoring flanges installed at 24 inch maximum snaplock receiver. Insert the flashing the full depth of the slot and lock by indentations made with a dull-pointed tool, wedges, and filled with a sealant. For friction reglets, install flashing snaplock receivers at 24 inch on center maximum. When the flashing has been inserted the full depth, caulk the slot and lock and fill with sealant.

3.1.13 Metal Drip Edge

Provide a metal drip edge, designed to allow water run-off to drip free of underlying construction, at eaves and rakes prior to the application of roofing shingles. Apply directly on the wood deck at the eaves and over the underlay along the rakes. Extend back from the edge of the deck not more than 75 mm and secure with compatible nails spaced not more than250 mm on center along upper edge.

3.1.14 Gutters

The hung type of shape indicated and supported on underside by brackets that permit free thermal movement of the gutter. Provide gutters in sizes indicated complete with mitered corners, end caps, outlets, brackets, and other accessories necessary for installation. Bead with hemmed edge or reinforce the outer edge of gutter with a stiffening bar not less than 20 by 5 mm of material compatible with gutter. Fabricate gutters in sections not less than 2400 mm. Lap the sections a minimum of 25 mm in the direction of flow or provide with concealed splice plate 150 mm minimum. Join the gutters, other than aluminum, by riveted and soldered joints. Join aluminum gutters with riveted sealed joints. Provide expansion-type slip joints midway between outlets. Install gutters below slope line of the roof so that snow and ice can slide clear. Support gutters on adjustable hangers spaced not more than 750 mm on center by continuous cleats and or by cleats spaced not less than 36 inch apart. Adjust gutters to slope uniformly to outlets, with high points occurring midway between outlets. Fabricate hangers and fastenings from metals.

3.1.15 Downspouts

Space supports for downspouts according to the manufacturer's recommendation for the masonry or steel substrate. Types, shapes and sizes are indicated. Provide complete including elbows and offsets. Provide downspouts in approximately 3000 mm lengths. Provide end joints to telescope not less than 13 mm and lock longitudinal joints. Provide gutter outlets with wire ball strainers for each outlet. Provide strainers to fit tightly into outlets and be of the same material used for gutters. Keep downspouts not less than 25 mm away from walls. Fasten to the walls at top, bottom, and at an intermediate point not to exceed 1500 mm on center with leader straps or concealed rack-and-pin type fasteners. Form straps and fasteners of metal compatible with the downspouts.

3.1.15.1 Terminations

Neatly fit into the drainage connection the downspouts terminating in drainage lines and fill the joints with a portland cement mortar cap sloped away from the downspout. Provide downspouts terminating in splash blocks with elbow-type fittings. Set precast splash blocks of 4000 psi concrete with 6 percent air content on solid support true to line and grade for drainage. Splash blocks shall be precast at manufacturer's plant or 4000 psi concrete with 6 percent air content, have smooth surfaces true to line and face, and be free from defects and sharp rises. Provide splash pans as specified.

3.1.16 Eave Flashing

One piece in width, applied in 2400 to 3000 mm lengths with expansion joints spaced as specified in paragraph entitled "Expansion and Contraction." Provide a 20 mm continuous fold in the upper edge of the

sheet to engage cleats spaced not more than 250 mm on center. Locate the upper edge of flashing not less than 450 mm from the outside face of the building, measured along the roof slope. Fold lower edge of the flashing over and loose-lock into a continuous edge strip on the fascia. Where eave flashing intersects metal valley flashing, secure with 25 mm flat locked joints with cleats that are 250 mm on center.

3.1.17 Sheet Metal Covering on Flat or Sloped Surfaces

Except as specified or indicated otherwise, cover and flash all minor flat, sloped, or curved surfaces such as crickets, bulkheads, and small decks with metal sheets of the material used for flashing; maximum size of sheets, 375 by 455 mm. Fasten sheets to sheathing with metal cleats. Lock seams and solder. Lock aluminum seams as recommended by aluminum manufacturer. Provide an underlayment of roofing felt for all sheet metal covering.

3.1.18 Flashing at Roof Penetrations and Equipment Supports

Provide metal flashing for all pipes, ducts, and conduits projecting through the roof surface and for equipment supports, guy wire anchors, and similar items supported by or attached to the roof deck.

3.1.19 Single Pipe Vents

See Table I, footnote (d). Set flange of sleeve in bituminous plastic cement and nail 75 mm on center. Bend the top of sleeve over and extend down into the vent pipe a minimum of 50 mm. Set metal housing with a metal sleeve having a 100 mm roof flange in bituminous plastic cement and nailed 75 mm on center. Extend sleeve a minimum of 200 mm above the roof deck and lapped a minimum of 75 mm by a metal hood secured to the vent pipe by a draw band. Seal the area of hood in contact with vent pipe with an approved sealant.

3.1.20 Stepped Flashing

Stepped flashing shall be installed where sloping roofs surfaced with shingles abut vertical surfaces. Separate pieces of base flashing shall be placed in alternate shingle courses.

3.1.21 Copings

Provide coping using copper sheets 2400 or 3000 mm long joined by a 20 mm locked and soldered seam. Terminate outer edges in edge strips. Install with sealed joints as indicated.

3.2 PAINTING

Field-paint sheet metal for separation of dissimilar materials.

3.2.1 Aluminum Surfaces

Shall be solvent cleaned and given one coat of zinc-molybdate primer and one coat of aluminum paint.

3.3 CLEANING

Clean exposed sheet metal work at completion of installation. Remove grease and oil films, handling marks, contamination from steel wool,

fittings and drilling debris, and scrub-clean. Free the exposed metal surfaces of dents, creases, waves, scratch marks, and solder or weld marks.

3.4 REPAIRS TO FINISH

Scratches, abrasions, and minor surface defects of finish may be repaired in accordance with the manufacturer's printed instructions and as approved. Repair damaged surfaces caused by scratches, blemishes, and variations of color and surface texture. Replace items which cannot be repaired.

3.5 FIELD QUALITY CONTROL

Establish and maintain a Quality Control Plan for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Remove work that is not in compliance with the contract and replace or correct. Include quality control, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.

b. Verification that specified material is provided and installed.

c. Inspection of sheet metalwork, for proper size(s) and thickness(es), fastening and joining, and proper installation.

3.5.1 Procedure

Submit for approval prior to start of roofing work. Include a checklist of points to be observed. Document the actual quality control observations and inspections. Furnish a copy of the documentation to the Contracting Officer at the end of each day.

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES

Sheet Metal Items	Aluminum, mm	Stainless Steel, mm	Terne-Coated Stainless Steel, mm	Zinc-Coated Stainless Steel, mm
Building Expansion Joints Cover.....	0.81	0.38	0.38	0.6
Waterstop-bellows or flanged, U-type.....	-	0.38	0.38	-
Covering on minor flat, pitched or curved surfaces.....	1.02	0.46	0.46	-
Downspouts and leaders.....	0.81	0.38	0.38	0.6
Downspout clips and anchors.....	-	1.02 clip	-	-
	-	3.175 anchor	-	-
Downspout straps, 50 mm.....	1.52	1.27	-	-

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES

Sheet Metal Items	Aluminum, mm	Stainless Steel, mm	Terne-Coated Stainless Steel, mm	Zinc-Coated Stainless Steel, mm
Strainers, wire diameter or gage....	3.66 diameter	2.77 diameter		-
Flashings:				
Base.....	1.02	0.46	0.46	0.6
Cap (Counter-flashing)	0.81	0.38	0.38	0.5
Eave.....	-	0.38	0.38	0.6
Spandrel beam.....	-	0.25	0.25	-
Bond barrier.....	-	0.38	0.38	-
Stepped.....	0.81	0.38	0.38	-
Roof drain.....				
Pipe vent sleeve(d)				
Gravel stops and fascias:				
Extrusions.....	1.91	-	-	-
Sheets, corrugated.....	0.81	0.38	0.38	-
Sheets, smooth.....	1.27	0.46	0.46	0.6
Edge strip.....	1.27	0.635	-	-
Gutters:				
Gutter section.....	0.81	0.38	0.38	0.6
Continuous cleat.....	0.81	0.38	0.38	0.6
Hangers, dimensions.....	25 mm x 2 mm (c)	25 mm x 1 mm	-	-
Joint Cover plates... See Table II)	0.81	0.38	0.38	0.6
Reglets (c).....	-	0.25	0.25	-
Splash pans.....	1.02	0.46	0.46	-

(a) Brass.

(b) May be lead weighing 19.6 kilograms per square meter.

(c) May be polyvinyl chloride.

(d) 12.25 kilogram minimum lead sleeve with 100 mm flange. Where lead sleeve is impractical, refer to paragraph entitled "Single Pipe Vents" for optional material.

-- End of Section --

SECTION 07 84 00

FIRESTOPPING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 119	(2009) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E 1399	(1997; R 2000) Cyclic Movement and Measuring the Minimum and Maximum Joint Widths of Architectural Joint Systems
ASTM E 1966	(2001) Fire-Resistive Joint Systems
ASTM E 814	(2002) Standard Test Method for Fire Tests of Through-Penetration Fire Stops
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials

FM GLOBAL (FM)

FM AS 4991	(2001) Approval of Firestop Contractors
FM P7825a	(2005) Approval Guide Fire Protection

UNDERWRITERS LABORATORIES (UL)

UL 1479	(2003) Fire Tests of Through-Penetration Firestops
UL 2079	(2004) Tests for Fire Resistance of Building Joint Systems
UL 723	(2008) Standard for Test for Surface Burning Characteristics of Building Materials
UL Fire Resistance	(2009) Fire Resistance Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office

that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Firestopping Materials.

Detail drawings including manufacturer's descriptive data, typical details conforming to UL Fire Resistance or other details certified by another nationally recognized testing laboratory, installation instructions or UL listing details for a firestopping assembly in lieu of fire-test data or report. For those firestop applications for which no UL tested system is available through a manufacturer, a manufacturer's engineering judgement, derived from similar UL system designs or other tests, shall be submitted for review and approval prior to installation. Submittal shall indicate the firestopping material to be provided for each type of application. When more than a total of 5 penetrations and/or construction joints are to receive firestopping, provide drawings that indicate location, "F" and "T" ratings, and type of application.

SD-07 Certificates

Firestopping Materials.

Certificates attesting that firestopping material complies with the specified requirements. In lieu of certificates, drawings showing UL classified materials as part of a tested assembly may be provided. Drawings showing evidence of testing by an alternate nationally recognized independent laboratory may be substituted.

Installer Qualifications.

Documentation of training and experience.

Inspection.

Manufacturer's representative certification stating that firestopping work has been inspected and found to be applied according to the manufacturer's recommendations and the specified requirements.

1.3 GENERAL REQUIREMENTS

Firestopping shall consist of furnishing and installing tested and listed firestop systems, combination of materials, or devices to form an effective barrier against the spread of flame, smoke and gases, and maintain the integrity of fire resistance rated walls, partitions, floors, and ceiling-floor assemblies, including through-penetrations and construction joints and gaps. Through-penetrations include the annular space around pipes, tubes, conduit, wires, cables and vents. Construction joints include those used to accommodate expansion, contraction, wind, or seismic movement; firestopping material shall not interfere with the required movement of the joint. Gaps requiring firestopping include gaps between the top of the fire-rated walls and the roof or floor deck above.

1.4 DELIVERY AND STORAGE

Materials shall be delivered in the original unopened packages or containers showing name of the manufacturer and the brand name. Materials shall be stored off the ground and shall be protected from damage and exposure to elements. Damaged or deteriorated materials shall be removed from the site.

1.5 INSTALLER QUALIFICATIONS

The Contractor shall engage an experienced Installer who is:

a. FM Research approved in accordance with FM AS 4991, or

b. Certified, licensed, or otherwise qualified by the firestopping manufacturer as having the necessary staff, training, and a minimum of 3 years experience in the installation of manufacturer's products per specified requirements. A manufacturer's willingness to sell its firestopping products to the Contractor or to an installer engaged by the Contractor does not in itself confer qualification on the buyer. The Installer shall have been trained by a direct representative of the manufacturer (not distributor or agent) in the proper selection and installation procedures.

1.6 COORDINATION

The specified work shall be coordinated with other trades. Firestopping materials, at penetrations of pipes and ducts, shall be applied prior to insulating, unless insulation meets requirements specified for firestopping. Firestopping materials at building joints and construction gaps shall be applied prior to completion of enclosing walls or assemblies. Cast-in-place firestop devices shall be located and installed in place before concrete placement. Pipe, conduit or cable bundles shall be installed through cast-in-place device after concrete placement but before area is concealed or made inaccessible.

PART 2 PRODUCTS

2.1 FIRESTOPPING MATERIALS

Firestopping materials shall consist of commercially manufactured, asbestos-free, noncombustible products FM P7825a approved, or UL listed, for use with applicable construction and penetrating items, complying with the following minimum requirements:

2.1.1 Fire Hazard Classification

Material shall have a flame spread of 25 or less, and a smoke developed rating of 50 or less, when tested in accordance with ASTM E 84 or UL 723. Material shall be an approved firestopping material as listed in UL Fire Resistance or by a nationally recognized testing laboratory.

2.1.2 Toxicity

Material shall be nontoxic to humans at all stages of application or during fire conditions.

2.1.3 Fire Resistance Rating

Firestop systems shall be UL Fire Resistance listed or FM P7825a approved with "F" rating at least equal to fire-rating of fire wall or floor in which penetraded openings are to be protected, except that "F" rating may be 3 hours in through-penetrations of 4 hour fire rated wall or floor. Firestop systems shall also have "T" rating where required.

2.1.3.1 Through-Penetrations

Firestopping materials for through-penetrations, as described in paragraph GENERAL REQUIREMENTS, shall provide "F" and "T" fire resistance ratings in accordance with ASTM E 814 or UL 1479. Fire resistance ratings shall be as follows:

a. Penetrations of Fire Resistance Rated Walls and Partitions: F Rating = Rating of wall or partition being penetrated.

b. Penetrations of Fire Resistance Rated Floors, Floor-Ceiling Assemblies and the ceiling membrane of Roof-Ceiling Assemblies: F Rating = 1 hour, T Rating = 1 hour.

2.1.3.2 Construction Joints and Gaps

Fire resistance ratings of construction joints, as described in paragraph GENERAL REQUIREMENTS, and gaps such as those between floor slabs or roof decks shall be the same as the construction in which they occur. Construction joints and gaps shall be provided with firestopping materials and systems that have been tested per ASTM E 119, ASTM E 1966 or UL 2079 to meet the required fire resistance rating. Systems installed at construction joints shall meet the cycling requirements of ASTM E 1399 or UL 2079.

PART 3 EXECUTION

3.1 PREPARATION

Areas to receive firestopping shall be free of dirt, grease, oil, or loose materials which may affect the fitting or fire resistance of the firestopping system. For cast-in-place firestop devices, formwork or metal deck to receive device prior to concrete placement shall be sound and capable of supporting device. Surfaces shall be prepared as recommended by the manufacturer.

3.2 INSTALLATION

Firestopping material shall completely fill void spaces regardless of geometric configuration, subject to tolerance established by the manufacturer. Firestopping systems for filling floor voids 100 mm or more in any direction shall be capable of supporting the same load as the floor is designed to support or shall be protected by a permanent barrier to prevent loading or traffic in the firestopped area. Firestopping shall be installed in accordance with manufacturer's written instructions. Tested and listed firestop systems shall be provided in the following locations, except in floor slabs on grade:

a. Penetrations of duct, conduit, tubing, cable and pipe through floors and through fire-resistance rated walls, partitions, and ceiling-floor assemblies.

b. Penetrations of vertical shafts such as pipe chases, elevator shafts, and utility chutes.

c. Gaps at the intersection of floor slabs and curtain walls, including inside of hollow curtain walls at the floor slab.

d. Gaps at perimeter of fire-resistance rated walls and partitions, such as between the top of the walls and the bottom of roof decks.

e. Construction joints in floors and fire rated walls and partitions.

f. Other locations where required to maintain fire resistance rating of the construction.

3.2.1 Insulated Pipes and Ducts

Thermal insulation shall be cut and removed where pipes or ducts pass through firestopping, unless insulation meets requirements specified for firestopping. Thermal insulation shall be replaced with a material having equal thermal insulating and firestopping characteristics.

3.3 INSPECTION

For all projects, the firestopped areas shall not be covered or enclosed until inspection is complete and approved by the manufacturer's technical representative. The manufacturer's representative shall inspect the applications initially to ensure adequate preparations (clean surfaces suitable for application, etc.) and periodically during the work to assure that the completed work has been accomplished according to the manufacturer's written instructions and the specified requirements. The Contractor shall submit written reports indicating locations of and types of penetrations and types of firestopping used at each location; type shall be recorded by UL listed printed numbers.

-- End of Section --

SECTION 07 92 00

JOINT SEALANTS
01/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 1311	(2002) Standard Specification for Solvent Release Agents
ASTM C 509	(2006) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C 920	(2008) Standard Specification for Elastomeric Joint Sealants
ASTM D 1056	(2000) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D 2452	(2003) Standard Test Method for Extrudability of Oil- and Resin-Base Caulking Compounds
ASTM D 2453	(2003) Standard Test Method for Shrinkage and Tenacity of Oil- and Resin-Base Caulking Compounds

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants

Primers

Bond breakers

Backstops

Manufacturer's descriptive data including storage requirements, shelf life, curing time, instructions for mixing and application, and primer data (if required). Provide a copy of the Material Safety Data Sheet for each solvent, primer or sealant material.

SD-07 Certificates

Sealant

Certificates of compliance stating that the materials conform to the specified requirements.

1.3 ENVIRONMENTAL CONDITIONS

Apply sealant when the ambient temperature is between 4 and 32 degrees C.

1.4 DELIVERY AND STORAGE

Deliver materials to the job site in unopened manufacturers' external shipping containers, with brand names, date of manufacture, color, and material designation clearly marked thereon. Lable elastomeric sealant containers to identify type, class, grade, and use. Carefully handle and store materials to prevent inclusion of foreign materials or subjection to sustained temperatures exceeding 32 degrees C or less than 4 degrees C.

1.5 QUALITY ASSURANCE

1.5.1 Compatibility with Substrate

Verify that each of the sealants are compatible for use with joint substrates.

1.5.2 Joint Tolerance

Provide joint tolerances in accordance with manufacturer's printed instructions.

1.6 SPECIAL WARRANTY

Guarantee sealant joint against failure of sealant and against water penetration through each sealed joint for fiveyears.

PART 2 PRODUCTS

2.1 SEALANTS

Provide sealant that has been tested and found suitable for the substrates to which it will be applied.

2.1.1 Interior Sealant

Provide ASTM C 920, Type S or M, Grade NS, Class 12.5, Use NT. Location(s) and color(s) of sealant for the following:

	LOCATION	COLOR
a.	Small voids between walls or partitions and adjacent casework, shelving, door frames, built-in or surface-mounted equipment and fixtures, and similar items.	As selected
b.	Perimeter of frames at doors, windows, and access panels which adjoin exposed	As selected

LOCATION	COLOR
interior concrete and masonry surfaces.	
c. Joints of interior masonry walls and partitions which adjoin columns, pilasters, concrete walls, and exterior walls unless otherwise detailed.	As selected
d. Interior locations, not otherwise indicated or specified, where small voids exist between materials specified to be painted.	As selected
e. Joints between ablution trough and ceramic tile; joints between shower receptors and ceramic tile; joints formed where nonplaner tile surfaces meet.	As selected
f. Joints formed between tile floors and tile base cove; joints between tile and dissimilar materials; joints occuring where substrates change.	As selected
g. Behind escutcheon plates at valve pipe penetrations and showerheads in showers.	As selected

2.1.2 Exterior Sealant

For joints in vertical surfaces, provide ASTM C 920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C 920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows:

LOCATION	COLOR
a. Joints and recesses formed where frames and subsills of windows, doors, louvers, and vents adjoin masonry, concrete, or metal frames.	Match adjacent surface color
Use sealant at both exterior and interior surfaces of exterior wall penetrations.	Match adjacent surface color
b. Joints between new and existing exterior masonry walls.	Match adjacent surface color
c. Masonry joints where shelf angles occur.	Match adjacent surface color
d. Expansion and control joints.	Match adjacent surface color
e. Interior face of expansion joints in exterior concrete or masonry walls where metal expansion joint covers are not required.	Match adjacent surface color
f. Voids where items pass through exterior walls.	Match adjacent surface color
g. Metal reglets, where flashing is inserted	Match adjacent

LOCATION	COLOR
into masonry joints, and where flashing is penetrated by coping dowels.	surface color
h. Metal-to-metal joints where sealant is indicated or specified.	Match adjacent surface color
i. Joints between ends of fascias, copings, and adjacent walls.	Match adjacent surface color

2.1.3 Floor Joint Sealant

ASTM C 920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows:

LOCATION	COLOR
a. Seats of metal thresholds for exterior doors.	Gray
b. Control and expansion joints in floors, slabs, ceramic tile, and walkways.	Gray

2.1.4 Preformed Sealant

Provide preformed sealant of polybutylene or isoprene-butylene based pressure sensitive weather resistant tape or bead sealant capable of sealing out moisture, air and dust when installed as recommended by the manufacturer. At temperatures from minus 34 to plus 71 degrees C, the sealant must be non-bleeding and no loss of adhesion.

2.2 PRIMERS

Provide a nonstaining, quick-drying type and consistency recommended by the sealant manufacturer for the particular application.

2.3 BOND BREAKERS

Provide the type and consistency recommended by the sealant manufacturer to prevent adhesion of the sealant to backing or to bottom of the joint.

2.4 BACKSTOPS

Provide glass fiber roving or neoprene, butyl, polyurethane, or polyethylene foams free from oil or other staining elements as recommended by sealant manufacturer. Provide 25 to 33 percent oversized backing for closed cell and 40 to 50 percent oversized backing for open cell material, unless otherwise indicated. Make backstop material compatible with sealant. Do not use oakum and other types of absorptive materials as backstops.

2.4.1 Rubber

Conform to ASTM D 1056, Type 2, closed cell, Class A, Grade round, cross section for cellular rubber sponge backing.

2.4.2 Synthetic Rubber

Conform to ASTM C 509, Option I , Type I preformed rods for Synthetic rubber backing.

2.4.3 Neoprene

Conform to ASTM D 1056, closed cell expanded neoprene cord Type 2, Class C, Grade 2C2 for Neoprene backing.

2.4.4 Butyl Rubber Based

Provide Butyl Rubber Based Sealants of single component, solvent release, color as selected by contracting officer from manufacturers standard listing submitted by contractor, conforming to ASTM C 1311.

2.5 CAULKING

Conform to ASTM D 2452 and ASTM D 2453, Type I for Oil- and resin-based caulking.

2.6 CLEANING SOLVENTS

Provide type(s) recommended by the sealant manufacturer except for aluminum and bronze surfaces that will be in contact with sealant.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Clean surfaces from dirt frost, moisture, grease, oil, wax, lacquer, paint, or other foreign matter that would tend to destroy or impair adhesion. Remove oil and grease with solvent. Surfaces must be wiped dry with clean cloths. When resealing an existing joint, remove existing calk or sealant prior to applying new sealant. For surface types not listed below, contact sealant manufacturer for specific recommendations.

3.1.1 Steel Surfaces

Remove loose mill scale by sandblasting or, if sandblasting is impractical or would damage finish work, scraping and wire brushing. Remove protective coatings by sandblasting or using a residue-free solvent.

3.1.2 Aluminum Surfaces

Remove temporary protective coatings from surfaces that will be in contact with sealant. When masking tape is used as a protective coating, remove tape and any residual adhesive just prior to sealant application. For removing protective coatings and final cleaning, use nonstaining solvents recommended by the manufacturer of the item(s) containing aluminum or bronze surfaces.

3.1.3 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, remove materials by sandblasting or wire brushing. Laitance, remove efflorescence and loose mortar from the joint cavity.

3.1.4 Wood Surfaces

Keep wood surfaces to be in contact with sealants free of splinters and sawdust or other loose particles.

3.2 SEALANT PREPARATION

Do not add liquids, solvents, or powders to the sealant. Mix multicomponent elastomeric sealants in accordance with manufacturer's instructions.

3.3 APPLICATION

3.3.1 Joint Width-To-Depth Ratios

a. Acceptable Ratios:

JOINT WIDTH	JOINT DEPTH Minimum	JOINT DEPTH Maximum
For metal, glass, or other nonporous surfaces:		
6 mm (minimum)	6 mm	6 mm
over 6 mm	1/2 of width	Equal to width
For wood, concrete, masonry or stone		
6 mm (minimum)	6 mm	6 mm
Over 6 mm to 13 mm	6 mm	Equal to width
Over 13 mm to 50 mm	50 mm	16 mm
Over 50 mm	(As recommended by sealant manufacturer)	

b. Unacceptable Ratios: Where joints of acceptable width-to-depth ratios have not been provided, clean out joints to acceptable depths and grind or cut to acceptable widths without damage to the adjoining work. Grinding is not required on metal surfaces.

3.3.2 Masking Tape

Place masking tape on the finish surface on one or both sides of a joint cavity to protect adjacent finish surfaces from primer or sealant smears. Remove masking tape within 10 minutes after joint has been filled and tooled.

3.3.3 Backstops

Install backstops dry and free of tears or holes. Tightly pack the back or bottom of joint cavities with backstop material to provide a joint of the depth specified. Install backstops in the following locations:

a. Where indicated.

b. Where backstop is not indicated but joint cavities exceed the

acceptable maximum depths specified in paragraph entitled, "Joint Width-to-Depth Ratios".

3.3.4 Primer

Immediately prior to application of the sealant, clean out loose particles from joints. Where recommended by sealant manufacturer, apply primer to joints in concrete masonry units, wood, and other porous surfaces in accordance with sealant manufacturer's instructions. Do not apply primer to exposed finish surfaces.

3.3.5 Bond Breaker

Provide bond breakers to the back or bottom of joint cavities, as recommended by the sealant manufacturer for each type of joint and sealant used, to prevent sealant from adhering to these surfaces. Carefully apply the bond breaker to avoid contamination of adjoining surfaces or breaking bond with surfaces other than those covered by the bond breaker.

3.3.6 Sealants

Provide a sealant compatible with the material(s) to which it is applied. Do not use a sealant that has exceeded shelf life or has jelled and can not be discharged in a continuous flow from the gun. Apply the sealant in accordance with the manufacturer's printed instructions with a gun having a nozzle that fits the joint width. Force sealant into joints to fill the joints solidly without air pockets. Tool sealant after application to ensure adhesion. Make sealant uniformly smooth and free of wrinkles. Upon completion of sealant application, roughen partially filled or unfilled joints, apply sealant, and tool smooth as specified. Apply sealer over the sealant when and as specified by the sealant manufacturer.

3.4 PROTECTION AND CLEANING

3.4.1 Protection

Protect areas adjacent to joints from sealant smears. Masking tape may be used for this purpose if removed 5 to 10 minutes after the joint is filled.

3.4.2 Final Cleaning

Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean and neat condition.

a. Masonry and Other Porous Surfaces: Immediately scrape off fresh sealant that has been smeared on masonry and rub clean with a solvent as recommended by the sealant manufacturer. Allow excess sealant to cure for 24 hour then remove by wire brushing or sanding.

b. Metal and Other Non-Porous Surfaces: Remove excess sealant with a solvent-moistened cloth.

-- End of Section --

SECTION 08 11 13

STEEL DOORS AND FRAMES

07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2008; Errata 2009) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A 879/A 879M	(2006) Standard Specification for Steel Sheet, zinc Coated by the Electrolytic Process for Applications Requiring Designation of the Coating Mass on Each Surface

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

BHMA A115	(2006) (Complete Set - Spec dates Vary) Specifications for Door and Frame Preparation for Hardware (Incl A115.1 (1990), A115.2 (1987), A115.4 (1994), A115.5 (1992), A115.6 (1993), A115.12 (1994), A115.13 (1991), A115.14 (1994), A115.15 (1994), A115.16 (1990), A115.17 (1994), A115.18 (1994)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 105	(2006) Installation of Smoke Door Assemblies
NFPA 252	(2007) Standard Methods of Fire Tests of Door Assemblies
NFPA 80	(2007) Standard for Fire Doors and Other Opening Protectives

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR 111	(2000) Recommended Selection and Usage Guide for Standard Steel Doors, Frames and Accessories
SDI/DOOR A250.11	(2001) Recommended Erection Instructions for Steel Frames

SDI/DOOR A250.3	(1999) Test Procedure and Acceptance Criteria for Factory Applied Finish Painted Steel Surfaces for Steel Doors and Frames
SDI/DOOR A250.4	(2001) Test Procedure and Acceptance Criteria for Physical Endurance for Steel Doors, Frames, Frame Anchors and Hardware Reinforcings
SDI/DOOR A250.6	(2003) Hardware on Steel Doors (Reinforcement - Application)
SDI/DOOR A250.8	(2003) Recommended Specification for Standard Steel Doors and Frames

UNDERWRITERS LABORATORIES (UL)

UL 10B	(2008; Rev thru Apr 2009) Fire Tests of Door Assemblies

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

SD-02 Shop Drawings

Doors; G

Frames; G

Accessories

Weatherstripping

Show elevations, construction details, metal gages, hardware provisions, method of glazing, and installation details.

Schedule of doors; G

Schedule of frames; G

Submit door and frame locations.

SD-03 Product Data

Doors; G

Frames; G

Accessories

Weatherstripping

Submit manufacturer's descriptive literature for doors, frames, and accessories. Include data and details on door construction, panel internal reinforcement, insulation, and door edge

construction. When "custom hollow metal doors" are provided in lieu of "standard steel doors," provide additional details and data sufficient for comparison to SDI/DOOR A250.8 requirements.

SD-04 Samples

Factory-applied enamel finish; G

Where colors are not indicated, submit manufacturer's standard colors and patterns for selection.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver doors, frames, and accessories undamaged and with protective wrappings or packaging. Strap frames in bundles. Provide temporary steel spreaders securely fastened to the bottom of each welded frame. Store doors and frames on platforms under cover in clean, dry, ventilated, and accessible locations, with 6 mm airspace between doors. Remove damp or wet packaging immediately and wipe affected surfaces dry. Replace damaged materials with new.

PART 2 PRODUCTS

2.1 STANDARD STEEL DOORS

2.1.1 Standard Duty Doors

SDI/DOOR A250.8, except as specified otherwise. Prepare doors to receive door hardware. Undercut where indicated. Exterior doors shall have top edge closed flush and sealed to prevent water intrusion. Doors shall be 44.5 mm thick, unless otherwise indicated.

2.1.2 Maximum Duty Doors

SDI/DOOR A250.8, Level 4, physical performance Level A, Model 1 with core construction as required by the manufacturer for interior doors and for indicated exterior doors, of size(s) and design(s) indicated.

2.2 INSULATED STEEL DOOR SYSTEMS

Insulated steel doors shall have a core of polyurethane foam and an R factor of 10.0 or more (based on a k value of 0.16); face sheets, edges, and frames of galvanized steel not lighter than 0.7 mm thick, 1.5 mm thick, and 1.5 mm respectively; magnetic weatherstripping; nonremovable-pin hinges; thermal-break aluminum threshold; and vinyl door bottom. Doors and frames shall receive phosphate treatment, rust-inhibitive primer, and baked acrylic enamel finish. Doors shall have been tested in accordance with SDI/DOOR A250.4 and shall have met the requirements for Level C. Prepare doors to receive specified hardware. Doors shall be 44.5 mm thick. Provide insulated steel doors and frames at exterior doors to all buildings.

2.3 ACCESSORIES

2.3.1 Moldings

Provide moldings around glass of interior and exterior doors and louvers of interior doors. Provide nonremovable moldings on outside of exterior doors and on corridor side of interior doors. Other moldings may be stationary or removable. Secure inside moldings to stationary moldings, or provide

snap-on moldings. Muntins shall interlock at intersections and shall be fitted and welded to stationary moldings.

2.4 STANDARD STEEL FRAMES

SDI/DOOR A250.8, Level 2, except as otherwise specified. Form frames to sizes and shapes indicated, with welded corners. Provide steel frames for doors, unless otherwise indicated.

2.4.1 Welded Frames

Continuously weld frame faces at corner joints. Mechanically interlock or continuously weld stops and rabbets. Grind welds smooth.

Weld frames in accordance with the recommended practice of the Structural Welding Code Sections 1 through 6, AWS D1.1/D1.1M and in accordance with the practice specified by the producer of the metal being welded.

2.4.2 Mullions and Transom Bars

Mullions and transom bars shall be closed or tubular construction and be a member with heads and jambs butt-welded thereto or knock-down for field assembly. Bottom of door mullions shall have adjustable floor anchors and spreader connections.

2.4.3 Stops and Beads

Form stops and beads from 0.9 mm thick steel. Provide for glazed and other openings in standard steel frames. Secure beads to frames with oval-head, countersunk Phillips self-tapping sheet metal screws or concealed clips and fasteners. Space fasteners approximately 300 to 400 mm on center. Miter molded shapes at corners. Butt or miter square or rectangular beads at corners.

2.4.4 Anchors

Provide anchors to secure the frame to adjoining construction. Provide steel anchors, zinc-coated or painted with rust-inhibitive paint, not lighter than 1.2 mm thick.

2.4.4.1 Wall Anchors

Provide at least three anchors for each jamb. For frames which are more than 2285 mm in height, provide one additional anchor for each jamb for each additional 760 mm or fraction thereof.

a. Masonry: Provide anchors of corrugated or perforated steel straps or 5 mm diameter steel wire, adjustable or T-shaped;

c. Completed openings: Secure frames to previously placed concrete or masonry with expansion bolts in accordance with SDI/DOOR 111; and

2.4.4.2 Floor Anchors

Provide floor anchors drilled for 10 mm anchor bolts at bottom of each jamb member. Where floor fill occurs, terminate bottom of frames at the indicated finished floor levels and support by adjustable extension clips resting on and anchored to the structural slabs.

2.5 FIRE AND SMOKE DOORS AND FRAMES

NFPA 80 and NFPA 105 and this specification. The requirements of NFPA 80 and NFPA 105 shall take precedence over details indicated or specified.

2.5.1 Door and Frame Labels

Fire doors and frames shall bear the label of Underwriters Laboratories (UL), Factory Mutual Engineering and Research (FM), or Warnock Hersey International (WHI) attesting to the rating required. Testing shall be in accordance with NFPA 252 or UL 10B. Labels shall be metal with raised letters, and shall bear the name or file number of the door and frame manufacturer. Labels shall be permanently affixed at the factory to frames and to the hinge edge of the door. Door labels shall not be painted.

2.5.2 Oversized Doors

For fire doors and frames which exceed the size for which testing and labeling are available, furnish certificates stating that the doors and frames are identical in design, materials, and construction to a door which has been tested and meets the requirements for the class indicated.

2.5.3 Astragal on Fire and Smoke Doors

On pairs of labeled fire doors, conform to NFPA 80 and UL requirements. On smoke control doors, conform to NFPA 105.

2.6 WEATHERSTRIPPING

As specified in Section 08 71 00 DOOR HARDWARE.

2.7 HARDWARE PREPARATION

Provide minimum hardware reinforcing gages as specified in SDI/DOOR A250.6. Drill and tap doors and frames to receive finish hardware. Prepare doors and frames for hardware in accordance with the applicable requirements of SDI/DOOR A250.8 and SDI/DOOR A250.6. For additional requirements refer to BHMA A115. Drill and tap for surface-applied hardware at the project site. Build additional reinforcing for surface-applied hardware into the door at the factory. Locate hardware in accordance with the requirements of SDI/DOOR A250.8, as applicable. Punch door frames to receive a minimum of two rubber or vinyl door silencers on lock side of single doors and one silencer for each leaf at heads of double doors. Set lock strikes out to provide clearance for silencers.

2.8 FINISHES

2.8.1 Electrolytic Zinc-Coated Anchors and Accessories

Provide electrolytically deposited zinc-coated steel in accordance with ASTM A 879/A 879M, Commercial Quality, Coating Class A. Phosphate treat and factory prime zinc-coated surfaces as specified in SDI/DOOR A250.8.

2.8.2 Factory-Applied Enamel Finish

Coatings shall meet test procedures and acceptance criteria in accordance with SDI/DOOR A250.3. After factory priming, apply two coats of medium-gloss enamel to exposed surfaces. Separately bake or oven dry each

coat. Drying time and temperature requirements shall be in accordance with the coating manufacturer's recommendations. Color(s) of finish coat shall be as selected by Contracting Officer from manufacturers standard listing submitted by contractor and shall match approved color sample(s).

2.9 GLAZING

Vision panel requirements shall be as shown and as specified in Section 08 81 00.

2.10 FABRICATION AND WORKMANSHIP

Finished doors and frames shall be strong and rigid, neat in appearance, and free from defects, waves, scratches, cuts, dents, ridges, holes, warp, and buckle. Molded members shall be clean cut, straight, and true, with joints coped or mitered, well formed, and in true alignment. Dress exposed welded and soldered joints smooth. Design door frame sections for use with the wall construction indicated. Corner joints shall be well formed and in true alignment. Conceal fastenings where practicable. On wraparound frames for masonry partitions, provide a throat opening 3 mm larger than the actual masonry thickness. Design other frames in exposed masonry walls or partitions to allow sufficient space between the inside back of trim and masonry to receive calking compound.

2.10.1 Grouted Frames

Frames to be installed in exterior walls are to be filled with mortar or grout. Fill the stops with strips of rigid insulation to keep the grout out of the stops and to facilitate installation of stop-applied head and jamb seals.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Frames

Set frames in accordance with SDI/DOOR A250.11. Plumb, align, and brace securely until permanent anchors are set. Anchor bottoms of frames with expansion bolts or powder-actuated fasteners. Build in or secure wall anchors to adjoining construction. Where frames require ceiling struts or overhead bracing, anchor frames to the struts or bracing. Backfill frames with mortar. Coat inside of frames with corrosion-inhibiting bituminous material. For frames in exterior walls, ensure that stops are filled with rigid insulation before grout is placed.

3.1.2 Doors

Hang doors in accordance with clearances specified in SDI/DOOR A250.8. After erection and glazing, clean and adjust hardware.

3.1.3 Fire and Smoke Doors and Frames

Install fire doors and frames, including hardware, in accordance with NFPA 80. Install fire rated smoke doors and frames in accordance with NFPA 80 and NFPA 105.

3.2 PROTECTION

Protect doors and frames from damage. Repair damaged doors and frames prior to completion and acceptance of the project or replace with new, as directed. Wire brush rusted frames until rust is removed. Clean thoroughly. Apply an all-over coat of rust-inhibitive paint of the same type used for shop coat.

3.3 CLEANING

Upon completion, clean exposed surfaces of doors and frames thoroughly. Remove mastic smears and other unsightly marks.

3.4 SCHEDULE

Some metric measurements in this section are based on mathematical conversion of inch-pound measurements, and not on metric measurement commonly agreed to by the manufacturers or other parties. The inch-pound and metric measurements are as follows:

PRODUCTS	INCH-POUND	METRIC
Door thickness	1-3/4 inch	44.5 mm
Steel channels	16 gage	1.5 mm
Steel Sheet	23 gage	0.7 mm
	16 gage	1.5 mm
	20 gage	0.9 mm
	18 gage	1.2 mm
Anchor bolts	3/8 inch	10 mm

-- End of Section --

SECTION 08 33 13

METAL ROLLING COUNTER DOORS
05/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B 209M	(2007) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80	(2007) Standard for Fire Doors and Other Opening Protectives

1.2 SUSTEM DESCRIPTION

Furnish rolling counter doors of the type, size, and design indicated on the drawings. Provide the standard product of a manufacturer regularly engaged in the production of rolling counter doors. Provide each door with a permanent label showing the manufacturer's name and address and the model number of the door.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

Detail drawings as specified.

SD-03 Product Data

Rolling Counter Doors

Manufacturer's descriptive data and catalog cuts.

Installation
Cleaning

Manufacturer's preprinted installation and cleaning instructions.

SD-10 Operation and Maintenance Data

Rolling Counter Door (Non-Rated)
Fire-Rated Rolling Counter Door

Six complete copies of Data Package 2 for Rolling Counter Doors (Non-Rated) and Fire-Rated Rolling Counter Doors in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA. Provide a list of the parts recommended by the manufacturer to be replaced after 1 year and 3 years of service.

1.4 QUALITY ASSURANCE

Submit Detail Drawings showing elevations of each door type, details of anchorage, details of construction, location and description of hardware, shape and thickness of materials, details of joints and connections, and details of guides and fittings. Include a schedule showing the location of each counter door with the drawings.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver rolling counter doors to the jobsite wrapped in a protective covering with the brands and names clearly marked thereon. Store rolling counter doors in accordance with the manufacturer's instructions in a dry location that is adequately ventilated and free from dust, water, or other contaminants, and in a manner that permits easy access for inspecting and handling. Handle doors carefully to prevent damage. Replace damaged items that cannot be restored to like-new condition.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period.

PART 2 PRODUCTS

2.1 BASIC COMPONENTS

2.1.1 Curtain

Fabricate the curtain of Type 304 stainless steel slats conforming to ASTM A 240/A 240M, Type 304 or Type 430. Provide thickness of slat material as required by width of opening or as required by specified fire-rating. Use slats approximately 32 to 38 mm wide with a depth of crown of 13 mm. Fit alternate slats with end locks to maintain curtain alignment. Provide bottom of curtain with angle or tubular bar reinforcement matching the curtain, and fitted with a resilient bottom seal.

2.1.2 Jamb Guides

Furnish guides of minimum thickness stainless steel conforming to ASTM A 240/A 240M, Type 304 or Type 430.

2.1.3 Counterbalance Shaft Assembly

Furnish the curtain coiled around a steel tube of sufficient thickness and diameter to prevent deflection exceeding 2.5 mm per meter. Provide a barrel containing oil tempered helical steel torsion springs capable of sufficient torque to counterbalance the weight of the curtain. Calculate the springs to provide a minimum of 7,500 operating cycles (one complete

cycle of door operation will begin with the door in the closed position, move to the full open position and return to the closed position).

2.1.4 Brackets

Furnish brackets of a minimum 2.657 mm thickness steel if flat plate, or 1.519 mm thickness if there are a minimum of 3 returns of 19 mm width.

2.1.5 Hood

Provide a hood of 1.02 mm minimum thickness aluminum sheet conforming to ASTM B 209M, Alloy 5005.

2.1.6 Locks

Lock the curtain at each side of the bottom bar by an integral slide bolt suitable for padlocks by others. Locate lock on the Kitchen side of the counter door.

2.2 FIRE-RATED ROLLING COUNTER DOOR

Furnish fire-rated rolling counter doors, Class B (1-1/2 hr.) rated and conforming to the requirements specified and to NFPA 80 for the class indicated. Provide labels of a recognized testing agency for the doors, indicating the applicable fire resistance rating. The construction details necessary for labeled rolling counter doors will take precedence over details indicated or specified herein. Furnish door curtains, guides and hood of stainless steel. Provide fire-rated rolling counter doors complete with hardware, accessories, and automatic closing device. Provide rolling counter doors, in exit corridor walls, with perimeter smoke and draft control gasketing.

2.3 AUTOMATIC CLOSING DEVICE

Equip fire-rated counter doors with an automatic closing device which operates upon the fusing of a 74 degrees C fusible link

2.4 FINISH

Exposed parts of the counter door, including the curtain, bottom rail, guides, and hood shall be of uniform finish and appearance. Furnish stainless steel with a No. 4 finish. Give all other steel parts a shop coat of primer paint in color that is standard with the manufacturer.

PART 3 EXECUTION

3.1 INSTALLATION

Install doors in accordance with approved detail drawings and manufacturer's instructions. Accurately locate anchors and inserts for guides, brackets, hardware, and other accessories. Upon completion, doors shall be free from warp, twist, or distortion. Lubricate, properly adjust, and demonstrate doors to operate freely. Conform fire-door installation with NFPA 80 for the class indicated and the manufacturer's instructions.

3.2 OPERATION

3.2.1 Manual Operation

Provide curtain operated by means of manual push-up with lift handles or continuous full width lift bar.

3.3 TESTS

Drop-test the fire doors in accordance with NFPA 80 to show proper operation and full automatic closure and reset in accordance with the manufacturer's instructions. Provide a written record of initial test to the Contracting Officer.

3.4 CLEANING

Clean aluminum and stainless steel doors in accordance with manufacturer's approved instructions.

-- End of Section --

SECTION 08 33 23

OVERHEAD COILING DOORS
07/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE/SEI 7-05	(2006) Minimum Design Loads for Buildings and Other Structures, Including Supplement No. 1

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE FUN IP	(2005) Fundamentals Handbook, I-P Edition

ASTM INTERNATIONAL (ASTM)

ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 27/A 27M	(2008) Standard Specification for Steel Castings, Carbon, for General Application
ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel
ASTM A 48/A 48M	(2003; R 2008) Standard Specification for Gray Iron Castings
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A 780	(2001; R 2006) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A 924/A 924M	(2009) Standard Specification for General Requirements for Steel Sheet,

	Metallic-Coated by the Hot-Dip Process
ASTM D 2000	(2006a) Standard Classification System for Rubber Products in Automotive Applications
ASTM E 2074	(2000e1) Standard Test Method for Fire Tests of Door Assemblies, Including Positive Pressure Testing of Side-Hinged and Pivoted Swinging Door Assemblies
ASTM E 330	(2002) Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM F 568M	(2007) Standard Specification for Carbon and Alloy Steel Externally Threaded Metric Fasteners

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80	(2007) Standard for Fire Doors and Other Opening Protectives

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir	(2009) Building Materials Directory

1.2 DESCRIPTION

Overhead coiling doors to be counterbalanced doors by methods of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed or self-lubricating bearings for rotating members. Doors to be coiling type, with interlocking slats, complete with anchoring and door hardware, guides, hood, and operating mechanisms, and designed for use on openings as indicated.

Fire-rated door assemblies must bear the Underwriters Laboratories, Warnock Hersey, Factory Mutual or other nationally recognized testing laboratory label for the rating listed on the drawings. Provide a permanent label for each door showing the manufacturer's name and address and the model/serial number of the door.

Oversized fire-rated door assemblies must be provided with a listing agency oversize label, or a certificate signed by an official of the manufacturing company certifying that the door and operator have been designed to meet the specified requirements.

1.3 PERFORMANCE REQUIREMENTS

1.3.1 Wind Loading

Design and fabricate door assembly to withstand the wind loading pressure

as indicated and at least 0.960 kilopascal with a maximum deflection of 1/120 of the opening width. Provide test data showing compliance with ASTM E 330. Sound engineering principles may be used to interpolate or extrapolate test results to door sizes not specifically tested Complete assembly must meet or exceed the requirements of ASCE/SEI 7-05.

1.3.2 Fire-Rated Doors, Frames, and Hardware

Provide fire-rated doors, frames, and hardware which are tested, rated, and labeled in accordance with Underwriters Laboratories, Factory Mutual or Warnock Hersey. The doors, frames, and hardware must bear metal UL labels as evidence of the fire resistance rating, as tested under ASTM E 2074. The labels must indicate the rating in hours, per NFPA 80 of duration of exposure to fire, with a letter following the hourly rating to designate the location for which the assembly is designed and the temperature rise on the unexposed face of the door at the end of 30 minutes of fire exposure.

Provide and attach metal UL labels to each item of hardware in accordance with requirements specified in the UL Bld Mat Dir.

1.3.3 Oversized Coiling Fire-rated Door Assemblies

Where fire-rated doors and frames exceed the size for which testing and labeling services are offered, furnish certificates of inspection from the UL, Factory Mutual or Warnock Hersey. State within certificates that except for size; doors, frames, and hardware are identical in design, materials, and construction to a door that has been tested and rated..

1.3.4 Operational Cycle Life

All portions of the door, hardware and operating mechanism that are subject to movement, wear, or stress fatigue must be designed to operate through a minimum number of 10 cycles per day. One complete cycle of door operation is defined as when the door is in the closed position, moves to the fully open position, and returns to the closed position.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Provide fabrication drawings that show complete assembly with hardware and framing details for the following items:

Overhead Coiling Doors; GA
Counterbalancing Mechanism
Manual Door Operators
Bottom Bar
Guides
Mounting Brackets
Overhead Drum
Hood
Painting

Submit Installation Drawings in accordance with paragraph entitled, "Overhead Coiling Door Assemblies," of this section.

SD-03 Product Data

Submit manufacturer's catalog data for the following items listing all accessories including supports, locks and latches, and weather stripping.

Overhead Coiling Doors; GA
Hardware
Counterbalancing Mechanism
Manual Door Operators
Fire-Rated Door Assembly

SD-05 Design Data

Submit equipment and performance data for the following items in accordance with the paragraph entitled, "Performance Requirements," of this section.

Overhead Coiling Doors; GA
Hardware
Counterbalancing Mechanism
Manual Door Operators
Fire-Rated Door

SD-10 Operation and Maintenance Data

Submit Operation and Maintenance Manuals for Overhead Coiling Door Assemblies , including the following items:

Materials
Devices
Procedures
Manufacture's Brochures
Parts Lists
Cleaning

1.5 OVERHEAD COILING DOOR DETAIL SHOP DRAWINGS

Provide installation drawings for overhead coiling door assemblies which show elevations of each door type, shape and thickness of materials, finishes, details of joints and connections, and details of guides and fittings, rough opening dimensions, location and description of hardware, anchorage locations, and counterbalancing mechanism and door operator details. Include a schedule showing the location of each door with the drawings.

Contractor must submit 6 copies of the Operation and Maintenance Manuals 30 calendar days prior to testing the Overhead Coiling Door Assemblies. Update and resubmit data for final approval no later than 30 calendar days prior to contract completion.

Provide operation and maintenance manuals which are consistent with manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions. Provide test data that is legible and of good quality.

1.6 WARRANTY, OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance Manuals for Overhead Coiling Door Assemblies, including the following items:

- Materials
- Devices
- Manual Door Operators
- Hood
- Counterbalancing Mechanism
- Painting
- Procedures
- Manufacture's Brochures
- Parts Lists

Contractor must furnish a written guarantee that the helical spring and counterbalance mechanism are free from defects in material and workmanship and that they will remain so for not less than two years after completion and acceptance of the project.

Contractor must warrant that upon notification by the Government, he will immediately make good any defects in material, workmanship, and door operation within the same time period covered by the guarantee, at no cost to the Government.

1.7 DELIVERY AND STORAGE

Delivered doors to the jobsite wrapped in a protective covering with the brands and names clearly marked thereon. Store doors in a dry location that is adequately ventilated and free from dirt and dust, water, and other contaminants, and in a manner that permits easy access for inspection and handling.

PART 2 PRODUCTS

2.1 OVERHEAD COILING DOORS

2.1.1 Curtain Materials and Construction

Provide curtain slats which are fabricated from steel sheets conforming to ASTM A 653/A 653M, Grade A, with the additional requirement of a minimum yield point of 228 Megapascal. Provide sheets which are galvanized in accordance with ASTM A 653/A 653M and ASTM A 924/A 924M.

Fabricate doors from interlocking cold-rolled slats, with section profiles as specified, designed to withstand the specified wind loading. Provide slats which are continuous without splices for the width of the door.

Provide slats filled with manufacturer's standard thermal insulation complying with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, according to ASTM E 84. Enclose insulation completely within slat faces on interior surface of slats.

2.1.2 Insulated Curtains

Form Curtains from manufacturer's standard shapes of interlocking slats. Supply slat system with a minimum R-value of 4 when calculated in accordance with ASHRAE FUN IP. Slats to consist of a urethane core not less than 17 mm thick, completely enclosed within metal facings. Exterior face

of slats must be the same gauge as specified for curtains. Interior face must be not lighter than 0.56 mm. The insulated slat assembly is to have a flame spread rating of not more than 25 and a smoke development factor of not more than 50 when tested in accordance with ASTM E 84.

2.1.3 Curtain Bottom Bar

Curtain bottom bars must be pairs of angles from the manufacturer's standard steel, stainless and aluminum extrusions not less than 50 by 50 millimeter by 4.8 millimeter. Steel extrusions must conform to ASTM A 36/A 36M. Stainless steel extrusions conforming to ASTM A 666, Type 304. Aluminum extrusions conforming to ASTM B 221 or(ASTM B 221M). Galvanize angles and fasteners in accordance with ASTM A 653/A 653M and ASTM A 924/A 924M. Coat welds and abrasions with paint conforming to ASTM A 780.

2.1.4 Locks

Provide end and/or wind locks of cast steel conforming to ASTM A 27/A 27M, Grade B; galvanized in accordance with ASTM A 653/A 653M, ASTM A 153/A 153M and ASTM A 924/A 924M and secured at every other curtain slat.

2.1.5 Weather Stripping

Weather-stripping at the door-head and jamb must be 3.2 millimeter 1/8-inch thick sheet of natural or neoprene rubber with air baffles, secured to the insides of hoods with galvanized-steel fasteners through continuous galvanized-steel pressure bars at least 15.9 millimeter 5/8-inch wide and 3.2 millimeter 1/8-inch thick.

Threshold weather-stripping must be 3.2 millimeter 1/8-inch thick sheet natural or neoprene rubber secured to the bottom bars.

Provide weather-stripping of natural or neoprene rubber conforming to ASTM D 2000.

2.1.6 Locking Devices

Slide Bolt to engage through slots in tracks for locking by padlock, located on both left and right jamb sides, operable from coil side.

Locking Device Assembly which includes cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

2.1.7 Overhead Drum

Fabricate drums from nominal 0.028-inch- (0.71-mm-) thick, hot-dip galvanized steel sheet with G90 (Z275) zinc coating, complying with ASTM A 653/A 653M.

2.2 HARDWARE

All hardware must conform to ASTM A 153/A 153M, ASTM A 307, ASTM F 568M, and ASTM A 27/A 27M.

2.2.1 Guides

Fabricate curtain jamb guides from the manufacturer's standard angles or

channels of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for track adjustment.

2.2.2 Equipment Supports

Fabricate door-operating equipment supports from the manufacturer's standard steel shapes and plates conforming to ASTM A 36/A 36M, galvanized in accordance with ASTM A 653/A 653M and ASTM A 924/A 924M. Size the shapes and plates in accordance with the industry standards for the size, weight, and type of door installation..

2.3 COUNTERBALANCING MECHANISM

Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed or self-lubricating bearings for rotating members.

2.3.1 Brackets

Provide the manufacturer's standard mounting brackets of either cast iron or cold-rolled steel with one located at each end of the counterbalance barrel conforming to ASTM A 48/A 48M.

2.3.2 Counterbalance Barrels

Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, welded or seamless carbon-steel pipe, conforming to ASTM A 53/A 53M, of sufficient diameter and wall thickness to support rolled-up curtain without distortion of slats and to limit barrel deflection to not more than 2.5 mm per meter 0.03 inch per foot of span under full load.

2.3.3 Spring Balance

One or more oil-tempered, heat-treated steel helical torsion springs installed within the barrel capable of producing sufficient torque to assure easy operation of the door curtain. Provide and size springs to counterbalance weight of curtain, with uniform adjustment accessible from outside barrel. Secure ends of springs to barrel and shaft with cast-steel barrel plugs.

2.3.4 Torsion Rod for Counter Balance

Fabricate rod from the manufacturer's standard cold-rolled steel, sized to hold fixed spring ends and carry torsional load.

2.4 MANUAL DOOR OPERATORS

2.4.1 Manual Push-Up Door Operators

Equip door with manufacturer's recommended lifting handles, locks, and latches. Adjust counterbalance mechanisms so that the required lift or pull for operation does not exceed 11 kilogram 25 pounds unless another type of door operator is indicated. Design operating mechanisms so that the curtain can be stopped at any point in its upward or downward travel

and will remain in that position until pushed to the fully open or closed position.

2.5 FIRE-RATED DOOR ASSEMBLY

2.5.1 Fire Ratings

Provide fire-rated door assemblies complying with NFPA 80 Standard for Fire Doors and Other Opening Protectives and UL Fire Resistance - Volume 3.

2.6 SURFACE FINISHING

Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Noticeable variations in the same metal component are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved samples and are assembled or installed to minimize contrast.

PART 3 EXECUTION

3.1 GENERAL

Install overhead coiling door assembly, anchors and inserts for guides, brackets, hardware, and other accessories in accordance with approved detail drawings and manufacturer's written instructions. Upon completion of installation, doors must be free from all distortion.

Install overhead coiling doors, hoods, and operators at the mounting locations as indicated for each door in the contract documents and as required by the manufacturer.

Install overhead coiling doors, in compliance with regulatory requirements for accessibility and as required by the manufacturer.

3.2 FIELD PAINTED FINISH

Steel doors and frames which are to be field painted must accordance with Section 09 90 00 PAINTS AND COATINGS and manufacturer's written instructions. Protect weather stripping from paint. Finishes must be free of scratches or other blemishes.

3.3 ACCEPTANCE PROVISIONS

After installation, adjust hardware and moving parts. Lubricate bearings and sliding parts as recommended by manufacturer to provide smooth operating functions for ease movement, free of warping, twisting, or distortion of the door assembly.

Adjust seals to provide weather-tight fit around entire perimeter.

Engage a factory-authorized service representative to perform startup service and checks according to manufacturer's written instructions.

Test and make final adjustment of new doors at no additional cost to the Government.

3.3.1 Maintenance and Adjustment

Not more than 90 calendar days after completion and acceptance of the project, the Contractor must examine, lubricate, test, and re-adjust doors as required for proper operation.

3.3.2 CLEANING

Clean doors in accordance with manufacturer's approved instructions.

-- End of Section --

SECTION 08 34 63

HOLLOW METAL FRAMES, DOORS, AND DOOR FRAMES
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 1011/A 1011M	(2009a) Standard Specification for Steel, Sheet, and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability
ASTM A 366/A 366M	(1997e1) Standard Specification for Commercial Steel, Sheet, Carbon,(0.15 Maximum Percent Cold-Rolled
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM G 60	(2001; R 2007) Conducting Cyclic Humidity Exposures

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM HMMA 863	(2004) Guide Specifications for Detention Security Hollow Metal Doors and Frames

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detention hollow metal doors and frames; GA

Submit details at not less than 1/4 full size for each frame type, and elevations of door design type at 1:50 minimum, show conditions at openings, details of construction, location and installation requirements of finish hardware and reinforcements, and details of joints and connections. Indicate fabrication, erection, anchorage, and accessory items.

Submit a schedule listing the location of each door and frame using indicated reference numbers for details and openings shown.

SD-03 Product Data

Detention hollow metal doors and frames

Submit manufacturer's material and fabrication specifications.

SD-06 Test Reports

Door fabrication

Prior to fabrication, submit test report for reinforced flush door of the type to be provided on this project.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver hollow metal work with packaging to provide protection during transit and job storage as recommended by the manufacturer. Door frames shall be provided with steel spreader angles, temporarily attached to the bottom of both jambs, one on each side of the opening to serve as a brace during shipping and handling. Inspect hollow metal work upon delivery for damage. Store hollow metal units on raised platforms in vertical positions with blocking between units to allow air circulation. Keep stored material covered and protected from damage and rust. Do not cover with plastic or unvented canvas.

1.4 HARDWARE COORDINATION CONFERENCE

Conduct a conference for hardware and hollow metal work prior to submittals for the purpose of coordinating the interface of materials that are furnished by the participants listed. Require that a representative of the entity responsible for each of the following functions attend the conference. Notify the following participants a minimum of 5 working days before the conference:

a. Contractor

b. Hollow metal supplier and installer

c. Detention hollow metal supplier and installer

d. Hardware supplier

e. Hardware installer

f. Detention hardware supplier

g. Detention hardware installer

h. Remote control operator and locking device supplier and installer

i. Electrical contractor.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Hot-Rolled Carbon Steel

ASTM A 1011/A 1011M, commercial quality, 14 gage and thicker.

2.1.2 Cold-Rolled Carbon Steel

ASTM A 366/A 366M, commercial quality, stretcher level sheets, 12 gage.

2.1.3 Galvanized Steel

ASTM A 653/A 653M, CQ, mill phosphatized tested by ASTM G 60.

2.2 DETENTION HOLLOW METAL DOORS AND FRAMES

2.2.1 Door Fabrication

a. Provide doors fabricated of cold rolled, pickled and oiled stretcher leveled steel sheets with clean smooth surfaces. Gages shall be as indicated for each type of door. Form molded members straight with joints coped or mitered, and in true alignment. Welded joints on exposed surfaces shall be dressed smooth, to be invisible. Doors shall be custom made full flush design, internally reinforced, sound deadened and insulated, 50 mm thick to receive detention locks, of the elevations, types and sizes shown on the approved shop drawings and schedules.

b. Face sheets shall be mild steel fully welded on edges with continuous inner-reinforcements full height and width. Provide internally 10 gage steel channel banding around complete door perimeter, spot welded to face sheet 75 mm on center. Inner reinforcements shall be truss design with triangular form, or interlocking channels with "Z" bar stiffeners, the shape of which cannot be altered without changing the length of the sides. Flat apexes shall be resistance spot welded on 70 mm centers horizontally and 75 mmcenters vertically. Insulate each flute of reinforcement with 96 kg/cubic meter density rock wool.

c. Bevel vertical door edges 3 mm in 50 mm and internally reinforced full length with 3 mm thick steel channels spot welded not over 75 mm on center inside both door faces. Close top and bottom door edges with continuous recessed 10 gage channels extending the full width of the door and welded 75 mm on center maximum to both faces and continuously welded to the vertical door edge channels to form a single perimeter frame inside the door. Top and bottom edges of doors shall be finished flush, except for provisions for weatherproofing. Mortise, reinforce, drill and tap door edges to receive templated specified hardware in accordance with the approved hardware schedule and the hardware manufacturer's recommendations for the proper installation of hardware and detention equipment.

d. Clearances shall be coordinated with frame and in accordance with NAAMM HMMA 863, Part 2, Section 2.02.

e. Doors shall be free from warpage, wind or buckle. Bends shall be

of minimum radius for the gage of metal used.

f. The removable glass stop shall consist of 10 gage angle securely fastened to the frame using machine screws (6 mm #20UNRC: 25 mm at 150 mm on center and no more than 100 mm from corners). Exposed screw heads shall be button head type, and shall be torx fitting tamperproof. The finished glass stop shall be tight fitting and mitered at the corner joints. There shall be a minimum 25 mm glass engagement.

2.2.2 Door and View Window Frame Fabrication

a. Custom-made, fully assembled, factory-welded units of the size and shapes shown on the approved shop drawings. "Knock-down" frames will not be accepted. Coordinate frame dimension to thickness of door or glass.

b. Strong, rigid, neat in appearance, and free from defects. Frame members shall be clean cut, straight, and of uniform profile.

c. Form frames to provide mitered trim and butted stops. Join head and jamb members by continuous welds occupying the full depth and width of the frame. Grind exposed welds smooth and flush.

d. When frames are for door light or food pass, fabricate members as closed tubular shapes having no visible seams or joints on exposed surfaces. Grind exposed welds smooth and flush.

e. Frames over 1200 mm wide installed in masonry partitions shall have a channel stiffener not less than 13 gage welded into the head at the factory.

f. Protect cutouts and reinforcements with pressed steel mortar guards on the inside of the frame.

g. Floor anchors formed of not less than 12 gage steel shall be securely welded to the bottom of each jamb.

h. Frames for installation in masonry walls shall be provided with non-removable adjustable jamb anchors constructed of not less than 14 gage material. Provide jamb anchors at 400 mm on center.

i. Welded frames that are to be installed in previously prepared masonry openings shall be 12 mm smaller in width and 6 mm smaller in height than the masonry opening to provide 6 mm clearance on all sides.

j. When shipping limitations dictate, frames for large openings shall be fabricated in sections designed for field welded splicing. Welds shall be ground smooth and primed for painting. Sections shall be assembled at the factory to ensure proper fit and be clearly marked for field reassembly.

2.2.3 Door Reinforcement for Hardware

a. Mortise, reinforce, drill, and tap doors at the factory for mortised hardware in accordance with the approved hardware schedule and templates. Doors to receive surface-mounted hardware shall have inner reinforcing plates for drilling and tapping to be

performed in the field.

b. For each mortised hinge, provide a reinforcing plate measuring 5 by 38 by 250 mm that is continuously welded inside the edge channel. The top hinge preparation shall be additionally braced by a channel, welded to the back of the hinge reinforcing plate and inside the edge reinforcing channel.

c. Where detention locks are scheduled, provide reinforced pocket to receive locks. The secure side of the door shall be finished flush with a 5 mm backup plate to protect lock. Form the pocket perimeter of 12 gage channels on three sides with the door edge channel completing the perimeter frame. Do not cut the door edge channel except for passage of the lock bolt. Provide a 5 mm thick steel mounting and protection plate to cover the lock pocket and extend at least 20 mm on three sides beyond the cutout. Secure the lock to the protection plate in accordance with the lock manufacturer's instructions. Secure the cover plate to the door by at least six 6 mm security-type machine screws. Make provisions so that removal of the lock is impossible when the lock bolt is extended.

d. Reinforcements for door pulls shall be 5 mm steel welded inside door. Reinforcement size shall be 38 by 250 mm for loop type pull and 150 by 175 mm for flush type pull. Minimum 12 gage reinforcing shall be welded inside the door for all other surface hardware items.

2.2.4 Frame Reinforcement for Hardware

a. Mortise, reinforce, drill, and tap frames at the factory for templated mortised hardware, in accordance with the approved hardware schedules and templates. Where surface-mounted hardware is to be applied, frames shall have reinforcing plates completely drilled and tapped for installation in the field.

b. For each mortised hinge, provide a 7 gage, off-set reinforcing plate that is factory drilled and tapped and measures 38 by 250 mm. Top hinge reinforcement shall be additionally braced by a 7 gage backup angle welded to the reinforcement and to the inside of the frame trim.

c. All other mortised and surface-mounted hardware reinforcements shall be not less than 12 gage.

2.2.5 Factory Finishing

a. After fabrication, dress, fill, and sand tool marks and surface imperfections to make faces and vertical edges smooth, level, and free of irregularities.

b. Surfaces shall be chemically treated and cleansed of rust, oil, and impurities and given a phosphate treatment to ensure paint adhesion.

c. Paint exposed surfaces of doors, and both inside and outside of frames with a minimum of one-mil thickness of rust inhibitive primer which shall be dried and completely cured to develop hardness before shipment.

2.3 ACCESS PANELS

Provide steel access panels of sizes and locations as indicated and where required for access to utilities, equipment, and controls.

a. Doors shall be 10 gage steel, flanged 32 mm on four sides, with welded corners.

b. Frame shall be composed of steel angles measuring 5 by 50 by 50 mm. Weld and grind joints smooth.

c. Provide detention type hinges with nonremovable pin, three per frame. Weld to door and frames.

d. Weld steel stop angles measuring 3 by 25 by 25 mm to frame on all four sides.

e. Masonry anchors shall be welded at factory, 3 by 25 by 150 mm, minimum four per panel. Provide expansion shields at concrete openings, factory countersunk for 10 mm flathead machine screw, minimum two per jamb.

f. Factory finish with prime coat of rust-inhibitive, baked-on enamel.

g. Provide locks at panels within the security perimeter and points of egress from ducts and tunnels terminating outside the security perimeter. Lock case and cover shall be malleable iron and steel. Bolt shall be high strength bronze and project 20 mm from case when retracted and have a throw of not less than 16 mm. Locks shall have five tumblers, each actuated by phosphor bronze springs. Locks shall operate from one side only. Attach to panel with detention type screws. Locks shall be keyed alike. Enter coded keys into keying system.

2.4 OPENING PROVISION

Speaking ports, view ports, food passes shall be manufactured as indicated.

2.5 SOURCE QUALITY CONTROL

Prior to fabrication, perform the following minimum performance test on a 12 gage reinforced flush door of the type to be provided on this project:

a. Test "A" - Static Load: Under centrally applied load of 62 kN (32 kPa) at quarter points, the maximum permitted deflection shall be 15 mm with a rebound of 0.4 mm after release of load.

b. Test "B" - Rack Test: Under a concentrated load of 33 kN on one unsupported corner of door, the maximum deflection shall not exceed 90 mm without failure.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Door Schedule

Refer to door schedule on drawings for location of doors, door frames, and

door hardware.

3.1.2 Frames

Set frames accurately in position, plumbed, aligned, and braced securely until permanent anchors are set. After completing wall construction, remove temporary braces and spreaders. Do not use any part of the frame as lintels or load-carrying members. Anchor frame to masonry with flat head security type machine screws into expansion shields or attached to a pre-set rough buck anchored to the masonry in the same way. Install five anchors on each jamb for doors up to and including 2250 mm in height and six on each jamb for taller doors.

3.1.3 Doors

Fit hollow metal doors accurately in frames. Provide metal shims where necessary.

3.1.4 Access Panels

Prepare openings as required to receive frame. Use fasteners as specified and required by type of surrounding construction. Ensure that frames are properly seated into opening with steel shims and that doors are true, in alignment, and completely flush in appearance. Maintain 3 mm maximum clearance between door and frame.

3.2 ADJUSTMENT AND CLEANING

Remove and replace defective work which is warped, bowed, or otherwise damaged. Adjust hollow metal work for smooth operation. Touch up scratches and bare edges in the field with a rust inhibiting primer prior to painting.

-- End of Section --

SECTION 08 51 13

ALUMINUM WINDOWS
08/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA/WDMA/CSA 101/I.S.2/A440	(2008; Update 1 2008; Update 2 2008; Update 3 2009) North American Fenestration Standard/Specification for Windows, Doors, and Skylights

ASTM INTERNATIONAL (ASTM)

ASTM A 276	(2008a) Standard Specification for Stainless Steel Bars and Shapes

GREEN SEAL (GS)

GS-36	(2000) Commercial Adhesives

INTERNATIONAL WINDOW CLEANING ASSOCIATION (IWCA)

IWCA I-14.1	(2001) Window Cleaning Safety Standard

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(1989; R 2005) Adhesive and Sealant Applications

U.S. GREEN BUILDING COUNCIL (USGBC)

LEED	(2002; R 2005) Leadership in Energy and Environmental Design(tm) Green Building Rating System for New Construction (LEED-NC)

1.2 CERTIFICATION

Each prime window unit must bear the AAMA Label warranting that the product complies with AAMA/WDMA/CSA 101/I.S.2/A440. Certified test reports attesting that the prime window units meet the requirements of AAMA/WDMA/CSA 101/I.S.2/A440, including test size, will be acceptable in lieu of product labeling.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When

used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Windows; G

Fabrication Drawings

SD-03 Product Data

Windows; G

Hardware; G

Fasteners; G (LEED)

Window performance; G

THERMAL-BARRIER WINDOWS; G

MULLIONS; G

WINDOW CLEANERS' BOLTS; G

Screens; G

Weatherstripping; G

Accessories; G

Thermal performance

Submit documentation for Energy Star qualifications.

SD-04 Samples

Finish Sample

Window Sample

SD-05 Design Data

Structural calculations for deflection; G

SD-06 Test Reports

Minimum condensation resistance factor

SD-10 Operation and Maintenance Data

Windows, Data Package 1; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

Plastic Identification

When not labeled, identify types in Operation and Maintenance Manual.

1.4 QUALITY ASSURANCE

1.4.1 Shop Drawing Requirements

Provide drawings that indicate elevations of windows, full-size sections, thickness and gages of metal, fastenings, proposed method of anchoring, size and spacing of anchors, details of construction, method of glazing, details of operating hardware, installation details, and other related items.

1.4.2 Sample Requirements

1.4.2.1 Finish Sample Requirements

Submit color chart of standard factory color coatings when factory-finish color coating is to be provided.

1.4.2.2 Window Sample Requirements

Submit one full-size window of each type proposed for use, complete with AAMA Label, glazing, hardware, anchors, and other accessories. Where screens or weatherstripping is required, fit sample windows with such items that are to be used. After approval, install each sample in work, clearly identified, and record its location.

1.4.3 Design Data Requirements

Submit calculations to substantiate compliance with deflection requirements. A registered Professional Engineer must provide calculations.

1.4.4 Test Report Requirements

Submit test reports for each type of window attesting that identical windows have been tested and meet the requirements specified herein for conformance to AAMA/WDMA/CSA 101/I.S.2/A440 including test size, and minimum condensation resistance factor (CRF).

1.5 DELIVERY AND STORAGE

Deliver windows to project site in an undamaged condition. Use care in handling and hoisting windows during transportation and at the jobsite. Store windows and components out of contact with the ground, under a weathertight covering, so as to prevent bending, warping, or otherwise damaging the windows. Repair damaged windows to an "as new" condition as approved. If windows can not be repaired, provide a new unit.

1.6 PROTECTION

Protect finished surfaces during shipping and handling using the manufacturer's standard method. Do not apply coatings or lacquers to surfaces to which calking and glazing compounds must adhere.

1.7 FIELD MEASUREMENTS

Take field measurements prior to preparation of the drawings and fabrication.

1.8 PERFORMANCE REQUIREMENTS

1.8.1 Wind Loading Design Pressure

Design window components, including mullions, hardware, and anchors, to withstand a wind-loading design pressure of at least 75 pascal.

1.9 DRAWINGS

Submit the Fabrication Drawings for aluminum window units showing complete window assembly including hardware, weatherstripping, and subframe assembly details.

1.10 WINDOW PERFORMANCE

Aluminum windows must meet the following performance requirements. Perform testing requirements by an independent testing laboratory or agency.

1.10.1 Structural Performance

Structural test pressures on window units must be for positive load (inward) and negative load (outward). After testing, there will be no glass breakage, permanent damage to fasteners, hardware parts, support arms or actuating mechanisms or any other damage which could cause window to be inoperable. There must be no permanent deformation of any main frame, sash or ventilator member in excess of the requirements established by AAMA/WDMA/CSA 101/I.S.2/A440 for the window types and classification specified in this section.

1.10.2 Air Infiltration

Air infiltration must not exceed the amount established by AAMA/WDMA/CSA 101/I.S.2/A440 for each window type.

1.10.3 Water Penetration

Water penetration must not exceed the amount established by AAMA/WDMA/CSA 101/I.S.2/A440 for each window type.

1.11 QUALIFICATION

Window manufacturer must specialize in designing and manufacturing the type of aluminum windows specified in this section, and have a minimum of 5 years of documented successful experience. Manufacturer must have the facilities capable of meeting contract requirements, single-source responsibility and warranty.

1.12 WARRANTY

Provide Manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period.

PART 2 PRODUCTS

2.1 WINDOWS

Provide prime windows that comply with AAMA/WDMA/CSA 101/I.S.2/A440 and the requirements specified herein. In addition to compliance with

AAMA/WDMA/CSA 101/I.S.2/A440, window framing members for each individual light of glass must not deflect to the extent that deflection perpendicular to the glass light exceeds L/175 of the glass edge length when subjected to uniform loads at specified design pressures. Provide Structural calculations for deflection to substantiate compliance with deflection requirements. Provide windows of types, performance classes, performance grades, combinations, and sizes indicated or specified.

2.1.1 Awning Windows (AP)

Type AP-C30. Conceal operating mechanism within the frame members or enclose within a metal casing not less than 1.59 mm thick sheet aluminum.

2.1.2 Casement Windows (C)

Type C-C30. Ventilators must be rotary crank operated. Provide ventilators over 1650 millimeters high with two separate locking devices or a two-point locking device operated by rods from a single lever handle. Conceal rods where possible.

Design windows, mullions, hardware, and anchors to withstand the wind loading specified.

2.1.3 Glass and Glazing

Materials are specified in Section 08 81 00 GLAZING.

2.1.4 Calking and Sealing

Are specified in Section 07 92 00 JOINT SEALANTS.

2.1.5 Weatherstripping

AAMA/WDMA/CSA 101/I.S.2/A440.

2.1.6 Sash Poles

Seamless aluminum tube, 1.59 mm minimum wall thickness, 25 mm diameter, suitable length for convenient and proper window operations, with cast aluminum hook and protective cover or tip on the lower end. Finish must match windows.

2.2 FABRICATION

Fabrication of window units must comply with AAMA/WDMA/CSA 101/I.S.2/A440.

2.2.1 Provisions for Glazing

Design windows and rabbets suitable for glass thickness shown or specified.

2.2.2 Weatherstripping

Provide for ventilating sections of all windows to ensure a weather-tight seal meeting the infiltration requirements specified in AAMA/WDMA/CSA 101/I.S.2/A440. Provide easily replaceable factory-applied weatherstripping. Use molded vinyl, molded or molded-expanded neoprene or molded or expanded Ethylene Propylene Diene Terpolymer (EPDM) compression-type weatherstripping for compression contact surfaces. Use treated woven pile or wool, or polypropylene or nylon pile bonded to nylon

fabric and metal or plastic backing strip weatherstripping for sliding surfaces. Do no use neoprene or polyvinylchloride weatherstripping where they will be exposed to direct sunlight.

2.2.3 Fasteners

Fabricated from 100 percent re-melted steel. Use fasteners as standard with the window manufacturer for windows, trim, and accessories. Self-tapping sheet-metal screws are not acceptable for material more than 2 mm thick.

2.2.4 Adhesives

Comply with applicable regulations regarding toxic and hazardous materials, GS-36, SCAQMD Rule 1168, and as specified in Section 07 92 00 JOINT SEALANTS.

2.2.5 Drips and Weep Holes

Provide continuous drips over heads of top ventilators. Provide drips and weep holes as required to return water to the outside.

2.2.6 Combination Windows

Windows used in combination must be the same class and grade and will be factory assembled. Where factory assembly of individual windows into larger units is limited by transportation considerations, prefabricate, match mark, transport, and field assemble.

2.2.7 Mullions and Transom Bars

Provide mullions between multiple window units which meet the design pressure of 720 Pa. Provide mullions with a thermal break. Secure mullions and transom bars to adjoining construction and window units in such a manner as to permit expansion and contraction and to form a weathertight joint. Where window cleaner anchors are required, reinforce mullions and anchor to adjoining construction so as to provide safe and adequate support. Provide mullion covers on the interior and exterior to completely close exposed joints and recesses between window units and to present a neat appearance. Provide special covers over structural support at mullions as indicated.

2.2.8 Accessories

Provide windows complete with necessary hardware, fastenings, clips, fins, anchors, glazing beads, and other appurtenances necessary for complete installation and proper operation. Furnish extruded aluminum subframe receptors and subsill with each window unit.

2.2.8.1 Hardware

AAMA/WDMA/CSA 101/I.S.2/A440. The item, type, and functional characteristics must be the manufacturer's standard for the particular window type. Provide hardware of suitable design and of sufficient strength to perform the function for which it is used. Equip all operating ventilators with a lock or latching device which can be secured from the inside.

2.2.8.2 Fasteners

Provide concealed anchors of the type recommended by the window manufacturer for the specific type of construction. Anchors and fasteners must be compatible with the window and the adjoining construction. Provide a minimum of three anchors for each jamb located approximately 150 mm from each end and at midpoint.

2.2.8.3 Window-Cleaner Anchors

Provide double head anchors for windows specified. Anchors must be stainless steel of size and design required for the window type and application, conforming to ASTM A 276. Provide two anchors for each single window and each adjacent fixed glass window unit. Fasten anchors 1120 mm above the window sill utilizing appropriate methods for the window type and application in accordance with industry safety standards.

2.2.8.4 Window Anchors

Anchoring devices for installing windows must be made of aluminum, cadmium-plated steel, stainless steel, or zinc-plated steel conforming to AAMA/WDMA/CSA 101/I.S.2/A440.

2.2.9 Finishes

Exposed aluminum surfaces must be factory finished with an organic coating. Color must be as indicated. All windows will have the same finish.

2.2.9.1 Organic Coating

Clean and prime exposed aluminum surfaces. Provide a baked enamel finish in accordance with AAMA 2603 with total dry film thickness not less than 0.02 mm 0.8 mil.

2.2.10 Screens

AAMA/WDMA/CSA 101/I.S.2/A440. Provide one insect screen for each operable exterior sash or ventilator. Design screens to be rewirable, easily removable from inside the building, and to permit easy access to operating hardware.

2.3 SPECIAL OPERATORS

For windows having operating hardware or locking or latching devices located more than 1800 mm above the floor, provide suitably designed operators or locking or latching devices necessary for convenient and proper window operation.

2.3.1 Pole Operators

Poles must be of proper length to permit window operation from 1500 mm above the floor. Provide one pole operator for each room, and one pole hanger for each pole. Locate hangers where directed.

2.3.2 Extension Crank Operators

Provide removable handles for crank-operated rotary-type operators located more than 1800 mm above the floor. Provide one removable handle for each

room.

2.4 THERMAL-BARRIER WINDOWS

Provide thermal-barrier windows, complete with accessories and fittings, where indicated.

Specify material and construction except as follows:

a. Aluminum alloy must be 6063-T6.

b. Frame construction, including operable sash, must be factory-assembled and factory-sealed inner and outer aluminum completely separated from metal-to-metal contact. Join assembly by a continuous, concealed, low conductance divider housed in an interlocking extrusion of the inner frame. Metal fasteners, straps, or anchors will not bridge the connection between the inner and outer frame.

c. Operating hardware for each sash must consist of spring-loaded nylon cushion blocks and pin locks designed to lock in predetermined locations.

d. Sash must be completely separated from metal-to-metal contact by means of woven-pile weatherstripping, plastic, or elastomeric separation members.

e. Operating and storm sash will be factory-glazed with the type of glass indicated and of the quality specified in Section 08 81 00 GLAZING.

2.5 MULLIONS

Provide mullions between multiple-window units where indicated.

Mullions and mullion covers must be the profile indicated, reinforced as required for the specified wind loading, and securely anchored to the adjoining construction. Mullion extrusion will include serrations or pockets to receive weatherstripping, sealant, or tape at the point of contact with each window flange.

Mullion assembly must include aluminum window clamps or brackets screwed or bolted to the mullion and the mullion cover.

Mullion cover must be screw-fastened to the mullion unless otherwise indicated.

Mullion reinforcing members shall be fabricated of the materials specified in AAMA/WDMA/CSA 101/I.S.2/A440 and meet the specified design loading.

2.6 WINDOW CLEANERS' BOLTS

Provide window cleaners' bolts for all windows 2100 millimeter or higher above finished grade, except windows located so they may be removed for cleaning or cleaned from the ground or from a lower roof level without the use of an extension ladder. Provide two bolts for each single window unit and each fixed glass unit and must be located 1120 millimeter above the window sill.

Window cleaners' bolts must be double-head type, AISI Series 300 corrosion-resistant steel, size and design complying with IWCA I-14.1.

Contact side of the bolts will be ground to fit flat against window jambs. Bolts may be factory- or field-attached before windows are set. Reinforce backs of frames to receive bolts with 6 by 150 millimeter corrosion-resistant steel or aluminum plates bolted or welded to the frames at the factory. Special wall anchors must be provided on frames at the point of bolt attachment.

PART 3 EXECUTION

3.1 SCHEDULE

Some metric measurements in this section are based on mathematical conversion of inch-pound measurements, and not on metric measurement commonly agreed to by the manufacturers or other parties. The inch-pound and metric measurements are as follows:

PRODUCTS	INCH-POUND	METRIC
Metal Casing	0.0625 inch	1.59 mm
Aluminum Tube	0.0625 inch	1.59 mm
(Diameter)	1 inch	25 mm

3.2 INSTALLATION

3.2.1 Method of Installation

Install in accordance with the window manufacturer's printed instructions and details. Build in windows as the work progresses or install without forcing into prepared window openings. Set windows at proper elevation, location, and reveal; plumb, square, level, and in alignment; and brace, strut, and stay properly to prevent distortion and misalignment. Protect ventilators and operating parts against accumulation of dirt and building materials by keeping ventilators tightly closed and locked to frame. Bed screws or bolts in sill members, joints at mullions, contacts of windows with sills, built-in fins, and subframes in mastic sealant of a type recommended by the window manufacturer. Install and caulk windows in a manner that will prevent entrance of water and wind. Fasten insect screens securely in place.

3.2.2 Dissimilar Materials

Where aluminum surfaces are in contact with, or fastened to masonry, concrete, wood, or dissimilar metals, except stainless steel or zinc, protect the aluminum surface from dissimilar materials as recommended in the Appendix to AAMA/WDMA/CSA 101/I.S.2/A440. Do not coat surfaces in contact with sealants after installation with any type of protective material.

3.2.3 Anchors and Fastenings

Make provision for securing units to each other, to masonry, and to other adjoining construction. Windows installed in masonry walls must have head and jamb members designed to recess into masonry wall not less than 11 mm.

3.2.4 Adjustments After Installation

After installation of windows and completion of glazing and field painting, adjust all ventilators and hardware to operate smoothly and to provide

weathertight sealing when ventilators are closed and locked. Lubricate hardware and operating parts as necessary. Verify that products are properly installed, connected, and adjusted.

3.3 CLEANING

Clean interior and exterior surfaces of window units of mortar, plaster, paint spattering spots, and other foreign matter to present a neat appearance, to prevent fouling of weathering surfaces and weather-stripping, and to prevent interference with the operation of hardware. Replace all stained, discolored, or abraded windows that cannot be restored to their original condition with new windows.

3.4 WASTE MANAGEMENT

Separate corrugated cardboard and protective materials in accordance with the Waste Management Plan and place in designated areas for reuse or recycling. Place materials defined as hazardous or toxic waste in designated containers. Close and seal tightly all partly used sealant containers and store protected in well ventilated fire-safe area at moderate temperature. Place used sealant tubes and containers in areas designated for hazardous materials.

-- End of Section --

SECTION 08 53 00

PLASTIC WINDOWS
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 1503	(2009) Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections
AAMA/WDMA/CSA 101/I.S.2/A440	(2008; Update 1 2008; Update 2 2008; Update 3 2009) North American Fenestration Standard/Specification for Windows, Doors, and Skylights

ASME INTERNATIONAL (ASME)

ASME A39.1	(1995) Safety Requirements for Window Cleaning

ASTM INTERNATIONAL (ASTM)

ASTM D 3656	(2007) Insect Screening and Louver Cloth Woven from Vinyl-Coated Glass Yarns
ASTM D 4099	(1995) Poly(Vinyl Chloride) (PVC) Prime Windows and Sliding Glass Doors

GREEN SEAL (GS)

GS-36	(2000) Commercial Adhesives

NATIONAL FENESTRATION RATING COUNCIL (NFRC)

NFRC 100	(2004) Procedure for Determining Fenestration Product U-Factors
NFRC 200	(2004) Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

Energy Star	(1992; R 2006) Energy Star Energy Efficiency Labeling System

U.S. GREEN BUILDING COUNCIL (USGBC)

LEED	(2002; R 2005) Leadership in Energy and Environmental Design(tm) Green Building Rating System for New Construction (LEED-NC)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Windows; G

Indicate elevations of windows, full-size sections, thicknesses of PVC, reinforcing members, fastenings, proposed method of anchoring, size and spacing of anchors, details of construction, method of glazing, details of operating hardware, accessories, installation details, window flashings and other related items.

Schedule of windows; G

Submit with drawings indicating location of each window unit.

SD-03 Product Data

Windows; G (LEED)

Documentation for Energy Star Qualifications

Fasteners

Hardware

Screens

Weatherstripping

Accessories

SD-04 Samples

Windows; G

Submit one full-size window of each type, complete with certification label indicating conformance to AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099, glazing, hardware, anchors, and other accessories. Where screens or weatherstripping are required, fit sample windows with such items that are to be provided. After approval, install each sample in the work, clearly identified, and record its location.

SD-06 Test Reports

Windows; G

Submit for each window type attesting that identical or larger windows have been tested and meet the requirements specified herein for conformance to AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099 and the specified minimum Condensation Resistance Factor (CRF).

SD-07 Certificates

Windows

Submit NFRC Certification documentation.

SD-10 Operation and Maintenance Data

Windows, Data Package 1; G

Submit data package in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

Plastic Identification

When not labeled, identify types in Operation and Maintenance Manual.

1.3 QUALITY ASSURANCE

1.3.1 Labels

Each window unit shall bear a certification label from an independent, nationally recognized testing organization validating that the product complies with AAMA/WDMA/CSA 101/I.S.2/A440 for the type, grade, and performance class specified or that the product complies with ASTM D 4099 for the grade specified.

1.3.2 Certification

Certified test reports attesting that the window units meet the requirements of AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099 as specified will be acceptable in lieu of product labeling or marking.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver windows to the project site in an undamaged condition. Use care in handling and hoisting windows during transportation and at the job site. Store windows and components out of contact with the ground, under a weathertight covering, to prevent bending, warping, or otherwise damaging the windows. Repair damaged windows to an "as new" condition as approved. Provide new units if windows cannot be repaired.

1.5 PROTECTION

Protect finished surfaces during shipping and handling using the manufacturer's standard method, except do not apply coatings or lacquers on surfaces to receive caulking and glazing compounds.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS FOR WINDOWS

Windows shall conform to AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099 and to requirements specified herein. Provide windows of materials, types, grades, performance classes, combinations and sizes indicated or specified. Each window shall be a unit consisting of frame, sash, glass, hardware, anchors and accessories complete. Design windows to accommodate glass, hardware, screens, weatherstripping, and accessories to be furnished. Glass shall be factory or field installed. Provide windows with a minimum CRF of 60, or as directed by the Contracting Officer when tested in accordance with AAMA 1503.

Non-residential plastic windows (including frames and glass) shall be certified by the National Fenestration Rating Council with a whole-window Solar Heat Gain Coefficient (SHGC) maximum of 0.30 determined according to NFRC 200 procedures and a U-factor maximum of 1.8737 W per square m x K in accordance with NFRC 100.

2.2 MATERIALS

2.2.1 Windows

Provide PVC, reinforcing members, fasteners, hardware, weatherstripping, and anchors conforming to AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099 and as specified herein.

2.2.2 Sash Insulation

Use hollow PVC or fiberglass profile insulated with foam or fiberglass, or use foamed PVC for good sash insulation performance.

2.2.3 Glass and Glazing

As specified in Section 08 81 00 GLAZING.

2.2.4 Calking and Sealing

As specified in Section 07 92 00 JOINT SEALANTS.

2.2.5 Adhesives

Comply with applicable regulations regarding toxic and hazardous materials, GS-36, and as specified in Section 07 92 00 JOINT SEALANTS.

2.2.6 Insect Screening

ASTM D 3656, Class 2, 18 by 14 mesh, color charcoal.

2.2.7 Accessories

As standard with the manufacturer and as specified herein.

2.3 WINDOW TYPES

Windows shall be of the following types, as indicated.

2.3.1 Awning Windows

AAMA/WDMA/CSA 101/I.S.2/A440, Type A- C 20 or ASTM D 4099, Grade 20. Provide compression-type weatherstripping.

2.3.2 Casement Windows

AAMA/WDMA/CSA 101/I.S.2/A440, Type C- C 20 or ASTM D 4099, Grade 20. Ventilators shall be rotary crank operated. Provide ventilators over 1675 mm high with two separate locking devices or a two-point locking device operated by rods from a single lever handle. Conceal rods where possible. Provide compression-type weatherstripping.

2.3.3 Construction

Ventilators shall have one or more stabilizing arms attached to the frame when ventilator is opened from top. When ventilator is in the tilt-open position, stabilizing arms shall provide positive positioning of the ventilator.

2.3.3.1 Hardware

Equip each ventilator with one handle to provide both tilt and swing operation. The tilt or swing operation shall be individually selected and rendered operable starting only from the closed sash position. Provide a secondary locking device for each ventilator to prevent accidental swing operation.

2.3.3.2 Performance Requirements

Dual action windows shall meet the primary performance requirements specified in AAMA/WDMA/CSA 101/I.S.2/A440 for Grade and Performance Class C 20 or the performance requirements specified in ASTM D 4099 for Grade 20.

2.4 FABRICATION

Conform to AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099 and to the requirements specified herein.

2.4.1 Subframes, Mullions and Transom Bars

Provide subframes, transom bars and mullions between multiple window units which meet the design pressure of 96 kilograms per square meter (kg/sq m). Fabricate mullions and transom bars in such a manner as to permit expansion and contraction between adjoining construction and window units and to form a weathertight joint. Provide mullion covers on the interior and exterior to completely close exposed joints and recesses between window units and to present a neat appearance. Provide special covers over structural support at mullions as indicated. Where window cleaner anchors are required, reinforce mullions to provide safe and adequate support.

2.4.2 Combination Windows

Windows provided in combination shall be the same grade and performance class and shall be factory assembled. Where factory assembly of individual windows into larger units is limited by transportation considerations, prefabricate, match mark, transport, and field assemble.

2.4.3 Frames and Sash

2.4.3.1 Corners and Reinforcement

Corners of PVC frames and sashes shall be mechanically fixed and sealed or welded or welded for cold climate applications as per directions of Contracting Officer. Reinforce frames and sash as necessary to meet the requirements for the performance classes or grades specified herein.

2.4.3.2 Adjustability

Ventilating sash shall be adjustable vertically and horizontally to ensure smooth operation.

2.4.3.3 Drips and Weep Holes

Provide continuous drips over heads of top ventilators. Where fixed windows adjoin ventilators, provide continuous drips across tops of fixed windows. Provide drips and weep holes as required to return water to the outside.

2.4.3.4 Provisions for Glazing

Design windows and rabbets suitable for glass thickness shown or specified. Design sash for double glazing and for securing glass with glazing beads, glazing clips, glazing channels, glazing gaskets, or glazing compound as directed by the Contracting Officer except do not use glazing compound, vinyl glazing gaskets or exterior glazing beads in cold regions; dry glaze with EPDM or silicone rubber gaskets.

2.4.4 Hardware

The item, type, and functional characteristics shall be the manufacturer's standard for the particular window type. Provide hardware of suitable design and of sufficient strength to perform the function for which it is used. Equip operating ventilators with a lock or latching device which can be secured from the inside.

2.4.5 Weatherstripping

Provide for ventilating sections of windows to ensure a weathertight seal meeting the infiltration requirements specified in AAMA/WDMA/CSA 101/I.S.2/A440 or ASTM D 4099. Provide easily replaceable factory-applied weatherstripping.

2.4.6 Screens

Provide one insect screen for each operable exterior sash or ventilator. Design screens to be rewirable, easily removable from inside the building, and to permit easy access to operating hardware.

2.4.7 Color

Window (PVC) color shall be as directed by the Contracting Officer. Color shall be integral or co-extruded to the PVC to prevent heat build-up.

2.4.8 Fasteners

Provide fastener types as standard with the window manufacturer for

windows, trim, and accessories. Fabricated from 100 percent re-melted steel.

2.4.9 Accessories

Provide windows complete with clips, fins, anchors, and other appurtenances necessary for complete installation and proper operation.

2.4.9.1 Anchors

Provide concealed anchors of the type recommended by the window manufacturer for the specific type of construction. Anchors and fasteners shall be compatible with the window and the adjoining construction. For each jamb 900 mm or longer, provide a minimum of three anchors located approximately 150 mm from each end and at midpoint. For jambs less than 900 mm long, provide two anchors.

2.4.9.2 Window-Cleaner Anchors

Provide double head anchors for windows specified. Anchors shall be stainless steel of size and design conforming to ASME A39.1. Provide two anchors for each single window. Fasten anchors 1120 mm above the window sill in accordance with ASME A39.1. Reinforce frames to receive anchors. Provide wall anchors on backs of frames at points where anchors are located.

2.4.9.3 Grills

Provide the manufacturer's standard grills, if any, for the windows indicated. Grills shall be removable or shall be sealed within insulating glass units. Unless otherwise indicated, grill pattern shall be the manufacturer's standard design or as approved.

2.4.9.4 Integral Venetian Blinds

Provide the manufacturer's standard venetian blinds mounted within the window frame for the windows indicated. Venetian blinds shall be fully adjustable allowing full angle tilting and stops at any position. Color of blinds shall be as directed by the Contracting Officer.

PART 3 EXECUTION

3.1 INSTALLATION

Install in accordance with the window manufacturer's printed instructions and details. Build in windows as work progresses or install without forcing into prepared window openings. Set windows at proper elevation, location, and reveal; plumb, square, level, and in alignment; and brace, strut, and stay properly to prevent distortion and misalignment. Bed screws or bolts in sill members, joints at mullions, contacts of windows with sills, built-in fins, and subframes in mastic sealant of a type recommended by the window manufacturer. Install and seal windows in a manner that will prevent entrance of water and wind. Fasten insect screens securely in place. Fasten hardware to windows.

3.1.1 Anchors and Fastenings

Secure units to each other, to masonry, and to other adjoining construction with clips, fins, screws, or other devices recommended by the window manufacturer. Where window cleaner anchors are provided, anchor windows

and mullions to provide safe and adequate support for the window cleaner.

3.2 ADJUSTING

After installation of windows and completion of glazing and field painting, adjust ventilators and hardware to operate smoothly and to provide weathertight sealing when ventilators are closed and locked. Lubricate hardware and operating parts as necessary. Verify products are properly installed, connected, and adjusted.

3.3 CLEANING

Clean interior and exterior surfaces of window units of mortar, plaster, paint spattering spots, and other foreign matter to present a neat appearance, to prevent fouling of weathering surfaces and weatherstripping, and to prevent interference with operation of hardware. Replace stained, discolored, or abraded windows that cannot be restored to their original condition with new windows.

3.4 PROTECTION

Protect ventilators and operating parts against accumulation of dirt and building materials by keeping ventilators tightly closed and locked to frame.

3.5 WASTE MANAGEMENT

Separate plastic materials, corrugated cardboard, and protective materials in accordance with the Waste Management Plan and reuse or recycle. Place materials defined as hazardous or toxic waste in designated containers and dispose of properly. Close and seal tightly all partly used sealant containers and store protected in well ventilated fire-safe area at moderate temperature. Place used sealant tubes and containers in areas designated for hazardous materials and dispose of properly.

-- End of Section --

SECTION 08 71 00

DOOR HARDWARE
10/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 283	(2004) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

BHMA A156.1	(2006) Butts and Hinges
BHMA A156.13	(2005) Mortise Locks & Latches, Series 1000
BHMA A156.15	(2006) Closer Holder Release Devices
BHMA A156.16	(2002) Auxiliary Hardware
BHMA A156.18	(2006) Materials and Finishes
BHMA A156.2	(2003) Bored and Preassembled Locks and Latches
BHMA A156.21	(2006) Thresholds
BHMA A156.22	(2005) Door Gasketing and Edge Seal Systems
BHMA A156.3	(2001) Exit Devices
BHMA A156.4	(2000) Door Controls - Closers
BHMA A156.5	(2001) Auxiliary Locks & Associated Products
BHMA A156.6	(2005) Architectural Door Trim
BHMA A156.7	(2003) Template Hinge Dimensions
BHMA A156.8	(2005) Door Controls - Overhead Stops and Holders

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2008; Amendment 2009) Life Safety Code

NFPA 80 (2007) Standard for Fire Doors and Other Opening Protectives

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR A250.8 (2003) Recommended Specification for Standard Steel Doors and Frames

UNDERWRITERS LABORATORIES (UL)

UL 14C (2006) Swinging Hardware for Standard Tin-Clad Fire Doors Mounted Singly and in Pairs

UL Bld Mat Dir (2009) Building Materials Directory

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

SD-02 Shop Drawings

Hardware schedule; G

Keying system

SD-03 Product Data

Hardware items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule items, Data Package 1; G

Submit data package in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

Key Bitting

1.3 HARDWARE SCHEDULE

Prepare and submit hardware schedule in the following form:

Hardware Item	Quantity	Size	Reference Publication Type No.	Finish	Mfr. Name and Catalog No.	Key Control Symbols	UL Mark (If fire rated and listed)	BHMA Finish Designation

1.4 KEY BITTING CHART REQUIREMENTS

Submit key bitting charts to the Contracting Officer prior to completion of the work. Include:

a. Complete listing of all keys (AA1, AA2, etc.).

b. Complete listing of all key cuts (AA1-123456, AA2-123458).

c. Tabulation showing which key fits which door.

d. Copy of floor plan showing doors and door numbers.

e. Listing of 20 percent more key cuts than are presently required in each master system.

1.5 QUALITY ASSURANCE

1.5.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, locks, hinges, and closers of one lock, hinge, or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.6 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown in hardware schedule. Deliver permanent keys and removable cores to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Provide hardware to be applied to metal or to prefinished doors manufactured to template. Promptly furnish template information or templates to door and frame manufacturers. Conform to BHMA A156.7 for template hinges. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 80 for fire doors and NFPA 101 for exit doors, as well as to other requirements indicated, even if such hardware is not specifically mentioned under paragraph entitled "Hardware Schedule." Conform to UL 14C for swinging hardware for the tin-clad fire doors. Provide the label of Underwriters Laboratories, Inc. for such hardware listed in UL Bld Mat Dir or labeled and listed by another testing laboratory acceptable to the Contracting Officer.

2.3 HARDWARE ITEMS

Clearly and permanently mark with the manufacturer's name or trademark, hinges, pivots, locks, latches, exit devices, bolts and closers where the identifying mark will be visible after the item is installed. For closers

with covers, the name or trademark may be beneath the cover.

2.3.1 Hinges

BHMA A156.1, size as indicated. Construct loose pin hinges for exterior doors and reverse-bevel interior doors so that pins will be nonremovable when door is closed. Other antifriction bearing hinges may be provided in lieu of ball-bearing hinges. There shall be at least 3 hinges at each door. Each hinge shall be at least 200/16/5 MM, secured with threaded pins.

2.3.2 Locks and Latches

2.3.2.1 Mortise Locks and Latches

BHMA A156.13, Series 1000, Operational Grade 1, Security Grade 2. Provide mortise locks with escutcheons not less than 178 by 57 mm with a bushing at least 6 mm long. Cut escutcheons to suit cylinders and provide trim items with straight, beveled, or smoothly rounded sides, corners, and edges. Install knobs and roses of mortise locks with screwless shanks and no exposed screws.

2.3.2.2 Bored Locks and Latches

BHMA A156.2, Series 4000, Grade 1.

2.3.2.3 Residential Bored Locks and Latches

BHMA A156.2, Series 4000, Grade 2. Install locks for exterior doors with threaded roses or concealed machine screws.

2.3.2.4 Auxiliary Locks

BHMA A156.5, Grade 1.

2.3.3 Exit Devices

BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices. Provide escutcheons, not less than 178 by 57 mm.

2.3.4 Cylinders and Cores

Provide cylinders and cores for new locks, including locks provided under other sections of this specification. Provide cylinders and cores with seven pin tumblers. Provide cylinders from products of one manufacturer, and provide cores from the products of one manufacturer. Rim cylinders, mortise cylinders, and knobs of bored locksets have interchangeable cores which are removable by special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.5 Keying System

Provide a master keying system. Provide a construction master keying system. Provide key cabinet as specified.

2.3.6 Lock Trim

Cast, forged, or heavy wrought construction and commercial plain design.

2.3.6.1 Lever Handles

Provide lever handles in lieu of knobs. Conform to the minimum requirements of BHMA A156.13 for mortise locks of lever handles for exit devices. Provide lever handle locks with a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when force in excess of that specified in BHMA A156.13 is applied to the lever handle. Provide lever handles return to within 13mm.

2.3.7 Keys

Furnish one file key, one duplicate key, and one working key for each key change and for each master keying system. Furnish one additional working key for each lock of each keyed-alike group. Furnish two additional keys for each sleeping room. Furnish 2 construction master keys, and 2 control keys for removable cores. Furnish a quantity of key blanks equal to 20 percent of the total number of file keys. Stamp each key with appropriate key control symbol and "U.S. property - Do not duplicate." Do not place room number on keys.

2.3.8 Closers

BHMA A156.4, Series C02000, and Series C02061, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, full size covers, except at storefront mounting, and other features necessary for the particular application. Size closers in accordance with manufacturer's recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

2.3.8.1 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation located to be visible after installation.

2.3.9 Overhead Holders

BHMA A156.8.

2.3.10 Closer Holder-Release Devices

BHMA A156.15.

2.3.11 Door Protection Plates

BHMA A156.6. Door protection plates shall be stainless steel with smooth sanded surface, grain 240. Plates shall be fastened with glue and stainless steel screws.

2.3.11.1 Sizes of Mop Plates

Fifty mm less than door width for single doors; 25 mm less than door width for pairs of doors. Provide 150 mm mop plates.

2.3.11.2 Sizes of Kick Plates

Kick plates shall be full width of the door and 300 MM high. Kick plates shall be provided on both sides of the doors.

2.3.12 Door Stops and Silencers

BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair. Door stops shall be heavy-duty stainless steel post with skid nose made of white nylon. Length of stops shall be sufficient to prevent door handles from striking wall.

2.3.13 Thresholds

BHMA A156.21. Use J35100, with vinyl or silicone rubber insert in face of stop, for exterior doors opening out, unless specified otherwise.

2.3.14 Weather Stripping Gasketing

BHMA A156.22. Provide the type and function designation where specified in paragraph entitled "Hardware Schedule". Provide a set to include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weather stripped doors not to exceed 2.19 x 10-5 cms per minute of air per square meter of door area when tested in accordance with ASTM E 283. Provide weather stripping with one of the following:

2.3.14.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 1.25 mm wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Provide clear anodized aluminum.

2.3.14.2 Interlocking Type

Zinc or bronze not less than 0.45 mm thick.

2.3.14.3 Spring Tension Type

Spring bronze or stainless steel not less than 0.20 mm thick.

2.3.15 Rain Drips

Extruded aluminum, not less than 2.03 mm thick, clear anodized. Set drips in sealant and fasten with stainless steel screws.

2.3.15.1 Door Rain Drips

Approximately 38 mm high by 16 mm projection. Align bottom with bottom edge of door.

2.3.15.2 Overhead Rain Drips

Approximately 38 mm high by 64 mm projection, with length equal to overall width of door frame. Align bottom with door frame rabbet.

2.3.16 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, required to service and adjust hardware items.

2.4 FASTENERS

Provide fasteners of proper type, quality, size, quantity, and finish with hardware. Provide stainless steel or nonferrous metal fasteners that are

exposed to weather. Provide fasteners of type necessary to accomplish a permanent installation.

2.5 FINISHES

BHMA A156.18. Provide hardware in heavy duty commercial grade stainless steel unless specified otherwise.

2.6 KEY CABINET AND CONTROL SYSTEM

BHMA A156.5, Type required to yield a capacity (number of hooks) 50 percent greater than the number of key changes used for door locks.

PART 3 EXECUTION

3.1 INSTALLATION

Install hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weather Stripping Installation

Handle and install weather stripping to prevent damage. Provide full contact, weather-tight seals. Operate doors without binding.

3.1.1.1 Stop-Applied Weather Stripping

Fasten in place with color-matched sheet metal screws not more than 225 mm on center after doors and frames have been finish painted.

3.1.1.2 Interlocking Type Weather Stripping

Provide interlocking, self-adjusting type on heads and jambs and flexible hook type at sills. Nail weather stripping to door 25 mm on center and to heads and jambs at 100 mm on center.

3.1.1.3 Spring Tension Type Weather Stripping

Provide spring tension type on heads and jambs. Provide bronze nails with bronze, stainless steel nails with stainless steel. Space nails not more than 38 mm on center.

3.1.2 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves.

3.2 HARDWARE LOCATIONS

SDI/DOOR A250.8, unless indicated or specified otherwise.

a. Kick and Armor Plates: Push side of single-acting doors. Both sides of double-acting doors.

b. Mop Plates: Bottom flush with bottom of door.

3.3 KEY CABINET AND CONTROL SYSTEM

Locate where directed by Contracting Officer. Tag one set of file keys and one set of duplicate keys. Place other keys in appropriately marked envelopes, or tag each key. Furnish complete instructions for setup and use of key control system. On tags and envelopes, indicate door and room numbers or master or grand master key.

3.4 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks, and give keys to the Contracting Officer. Correct, repair, and finish, as directed, errors in cutting and fitting and damage to adjoining work.

3.5 HARDWARE SETS

Refer to Architectural Drawings for Hardware Sets.

-- End of Section --

SECTION 08 81 00

GLAZING
02/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1	(2004) Safety Glazing Materials Used in Buildings

ASTM INTERNATIONAL (ASTM)

ASTM C 1036	(2006) Standard Specification for Flat Glass
ASTM C 1172	(2009) Standard Specification for Laminated Architectural Flat Glass
ASTM C 1184	(2005) Standard Specification for Structural Silicone Sealants
ASTM C 509	(2006) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C 864	(2005) Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers
ASTM C 920	(2008) Standard Specification for Elastomeric Joint Sealants
ASTM D 2287	(1996; R 2001) Nonrigid Vinyl Chloride Polymer and Copolymer Molding and Extrusion Compounds
ASTM D 395	(2003; R 2008) Standard Test Methods for Rubber Property - Compression Set
ASTM E 1300	(2009a) Determining Load Resistance of Glass in Buildings

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual	(2004) Glazing Manual
GANA Sealant Manual	(1990) Sealant Manual

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)

IGMA TB-3001	(1990) Guidelines for Sloped Glazing

IGMA TM-3000	(1997) Glazing Guidelines for Sealed Insulating Glass Units

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201	Safety Standard for Architectural Glazing Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation

Drawings showing certain details of the proposed setting methods, mullion details, edge blocking, size of openings, frame details, materials, and types and thickness of glass. Follow industry practice otherwise.

SD-03 Product Data

Glazing Accessories

Manufacturer's descriptive product data, handling and storage recommendations, installation instructions, and cleaning instructions.

SD-04 Samples

Glazing Compound

Glazing Tape

Sealant

Three samples of each indicated material. Samples of plastic sheets shall be minimum 125 by 175 mm.

SD-07 Certificates

Plastic Glazing

Certificates stating that the glass meets the specified requirements. Labels or manufacturers marking affixed to the glass will be accepted in lieu of certificates.

SD-08 Manufacturer's Instructions

Setting and sealing materials

Glass setting

Submit glass manufacturer's recommendations for setting and sealing materials and for installation of each type of glazing material specified.

1.3 SYSTEM DESCRIPTION

Glazing systems shall be fabricated and installed watertight and airtight to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, and defects in the work. Glazed panels shall comply with the safety standards, as indicated in accordance with ANSI Z97.1. Glazed panels shall comply with indicated wind/snow loading in accordance with ASTM E 1300.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver products to the site in unopened containers, labeled plainly with manufacturers' names and brands. Store glass and setting materials in safe, enclosed dry locations and do not unpack until needed for installation. Handle and install materials in a manner that will protect them from damage.

1.5 ENVIRONMENTAL REQUIREMENTS

Do not start glazing work until the outdoor temperature is above 4 degrees C and rising, unless procedures recommended by the glass manufacturer and approved by the Contracting Officer are made to warm the glass and rabbet surfaces. Provide ventilation to prevent condensation of moisture on glazing work during installation. Do not perform glazing work during damp or rainy weather.

PART 2 PRODUCTS

2.1 GLASS

ASTM C 1036, unless specified otherwise. In doors and sidelights, provide safety glazing material conforming to 16 CFR 1201.

2.1.1 Laminated Glass

Fabricated from two pieces of Type I, Class 1, Quality q3 glass laminated together with a clear 0.38 mm thick polyvinyl butyral interlayer or alternatives such as resin laminates, conforming to requirements of 16 CFR 1201 and ASTM C 1172. Color shall be clear. The total thickness shall be nominally 6 mm.

2.1.2 Mirrors

2.1.2.1 Glass Mirrors

Glass for mirrors shall be Type I transparent flat type, Class 1-clear, Glazing Quality q1 6 mm (1/4 inch) thick conforming to ASTM C 1036. Glass shall be coated on one surface with silver coating, copper protective coating, and mirror backing paint. Silver coating shall be highly adhesive pure silver coating of a thickness which shall provide reflectivity of 83 percent or more of incident light when viewed through 6 mm (1/4 inch) thick glass, and shall be free of pinholes or other defects. Copper protective coating shall be pure bright reflective copper, homogeneous without sludge, pinholes or other defects, and shall be of proper thickness to prevent "adhesion pull" by mirror backing paint. Mirror backing paint shall

consist of two coats of special scratch and abrasion-resistant paint, and shall be baked in uniform thickness to provide a protection for silver and copper coatings which will permit normal cutting and edge fabrication.

2.2 SETTING AND SEALING MATERIALS

Provide as specified in the GANA Glazing Manual, IGMA TM-3000, IGMA TB-3001, and manufacturer's recommendations, unless specified otherwise herein. Do not use metal sash putty, nonskinning compounds, nonresilient preformed sealers, or impregnated preformed gaskets. Materials exposed to view and unpainted shall be gray or neutral color.

2.2.1 Putty and Glazing Compound

Putty and glazing compounds shall not be used with laminated glass.

2.2.2 Sealants

Provide elastomeric and structural sealants.

2.2.2.1 Elastomeric Sealant

ASTM C 920, Type S, Grade NS, Class 12.5, Use G. Use for channel or stop glazing metal sash. Sealant shall be chemically compatible with setting blocks, edge blocks, and sealing tapes. Color of sealant shall be white.

2.2.2.2 Structural Sealant

ASTM C 1184, Type S.

2.2.3 Joint Backer

Joint backer shall have a diameter size at least 25 percent larger than joint width; type and material as recommended in writing by glass and sealant manufacturer.

2.2.4 Preformed Channels

Neoprene, vinyl, or rubber, as recommended by the glass manufacturer for the particular condition.

2.2.5 Sealing Tapes

Preformed, semisolid, PVC-based material of proper size and compressibility for the particular condition, complying with ASTM D 2287. Use only where glazing rabbet is designed for tape and tape is recommended by the glass or sealant manufacturer. Provide spacer shims for use with compressible tapes. Tapes shall be chemically compatible with the product being set.

2.2.6 Setting Blocks and Edge Blocks

Closed-cell neoprene setting blocks shall be dense extruded type conforming to ASTM C 509 and ASTM D 395, Method B, Shore A durometer between 70 and 90. Edge blocking shall be Shore A durometer of 50 (+ or - 5). Silicone setting blocks shall be required when blocks are in contact with silicone sealant. Profiles, lengths and locations shall be as required and recommended in writing by glass manufacturer. Block color shall be black.

2.2.7 Glazing Gaskets

Glazing gaskets shall be extruded with continuous integral locking projection designed to engage into metal glass holding members to provide a watertight seal during dynamic loading, building movements and thermal movements. Glazing gaskets for a single glazed opening shall be continuous one-piece units with factory-fabricated injection-molded corners free of flashing and burrs. Glazing gaskets shall be in lengths or units recommended by manufacturer to ensure against pull-back at corners. Glazing gasket profiles shall be as indicated on drawings.

2.2.7.1 Fixed Glazing Gaskets

Fixed glazing gaskets shall be closed-cell (sponge) smooth extruded compression gaskets of cured elastomeric virgin neoprene compounds conforming to ASTM C 509, Type 2, Option 1.

2.2.7.2 Wedge Glazing Gaskets

Wedge glazing gaskets shall be high-quality extrusions of cured elastomeric virgin neoprene compounds, ozone resistant, conforming to ASTM C 864, Option 1, Shore A durometer between 65 and 75.

2.2.7.3 Aluminum Framing Glazing Gaskets

Glazing gaskets for aluminum framing shall be permanent, elastic, non-shrinking, non-migrating, watertight and weathertight.

2.2.8 Accessories

Provide as required for a complete installation, including glazing points, clips, shims, angles, beads, and spacer strips. Provide noncorroding metal accessories. Provide primer-sealers and cleaners as recommended by the glass and sealant manufacturers.

2.3 MIRROR ACCESSORIES

2.3.1 Mirror Frames

Mirrors shall be provided with mirror frames (J-mold channels) fabricated of one-piece roll-formed Type 304 stainless steel with No. 4 brushed satin finish and concealed fasteners which will keep mirrors snug to wall. Frames shall be 32 x 6 x 6 mm (1-1/4 x 1/4 x 1/4 inch) continuous at top and bottom of mirrors. Concealed fasteners of type to suit wall construction material shall be provided with mirror frames.

PART 3 EXECUTION

3.1 PREPARATION

Preparation, unless otherwise specified or approved, shall conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Determine the sizes to provide the required edge clearances by measuring the actual opening to receive the glass. Grind smooth in the shop glass edges that will be exposed in finish work. Leave labels in place until the installation is approved, except remove applied labels on heat-absorbing glass and on insulating glass units as soon as glass is installed. Securely fix movable items or keep in a closed and locked position until glazing

compound has thoroughly set.

3.2 GLASS SETTING

Shop glaze or field glaze items to be glazed using glass of the quality and thickness specified or indicated. Glazing, unless otherwise specified or approved, shall conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Aluminum windows may be glazed in conformance with one of the glazing methods described in the standards under which they are produced, except that face puttying with no bedding will not be permitted. Handle and install glazing materials in accordance with manufacturer's instructions. Use beads or stops which are furnished with items to be glazed to secure the glass in place. Verify products are properly installed, connected, and adjusted.

3.2.1 Installation of Laminated Glass

Sashes which are to receive laminated glass shall be weeped to the outside to allow water drainage into the channel.

3.3 CLEANING

Clean glass surfaces and remove labels, paint spots, putty, and other defacement as required to prevent staining. Glass shall be clean at the time the work is accepted.

3.4 PROTECTION

Glass work shall be protected immediately after installation. Glazed openings shall be identified with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Reflective glass shall be protected with a protective material to eliminate any contamination of the reflective coating. Protective material shall be placed far enough away from the coated glass to allow air to circulate to reduce heat buildup and moisture accumulation on the glass. Upon removal, separate protective materials for reuse or recycling. Glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities shall be removed and replaced with new units.

3.5 WASTE MANAGEMENT

Disposal and recycling of waste materials, including corrugated cardboard recycling, shall be in accordance with the Waste Management Plan. Separate float glass and reuse or recycle. Upon removal, separate protective materials and reuse or recycle. Separate tempered glass for use as aggregate or nonstructural fill. Close and seal tightly all partly used sealant containers and store protected in well-ventilated, fire-safe area at moderate temperature.

3.6 SCHEDULE

Some metric measurements in this section are based on mathematical conversion of inch-pound measurements, and not on metric measurement commonly agreed to by the manufacturers or other parties. The inch-pound and metric measurements are as follows:

PRODUCTS	INCH-POUND	METRIC
Glass	1/8 inch	3 mm
	3/16 inch	4.5 mm
	7/32 inch	6 mm
	1/4 inch	6 mm
	3/8 inch	10 mm
Interlayer	0.015 inch	0.38 mm
Glazing Channels	1/4 inch	6 mm

-- End of Section --

SECTION 09 22 00

METAL SUPPORT ASSEMBLIES
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 463/A 463M	(2006) Standard Specification for Steel Sheet, Aluminum-Coated
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM C 841	(2003) Installation of Interior Lathing and Furring

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM ML/SFA 920	(1991) Metal Lathing and Furring

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Metal support systems; G

Submit for the erection of metal framing, furring, and ceiling suspension systems. Indicate materials, sizes, thicknesses, and fastenings.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the job site and store in ventilated dry locations. Storage area shall permit easy access for inspection and handling. If materials are stored outdoors, stack materials off the ground, supported on a level platform, and fully protected from the weather. Handle materials carefully to prevent damage. Remove damaged items and provide new items.

PART 2 PRODUCTS

2.1 MATERIALS

Provide steel materials for metal support systems with galvanized coating ASTM A 653/A 653M, Z180; aluminum coating ASTM A 463/A 463M, T1-75; or a 55-percent aluminum-zinc coating.

2.1.1 Materials for Attachment of Lath

2.1.1.1 Suspended and Furred Ceiling Systems and Wall Furring

ASTM C 841.

2.1.1.2 Nonload-Bearing Wall Framing

NAAMM ML/SFA 920.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Systems for Attachment of Lath

3.1.1.1 Suspended and Furred Ceiling Systems and Wall Furring

ASTM C 841, except as indicated otherwise.

3.1.1.2 Nonload-Bearing Wall Framing

NAAMM ML/SFA 920, except that framing members shall be 400 mm o.c. unless indicated otherwise.

3.2 ERECTION TOLERANCES

Framing members which will be covered by finish materials such as plaster, or ceramic tile set in a mortar setting bed, shall be within the following limits:

a. Layout of walls and partitions: 6 mm from intended position;

b. Plates and runners: 5 mm in 1.9 meters from a straight line;

c. Studs: 5 mm in 1.9 meters out of plumb, not cumulative; and

d. Face of framing members: 5 mm in 1.9 meters from a true plane.

Framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive shall be within the following limits:

a. Layout of walls and partitions: 6 mm from intended position;

b. Plates and runners: 5 mm in 3.8 meters from a straight line;

c. Studs: 5 mm in 3.8 meters out of plumb, not cumulative; and

d. Face of framing members: 5 mm in 3.8 meters from a true plane.

-- End of Section --

SECTION 09 22 37.00 10

LATHING AND PLASTERING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 580/A 580M	(2008) Standard Specification for Stainless Steel Wire
ASTM A 853	(2004) Standard Specification for Steel Wire, Carbon, for General Use
ASTM B 164	(2003; R 2008) Standard Specification for Nickel-Copper Alloy Rod, Bar, and Wire
ASTM C 1002	(2004) Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs
ASTM C 150	(2007) Standard Specification for Portland Cement
ASTM C 206	(2003) Standard Specification for Finishing Hydrated Lime
ASTM C 29/C 29M	(2007) Standard Test Method for Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C 645	(2006) Nonstructural Steel Framing Members
ASTM C 754	(2004) Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products
ASTM C 842	(2005) Application of Interior Gypsum Plaster
ASTM C 841	(2003) Installation of Interior Lathing and Furring
ASTM C 847	(2009) Standard Specification for Metal Lath
ASTM C 897	(2000) Aggregate for Job-Mixed Portland Cement-Based Plasters

ASTM C 926 (2006) Application of Portland Cement-Based Plaster

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Approved Detail Drawings; G

Drawings including installation details, ceiling framing, and furring.

SD-03 Product Data

Lathing Installation; G

Manufacturer's pre-printed descriptive data, catalog cuts, and installation instructions for plastering materials and accessories.

SD-04 Samples

Portland Cement Plaster

One 1 m square sample panel of each specified finish.

SD-07 Certificates

Qualifications

Manufacturer's experience in specified work.

1.3 QUALIFICATIONS

Manufacturer shall specialize in manufacturing the types of material specified, and shall have a minimum of 5 years of documented successful experience. Applicator shall specialize in the type of lath and plaster work required to meet requirements, with a minimum of 3 years of documented experience.

1.4 DELIVERY, STORAGE AND HANDLING

Materials shall be delivered to project site in the original containers bearing the name of manufacturer, contents, and brand name. Plaster, cement, and lime shall be stored off the ground under weathertight cover and away from sweating walls and other damp surfaces until ready for use. Accessories shall be stored off the ground in a weathertight structure for protection. Damaged or deteriorated materials shall be removed from project site.

1.5 ENVIRONMENTAL CONDITIONS

A temperature between 4 and 27 degrees C shall be evenly maintained in the

building for a period of not less than 1 week prior to application of plaster, and for a period of at least 1 week after the gypsum plaster is set, in accordance with ASTM C 842. Interior spaces shall be ventilated in accordance with ASTM C 842 immediately after applying plaster.

PART 2 PRODUCTS

2.1 NON-LOADBEARING WALLS

2.1.1 Studs

Studs for non-loadbearing walls shall conform to ASTM C 645. Studs shall be C-shaped, roll-formed steel with minimum uncoated design thickness of 0.72 mm made from G40 hot-dip galvanized coated sheet.

2.1.2 Runner Tracks

Prefabricated floor and ceiling runner tracks shall conform to ASTM C 645. Tracks shall be prefabricated, U-shaped, unpunched web, thickness to match studs, made from G40 hot-dip galvanized coated sheet.

2.2 METAL WALL FURRING

Metal wall furring channels shall conform to ASTM C 645. Furring channels shall be formed from cold-rolled steel, 19 mm wide by 11 mm deep, made from G40 hot-dip galvanized coated sheet.

2.3 SUSPENDED CEILING FRAMING

Suspended ceiling framing system shall have the capability to support the finished ceiling, light fixtures, air diffusers, and accessories, as shown. The suspension system shall have a maximum deflection of L/240. Carrying channels shall be formed from minimum 1.40 mm thick cold-rolled steel, 38 mm wide by 11 mm deep. Cross furring members shall conform to ASTM C 645, and shall be formed from cold-rolled steel, 19 mm wide by 11 mm deep. Carrying channels and furring members shall be made from hot-dip galvanized coated sheet.

2.4 TRIM, MOLDINGS, AND ACCESSORIES

2.4.1 Hangers

Suspended ceiling runner channel hangers shall be soft, annealed steel wire not less than No. 8 SWG nominal diameter, conforming to ASTM A 853 or flat iron or steel straps, at least 2 x 22 mm size, coated with zinc, cadmium, or rust-inhibiting paint.

2.4.2 Fastenings

Tie wire, rings, and other fastenings shall be corrosion-resisting steel conforming to ASTM A 580/A 580M, composition 302, 304, or 316, Condition A, or nickel-copper alloy conforming to ASTM B 164, annealed condition. Walls, partitions, and other vertical surfaces not incorporated in ceiling construction may be erected with soft, annealed steel conforming to ASTM A 853.

2.4.2.1 Tie Wire

Tie wire for constructing partitions and vertical furring, for securing

metal lath to supports, and for lacing shall be not less than No. 18 SWG diameter. Tie wire for all other applications shall be not less than No. 16 SWG diameter.

2.4.2.2 Clips

Clips used in lieu of tie wire for securing furring channels to the runner channels in ceiling construction shall be made from strips not less than 3 mm thick or shall be hairpin clip formed of No. 8 SWG wire. Other clips and rings or fastenings of similar materials shall be equivalent in holding power to that provided by tie wire for the specific application.

2.4.3 Expanded Flange Corner Beads

Expanded flange corner beads shall be fabricated of 0.50 mm thick galvanized steel, with 64 mm wide flanges and 3 mm wide bead.

2.4.4 Bullnose Corner Beads

Bullnose corner beads shall be fabricated of 0.50 mm thick galvanized steel, with 64 mm wide flanges and 19 mm bead.

2.4.5 Cornerites

Cornerites shall conform to ASTM C 847. Cornerites shall be fabricated of galvanized expanded metal lath to form an angle of at least 100 degrees, with outstanding legs of not less than 50 mm.

2.4.6 Base or Parting Screed

Base screeds shall be fabricated of 0.50 mm thick galvanized steel, 13 mm depth, with not less than 50 mm wide expansion flanges.

2.4.7 Casing Beads

Casing beads shall be fabricated of galvanized 0.70 mm thick steel 13 mm depth, 25 mm wide expansion wings, front edge of face flange shaved for intended use, back slightly arched to provide a spring effect.

2.4.8 Control Joints

Control joints shall be designed for expansion and contraction of plaster work due to thermal exposure. Control joints shall be fabricated of vinyl (for interior) or galvanized steel (for exterior back to back casing beads).

2.4.9 Reveal Molding

Reveal moldings shall be fabricated of vinyl (for interior) or galvanized steel (for exterior application) or zinc. Reveal molding shall be size and shape as shown.

2.4.10 Screws

Self-drill steel screws shall conform to ASTM C 1002. Screws shall be Type S for use with steel framing and Type W for use with wood members.

2.5 METAL LATH

2.5.1 Expanded Metal Lath

Expanded metal lath shall conform to ASTM C 847. Lath shall be self-furring lath or flat rib lath, expanded from cold-rolled carbon sheet steel of commercial quality, coated with rust-inhibitive paint after fabrication, 1.8 kg/square meter, with backing.

2.6 CEMENT PLASTER MATERIALS

2.6.1 Portland Cement

Portland cement shall conform to ASTM C 150, white portland cement Type II with 13 mm chopped alkali-resistant fiberglass strands or polypropylene fibers, minimum 680 g per sack of cement.

2.6.2 Aggregates

The unit weight of aggregates shall be determined in accordance with ASTM C 29/C 29M. Portland cement based plaster aggregates shall conform to ASTM C 897, except that the gradation of natural or manufactured sand for portland-cement plaster shall be as follows:

Sieve Size (mm)	Sand, Percentage by Weight Retained on Each Sieve Maximum	Minimum
4.75	0	--
2.36	8	2
1.18	38	22
0.60	78	52
0.30	97	65
0.15	100	97

2.6.3 Water

Water shall be clean, fresh, potable, and free from injurious amounts of oils, acids, alkalis and organic matter injurious to the plaster and to any metal in the system.

2.6.4 Lime

Lime shall conform to ASTM C 206, Type S-Special hydrated finishing lime suitable for use in scratch brown and finish coats of portland-cement plaster.

2.7 WALL OPENING FRAMES

Steel frames for wall openings for doors, pass-through openings, and access panels shall be as specified in Section 08 11 13 STEEL DOORS AND FRAMES or Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS. Wood frames, wood bucks, and blocking for wall openings for doors, pass-through openings, and access panels shall be as specified in Section 06 10 00 ROUGH CARPENTRY.

PART 3 EXECUTION

3.1 PREPARATION

Project conditions shall be verified as ready to receive the work. Field measurements shall be verified for compliance with approved detail drawings and manufacturer's published recommendations. Beginning of installation means installer accepts existing conditions.

3.2 SUSPENDED CEILING FRAMING INSTALLATION

Suspended system shall be installed in accordance with ASTM C 841. Where channels are spliced, the ends shall be overlapped not less than 300 mm for 38 mm channels and not less than 200 mm for 19 mm channels with flanges of channels interlocked and securely tied near each end of the splice with two loops of the tie wire. Splices shall be staggered.

3.2.1 Hangers

Wire or strap hangers shall be attached to structural members in accordance with ASTM C 841, except hangers shall be spaced not more than 1220 mm along runner channels and 900 mm in the other direction or 1050 mm in both directions unless otherwise indicated or approved. Locations of hangers shall be coordinated with other work. Hangers at ends of runner channels shall be located not more than 150 mm from wall. Hanger wire shall be looped around bottom chord of open-web steel joist or secured to structural elements with suitable fasteners. Sags or twists in the suspended system shall be adjusted. Damaged or faulty parts shall be replaced.

3.2.2 Main Runners

Main runner channels shall be installed in accordance with ASTM C 841. Hanger wire shall be saddle-tied to runner channels, and the end of hanger wires shall be twisted three times around itself. Main runners shall not come in contact with abutting masonry or concrete walls and partitions. Main runners shall be located within 150 mm of the paralleling wall to support the ends of cross furring.

3.2.3 Furring Channels

Furring channels shall be spaced in accordance with ASTM C 841 for the type of lath used. Furring channels shall be securely saddle-tied to the runner channels and to structural supports at each crossing with tie wire, hairpin clips, or equivalent clips or fastenings. Furring channels shall be located within 50 mm of parallel walls and beams, and 13 mm from abutting walls.

3.2.4 Light Fixtures and Air Diffusers

Light fixtures and air diffusers shall be supported directly from suspended ceiling runners. Wires shall be provided at appropriate locations to carry the weight of recessed or surface mounted light fixtures and air diffusers.

3.3 FURRED CEILING FRAMING INSTALLATION

Ceiling runners at continuous furred ceilings shall be applied directly to furring channels and secured thereto with tie wire, bolts, or screws at not more than 600 mm centers.

3.4 WALL FRAMING INSTALLATION

3.4.1 Non-Loadbearing Wall Framing

Nonload-bearing steel studs shall be installed in accordance with ASTM C 754 with spacings as indicated in ASTM C 841 for the type of lath used. Studs shall be aligned and secure in top and bottom runners at spacings indicated on drawings. Two beads of acoustic sealant shall be placed between runners and substrate to achieve the required air seal. Stud splicing is not acceptable. Corners shall be constructed with a minimum of three studs. Stud framing system shall be braced and made rigid.

3.4.2 Adjoining Walls and Columns

Studs which adjoin walls or columns shall be secured near the top and bottom, and at least one intermediate point, but not more than 1.5 m on centers, with wire inserts, dovetail anchors, toggle bolts, or bolts set in expansion shields.

3.4.3 Wall Bracing

Partitions more than 3 m long or 2.7 m high shall be braced with 19 mm steel channel stiffeners concealed horizontally. Stiffeners shall be spaced vertically not more than 2 m and shall be secured to each stud. Unsupported partitions 6 m or more in height shall be braced with 38 mm channel type horizontal stiffeners.

3.4.4 Corners and Intersection

Corners and intersections of partitions shall be formed of three studs. Studs at internal corners shall be placed not more than 50 mm from partition intersection.

3.4.5 Wall Openings

One loadbearing metal stud shall be installed at each jamb of door openings continuous from floor to ceiling, and shall be welded to jamb anchors and runner tracks. Jack studs shall be attached to runner track on interior of head of frame, and to runner track or 19 mm channel at ceiling. A 19 mm channel reinforcement shall be placed inside the partition 150 to 200 mm above door openings continuously through two stud spaces on each side of jambs, and welded to the flange. Studs shall be doubled at wall openings, with not more than 50 mm each side of openings. Stud placement shall be coordinated with supports and attachments. Intermediate studs above and below openings shall be secured at same spacing as wall studs. Stud framing shall extend to ceiling or through ceiling as indicated on drawings. Clearance shall be maintained between partition and structure to avoid deflection transfer to studs of partitions which extend through ceiling to structure. Placement of insulation in stud spaces shall be made inaccessible after studs are installed.

3.4.6 Bucks, Anchors and Blocking

Installation of bucks, anchors, and blocking shall be coordinated with electrical and mechanical work to be placed in or behind stud framing, and shall be coordinated with blocking requirements for support of plumbing fixtures, toilet partitions, wall cabinets, toilet accessories, hardware and similar items scheduled for installation.

3.5 WALL FURRING INSTALLATION

Metal furring shall be installed in accordance with ASTM C 754 and ASTM C 841.

3.6 SINGLE/DOUBLE CHANNEL, PARTITION INSTALLATION

Channel studs for single channel and double channel stud partitions shall be spaced 400 mm on centers and shall be secured to ceiling runners and to floor runners or base clips with wire ties or sheet-metal screws. Studs on each side of door openings shall be doubled and stiffened with a 6 x 25 mm flat steel strut, shop-coated with rust-inhibiting paint. Ends of struts shall be bent and punched for bolting to floor and ceiling construction. Where rib metal lath is the plaster base in continuous lengths from ceiling runners to floor runners for partitions less than 3 m in height, steel channel studs may be excluded from the partition except at locations previously specified for door openings. Rib lath shall be firmly attached to ceiling runner tracks or cornerite and to floor runner track or base by wire ties located not more than 200 mm on centers. Studless rib lath partitions shall be limited to not less than 50 mm thick. Partitions shall be as shown.

3.7 LATHING INSTALLATION

3.7.1 Metal Lath on Vertical Surfaces

Metal lath shall be applied with the long dimension across the supports, with true even surfaces, and without sags or buckles in accordance with ASTM C 841. Metal lath on vertical surfaces shall be oriented to provide maximum mechanical bond with plaster and the upper sheet shall be attached to overlap the lower sheet. When paper-backed lath is used, the upper sheet shall be attached to overlap the lower sheet. The lath shall be secured to supports at intervals not exceeding 150 mm. Nails or staples shall be used for securing lath to wood supports. Tie wires, rings, clips, or other approved fasteners having equivalent holding power of the tie wires shall be used for securing the plaster base to metal supports and to concrete or masonry. Side-laps or junction of sides of plaster base shall be tied or otherwise secured at intervals not exceeding 225 mm between supports, in addition to being secured to supports.

3.7.2 Metal Lath on Ceilings

Metal lath on ceilings shall be in accordance with ASTM C 841. Lath on unrestrained ceilings shall not be turned down at junction with wall or tied to wall lath or furring. Lath on restrained ceilings shall be turned down at junction with wall, or shall be applied to cornerite or corner bead.

3.7.3 Side and End Laps

Side and end laps of metal plaster bases shall be performed in accordance with ASTM C 841 for flat lath and ribbed lath.

3.7.4 Chases and Recesses

Chases and recesses shall be lathed for plastering. Openings over 300 mm wide shall be bridged with furring channels spaced 300 mm on centers. Openings 300 mm wide and less do not need to be bridged. Lath shall extend 75 mm beyond the edges of opening. Lath shall be securely fastened by

nailing or tying. Lath shall be securely fastened with nails, screws or wire ties.

3.8 OPENINGS

Reinforcement shall be provided at corners of openings in plastered areas extending 300 mm or more in any dimension by securing striplath diagonally at corners. Striplath shall be at least 150 mm wide by 400 mm long. Shorter lengths shall be used to preclude lapping striplath. Striplath shall be secured to lathing without extending fastenings into or around supporting members. Where plaster is applied directly to concrete or masonry surfaces, striplath shall be secured to the concrete or masonry.

3.8.1 Steel Frames

Steel frames shall be securely attached through built-in anchors to the nearest stud on each side of opening with tie wire, bolts, screws, or welding or bracing where bracing is specified. Steel frames shall be grouted solid with plaster grout and a groove shall be formed within the frame returns to receive lath and plaster.

3.8.2 Ceiling Openings

Framing shall be provided for ceiling openings and supplemental supporting members for items mounted in ceiling or attached to ceiling suspension system. Frames for openings shall be secured to lath support members. Frames provided with expanded metal flanges shall be secured to lath. Intermediate structural members shall be provided for attachment or suspension of support members.

3.8.3 Openings in Hollow Partitions

Hollow partition door openings shall be additionally braced by tying together each set of double-jamb studs with not less than four solid metal column clips evenly spaced along each jamb.

3.8.4 Openings in Partitions Not To Structure

Partitions not extending to the structural ceiling or structural supports or frame shall be strengthened at openings with angle bracing from each jamb location anchored to the structural ceiling or supports.

3.8.5 Cross Bracing

Cross bracing between partitions or similar bracing may be substituted for angle bracing as approved. Minor frames such as those required for access panels may be provided with expanded metal flanges which shall be attached to lath.

3.9 INSTALLATION OF TRIM, MOLDINGS, AND ACCESSORIES

Trim, moldings, and accessories shall be installed in standard lengths level and plumb to straight lines and as indicated on drawings. Fastenings shall be spaced not over 300 mm on centers for single-flanged accessories and not over 600 mm on centers on each flange of double-flanged accessories. Items shall be mitered or coped at corners, or prefabricated corners shall be used. Joints in straight runs shall be formed with splice or tie plates.

3.9.1 Base Screeds

Base screeds shall be installed approximately 75 mm above finished floor elevation unless indicated otherwise.

3.9.2 Corner Beads

Corner beads shall be installed in standard lengths at external plastered corners, and shall be secured to furring members or supports.

3.9.3 Cornerites

Cornerites shall be installed at internal angles formed by abutting surfaces of gypsum lath or metal lath not turned down at horizontal corners or returned around vertical corners. Cornerites shall be secured to lathed surfaces. Cornerites shall be secured to concrete or masonry where plaster is applied directly to concrete or masonry surfaces. Cornerites shall not be installed at unrestrained ceilings.

3.9.4 Casing Beads

Casing beads shall be installed at the joints of dissimilar base materials in the same plane and at exposed edges of plaster including junctions of walls and ceilings except that beads shall not be installed at restrained ceilings abutting plastered surfaces. At the perimeter of unrestrained suspended ceilings, the casing bead shall be secured to the ceiling to provide a 10 mm opening between the abutting surfaces. The opening shall be sealed prior to plastering with sealant as specified in Section 07 92 00 JOINT SEALANTS.

3.9.5 Expansion and Control Joint Beads

Expansion joint beads shall be installed as control joints in plasterwork at the locations indicated. Plaster base shall not be run continuous through control joints. Additional supports shall be installed as required to support the beads.

3.9.6 Trim

Trim shall be installed where indicated and as required to complete the plaster work.

3.10 PLASTER THICKNESS AND SURFACE EVENNESS

Plaster thickness and surface evenness shall be controlled by grounds or screeds of metal, wood, or plaster. Wood grounds are specified under Section 06 10 00 ROUGH CARPENTRY. Plaster thickness shall be as shown.

3.10.1 Grounds and Screeds

Grounds shall be used for securing trim items, and for finished corners and terminations. Screeds shall be installed for base screeds when wood or metal grounds are not required. Temporary screeds shall be installed when permanent screeds or grounds cannot be used. On completion of approved base coats, temporary screeds shall be removed and voids immediately filled with plaster.

3.10.2 Plaster Screeds

Plaster screeds shall be used within the plastered areas to supplement wood and metal grounds and screeds.

3.11 PLASTER GROUT

Plaster grout shall be scratch-coat material mixed to a non-fluid consistency. Plaster grout shall be used to fill steel door frames and partition bases. Heads and jambs of frames shall be filled solid with grout, and 13 mm deep grooves shall be formed in the grout, while plastic, to receive gypsum lath.

3.12 PROPORTIONS AND MIXING

3.12.1 Portland Cement Plaster Base Coat

Base coat shall be proportioned and mixed in accordance with ASTM C 926.

3.12.2 Portland Cement-Plaster Finish

The finish coat shall be proportioned and mixed in accordance with ASTM C 926.

3.13 MACHINE APPLICATION

A plastering machine may be used for the application of scratch and brown coats. Plaster for machine application shall be a special plaster compounded and packaged by the manufacturer for this purpose. Slump cone equipment shall be present on the jobsite when base-coat plastering begins, and until completion. Testing of the mix shall be the responsibility of the Contractor, but equipment shall be available for use by the Government. Additional water shall not be added to the mix to allow pumping through extended hose lines to the plastering nozzle. The amount of water added to each batch of plaster shall be that quantity which results in a plaster slump of not more than 75 mm for gypsum and 65 mm for portland cement using a standard plaster slump cone or 150 mm for gypsum and 125 mm for portland cement using a concrete slump cone. Application of plaster shall conform to the provisions of ASTM C 842.

3.14 QUALITY CONTROL

Fluidity or stiffness of plaster shall be tested with a standard 50 x 100 x 150 mm plaster slump testing cone or by a 100 x 200 x 300 mm concrete slump testing cone. Method of making slump test shall be as follows:

a. Place cone on center of dry base plate located on a level, firm surface. Hold cone tightly against plate.

b. Fill the cone with plaster obtained from the hose or nozzle, without air on the nozzle, puddling with tamping rod during the operation to eliminate air bubbles or voids.

c. Screed plaster level with top of cone.

d. Lift cone straight up from base plate in a slow and uniform motion, and place it on the base plate next to plaster sample.

e. Lay a straightedge across top of cone, being careful not to

disturb or jostle the plate, and measure the slump in mm from the bottom of the straightedge to the top of the plaster sample.

3.15 APPLICATION OF FINISHES

The finish coat may be omitted back of projecting bases, wainscots, structural-glass wall finish, cabinets, chalkboards, tackboards, bulletin boards, acoustic treatments, fixed equipment, and other locations where indicated. Finish coats shall not be applied above wainscots until wainscots have been installed. Plaster shall have a smooth-trowelfinish.

3.15.1 Portland Cement-Based Plaster

Two-coat portland cement-based plaster shall be applied in accordance with ASTM C 926. The final coat shall be finished to a true and even surface free from rough areas, checks, or blemishes. Nominal plaster finish thickness shall be as shown.

3.16 PATCHING

Plaster showing oversanding, cracks, blisters, pits, checks, discoloration or other defects is not acceptable. Defective plaster work shall be removed and replaced with new plaster at the expense of Contractor. Patching of defective work will be permitted only when approved by the Contracting Officer. Patching shall match existing work in texture and color.

3.17 SAMPLES OF COMPLETED WORK

Samples of completed work may be taken by the Contracting Officer at any time for laboratory inspection and tests to determine conformance.

-- End of Section --

SECTION 09 24 23

STUCCO
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 185/A 185M	(2007) Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete
ASTM C 150	(2007) Standard Specification for Portland Cement
ASTM C 206	(2003) Standard Specification for Finishing Hydrated Lime
ASTM C 897	(2000) Aggregate for Job-Mixed Portland Cement-Based Plasters
ASTM C 926	(2006) Application of Portland Cement-Based Plaster

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Lath

Drawings showing details of construction for reinforcement, furring, and grounds; including manufacturer's installation instructions for stucco materials, and locations where each mix and coating thickness will be used.

SD-03 Product Data

Materials

Detailed description of the proposed bonding agent, acrylic polymer admixture and job-mix proportions for base and finish coats; including identification of thickness of coats.

SD-04 Samples

Colored Stucco Finish Coat

Samples including both a fabricated portion of unit of work and color samples.

Sample Panel

Sample panel, as specified.

1.3 DELIVERY AND STORAGE

Packaged materials shall be delivered to the site in the original packages and containers with labels intact and seals unbroken. Cementitious materials shall be kept dry and stored off the ground under cover away from damp surfaces until ready to be used. Aggregate shall be covered to prevent the absorption or loss of moisture.

1.4 ENVIRONMENTAL CONDITIONS

Stucco shall not be applied when the ambient temperature is 4 degrees C or lower, or when a drop in temperature below 4 degrees C is expected within 48 hours after application.

1.5 SAMPLE PANEL

The Contractor shall submit: One 300 mm square stucco panel showing finish texture and color and a 300 mm length of each accessory proposed, prior to proceeding with stucco work.

PART 2 PRODUCTS

2.1 PORTLAND CEMENT

Portland cement shall conform to ASTM C 150, White portland cement, Type I.

2.2 COLORED STUCCO FINISH COAT

Colored stucco finish coat shall be a mill mixed product using white portland cement and requiring only the addition of and mixing with water for application. Color shall be selected by the Contracting Officer from the color board provided by the contractor.

2.3 LIME

Lime shall conform to ASTM C 206, Type S.

2.4 SAND

Sand aggregate for job-mixed base coat and job-mixed finish coat stucco shall conform to ASTM C 897.

2.5 TRIM ACCESSORIES

Casing bead, control joint, welded wire corner reinforcements, etc. shall be zinc coated, galvanized 1.4 mm steel conforming to ASTM A 185/A 185M.

2.6 WATER

Water shall be clean, fresh, potable, and free from amounts of oils, acids,

alkalis and organic matter that would be injurious to the stucco.

2.7 BONDING AGENT

EUCO WELD (The Euclid Chemical Co., 19218 Redwood Road, Cleveland, OH 44110, (216) 531-9222, (800) 321-7828, Fax (216) 531-9596, www.euclidchemical.com) or equal.

2.8 ADDITIVE

Acrylic polymers admixture shall be a 100% acrylic polymer modifier that shall enhance performance properties of stucco, help retain water, promote cement hydration, and improve compression (crushing) strength without wet curing.

PART 3 EXECUTION

3.1 CONTROL JOINTS

Control joints shall be located as indicated on the drawings. Prefabricated control joint members shall be installed prior to the application of the stucco. Control joints shall be cleared of all stucco within the control area after stucco application and prior to final stucco set.

3.2 PREPARATION OF SURFACES

Preparation of surfaces for application of stucco to solid bases such as masonry or concrete shall conform to the applicable requirements of ASTM C 926.

3.3 PROPORTIONS AND MIXING

Proportions and mixing for job-mixed base coat and finish coat shall conform to the applicable requirements of ASTM C 926 and manufacturer's recommendations. Mixing of mill-mixed finish coat shall be in accordance with the manufacturer's directions.

3.4 STUCCO APPLICATION

Stucco shall be applied in two coats to a thickness of not less than 20 mm as measured to the finished stucco surface, including moderate texture variations. Stucco application shall conform to the applicable requirements of ASTM C 926 and the following:

3.4.1 Workmanship

Items or features of the work in connection with or adjoining the stucco shall be in place, plumb, straight, and true prior to beginning the stucco work. Masonry surfaces to receive stucco shall be evenly dampened immediately prior to application of stucco. Each stucco coat shall be applied continuously in one general direction, without allowing mortar to dry at edges. Where it is impossible to work the full dimension of a wall surface in a continuous operation, jointing shall be made at a break, opening, or other natural division of the surface. Edges to be joined shall be dampened slightly to produce a smooth confluence. Exterior corners of stucco shall be slightly rounded. Stucco on soffit surfaces shall be pitched forward to form a drip.

Stucco showing over sanding, cracks, blisters, pits, checks, discoloration or other defects is not acceptable. Defective plaster work shall be removed and replaced with new plaster at the expense of the Contractor. Patching of defective work will be permitted only when approved by the Contracting Officer. Patching shall match existing work in teture and color. All exterior color finish shall be intergral with the stucco finish.

3.4.2 Wetting/Bonding Agent

Wet/mix and apply bonding agent to masonry or concrete substrates as per manufacturer's instructions.

3.4.3 Scratch Coat

At the specified time, scratch coat shall be applied 10 mm thick under sufficient pressure to form good bond to masonry/concrete substrate. Before the scratch coat has set, it shall be lightly scratched in one direction and vertical surfaces shall be scratched in the horizontal direction only. The scratch coat shall be fog cured for a minimum of 7 days.

3.4.4 Finish Coat

Surfaces of the brown coat shall be dampened not more than 1 hour before the finish coat is to be applied to a uniform wetness with no free-standing water on the surface. The finish coat shall have a trowel-textured finish and shall conform to the approved sample. The finish coat shall be fog cured for a minimum of 48 hours. Care shall be taken to prevent staining.

3.4.5 Surface Tolerance

When a 3 m straightedge is placed at any location on the finished surface of the stucco, excluding rough-textured finish, the surface shall not vary more than 3 mm from the straightedge.

3.5 CURING AND PROTECTION

When directed, fog curing shall be accomplished by applying a very fine mist of water to the stucco. Care shall be exercised during fog curing to avoid entirely any erosion damage to the stucco surfaces. A solid stream of water shall not be used. Frequency of fogging shall be not less than three times daily. When directed the Contractor shall protect the stucco from the direct rays of the sun during severe drying conditions using canvas, cloth or other approved sheet material.

3.6 PATCHING AND POINTING

Loose, cracked, damaged or defective work shall be replaced or patched as directed. Patching shall match existing work in texture and color and shall be finished flush.

-- End of Section --

SECTION 09 30 00

CERAMIC TILE
01/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A108.1	(2005) Installation of Ceramic Tile
ANSI A137.1	(1988) Ceramic Tile

ASTM INTERNATIONAL (ASTM)

ASTM A 185/A 185M	(2007) Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete
ASTM C 1026	(2002) Standard Test Method for Measuring the Resistance of Ceramic Tile to Freeze-Thaw Cycling
ASTM C 1027	(1999; R 2004) Standard Test Method for Determining Visible Abrasion Resistance of Glazed Ceramic Tile
ASTM C 1028	(2007) Standard Test Method for Determining the Static Coefficient of Friction of Ceramic Tile and Other Like Surfaces by the Horizontal Dynamometer Pull-Meter Method
ASTM C 144	(2004) Standard Specification for Aggregate for Masonry Mortar
ASTM C 150	(2007) Standard Specification for Portland Cement
ASTM C 206	(2003) Standard Specification for Finishing Hydrated Lime
ASTM C 207	(2006) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C 241	(1990; R 2005) Standard Specification for Abrasion Resistance of Stone Subjected to Foot Traffic
ASTM C 33	(2003) Standard Specification for Concrete Aggregates

ASTM C 373	(1988; R 2006) Water Absorption, Bulk Density, Apparent Porosity, and Apparent Specific Gravity of Fired Whiteware Products
ASTM C 648	(2004) Breaking Strength of Ceramic Tile
ASTM C 847	(2009) Standard Specification for Metal Lath
ASTM D 226	(2006) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 4068	(2001) Chlorinated Polyethylene Sheeting for Concealed Water-Containment Membrane

MARBLE INSTITUTE OF AMERICA (MIA)

MIA Design Manual	(2003) Dimension Stone Design Manual

TILE COUNCIL OF AMERICA (TCA)

TCA Hdbk	(2007) Handbook for Ceramic Tile Installation

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings

Drawings showing ceramic tile pattern elevations, floor plans.

SD-03 Product Data

Tile
Setting-Bed
Mortar, Grout, and Adhesive

Manufacturer's catalog data and preprinted installation and cleaning instructions.

SD-04 Samples

Tile
Accessories
Marble Thresholds
Grout

Samples of sufficient size to show color range, pattern, type and joints.

SD-07 Certificates

Tile
Mortar, Grout, and Adhesive

Certificates indicating conformance with specified requirements. Furnish a master grade certificate for tile.

1.3 DELIVERY AND STORAGE

Deliver materials to the project site in manufacturer's original unopened containers with seals unbroken and labels and hallmarks intact. Protect materials from weather, and stored under cover in accordance with manufacturer's printed instructions.

1.4 ENVIRONMENTAL REQUIREMENTS

Close space in which tile is being set to traffic and other work. Keep closed until tile is firmly set. Do not walk or work on newly tiled floors without using kneeling boards or equivalent protection of the tiled surface. Keep traffic off horizontal portland cement mortar installations for at least 72 hours. Keep all traffic off epoxy installed floors for at least 40 hours after grouting, and heavy traffic off for at least 7 days, unless otherwise specifically authorized by manufacturer.

Do not perform ceramic tile work unless the substrate and ambient temperature is at least 10 degrees C and rising. Maintain temperature above 10 degrees C while the work is being performed and for at least 7 days after completion of the work. When temporary heaters are used, ventilate the area to the outside to avoid carbon dioxide damage to new tilework.

1.5 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a 1-year period.

1.6 EXTRA STOCK

Supply an extra two percent of each type tile used in clean and marked cartons.

1.7 DETAIL DRAWINGS

Dimension and draw detail drawings at a minimum scale of 6 mm = 300 mm. Include drawings of pattern at inside corners, outside corners, termination points and location of all equipment items such as thermostats, switch plates, mirrors and toilet accessories mounted on surface.

PART 2 PRODUCTS

2.1 TILE

Conform to ANSI A137.1 for standard grade tile. Provide grade sealed containers. Mark seals with the marks on the signed master grade certificate. Provide an impact resistant tile with a minimum floor breaking strength for wall tile of 41 kg and for floor tile of 113 kg in accordance with ASTM C 648. The manufacturer will provide a frost

resistant rating for tile used in cold climate projects as determined by ASTM C 1026. Provide a 0.50 maximum percent water absorption in accordance with ASTM C 373. Provide a minimum coefficient of friction of 0.60 wet and dry in accordance with ASTM C 1028. Identify floor tile as Class IV Plus-Extra Heavy Traffic, durability classification as rated by the manufacturer when tested in accordance with ASTM C 1027 for abrasion resistance as related to foot traffic.

2.1.1 Mosaic Tile

Provide ceramic mosaic tile and trim shall be unglazed natural clay with cushion edges porcelain unpolished with sharply formed face. Provide tile size 25 by 25 mm (1 by 2 inch) or a mixture of standard sizes in a stock pattern. Color to be selected by the Contract Officer from the manufacturers' standard list submitted by the contractor.

2.1.2 Glazed Wall Tile

Provide glazed wall tile with cushioned edges and trim edged with lead-free matte finish. Provide tile 150 by 150 mm. Color shall be as selected by Contracting Officer from manufacturers standard listing as submitted by the contractor.

2.2 SETTING-BED

Compose the setting-bed of the following materials:

2.2.1 Aggregate for Concrete Fill

Conform to ASTM C 33 for aggregate fill. Do not exceed one-half the thickness of concrete fill for maximum size of coarse aggregate.

2.2.2 Portland Cement

Conform to ASTM C 150 for cement, Type I, white for wall mortar and gray for other uses.

2.2.3 Sand

Conform to ASTM C 144 for sand.

2.2.4 Hydrated Lime

Conform to ASTM C 206 for hydrated lime, Type S or ASTM C 207, Type S.

2.2.5 Metal Lath

Conform to ASTM C 847 for flat expanded type metal lath, and weighing a minimum 1.4 kg/square meter.

2.2.6 Reinforcing Wire Fabric

Conform to ASTM A 185/A 185M for wire fabric. Provide 50 by 50 mm mesh, or 38 by 50 mm mesh, 16/13 wire.

2.3 WATER

Provide potable water.

2.4 MORTAR, GROUT, AND ADHESIVE

Conform to the following for mortar, grout, adhesive, and sealant:

2.4.1 Dry-Set Portland Cement Mortar

ANSI A108.1.

2.4.2 Latex-Portland Cement Mortar

ANSI A108.1.

2.4.3 Ceramic Tile Grout

ANSI A108.1; petroleum-free and plastic-free commercial portland cement grout.

2.4.4 Sealants

Comply with applicable regulations regarding toxic and hazardous materials and as specified.

2.4.5 Cementitious Backer Board

Provide cementitious backer units, for use as tile substrate over wood sub-floors, in accordance with ANSI A108.1. Furnish 6.35 mm thick cementitious backer units.

2.5 MARBLE THRESHOLDS

Provide marble thresholds of size required by drawings or conditions. Categorize marble Group A as classified by MIA Design Manual. Provide a fine sand-rubbed finish marble with white, pink or gray in color as approved by the Contracting Officer. Provide minimum 12.0 marble abrasion when tested in accordance with ASTM C 241.

2.6 MEMBRANE MATERIALS

Conform to ASTM D 226, Type 1 for 33 kg waterproofing membrane, asphalt-saturated building felt. Conform to ASTM D 4068 0.0102 for polyethylene film.

PART 3 EXECUTION

3.1 PREPARATORY WORK AND WORKMANSHIP

Inspect surface to receive tile in conformance to the requirements of ANSI A108.1 for surface conditions for the type setting bed specified and for workmanship. Provide variations of tiled surfaces that fall within maximum values shown below:

TYPE	WALLS	FLOORS
Dry-Set Mortar	3 mm in 2.4 meter	3.0 mm in 3 meter
Organic Adhesives	3 mm in 2.4 meter	1.5 mm in 1 meter
Latex Portland Cement Mortar	3 mm in 2.4 meter	3.0 mm in 3 meter

3.2 GENERAL INSTALLATION REQUIREMENTS

Do not start tile work until roughing in for mechanical and electrical work has been completed and tested, and built-in items requiring membrane waterproofing have been installed and tested. Do not start floor tile installation in spaces requiring wall tile until after wall tile has been installed. Apply tile in colors and patterns indicated in the area shown on the drawings. Install tile with the respective surfaces in true even planes to the elevations and grades shown. Provide special shapes as required for sills, jambs, recesses, offsets, external corners, and other conditions to provide a complete and neatly finished installation. Solidly back tile bases and coves with mortar.

3.3 INSTALLATION OF WALL TILE

Install wall tile in accordance with the TCA Hdbk.

3.3.1 Workable or Cured Mortar Bed

Install tile over workable mortar bed or a cured mortar bed at the option of the Contractor. Install a 0.102 mm polyethylene membrane, metal lath, and scratch coat. Conform to ANSI A108.1 for workable mortar bed, materials, and installation of tile. Conform to ANSI A108.1 for cured mortar bed and materials.

3.3.2 Dry-Set Mortar and Latex-Portland Cement Mortar

Use Dry-set or Latex-Portland Cement to install tile in accordance with ANSI A108.1. Use Latex Portland Cement when installing porcelain ceramic tile.

3.4 INSTALLATION OF FLOOR TILE

Install floor tile in accordance with TCA Hdbk method F121. Install shower receptors in accordance with TCA Hdbk method B414.

3.4.1 Workable or Cured Mortar Bed

Install floor tile over a workable mortar bed or a cured mortar bed at the option of the Contractor. Conform to ANSI A108.1 for workable mortar bed materials and installation. Conform to ANSI A108.1 for cured mortar bed materials and installation. Provide minimum 6.35 mm to maximum 9.53 mm.

3.4.2 Dry-Set and Latex-Portland Cement

Use dry-set or Latex-Portland cement mortar to install tile directly over properly cured, plane, clean concrete slabs in accordance with ANSI A108.1. Use Latex Portland cement when installing porcelain ceramic tile.

3.4.3 Ceramic Tile Grout

Prepare and install ceramic tile grout in accordance with ANSI A108.1.

3.4.4 Waterproofing

Install as shown and as specified in this Section, Section 22 00 00 PLUMBING, GENERAL PURPOSE and Section 07 13 53 ELASTOMETRIC SHEET WATERPROOFING.

3.4.5 Concrete Fill

Provide a 24.1 MPa concrete fill mix to dry as consistency as practicable. Compose concrete fill by volume of 1 part Portland cement to 3 parts fine aggregate to 4 parts coarse aggregate, and mix with water to as dry a consistency as practicable. Spread, tamp, and screed concrete fill to a true plane, and pitch to drains or levels as shown. Thoroughly damp concrete fill before applying setting-bed material. Reinforce concrete fill with one layer of reinforcement, with the uncut edges lapped the width of one mesh and the cut ends and edges lapped a minimum 50 mm. Tie laps together with 1.3 mm wire every 250 mm along the finished edges and every 150 mm along the cut ends and edges. Provide reinforcement with support and secure in the centers of concrete fills. Provide a continuous mesh; except where expansion joints occur, cut mesh and discontinue across such joints. Provide reinforced concrete fill under the setting-bed where the distance between the under-floor surface and the finished tiles floor surface is a minimum 50 mm, and of the same thickness that the mortar setting-bed over the concrete fill with the thickness required in the specified TCA Hdbk method.

3.5 INSTALLATION OF MARBLE THRESHOLDS

Install thresholds for interior doors, in a manner similar to that of the ceramic tile floor. Provide thresholds full width of the opening. Install head joints at ends not exceeding 6 mm in width and grouted full.

3.6 EXPANSION JOINTS

Form and seal joints as specified in Section 07 92 00 JOINT SEALANTS.

3.6.1 Walls

Provide expansion joints at control joints in backing material. Wherever backing material changes, install an expansion joint to separate the different materials.

3.6.2 Floors

Provide expansion joints over construction joints, control joints, and expansion joints in concrete slabs. Provide expansion joints where tile abuts restraining surfaces such as perimeter walls, curbs and columns and at intervals of 7.2 to 10.8 m each way in large interior floor areas and 3.6 to 4.8 m each way in large exterior areas or areas exposed to direct sunlight or moisture. Extend expansion joints through setting-beds and fill.

3.7 CLEANING AND PROTECTING

Upon completion, thoroughly clean tile surfaces in accordance with manufacturer's approved cleaning instructions. Do not use acid for cleaning glazed tile. Clean floor tile with resinous grout or with factory mixed grout in accordance with printed instructions of the grout manufacturer. After the grout has set, provide a protective coat of a noncorrosive soap or other approved method of protection for tile wall surfaces. Cover tiled floor areas with building paper before foot traffic is permitted over the finished tile floors. Provide board walkways on tiled floors that are to be continuously used as passageways by workmen. Replace damaged or defective tiles.

-- End of Section --

SECTION 09 66 16

TERRAZZO TILE
05/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 1028	(2007) Standard Test Method for Determining the Static Coefficient of Friction of Ceramic Tile and Other Like Surfaces by the Horizontal Dynamometer Pull-Meter Method
ASTM C 140	(2009) Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units
ASTM C 293	(2008) Standard Test Method for Flexural Strength of Concrete
ASTM C 501	(1984; R 2002) Relative Resistance to Wear of Unglazed Ceramic Tile by the Taber Abraser
ASTM E 648	(2009a) Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Terrazzo Tile; G

Drawings indicating pattern, size, style, and color of tiles.

SD-03 Product Data

Installation

The manufacturer's printed installation instructions for the conditions indicated.

SD-04 Samples

Terrazzo Tile

Two 150 by 150 mm minimum samples of each color and pattern of terrazzo tile to be used.

SD-07 Certificates

Terrazzo Tile
Adhesive

Certificates indicating that the materials conform to the specified requirements and flooring manufacturer's approval of adhesive, grout and cleaners.

SD-10 Operation and Maintenance Data

Manufacturer's Maintenance Instructions

Six copies of the manufacturer's maintenance literature.

1.3 QUALITY ASSURANCE

Installer shall possess, to the satisfaction of the Contracting Officer, the technical qualifications, experience, trained personnel, and facilities to properly install the specified items.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the jobsite in the manufacturer's original unopened containers marked with the manufacturer's brand name, color, and pattern. Store materials delivered and placed in indoor storage protected from damage, weather, humidity and temperature variation, dirt and dust, or other contaminants. Temperature of storage area shall not be lower than 10 degrees C or higher than 32 degrees C.

1.5 SITE CONDITIONS

Do not install tiles until other work that could cause damage to the finished work has been completed. A temperature of not less than 21 degrees C shall be maintained in areas where tile is to be installed for a period of not less than 48 hours before, during and after laying of tiles. Tiles shall be brought into installation areas and allowed to condition at not less than 21 degrees C for a period of 48 hours prior to installation. After installation of tiles, a minimum temperature of 13 degrees C shall be maintained.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide materials which are the standard products of a manufacturer regularly engaged in the manufacture of the material and that essentially duplicate products that have been in satisfactory use at least 2 years prior to bid opening.

2.2 TERRAZZO TILE

Terrazzo tile shall be of the indicated or as directed colors as per manufacturer's or NTMA color plates and shall consist of marble or granite chips embedded in a portland cement matrix. Tiles shall be 50 mm thick and nominal 250 by 250 mm. Tiles shall have a polished finish with uniform color distribution of chips. Marble chips shall be graded to 6 mm maximum size. Granite chips shall be manufacturer's standard gradation. Tile shall have the following properties:

TERRAZZO TILE PROPERTIES

PROPERTY	TEST METHOD	VALUE
Compressive Strength	ASTM C 140	62 MPa minimum
Flexural Strength	ASTM C 293	6.5 MPa minimum
Water Absorption	ASTM C 140	4.5 percent maximum
Abrasive Wear	ASTM C 501	Index 28
Coefficient of Friction	ASTM C 1028	0.6 dry, 0.5 wet
Flame Spread	ASTM E 84	Class A
Critical Radiant Flux	ASTM E 648	Class I

Sizing Tolerances:
1. All units to conform to shop drawings with a 1/16" tolerance in dimension.

Precast Surfaces and Edges:
1. All exposed edges to be ground and polished with a minimum of 1/16" bevel.
2. All finished surfaces to be ground and polished, free of holes and to have overall uniformity in matrix and aggregate.
3. All precast terrazzo finished surfaces to be sealed with a sealer approved by manufacturer.

2.3 MATERIALS

2.3.1 Portland Cement

ASTM C-150, White.

2.3.2 Aggregates

ASTM C-33, ASTM C-131

2.3.3 Coloring

Pigments used shall be inorganic, resistant to alkalinity, and used per manufacturer's recommendations

2.3.4 Bond Coat Thinset Mortar

Exceed requirements of ANSI A118.4-2005 Latex-Portland Cement Mortar. Use Medium-Bed, Latex-Portland Cement Mortar for tiles larger than 12” x 12”.

2.3.5 Grouting Materials

1. Heat Resistant Grout type: Polymer Modified Sand-Portland Cement Grout - Comply with ANSI A118.7 Polymer Modified Cement Grouts

a. Liquid Latex Admixture: Liquid Latex added as a replacement for part or all of the mixing water in dry grout mix as specified or recommended by latex manufacturer

b. Factory prepared cementitious grout mixture including a redispersible, latex/polymer powder to which only water is added at the job site

2. Heat Resistant Grout type: Standard Sand-Portland Cement grout - Exceed ANSI A118.6-2005 Standard Cement Grouts

2.3.6 Reinforcement and Hardware

1. To conform with NTMA and Manufacturer's design.
2. Reinforce precast with deformed rods or wire mesh or both as recommended by precast terrazzo manufacturer.

2.3.7 Cleaner

Liquid neutral chemical cleaner, with pH factor between 7 and 8, of formulation recommended by manufacture for type of precast terrazzo used and complying with NTMA requirements.

2.3.8 Sealer

Colorless, slip and stain-resistant penetrating sealer with pH factor between 7 and 8, that does not affect color or physical properties of precast terrazzo surface. High flash point (ASTM D56): 100 degrees C, Minimum, flame spread: Class A over noncombustable surfaces.

2.4 MIXES

2.4.1 Aggregate

Natural, sound, crushed marble chips or granite chips without excessive flats or flakes, complying with NTMA requirements.

2.4.2 Matrix Pigments

Pure mineral or synthetic pigments, resistant to alkalis and non-fading.

2.4.3 Monolithic Wet Cast

Terrazzo tile shall have 70 percent coverage of the precast terrazzo face

with marble or granite aggregate.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with details of the work, verify (in the field), dimensions, defects in existing work and deviations beyond allowable tollerances for substrate and advise the Contracting Officer of any discrepancy before performing the work.

3.2 GENERAL

Except as required for installation of new tile, nothing shall be kept on new tile for at least 24 hours after installation.

3.3 SUBSTRATE PREPARATION

Fill holes and cracks with mortar. Substrate shall be plumb, level and true with square corners, free of curing compounds, grease, dirt, loose particles and other foreign matter that would prevent adhesion. Projecting irregularities shall be chipped or ground smooth. Depressions shall be filled and uneven surfaces leveled; maximum variation from plane shall be 3 mm in 3m. Base shall then be rinsed and allowed to dry prior to applying setting mortar.

3.4 INSTALLATION

3.4.1 Tile Laying

Install tile in accordance with TCA Handbook, ANSI A108.3 and the manufacturer's approved installation instructions, except as specified herein. Tile shall be layed as indicated or symmetrical about center lines of vertical surfaces. Joints shall be a minimum of 3 mm to 4.5 mm, and in alignment. Tile shall be cut to fit snugly at pipes and other vertical surfaces. Joints at pipes shall be sealed with adhesive. Entire surface of finished tile countertop and vertical surfaces shall be smooth, straight, and free from mortar, buckles, waves, or projecting tile edges upon completion. Mortar on finished tile is cause for rejection by the Contracting Officer. Damaged or rejected tiles shall be removed and replaced.

3.4.2 Precast Terrazzo Finishing Guidelines

Grouting: Comply with ANSI A108.10-2005 Installation of Grout in Tilework.

3.4.3 Finishing

Apply grout release prior to grouting with cementitious grout. After the grout has set, remove the grout release, clean the floor thoroughly with a neutral ph cleaner and apply the final seal with a product compatible with cement terrazzo and following the sealer manufacturer’s guidelines.

3.5 MOISTURE TEST

After concrete/CMU/firebrick surfaces have been cleaned, small patches of setting mortar to be used shall be spread in several locations on top of encasement and vertical surfaces to receive tile and allowed to dry overnight. If the setting mortar can be peeled easily from the surfaces,

the surface is not sufficiently dry. The steps shall be repeated until the setting mortar adheres properly. Tiles shall not be applied until setting mortar adheres tightly to the substrate.

3.6 CLEANING

Upon completion of the installation and after setting mortar has cured, tile surface shall be thoroughly cleaned in accordance with the manufacturer's recommendations.

3.7 PROTECTION

The terrazzo tile work shall be covered and protected from damage until completion of the work of all other trades. Defects which develop, such as loose, broken, or curled tiles, shall be removed and replaced. Submit Manufacturer's Maintenance Instructions.

-- End of Section --

SECTION 09 90 00

PAINTS AND COATINGS
10/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100Doc	(2005) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM D 2092	(2001e1) Standard Guide for Preparation of Zinc-Coated (Galvanized) Steel Surfaces for Painting
ASTM D 235	(2002) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)
ASTM D 4214	(1998) Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D 4263	(1983; R 2005) Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D 4444	(1992; R 2003) Use and Calibration of Hand-Held Moisture Meters
ASTM D 523	(1989; R 1999) Standard Test Method for Specular Gloss
ASTM F 1869	(2004) Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride

MASTER PAINTERS INSTITUTE (MPI)

MPI 1	(2004) Aluminum Paint
MPI 107	(2004) Rust Inhibitive Primer (Water-Based)
MPI 11	(2004) Exterior Latex, Semi-Gloss, MPI Gloss Level 5
MPI 139	(2004) Interior High Performance Latex, MPI Gloss Level 3
MPI 141	(2004) Interior High Performance Latex MPI Gloss Level 5

MPI 147	(2004) Institutional Low Odor / VOC Interior Latex, Semi-Gloss, MPI Gloss Level 5
MPI 153	(2006) Interior W.B. Light Industrial Coating, Semi-Gloss, MPI Gloss Level 5
MPI 163	(2006) Exterior W.B. Light Industrial Coating, Semi-Gloss, MPI Gloss Level 5
MPI 19	(2004) Inorganic Zinc Rich Primer
MPI 21	(2004) Heat Resistant Enamel, Gloss (up to 205 degrees C and 400 degrees F), MPI Gloss Level 6
MPI 22	(2004) Aluminum Paint, High Heat (up to 590 degrees C and 1100 degrees F.
MPI 23	(2004) Surface Tolerant Metal Primer
MPI 39	(2004) Interior Latex-Based Wood Primer
MPI 4	(2004) Interior/Exterior Latex Block Filler
MPI 47	(2004) Interior Alkyd, Semi-Gloss, MPI Gloss Level 5
MPI 50	(2004) Interior Latex Primer Sealer
MPI 77	(2004) Epoxy Gloss
MPI 79	(Oct 2009) Alkyd Anti-Corrosive Metal Primer
MPI 94	(2004) Exterior Alkyd, Semi-Gloss, MPI Gloss Level 5
MPI 95	(2004) Quick Drying Primer for Aluminum

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS SP-01	(2000) Environmentally Preferable Product Specification for Architectural and Anti-Corrosive Paints

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1	(2000; E 2004) Shop, Field, and Maintenance Painting
SSPC PA Guide 3	(1982; E 1995) A Guide to Safety in Paint Application
SSPC SP 1	(1982; E 2004) Solvent Cleaning
SSPC SP 10	(2000; E 2004) Near-White Blast Cleaning

SSPC SP 12	(2002) Surface Preparation and Cleaning of Metals by Waterjetting Prior to Recoating
SSPC SP 2	(1982; E 2004) Hand Tool Cleaning
SSPC SP 3	(2004; E 2004) Power Tool Cleaning
SSPC SP 6	(2007) Commercial Blast Cleaning
SSPC SP 7	(2007) Brush-Off Blast Cleaning
SSPC VIS 1	(2002) Guide and Reference Photographs for Steel Surfaces Prepared by Dry Abrasive Blast Cleaning
SSPC VIS 3	(2004) Visual Standard for Power-and Hand-Tool Cleaned Steel
SSPC VIS 4	(1998; E 2000) Guide and Reference Photographs for Steel Surfaces Prepared by Waterjetting

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008) Safety and Health Requirements Manual

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-101	(Rev B) Color Code for Pipelines & for Compressed Gas Cylinders

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA Method 24	(2000) Determination of Volatile Matter Content, Water Content, Density, Volume Solids, and Weight Solids of Surface Coatings

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-313	(Rev D; Am 1) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The current MPI, "Approved Product List" which lists paint by brand, label,

product name and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. All coats on a particular substrate must be from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

Samples of specified materials may be taken and tested for compliance with specification requirements.

In keeping with the intent of Executive Order 13101, "Greening the Government through Waste Prevention, Recycling, and Federal Acquisition", products certified by SCS as meeting SCS SP-01 shall be given preferential consideration over registered products. Products that are registered shall be given preferential consideration over products not carrying any EPP designation.

SD-02 Shop Drawings

Piping identification

Submit color stencil codes

SD-03 Product Data

Coating

Manufacturer's Technical Data Sheets

Indicate VOC content.

Sealant

SD-04 Samples

Color

Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated.

SD-07 Certificates

Applicator's qualifications

Qualification Testing laboratory for coatings

SD-08 Manufacturer's Instructions

Application instructions

Mixing

Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times between coats.

Manufacturer's Material Safety Data Sheets

Submit manufacturer's Material Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

SD-10 Operation and Maintenance Data

Coatings:

Preprinted cleaning and maintenance instructions for all coating systems shall be provided.

SD-11 Closeout Submittals

1.3 APPLICATOR'S QUALIFICATIONS

1.3.1 Contractor Qualification

Submit the name, address, telephone number, FAX number, and e-mail address of the contractor that will be performing all surface preparation and coating application. Submit evidence that key personnel have successfully performed surface preparation and application of coatings on a minimum of three similar projects within the past three years. List information by individual and include the following:

a. Name of individual and proposed position for this work.

b. Information about each previous assignment including:

Position or responsibility

Employer (if other than the Contractor)

Name of facility owner

Mailing address, telephone number, and telex number (if non-US) of facility owner

Name of individual in facility owner's organization who can be contacted as a reference

Location, size and description of structure

Dates work was carried out

Description of work carried out on structure

1.4 QUALITY ASSURANCE

1.4.1 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph "Sampling Procedures." Test each chosen product as specified in the paragraph "Testing Procedure." Products which do not conform, shall be removed from the job site and replaced with new products that confrom to the referenced specification. Testing of replacement products that failed initial testing shall be at no cost to the Government.

1.4.1.1 Sampling Procedure

The Contracting Officer will select paint at random from the products that have been delivered to the job site for sample testing. The Contractor shall provide one liter samples of the selected paint materials. The samples shall be taken in the presence of the Contracting Officer, and labeled, identifying each sample. Provide labels in accordance with the paragraph "Packaging, Labeling, and Storage" of this specification.

1.4.1.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance Testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph "Qualification Testing" laboratory for coatings. The qualification testing lab report shall include the backup data and summary of the test results. The summary shall list all of the reference specification requirements and the result of each test. The summary shall clearly indicate whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If the Contractor chooses MPI to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.5 REGULATORY REQUIREMENTS

1.5.1 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.5.2 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.5.3 Asbestos Content

Materials shall not contain asbestos.

1.5.4 Mercury Content

Materials shall not contain mercury or mercury compounds.

1.5.5 Silica

Abrasive blast media shall not contain free crystilline silica.

1.5.6 Human Carcinogens

Materials shall not contain ACGIH 0100Doc and ACGIH 0100Doc confirmed human

carcinogens (A1) or suspected human carcinogens (A2).

1.6 PACKAGING, LABELING, AND STORAGE

Paints shall be in sealed containers that legibly show the contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Pigmented paints shall be furnished in containers not larger than 20 liters. Paints and thinners shall be stored in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 4 to 35 degrees C. Do not store paint, polyurethane, varnish, or wood stain products with materials that have a high capacity to adsorb VOC emissions. Do not store paint, polyurethane, varnish, or wood stain products in occupied spaces.

1.7 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Work shall comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN as specified in Appendix A of EM 385-1-1.

1.7.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA Guide 3.

1.7.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The applicable manufacturer's Material Safety Data Sheets (MSDS) or local regulation.

b. 29 CFR 1910.1000.

c. ACGIH 0100Doc, threshold limit values.

1.8 ENVIRONMENTAL CONDITIONS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation. Isolate area of application from rest of building when applying high-emission paints or coatings.

1.8.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 3 degrees C above dew point;

b. Below 10 degrees C or over 35 degrees C, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Under no circumstances shall application conditions exceed manufacturer recommendations.

1.8.2 Post-Application

Vacate space for as long as possible after application. Wait a minimum of 48 hours before occupying freshly painted rooms. Maintain one of the following ventilation conditions during the curing period, or for 72 hours after application:

a. Supply 100 percent outside air 24 hours a day.

b. Supply airflow at a rate of 6 air changes per hour, when outside temperatures are between 13 degrees C and 29 degrees C and humidity is between 30 percent and 60 percent.

c. Supply airflow at a rate of 1.5 air changes per hour, when outside air conditions are not within the range stipulated above.

1.9 COLOR SELECTION

Colors shall be selected by the Contracting Officer, from manufacturers standard list submitted by the contractor.

Tint each coat progressively darker to enable confirmation of the number of coats.

1.10 LOCATION AND SURFACE TYPE TO BE PAINTED

1.10.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.

b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.

c. Existing coated surfaces that are damaged during performance of the work.

1.10.1.1 Exterior Painting

Includes new surfaces, existing coated surfaces, and existing uncoated surfaces, of the buildings and appurtenances. Also included are existing coated surfaces made bare by cleaning operations.

1.10.1.2 Interior Painting

Includes new surfaces of the buildings and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

a. Exposed columns, girders, beams, joists, and metal deck; and

b. Other contiguous surfaces such as concrete floor slabs and plaster

walls.

1.10.2 Painting Excluded

Do not paint the following unless indicated otherwise.

a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.

b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.

c. Steel to be embedded in concrete.

d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.

e. Hardware, fittings, and other factory finished items.

1.10.3 Mechanical and Electrical Painting

Includes field coating of interior and exterior new surfaces.

a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.

(1) Exposed piping, conduit, and ductwork;

(2) Supports, hangers, air grilles, and registers;

(3) Miscellaneous metalwork and insulation coverings.

b. Do not paint the following, unless indicated otherwise:

(1) New zinc-coated, aluminum, and copper surfaces under insulation

(2) New aluminum jacket on piping

(3) New interior ferrous piping under insulation.

1.10.4 Exterior Painting of Site Work Items

Field coat the following items:

New Surfaces

a. Exterior unpainted exposed steel

b. Exterior previously primed exposed steel

c. Exterior exposed steel damaged during construction

1.10.5 MISCELLANEOUS PAINTING

Lettering Building

Lettering shall be provided as scheduled on the drawings, shall be block

type, and shall be black enamel. Samples shall be approved before application.

1.10.6 Definitions and Abbreviations

1.10.6.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.10.6.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing shall only be accomplished by MPI testing lab.

1.10.6.3 Coating

A film or thin layer applied to a base material called a substrate. A coating may be a metal, alloy, paint, or solid/liquid suspensions on various substrates (metals, plastics, wood, paper, leather, cloth, etc.). They may be applied by electrolysis, vapor deposition, vacuum, or mechanical means such as brushing, spraying, calendering, and roller coating. A coating may be applied for aesthetic or protective purposes or both. The term "coating" as used herein includes emulsions, enamels, stains, varnishes, sealers, epoxies, and other coatings, whether used as primer, intermediate, or finish coat. The terms paint and coating are used interchangeably.

1.10.6.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.10.6.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five (5) levels are generically defined under the Assessment sections in the MPI Maintenance Repainting Manual.

1.10.6.6 EPP

Environmentally Preferred Products, a standard for determining environmental preferability in support of Executive Order 13101.

1.10.6.7 EXT

MPI short term designation for an exterior coating system.

1.10.6.8 INT

MPI short term designation for an interior coating system.

1.10.6.9 micron / microns

The metric measurement for 0.001 mm or one/one-thousandth of a millimeter.

1.10.6.10 mil / mils

The English measurement for 0.001 in or one/one-thousandth of an inch, equal to 25.4 microns or 0.0254 mm.

1.10.6.11 mm

The metric measurement for millimeter, 0.001 meter or one/one-thousandth of a meter.

1.10.6.12 MPI Gloss Levels

MPI system of defining gloss. Seven (7) gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units @ 60 degrees	Units @ 85 degrees
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D 523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.10.6.13 MPI System Number

The MPI coating system number in each Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN). The Division number follows the CSI Master Format.

1.10.6.14 Paint

See Coating definition.

1.10.6.15 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.10.6.16 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit manufacturer's technical data sheets for specified coatings and solvents. Comply with applicable regulations regarding toxic and hazardous materials.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect, hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, workmen skilled in the trades involved shall reinstall removed items. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Oil and grease shall be removed prior to mechanical cleaning. Cleaning shall be programmed so that dust and other contaminants will not fall on wet, newly painted surfaces. Exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, shall be spot-primmed with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.2.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.

b. Wipe previously painted surfaces to receive solvent-based coatings, except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D 235. Allow surface to dry. Wiping shall immediately precede the application of the first coat of any coating, unless specified otherwise.

c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.

d. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer.

e. Previously painted surfaces specified to be repaintedor damaged during construction shall be thoroughly cleaned of all grease,

dirt, dust or other foreign matter.

f. Blistering, cracking, flaking and peeling or other deteriorated coatings shall be removed.

g. Chalk shall be removed so that when tested in accordance with ASTM D 4214, the chalk resistance rating is no less than 8.

h. Slick surfaces shall be roughened. Damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls shall be repaired with suitable material to match adjacent undamaged areas.

i. Edges of chipped paint shall be feather edged and sanded smooth.

j. Rusty metal surfaces shall be cleaned as per SSPC requirements. Solvent, mechanical, or chemical cleaning methods shall be used to provide surfaces suitable for painting.

k. New, proposed coatings shall be compatible with existing coatings.

3.2.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding or blasting so that when tested in accordance with ASTM D 4214, the chalk rating is not less than 8.

3.2.3 Removal of Existing Coatings

Remove existing coatings from the following surfaces:

a. Surfaces containing large areas of minor defects;

b. Surfaces containing more than 20 percent peeling area; and

c. Surfaces designated by the Contracting Officer, such as surfaces where rust shows through existing coatings.

3.2.4 Substrate Repair

a. Repair substrate surface damaged during coating removal;

b. Sand edges of adjacent soundly-adhered existing coatings so they are tapered as smooth as practical to areas involved with coating removal; and

c. Clean and prime the substrate as specified.

3.3 PREPARATION OF METAL SURFACES

3.3.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean or detergent wash in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2, SSPC SP 3, SSPC SP 6, or SSPC SP 10. Brush-off blast remaining surface in accordance with SSPC SP 7.

Shop-coated ferrous surfaces shall be protected from corrosion by treating and touching up corroded areas immediately upon detection.

b. Surfaces With More Than 20 Percent Rust, Mill Scale, and Other Foreign Substances: Clean entire surface in accordance with SSPC SP 6/SSPC SP 12 WJ-3.

c. Metal Floor Surfaces to Receive Nonslip Coating: Clean in accordance with SSPC SP 10.

3.3.2 Final Ferrous Surface Condition:

For tool cleaned surfaces, the requirements are stated in SSPC SP 2 and SSPC SP 3. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 3.

For abrasive blast cleaned surfaces, the requirements are stated in SSPC SP 7, SSPC SP 6, and SSPC SP 10. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 1.

For waterjet cleaned surfaces, the requirements are stated in SSPC SP 12. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 4.

3.3.3 Galvanized Surfaces

a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, or non-alkaline detergent solution in accordance with SSPC SP 1. If the galvanized metal has been passivated or stabilized, the coating shall be completely removed by brush-off abrasive blast. New galvanized steel to be coated shall not be "passivated" or "stabilized" If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D 2092, Appendix X2, and remove by one of the methods described therein.

b. Galvanized with Slight Coating Deterioration or with Little or No Rusting: Water jetting to SSPC SP 12 WJ3 to remove loose coating from surfaces with less than 20 percent coating deterioration and no blistering, peeling, or cracking. Use inhibitor as recommended by the coating manufacturer to prevent rusting.

c. Galvanized With Severe Deteriorated Coating or Severe Rusting: Spot abrasive blast rusted areas as described for steel in SSPC SP 6, and waterjet to SSPC SP 12, WJ3 to remove existing coating.

3.3.4 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal surfaces.

a. Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.3.5 Terne-Coated Metal Surfaces

Solvent clean surfaces with mineral spirits, ASTM D 235. Wipe dry with

clean, dry cloths.

3.3.6 Existing Surfaces with a Bituminous or Mastic-Type Coating

Remove chalk, mildew, and other loose material by washing with a solution of 0.20 liter trisodium phosphate, 0.1 liter household detergent, 1.6 liters 5 percent sodium hypochlorite solution and 4.8 liters of warm water.

3.4 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.4.1 Concrete and Masonry

a. Curing: Concrete, stucco and masonry surfaces shall be allowed to cure at least 30 days before painting, except concrete slab on grade, which shall be allowed to cure 90 days before painting.

b. Surface Cleaning: Remove the following deleterious substances.

(1) Dirt, Chalking, Grease, and Oil: Wash new and existing uncoated surfaces with a solution composed of 0.2 liter trisodium phosphate, 0.1 liter household detergent, and 6.4 liters of warm water. Then rinse thoroughly with fresh water. Wash existing coated surfaces with a suitable detergent and rinse thoroughly. For large areas, water blasting may be used.

(2) Fungus and Mold: Wash new surfaces with a solution composed of 0.2 liter trisodium phosphate, 0.1 liter household detergent, 1.6 liters 5 percent sodium hypochlorite solution and 4.8 liters of warm water. Rinse thoroughly with fresh water.

(3) Paint and Loose Particles: Remove by wire brushing.

(4) Efflorescence: Remove by scraping or wire brushing followed by washing with a 5 to 10 percent by weight aqueous solution of hydrochloric (muriatic) acid. Do not allow acid to remain on the surface for more than five minutes before rinsing with fresh water. Do not acid clean more than 0.4 square meter of surface, per workman, at one time.

c. Cosmetic Repair of Minor Defects: Repair or fill mortar joints and minor defects, including but not limited to spalls, in accordance with manufacturer's recommendations and prior to coating application.

d. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not to surfaces with droplets of water. Do not apply epoxies to damp vertical surfaces as determined by ASTM D 4263 or horizontal surfaces that exceed 3 lbs of moisture per 1000 square feet in 24 hours as determined by ASTM F 1869. In all cases follow manufacturers recommendations. Allow surfaces to cure a minimum of 30 days before painting.

e. Etching: If/as required, etch the surface with a concrete etching solution to allow for proper penetration and adhesion. After etching, rinse the surface thoroughly and let dry. If muratic acid is used, it must be neutralized before proceeding. Test surface for immediate water penetration before proceeding.

3.4.2 Plaster, and Stucco

a. Surface Cleaning: Plaster and stucco shall be clean and free from loose matter; gypsum board shall be dry. Remove loose dirt and dust by brushing with a soft brush, rubbing with a dry cloth, or vacuum-cleaning prior to application of the first coat material. A damp cloth or sponge may be used if paint will be water-based.

b. Repair of Minor Defects: Prior to painting, repair joints, cracks, holes, surface irregularities, and other minor defects with patching plaster or spackling compound and sand smooth.

c. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not surfaces with droplets of water. Do not apply epoxies to damp surfaces as determined by ASTM D 4263. New plaster to be coated shall have a maximum moisture content of 8 percent, when measured in accordance with ASTM D 4444, Method A, unless otherwise authorized. In addition to moisture content requirements, allow new plaster to age a minimum of 30 days before preparation for painting.

3.5 PREPARATION OF WOOD AND PLYWOOD SURFACES

3.5.1 New, Existing Uncoated, and Existing Coated Plywood and Wood Surfaces:

a. Wood surfaces shall be cleaned of foreign matter.

Surface Cleaning: Surfaces shall be free from dust and other deleterious substances and in a condition approved by the Contracting Officer prior to receiving paint or other finish. Do not use water to clean uncoated wood. Scrape to remove loose coatings. Lightly sand to roughen the entire area of previously enamel-coated wood surfaces.

b. Removal of Fungus and Mold: Wash existing coated surfaces with a solution composed of 0.2 liter trisodium phosphate, 0.1 liter household detergent, 1.6 liters 5 percent sodium hypochlorite solution and 4.8 liters of warm water. Rinse thoroughly with fresh water.

c. Moisture content of the wood shall not exceed 12 percent as measured by a moisture meter in accordance with ASTM D 4444, Method A, unless otherwise authorized.

d. Wood surfaces adjacent to surfaces to receive water-thinned paints shall be primed and/or touched up before applying water-thinned paints.

e. Cracks and Nailheads: Set and putty stop nailheads and putty cracks after the prime coat has dried.

f. Cosmetic Repair of Minor Defects:

(1) Knots and Resinous Wood : Prior to application of coating, cover knots and stains with two or more coats of 1.3-kg-cut shellac varnish, plasticized with 0.14 liters of castor oil per liter. Scrape away existing coatings from knotty areas, and sand before treating. Prime before applying any putty over shellacked area.

(2) Open Joints and Other Openings: Fill with whiting putty, linseed oil putty. Sand smooth after putty has dried.

(3) Checking: Where checking of the wood is present, sand the surface, wipe and apply a coat of pigmented orange shellac. Allow to dry before paint is applied.

g. Prime Coat For New Exterior Surfaces: Prime coat before wood becomes dirty, warped, or weathered.

3.6 APPLICATION

3.6.1 Coating Application

Painting practices shall comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint shall show no signs of deterioration. Uniform suspension of pigments shall be maintained during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Rollers for applying paints and enamels shall be of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

Paints, except water-thinned types, shall be applied only to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Special attention shall be given to insure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

Each coat of paint shall be applied so dry film shall be of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Hiding shall be complete.

Touch up damaged coatings before applying subsequent coats. Interior areas shall be broom clean and dust free before and during the application of coating material.

a. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.

b. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Each coat shall cover surface of preceding coat or surface completely, and

there shall be a visually perceptible difference in shades of successive coats.

c. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

d. Thermosetting Paints: Topcoats over thermosetting paints (epoxies and urethanes) should be applied within the overcoating window recommended by the manufacturer.

3.6.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. The written permission shall include quantities and types of thinners to use.

When thinning is allowed, paints shall be thinned immediately prior to application with not more than 0.125 L of suitable thinner per liter. The use of thinner shall not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning shall not cause the paint to exceed limits on volatile organic compounds. Paints of different manufacturers shall not be mixed.

3.6.3 Two-Component Systems

Two-component systems shall be mixed in accordance with manufacturer's instructions. Any thinning of the first coat to ensure proper penetration and sealing shall be as recommended by the manufacturer for each type of substrate.

3.6.4 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table

Division 3. Exterior Concrete Paint Table
Division 4. Exterior Concrete Masonry Units Paint Table
Division 5. Exterior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Exterior Wood Paint Table

Division 3. Interior Concrete Paint Table
Division 4. Interior Concrete Masonry Units Paint Table
Division 5. Interior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Interior Wood Paint Table
Division 9: Interior Plaster Paint Table

b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 0.038 mm each coat unless specified otherwise in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.

c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.

d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:

(1) One coat of primer.

(2) One coat of undercoat or intermediate coat.

(3) One topcoat to match adjacent surfaces.

e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.7 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.

b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.

c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 0.038 mm DFT immediately prior to application of epoxy or urethane coatings.

e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat, but shall be overcoated with the specified ferrous-metal primer prior to application of finish coats.

f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.8 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in Division 3, 4 and 9 for Exterior and Interior.

3.9 COATING SYSTEMS FOR WOOD AND PLYWOOD

a. Apply coatings of Tables in Division 6 for Exterior and Interior.

b. Prior to erection, apply two coats of specified primer to treat and prime wood and plywood surfaces which will be inaccessible after erection.

c. Apply stains in accordance with manufacturer's printed

instructions.

3.10 PIPING IDENTIFICATION

Piping Identification, Including Surfaces In Concealed Spaces: Provide in accordance with MIL-STD-101. Place stenciling in clearly visible locations. On piping not covered by MIL-STD-101, stencil approved names or code letters, in letters a minimum of 13 mm high for piping and a minimum of 50 mm high elsewhere. Stencil arrow-shaped markings on piping to indicate direction of flow using black stencil paint.

3.11 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.12 PAINT TABLES

All DFT's are minimum values. Use only materials having a minimum MPI "Environmentally Friendly" E1 rating based on VOC (EPA Method 24) content levels. Acceptable products are listed in the MPI Green Approved Products List, available at http://www.specifygreen.com/APL/ProductIdxByMPInum.asp.

3.12.1 EXTERIOR PAINT TABLES

DIVISION 3: EXTERIOR CONCRETE PAINT TABLE

A. New and uncoated existing concrete; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs:

1. Latex
   New; MPI EXT 3.1A-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 11	MPI 11	MPI 11

System DFT: 88 microns

Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces.

DIVISION 4: EXTERIOR CONCRETE MASONRY UNITS PAINT TABLE

A. New concrete masonry on uncoated surface:

1. Latex
   New; MPI EXT 4.2A-G5 (Semigloss) / Existing; MPI REX 4.2A-G5 (Semigloss)

Block Filler:	Primer:	Intermediate:	Topcoat:
MPI 4	N/A	MPI 11	MPI 11

System DFT: 275 microns

Topcoat: Coating to match adjacent surfaces.

DIVISION 5: EXTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

STEEL / FERROUS SURFACES

STEEL / FERROUS SURFACES

A. New Steel that has been hand or power tool cleaned to SSPC SP 2 or SSPC SP 3

1. Alkyd
New; MPI EXT 5.1Q-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 23 MPI 94 MPI 94
System DFT: 131 microns

EXTERIOR SURFACES, OTHER METALS (NON-FERROUS)

A. Surfaces adjacent to painted surfaces; Mechanical, Electrical, and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish:

1. Waterborne Light Industrial Coating
MPI EXT 5.1C-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 163 MPI 163
System DFT: 125 microns

3.12.2 3.12.2 INTERIOR PAINT TABLES

DIVISION 3: INTERIOR CONCRETE PAINT TABLE

A. New Concrete, vertical surfaces, not specified otherwise:

1. Institutional Low Odor / Low VOC Latex
New; MPI INT 3.1M-G5 (Semigloss) / Existing; MPI RIN 3.1L-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 50 MPI 147 MPI 147
System DFT: 100 microns

B. New concrete in toilet areas, food-preparation areas, food-serving areas, restrooms, laundry areas, shower areas, areas requiring a high degree of sanitation, and other high-humidity areas not otherwise specified except floors:

1. Waterborne Light Industrial Coating
New; MPI INT 3.1L-G5(Semigloss) / Existing; MPI RIN 3.1C-G5(Semigloss)
Primer: Intermediate: Topcoat:
MPI 153 MPI 153 MPI 153
System DFT: 120 microns

C. New concrete floors in indicated areas.

1. Epoxy
New; MPI INT 3.2C-G6 (Gloss)
Primer: Intermediate: Topcoat:
MPI 77 MPI 77 MPI 77
System DFT: 5 mils 125 microns

Note: Primer may be reduced for penetration per manufacturer's instructions.

DIVISION 5: INTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

INTERIOR STEEL / FERROUS SURFACES

A. Metal, Mechanical, Electrical, ssurfaces adjacent to painted surfaces (match surrounding finish), and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment:

1. High Performance Architectural Latex
   MPI INT 5.1R-G5 (Semigloss)
   Primer: Intermediate: Topcoat:
   MPI 79 MPI 139 MPI 139
   System DFT:

B. Metal in toilets areas, food-preparation areas, food-serving areas, restrooms, laundry areas, shower areas, areas requiring a high degree of sanitation, and other high-humidity areas not otherwise specified except floors, hot metal surfaces, and new prefinished equipment:

1. MPI INT 5.1E-G5 (Semigloss)
   Primer: Intermediate: Topcoat:
   MPI 79 MPI 47 MPI 47
   System DFT:

C. Ferrous metal in concealed damp spaces or in exposed areas having unpainted adjacent surface:

1. Aluminum Paint
   MPI INT 5.1M
   Primer: Intermediate: Topcoat:
   MPI 79 MPI 1 MPI 1
   System DFT: 106 microns

D. Miscellaneous non-ferrous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish:

1. High Performance Architectural Latex
   MPI INT 5.4F-G5 (Semigloss)
   Primer: Intermediate: Topcoat:
   MPI 95 MPI 141 MPI 141
   System DFT:

E. Hot metal surfaces including smokestacks subject to temperatures up to 205 degrees C (400 degrees F):

1. Heat Resistant Enamel
   MPI INT 5.2A
   Primer: Intermediate: Topcoat:
   MPI 21 Surface preparation and number of coats per manufacturer's instructions.
   System DFT: Per Manufacturer

F. Ferrous metal subject to high temperature, up to 400 degrees C (750 degrees F):

1. Inorganic Zinc Rich Coating
   MPI INT 5.2C
   Primer: Intermediate: Topcoat:

INTERIOR STEEL / FERROUS SURFACES
MPI 19 Surface preparation and number of coats per manufacturer's instructions.
System DFT: Per Manufacturer

G. New surfaces made bare cleaning to SSPC SP 10 subject to temperatures up to 593 degrees C (1100 degrees F):

1. High Heat Resistant Coating
MPI INT 5.2D
Primer: Intermediate: Topcoat:
MPI 22 Surface preparation and number of coats per manufacturer's instructions.
System DFT: Per Manufacturer

DIVISION 6: INTERIOR WOOD PAINT TABLE

A. New uncoated Wood and plywood not otherwise specified:

1. Institutional Low Odor / Low VOC Latex
New; MPI INT 6.3V-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 39 MPI 147 MPI 147
System DFT: 100 microns

DIVISION 9: INTERIOR PLASTER SURFACES PAINT TABLE

A. New and previously painted Plaster not otherwise specified:

1. Institutional Low Odor / Low VOC Latex
New; MPI INT 9.2M-G5 (Semigloss) / Existing; MPI RIN 9.2M-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 50 MPI 147 MPI 147
System DFT: 100 microns

B. New and previously painted in toilet areas, food-preparation areas, food-serving areas, restrooms, laundry areas, shower areas, areas requiring a high degree of sanitation, and other high humidity areas not otherwise specified.

1. Waterborne Light Industrial Coating
New; MPI INT 9.2L-G5(Semigloss) / Existing; MPI RIN 9.2L-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 50 MPI 153 MPI 153
System DFT: 100 microns

-- End of Section --

SECTION 10 22 26.13

OPERABLE PARTITIONS
10/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B 221M	(2007) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM C 423	(2008a) Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
ASTM D 751	(2006) Coated Fabrics
ASTM E 336	(2009) Measurement of Airborne Sound Insulation in Buildings
ASTM E 413	(2004) Rating Sound Insulation
ASTM E 557	(2000; R 2006) Installation of Operable Partitions
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E 90	(2009) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements

CHEMICAL FABRICS & FILM ASSOCIATION (CFFA)

CFFA-W-101-D	(2002) Vinyl Coated Fabric Wallcovering

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2008; Amendment 2009) Life Safety Code
NFPA 286	(2006) Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth

UNDERWRITERS LABORATORIES (UL)

UL 10B (2008; Rev thru Apr 2009) Fire Tests of Door Assemblies

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Manufacturer's Qualifications

Manufacturer's Sample Warranty

Statement of Code Compliance

Statement of Standards Conformity

Verification of Field Measurements

SD-02 Shop Drawings

Submit Fabrication Drawings for Paired Panel Partitions consisting of fabrication and assembly details to be performed in the factory.

Submit Installation Drawings for the following items in accordance with paragraph entitled, "Installation," of this section.

Paired Panel Partition Layouts

Suspension System

Finish Hardware

Jamb Panels

Accessories

Submit drawings for the system that include dimensions and weight of stacked partition, layout of the work including stacking area, track and jamb fastening methods, seal details, and installation details.

SD-03 Product Data

Framework

Suspension system

Finish Hardware

Sound Seals and Sweepstrips

Covering

Ceiling Guard

Meeting Posts

Jamb Panels

Rolling Post

Pull-In Latch

SD-04 Samples

Covering; G

SD-06 Test Reports

Laboratory Acoustical Requirements

Acoustical test

SD-07 Certificates

Submit Certificates to the Contracting Officer for this installation clearly indicating:

Statement of Code Compliance

Statement of Standards Conformity

SD-10 Operation and Maintenance Data

Folding partitions, Data Package 1

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

Manufacturer's Guarantee

1.3 PRE-INSTALLATION REQUIREMENTS

1.3.1 Preconstruction Requirements

No less than 30 calendar days prior to the scheduled commencement of installation of Accordion Folding Partitions, submit the following to the Contracting Officer:

Manufacturer's Qualifications

Manufacturer's Sample Warranty

Statement of Code Compliance

Statement of Standards Conformity

Verification of Field Measurementsand Existing Electrical Data

Fabrication Drawings and Installation Drawings

1.3.2 Product Data

Submit the following information for review:

Finish Hardware

Jamb Panels and Accessories

Sound Seals and Sweepstrips

Ceiling Guard, Meeting Posts, Rolling Post

Pull-In Latch

1.3.3 Manufacturer's Guarantee

Provide Manufacturer's Guarantee for partitions against defects in material and workmanship for a period of two years from date of installation. In addition, provide ten year guarantee for the pantographs, trolleys and tracks from date of acceptance for beneficial use.

1.4 DELIVERY, HANDLING AND STORAGE

Deliver materials to project site in manufacturer's original, unopened, and undamaged packages with labels legible and intact. Labels must indicate the manufacturer, brand name, size, finish, and placement location. Store folding partitions and accessories in unopened packages in a manner that will prevent damage. Handle partition materials in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 FOLDING PARTITIONS

Provide paired, hinged flat panel type partitions, factory finished, supported from overhead track without floor guides, and complete with all hardware, track, and accessories necessary for operation. Provide partition framework with a mechanism that gives stability and maintains uniform spacing of partition folds in all partition positions. Provide completely concealed framework with a vinyl-coated fabric covering. Provide partitions manually operated, bi-parting type as indicated. Provide patterns and colors of fabric approved by the Contracting Officer Provide final closure via hinged panel.

2.2 MATERIALS

2.2.1 Aluminum Extrusions

ASTM B 221M, Alloy 3003.

2.2.2 Steel Sheets

ASTM A 653/A 653M, Z 180 coating designation.

2.2.3 Fabric Covering

CFFA-W-101-D, Type III or better as per manufacturer's standard panel face finish.

2.2.4 Seals and Sweepstrips

Provide perimeter seals of manufacturer's standard product, without crack or craze when subjected to severe usage.

2.2.5 Ceiling Guards

Furnish partitions with ceiling guards or integral track and ceiling guards if/as recommended by the manufacturer.

2.3 PERFORMANCE REQUIREMENTS

2.3.1 Fire Endurance

For partitions more than 5.6 square meters in area, provide fabric and lining with flame spread rating of 25 or less, fuel contribution rating of 15 or less, smoke generation of 50 or less when tested in accordance with ASTM E 84. Complete assembly must also meet or surpass the requirements of NFPA 101 and UL 10B.

Pass Doors: Provide doors in fire-rated operable panel partition assemblies with fire-resistance ratings indicated. Pass doors shall meet positive-pressure requirements.

2.3.2 Laboratory Acoustical Requirements

Provide certificates verifying folding partitions have been tested in accordance with ASTM C 423 and ASTM E 90 by a laboratory accredited by the U.S. Bureau of Standards and have attained a sound transmission class (STC) of not less than 55 in a fully extended position. Partition tested must be of the same construction, materials, and model number as the partition to be provided and be fully operable. Test specimen must be not less than 12 square meters in area 4200 by 2700 mm. Panel weight must be 14 kg per square meter.

2.4 FABRICATION

2.4.1 Panel Construction

A. Nominal 4-1/4-inch (108 mm) thick panels in manufacturer’s standard 48-inch (1220 mm) widths. All panel horizontal and vertical framing members fabricated from minimum 16-gage formed steel with overlapped and welded corners for rigidity. Top channel is reinforced to support suspension system components. Frame is designed so that full vertical edges of panels are of formed steel and provide concealed protection of the edges of the panel skin.

B. Panel Skin Options:
1. Roll-formed steel wrapping around panel edge.
Panel skins shall be lock formed and welded directly to the frame for unitized construction. Acoustical ratings of panels with this construction: 55 STC.

C. Hinges for Panels, Closure Panels, Pass Doors, and Pocket Doors

shall be (select one):
1. Full leaf butt hinges, attached directly to panel frame with welded hinge anchor plates within panel to further support hinge mounting to frame. Lifetime warranty on hinges. Hinges mounted into panel edge or vertical astragal are not acceptable.

D. Panel Trim: No vertical trim required or allowed on edges of panels; minimal groove appearance at panel joints.

E. Panel Weight: Steel Skin
1. 55 STC - 13 lbs./square foot.

2.4.2 Suspension System

Suspension Tracks: Minimum 7-gage, 0.18-inch (4.57 mm) roll-formed steel. Static loading of track with brackets at 48-inch (1220 mm) centers shall show no failure of track or brackets at 5,000 pounds (2550 kg) point loading at mid-span. Track shall be supported by adjustable steel hanger brackets connected to structural support pairs of 1/2-inch (13 mm) diameter threaded rods. Brackets must support the load bearing surface of the track.

Exposed track soffit: Steel, removable for service and maintenance, attached to track bracket without exposed fasteners, and pre-painted off-white.

Carriers: One all steel trolley with steel-tired ball bearing wheels per panel (except hinged panels). Non-steel tires are not acceptable.

2.4.3 Covering

Covering fabrics must conform to the requirements of ASTM D 751 and NFPA 286 and manufacturer's standard.

Attach fabric to the framework with fasteners that permit easy removal of the cover but prevent sagging or separation. Position vertical seams in the bottoms of valleys and reinforce. Provide top and bottom edges of cover fabrics with 12 mm minimum turned hems.

2.4.4 Sound Insulation

Provide sound insulation as necessary to achieve the specified sound transmission mission class, conforming to ASTM E 413.

2.4.5 Seals

Vertical Interlocking Sound Seals between panels:
Aluminum astragals, with reversible tongue and groove configuration in each panel edge for universal panel operation. Rigid plastic astragals or astragals in only one panel edge are not acceptable.

Horizontal Top Seals: Continuous contact-extruded vinyl bulb shape with pairs of non-contacting vinyl fingers to prevent distortion without the need for mechanically operated parts.

Horizontal Bottom Seals shall be: Automatic operable seals providing nominal 2-inch (51 mm) operating clearance with an operating range of +1/2-inch (13 mm) to -1-1/2-inch (38 mm) which automatically drop as panels are positioned, without the need for tools or cranks.

2.4.6 Hardware

Provide hardware of the heavy-duty type standard with the manufacturer. Provide pulls and latches for all partitions.

2.4.7 Accessories

Provide markerboard, bulkboard, and tackboard, recessed eraser holder as indicated.

2.4.8 Pass Doors

Fabricated to comply with recommendations in ICC/ANSI A117.1. Swinging door built into and matching panel materials, construction, acoustical qualities, fire rating finish, and thickness, complete with frames and operating hardware. Hinges finished to match other exposed hardware.

1. Single Pass Door: 914 by 2032 mm, same thickness and appearance as panels with the following:
   a. Door Seals: Sweep floor seals.
   b. Panic exit device.
   c. Recessed hand pull with friction latch (ADA compliant).
   d. Door Viewer: Installed with view in direction of swing.
   e. Exit Sign: Surface or Recessed, self-illuminated.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Existing Work

Check openings scheduled to receive paralel panel partitions for correct dimensions.

Install and match partitions in accordance with the approved Paired Panel Partition Layouts, manufacturer's directions, and ASTM E 557. Provide structural support for the track support elements as indicated.

Submit to the Contracting Officer a certification of the following:

Statement of Code Compliance for the completed partition installation.

Statement of Standards Conformity

3.1.2 Adjustment

Adjust manually operated partitions to open and close from any position with a maximum horizontal force of 130 N applied to pendant pull, box or handle.

Adjust operable partitions to operate smoothly, easily, and quietly, free from binding, warp, excessive deflection, distortion, nonalignment, misplacement, disruption, or malfunction, throughout entire operational range. Lubricate hardware and other moving parts.

3.2 FIELD TESTS

3.2.1 Operational Test

Operate partition at least three times to demonstrate that partition is capable of being moved from the stored position to the fully extended position smoothly and quietly. Provide Operation & Maintenance Manual to Contracting Officer.

3.2.2 Visual Test

Conduct visual field tests for light leakage with all room lights turned on in the space on one side of the partition. Darken space on the other side of the partition. Light leakage from the lighted space to the darkened space is not acceptable. If light leakage does occur, adjust the partition to correct the problem and retest.

3.2.3 Acoustical Test

Field sound performance: provide partition testing by an independent certified acoustical consultant in accordance with ASTM E 336, and achieve a Noise Isolation Class (NIC) of 40 plus or minus two. Adjust and/or modify partitions which do not comply, and retest.

3.3 CLEANING

Clean the partition according to manufacturer's instructions to remove dust, dirt, adhesives and other foreign materials.

3.4 SUPPORT SERVICE

Equipment and component maintenance must be supported by a service organization which is reasonably convenient to the site of installation.

-- End of Section --

SECTION 10 35 23.13

PROPANE STOVE
10/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

NSF INTERNATIONAL (NSF)

NSF 2	(2008) Food Equipment

UNDERWRITERS LABORATORIES (UL)

UL 710	(1995; Rev thru Feb 2007) Exhaust Hoods for Commercial Cooking Equipment

1.2 RELATED REQUIREMENTS

Sections 22 00 00 PLUMBING - GENERAL PURPOSE, 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS, 26 20 00 INTERIOR DISTRIBUTION SYSTEM, apply to this section, with additions and modifications specified herein.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Propane stove

SD-08 Manufacturer's Instructions

Propane stove

Exhaust hood

SD-10 Operation and Maintenance Data

Propane stove, Data Package 2; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.4 WARRANTY

1.4.1 Propane Stove

Full warranty includes parts and labor for on-site service on unit. Warranty period for components: Five years from date of Substantial Completion.

PART 2 PRODUCTS

2.1 PROPANE STOVE

2.1.1 Stove

Standard Features as follows:

Ignition via match lit

Stainless Steel 304

Large triple ring burner and three independent control valves on face of unit to produce a wide heat range and accurate temperature control.

Inner center burner ring for low heat approximately 1-10,000 BTUs, middle burner ring for approximately 1-20,000 BTUs (center and middle burner for medium heat), outer burner ring for approximately 1-30,000 BTUs, total of approximately 60,000 BTUs of evenly distributed, clean burning blue flame with all three burners on for high heat.

Leg extensions for indicated cooking height.

Hose and regulator with quick disconnect fittings.

Stainless Steel rod cooking grid

2.1.2 Materials

Except as modified herein, provide manufacturer's standard materials for propane stove. Provide quantities, physical dimensions, colors, and electrical characteristics as indicated.

2.1.3 Exhaust Hoods Over Cooking Equipment

Section 23 00 00, Paragraph 2.16, NSF 2, factory fabricated, with replaceable grease filters.

2.1.3.1 Hood Construction

Section 23 00 00, Paragraph 2.16, welded joints and seams, ground and polished to match adjacent exterior surfaces. Provide stainless steel duct collars and risers.

2.1.3.2 Filter Housing, Grease Gutter, and Removable Grease Container

Section 23 00 00, Paragraph 2.16.

2.1.3.3 Accessories

Provide UL classified washable grease filters, vaporproof light fixtures, wiring in conduit between light fixtures, fan control, damper controls and fire protection system as per Section 23 00 00, Paragraph 2.16.

2.1.4 Fans - Supply and Exhaust

Section 23 00 00, Paragraph 2.16, type as indicated, UL 710; centrifugal fan with maximum sound pressure level 45 dB. Provide factory fabricated adjustable roof curbs.

2.1.5 Gas Piping

Section 22 00 00, black/galvanized steel.

2.1.6 Propane Tanks

By Others: Tank size not exceeding 100 pounds or 22 water gallons in volume; NFPA 58.

PART 3 EXECUTION

3.1 INSTALLATION

NFPA 70, ANSI Z21, ANSI Z83, Section 22 00 00 PLUMBING, GENERAL PURPOSE, Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Install propane stove in encasement (Section 04 20 00 Masonry) on concrete equipment pad (Section 03 31 00.00 10) in accordance with manufacturers' instructions and as indicated. Field verify actual stove dimentions prior to construction of CMU and tile encasement. Verify placement of stainless steel back splash (Section 05 50 00) between bottom of hood and top of terrazo tile (Section 09 66 16) and placement of steel corner guard (Section 05 50 00) at outside corners, horizontal and vertical edges of encasement.

Terminate steel gas piping in front of propane stove with shut-off valves and quick disconnect nipple. Connect propane stove to stainless piping with stainless steel flexible hose (Gastite or equal) as per NFPA 58 Section 5.8.6 using quick disconnect dielectric fittings.

3.2 FIELD QUALITY CONTROL

Conduct inspection and testing in the presence of the Contracting Officer to certify compliance with specified and manufacturer's performance parameters. Affect repairs and retest until no deficiences exist.

3.2.1 Field Inspection

Before and after installation, inspect propane stove and ancillary work for compliance with specified requirements.

3.2.2 Operation Tests

Upon completion, but before final acceptance, perform operation tests on propane stove and ancillary work as to piping, exhaust and make-up air flow, etc. to determine that components, including controls, safety devices, and attachments, operate properly and in accordance with specified requirements.

-- End of Section --

SECTION 10 44 16

FIRE EXTINGUISHERS
06/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INTERNATIONAL CODE COUNCIL (ICC)

IFC 1414	(2004) Portable Fire Extinguishers(Where Required)(Construction, Alteration, Demolition)
IFC 906	(2004) Portable Fire Extinguishers

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 1	(2006) Uniform Fire Code, 2006 Edition
NFPA 10	(2006; Errata 2006) Standard for Portable Fire Extinguishers
NFPA 101	(2008; Amendment 2009) Life Safety Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.106	Flammable and Combustible Liquids
29 CFR 1910.157	(2003) Portable Fire Extinguishers

UNDERWRITERS LABORATORIES (UL)

UL 299	(2002; R 2005e10) Standards for Dry Chemical Fire Extinguishers

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Manufacturer's Data for each type of required Fire Extinguisher with all related details, cabinets, accessories, and recommended operation manuals.

SD-02 Shop Drawings

Submit fabrication drawings for the following items consisting of

fabrication and assembly details to be performed in the factory. Submit installation drawings for the following items in accordance with the paragraph entitled, "Installation," of this section.

Fire Extinguishers
Accessories
Wall Brackets

SD-03 Product Data

Submit Manufacturer's catalog and warranty data for the following items:

Fire Extinguishers
Accessories
Wall Brackets
Replacement Parts

SD-04 Samples

One Fire Extinguisher of each type to be installed

One full-sized sample of each type of Cabinet to be installed

Three samples of Wall Brackets and Accessories of each type to be used

Approved samples may be used for installation, with proper identification and storage.

SD-07 Certificates

Submit Certificates showing the following:

Certification that Fire Extinguishers comply with local codes and regulations.

Certification that Fire Extinguishers comply with OSHA, NFPA, and UL requirements.

Submit Manufacturer's Warranty with Inspection Tag on each extinguisher.

Guarantee that Fire Extinguishers are free of defects in materials, fabrication, finish, and installation and that they will remain so for a period of not less than 3 years after completion.

1.3 DELIVERY, HANDLING, AND STORAGE

Protect materials from weather, soil, and damage during delivery, storage, and construction.

Deliver materials in their original packages, containers, or bundles bearing the brand name and the name and type of the material.

PART 2 PRODUCTS

2.1 TYPES

Fire Extinguishers must conform to NFPA 10 Quantity and placement must comply with the applicable sections of IFC 1414, IFC 906, NFPA 1, NFPA 101, 29 CFR 1910.106 and 29 CFR 1910.157.

Provide dry chemical type fire extinguishers compliant with UL 299.

Submit Manufacturer's Data for each type of Fire Extinguisher required, detailing all related wall mounting and accessories information, complete with Manufacturer's Warranty with Inspection Tag.

2.2 MATERIAL

Extinguisher shell must be corrosion-resistant steel.

2.3 SIZE

Extinguishers must be 4.5 kilogram.

2.4 ACCESSORIES

Forged brass valve

Fusible plug

Safety release

Antifreeze

Pressure gage

2.5 WALL BRACKETS

Provide wall-hook fire extinguisher wall brackets.

Wall bracket and Accessories must be as approved.

PART 3 EXECUTION

3.1 INSTALLATION

Install Fire Extinguishers where indicated on the drawings. Verify exact locations prior to installation.

Comply with the manufacturer's recommendations for all installations.

Provide extinguishers which are fully charged and ready for operation upon installation. Provide extinguishers complete with Manufacturer's Warranty with Inspection Tag attached.

3.2 ACCEPTANCE PROVISIONS

3.2.1 Repairing

Remove and replace damaged and unacceptable portions of completed work with new work at no additional cost to the Government.

Provide Replacement Parts list indicating specified items replacement part, replacement cost, and name, address and contact for replacement parts distributor.

3.2.2 Cleaning

Clean all surfaces of the work, and adjacent surfaces which are soiled as a result of the work. Remove from the site all construction equipment, tools, surplus materials and rubbish resulting from the work.

-- End of Section --

SECTION 10 75 00.00 48

FLAGPOLES
04/06

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Shop Drawings.; FIO
Indicate detailed dimensions, base attachment details, anchor requirements, and imposed loads.

SD-03 Product Data

Product Data; FIO

Provide data on pole, accessories, and configurations.

Operation Data; FIO

Provide operating data for the controller.

Maintenance Data; FIO

Provide lubrication and periodic maintenance requirement schedules.

Acceptable Manufacturer Products; FIO

Manufacturers products listed in this specification are referenced to establish a standard of quality. When the specific product listed is submitted by the Contractor, that submittal will be considered For Information Only). When an equal to that named in this specification is submitted, it shall be for Government Approval (G). The following manufacturer products are specifically mentioned in this specification:

Flagpole Manufacturer Product submitted as an "or equal"; G

SD-04 Samples

Samples; FIO

Submit two samples 100 mm x 100 mm in size illustrating pole material, color, and finish.

1.2 DELIVERY, STORAGE, AND HANDLING

Deliver flagpoles and accessories completely identified for installation procedure. Handle and store flagpoles to prevent damage or soiling.

Spiral wrap flagpole with protective covering and pack in protective shipping tubes or containers.

PART 2 PRODUCTS

2.1 POLE MATERIALS

Aluminum: ASTM B241, 6063 alloy, T6 temper.

2.2 POLE CONFIGURATION

2.2.1 Ground Mounted

Ground set, tapered shaft, internal halyard with winch.

1. Outside Butt Diameter: 152 mm.
2. Nominal Wall Thickness: 4 mm.
3. Nominal Height: 9.14 meters measured from nominal ground elevation.

2.3 COMPONENTS AND ACCESSORIES

Designer to make selection.

2.3.1 Finial Ball

Stainless steel, diameter.

2.3.2 Truck Assembly

Cast aluminum revolving, stainless steel ball bearings, non-fouling.

2.3.3 Flag

Flag shall be provided by others.

2.3.4 Winch

An internal winch operated by a removable handcrank. The winch contains an automatic brake system to permit locking of the flag in any position.

2.3.5 Winch Box

Aluminum, with built-in hinge and lock assembly, attached to pole with tamper proof screws inside box. Provide two keys to operate the lock.

2.3.6 Halyard

Stainless steel aircraft cable with two chrome plated bronze swivel snaphooks, plastic covered counterweight and beaded sling.

2.3.7 Primer

As recommended by the flagpole manufacturer.

2.4 MOUNTING COMPONENTS

Foundation to be sized based on local conditions.

2.4.1 Foundation Tube Sleeve

AASHTO M-36, corrugated 16 gage steel, galvanized, depth as recommended by the flagpole manufacturer.

2.4.2 Pole Base Attachment

Flush aluminum base with base cover.

2.4.3 Wall Support Assembly

Aluminum; round; one piece assembly, back-plate for through bolting, with stainless steel anchor bolts and cover.

2.4.4 Lighting Ground Rod

304.8 mm (12 inches) long copper rod, 19.05 mm (3/4 inch) diameter.

2.4.5 Lightning Ground Cable

Copper No. 6 AWG, soft drawn.

2.5 FINISHES

Selection to be made from manufacturer's standard.

2.5.1 Metal Surfaces in Contact With Concrete: Asphaltic paint.

2.5.2 Aluminum: Anodized clear satin finish.

2.5.3 Finial: Gold anodized finish atop stainless steel.

PART 3 EXECUTION

3.1 EXAMINATION

Verify that concrete foundation is ready to receive work and dimensions are as indicated on shop drawings.

3.2 PREPARATION

Coat metal sleeve surfaces below grade and surfaces in contact with dissimilar materials with asphaltic paint.

3.3 INSTALLATION

Install flagpole, base assembly, and fittings in accordance with manufacturer's instructions.

Fill foundation tube sleeve with concrete specified in Section 03 31 00.00 10, CAST-IN-PLACE STRUCTURAL CONCRETE.

Install foundation plate and centering wedges for flagpoles base set in concrete base and fasten.

3.4 ERECTION TOLERANCES

Maximum Variation From Plumb: 25 mm.

3.5 ADJUSTING

Adjust operating devices so that halyard and flag function smoothly.

---End of Section--

SECTION 10 90 00.00 48

MISCELLANEOUS SPECIALTIES
4/06

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Clothesline Structure

Drawings showing construction and installation details.

SD-03 Product Data

Product certification and installation recommendation data.

Clothesline Structure

1.2 DELIVERY AND STORAGE

All items shall be delivered to the project site in manufacturer's undamaged containers.

1.3 WARRANTY

Provide manufacturer's standard warranty for the items.

PART 2 PRODUCTS

2.1 CLOTHESLINE ASSEMBLY

Each clothesline assembly shall be approximately 5 m in length with four lines across spaced 410 mm apart and shall have sufficient strength to prevent sagging when all of the lines are loaded with wet laundry. Clotheslines shall be installed 1.6 m above surrounding finished grades.

Materials shall comply with requirements of this specification. Clothesline assemblies shall be either the standard product of a manufacturer regularly engaged in the manufacture of outdoor clotheslines, or shall be fabricated in accordance with this specification.

2.1.1 Supporting Structure

The clothesline supporting structure shall be constructed with galvanized steel pipes, fittings and eyebolts conforming to requirements of Section 05 50 13 unless otherwise approved. Piping, fittings, and eyebolts shall have sufficient strength to comply with requirements of Section 2.1 of this specification.

2.1.2 Clothesline

Clothesline shall consist of rope or vinyl covered steel wire that does not stretch when pulled taut or weighted down.

2.1.3 Concrete

Concrete for the foundations shall conform to requirements of Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

PART 3 EXECUTION

3.1 INSTALLATION

Install all items in strict accordance with manufacturer's recommendations and these specifications. Install at the locations indicated on the drawings. Align and plumb all items with adjacent surfaces and set accurately in location.

Clotheslines shall be installed behind each barracks.

Clothesline posts shall be embedded below grade in concrete. The depth and width of concrete embedment shall be that needed to satisfy the clothesline assembly strength requirements outlines in Section 2.1 of this Specification. In no case shall the depth of embedment be less than the frost depth.

Clotheslines shall have a minimum furnished height of 1.6 m.

3.2 PROTECTION AND CLEANING

Protect the work from other trades and remove all protective wrappings when appropriate. Clean all surfaces in accordance with manufacturer's recommendations.

-- End of Section --

SECTION 13 21 26

COLD-STORAGE ROOMS FIELD-FABRICATED
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 365	(2002) Commercial and Industrial Unitary Air-Conditioning Condensing Units
AHRI 420	(2008) Unit Coolers for Refrigeration

NSF INTERNATIONAL (NSF)

NSF 7	(2009) Commercial Refrigerators and Freezers

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-R-43900	(Rev B; Notice 1; CANC Notice 2) Refrigerators, Freezers, Prefabricated, Mechanical, Commercial, Walk-In

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS A-A-52128	(Basic) Shelving, Storage, Stationary and Mobile, Food Storage

UNDERWRITERS LABORATORIES (UL)

UL 1995	(2005; Rev thru Jul 2009) Standard for Heating and Cooling Equipment
UL 412	(2004; Rev thru Jan 2009) Refrigeration Unit Coolers
UL 427	(2006; Rev thru Mar 2009) Refrigerating Units

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Cold-storage rooms

SD-03 Product Data

Cold-storage rooms

Shelves

Refrigeration equipment

SD-06 Test Reports

Start-up and initial operational tests

SD-08 Manufacturer's Instructions

Cold-storage rooms

Refrigeration equipment

Include equipment start-up and initial operation. Include evacuation and charging procedures for refrigeration equipment.

SD-10 Operation and Maintenance Data

Cold-storage rooms, Data Package 1; G

Refrigeration equipment, Data Package 2; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

Posted operating instructions for refrigeration equipment

1.3 REFRIGERATION PIPING

Provide as specified under 22 00 00.

PART 2 PRODUCTS

2.1 COLD-STORAGE ROOMS

Field-fabricated with the following requirements:

a. Entrance doors shall be swing type with left-handed openings.

b. Refrigeration systems shall be the remote type.

c. Electrical characteristics as indicated.

d. Preservation and packing shall be commercial grade.

e. Provide recording thermometer.

f. Provide temperature alarm system with connector for remote temperature alarm.

g. Provide interior lighting.

h. Provide 2" depressed slab and ramp to freezer.

i. Provide condensing unit outdoor controls for operation down to specified ambient temperature.

2.2 SHELVES

FS A-A-52128, stationary type, slotted shelves, stainless steel construction, 450 to 500 mm front to rear, by 1200 mm long, by 1470 to 1680 mm high, except as indicated otherwise. Preproduction samples are not required.

2.3 REFRIGERATION EQUIPMENT

MIL-R-43900, except as modified in this section. Refrigerant equipment shall be designed for remote installation. Design units for 16 to 18 hour operation at the indicated interior temperature in specified ambient temperature. Capacities, air delivery, and dimensions shall be as indicated.

2.3.1 Remote Condensing Units

Factory-fabricated and rated in accordance with UL 1995 and AHRI 365. Provide with motor, air-cooled condenser, receiver, compressors, mounted on a common base. Compressors shall be hermetic type.

2.3.2 Evaporators

Factory-fabricated and rated in accordance with UL 412 and AHRI 420. Forced-convection, unit-cooler type, made to be suspended from the ceiling panels, with forced-air discharged parallel to the ceiling. Provide with air circulating motor, multifin tube-type coil and grille assembled within a protective housing. Air circulation motors shall be lifetime sealed, and the entire unit-cooler assembly shall be accessible for cleaning. Provide a drip pan and drain connection. When the cold storage room is used for freezing, provide an automatic electric heat defrosting system. Provide demand type defrost controllers.

2.3.3 Self-Contained Refrigerant Systems

Field-fabricated in accordance with UL 427 for side-wall mounting. Systems shall include a condensing unit mounted on the exterior and a forced air evaporator mounted on the interior directly opposite.

2.4 HEATING CABLE

Provide condensate drain lines and drains below freezer floors with electric heating cable, thermostatically controlled to maintain 5 degrees C at zero flow rate. Cable shall be sized to provide necessary wattage per meter.

PART 3 EXECUTION

3.1 INSTALLATION

Installation procedures shall conform to NSF 7, and the equipment manufacturer's instructions. Submit a set of instructions covering both assembly of the room and installation of the refrigeration equipment before

starting installation.

3.2 MANUFACTURER'S FIELD SERVICES

Furnish manufacturer's representatives who are trained to perform the services specified. The representatives shall furnish and services on the following matters:

a. Testing.

b. Charging equipment with refrigerant and oil.

c. Starting equipment and training government personnel as to its proper care, operation, and maintenance.

3.3 TESTS

Perform the tests for each room and provide everything required. Notify the Contracting Officer 10 days before performing the tests. Tests shall be performed in the presence of a manufacturer's representative.

3.3.1 Start-Up and Operational Tests

Start up and initially operate the systems upon completion of the installation of the equipment and refrigerant piping. Adjust the safety and automatic controls to place them in operation and sequence. Record manufacturer's recommended readings hourly. Operational tests shall cover a period of not less than 24 hours.

3.3.2 Performance Tests

Upon completion of the operational tests the systems shall be performance tested. Test duration shall not be less than 8 hours. Tests shall include the following information to be in the report with conclusions regarding the adequacy of the systems:

a. Time, dates and duration of tests.

b. Inside dry-bulb and wet-bulb temperatures maintained in each room during the tests employing recording instruments calibrated before the tests.

c. Outside dry-bulb and wet-bulb temperatures obtained from recording instruments calibrated and checked hourly with a sling psychrometer.

d. Evaporator and condenser entering and leaving temperatures taken hourly with the compressors in operation.

e. The make, model and capacity of each evaporator and condensing unit.

f. Voltmeter and ammeter readings for condensing units and evaporators.

3.4 OPERATING INSTRUCTIONS

Provide a framed and glassed control chart indicating a layout of the refrigeration systems, including piping, valves, wiring, and control

mechanisms. Install control chart where directed. Submit printed instructions covering the maintenance and operation of refrigeration equipment. Tag shutoff valves in accordance with the printed instructions. Provide special tools as necessary for repair and maintenance of the equipment.

3.5 CLEANING

Remove masking-protection from stainless steel and other finished surfaces. Wash and clean floors, walls, shelves, and ceilings inside rooms and exposed surfaces on the outside. Clean glass, fixtures and fittings.

3.6 INSTRUCTING OPERATING PERSONNEL

Upon completion of the work and at a time designated by the Contracting Officer, provide for the instruction of Government personnel in the operation and maintenance of each refrigeration system. The period of instruction shall be for not less than one 8-hour working day.

-- End of Section --

SECTION 13 48 00

SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(1996; Addenda A 1999; Errata 2003; R 2005) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(1987; R 2005) Standard for Square and Hex Nuts

ASTM INTERNATIONAL (ASTM)

ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel
ASTM A 500	(2003a) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 563M	(2006) Standard Specification for Carbon and Alloy Steel Nuts (Metric)
ASTM A 572/A 572M	(2006) Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Structural Steel
ASTM A 603	(1998; R 2003) Standard Specification for Zinc-Coated Steel Structural Wire Rope
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by

the Hot-Dip Process

ASTM E 488 (1996; R 2003) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-310-03A (2005) Seismic Design for Buildings

1.2 SYSTEM DESCRIPTION

1.2.1 General Requirements

The requirements for seismic protection measures described in this section shall be applied to the mechanical equipment and systems outlined in Section 22 00 00 PLUMBING, GENERAL PURPOSE, the electrical equipment and systems outlined in Section 26 05 48.00 10 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT, and the miscellaneous equipment and systems listed below. Seismic protection requirements shall be in accordance with UFC 3-310-03A and additional data furnished by the Contracting Officer, and shall be provided in addition to any other requirements called for in other sections of these specifications. The design for seismic protection shall be based on a Seismic Use Group I building occupancy and on site response coefficients for S_{MS} and S_{M1}. Resistance to lateral forces induced by earthquakes shall be accomplished without consideration of friction resulting from gravity loads. The basic force formulas, for Ground Motions A and B in Chapter 3 of UFC 3-310-03A, use the design spectral response acceleration parameters for the performance objective of the building, not for equipment in the building; therefore, corresponding adjustments to the formulas shall be required.

1.2.2 Miscellaneous Equipment and Systems

The bracing for the following miscellaneous equipment and systems shall be developed by the Contractor in accordance with the requirements of this specification:

Storage cabinets
Storage Racks
Shelving
Partitions
Ornamentations
Signs and Billboards
Furnishings

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Bracing; G
Resilient Vibration Isolation Devices; G
Equipment Requirements; G

Detail drawings along with catalog cuts, templates, and erection

and installation details, as appropriate, for the items listed. Submittals shall be complete in detail; shall indicate thickness, type, grade, class of metal, and dimensions; and shall show construction details, reinforcement, anchorage, and installation with relation to the building construction. For equipment and systems in buildings that have a performance objective higher than life-safety, the drawings shall be stamped by the registered engineer who stamps the calculations required above.

SD-03 Product Data

Bracing; G
Equipment Requirements; G

Copies of the design calculations with the detail drawings. Calculations shall be stamped by a registered engineer and shall verify the capability of structural members to which bracing is attached for carrying the load from the brace.

1.4 EQUIPMENT REQUIREMENTS

1.4.1 Rigidly Mounted Equipment

Rigidly mounted equipment to be furnished under this contract shall be constructed and assembled to withstand the seismic forces specified in UFC 3-310-03A, Chapter 10. For any rigid equipment which is rigidly attached on both sides of a building expansion joint, flexible joints for piping, electrical conduit, etc., that are capable of accommodating displacements equal to the full width of the joint in both orthogonal directions, shall be provided.

1.4.2 Nonrigid or Flexibly-Mounted Equipment

Non-rigid or flexibly mounted equipment to be furnished shall be constructed and assembled to resist a horizontal lateral force of 5 times the operating weight of the equipment at the vertical center of gravity of the equipment.

PART 2 PRODUCTS

2.1 BOLTS AND NUTS

Squarehead and hexhead bolts, and heavy hexagon nuts, ASME B18.2.1, ASME B18.2.2 for bolts and ASTM A 563M for nuts for bolts and nuts. Bolts and nuts used underground and/or exposed to weather shall be galvanized in accordance with ASTM A 153/A 153M.

2.2 SWAY BRACING

Material used for members listed in this section and on the drawings, shall be structural steel conforming with the following:

a. Plates, rods, and rolled shapes, ASTM A 36/A 36M, Grade 503. If the Contractor does the design, both ASTM A 36/A 36Mand ASTM A 572/A 572M, grade 503 will be allowed.

b. Wire rope, ASTM A 603.

c. Tubes, ASTM A 500, Grade B.

d. Pipes, ASTM A 53/A 53M, Type E or S, Grade B.

e. Light gauge angles, less than 6 mm thickness, ASTM A 653/A 653M.

PART 3 EXECUTION

3.1 BRACING

Bracing shall conform to the arrangements shown. Trapeze-type hanger shall be secured with not less than two 13 mm bolts.

3.2 BUILDING DRIFT

Sway braces for a piping run shall not be attached to two dissimilar structural elements of a building that may respond differentially during an earthquake unless a flexible joint is provided.

3.3 ANCHOR BOLTS

3.3.1 Cast-In-Place

Floor or pad mounted equipment shall use cast-in-place anchor bolts, except as specified below. One nut shall be provided on each bolt. Anchor bolts shall conform to ASTM A 307. Anchor bolts shall have an embedded straight length equal to at least 12 times nominal diameter of the bolt. Anchor bolts that exceed the normal depth of equipment foundation piers or pads shall either extend into concrete floor or the foundation shall be increased in depth to accommodate bolt lengths.

3.3.2 Expansion or Chemically Bonded Anchors

Expansion or chemically bonded anchors shall not be used unless test data in accordance with ASTM E 488 has been provided to verify the adequacy of the specific anchor and application. Expansion or chemically bonded anchors shall not be used to resist pull-out in overhead and wall installations if the adhesive is manufactured with temperature sensitive epoxies and the location is accessible to a building fire. Expansion and chemically bonded anchors shall be installed in accordance with the manufacturer's recommendations. The allowable forces shall be adjusted for the spacing between anchor bolts and the distance between the anchor bolt and the nearest edge, as specified by the manufacturer.

3.3.2.1 General Testing

Expansion and chemically bonded anchors shall be tested in place after installation. The tests shall occur not more than 24 hours after installation of the anchor and shall be conducted by an independent testing agency; testing shall be performed on random anchor bolts as described below.

3.3.2.2 Torque Wrench Testing

Torque wrench testing shall be done on not less than 50 percent of the total installed expansion anchors and at least one anchor for every piece of equipment containing more than two anchors. The test torque shall equal the minimum required installation torque as required by the bolt manufacturer. Torque wrenches shall be calibrated at the beginning of each day the torque tests are performed. Torque wrenches shall be recalibrated

for each bolt diameter whenever tests are run on bolts of various diameters. The applied torque shall be between 20 and 100 percent of wrench capacity. The test torque shall be reached within one half turn of the nut, except for 9 mm sleeve anchors which shall reach their torque by one quarter turn of the nut. If any anchor fails the test, similar anchors not previously tested shall be tested until 20 consecutive anchors pass. Failed anchors shall be retightened and retested to the specified torque; if the anchor still fails the test it shall be replaced.

3.3.2.3 Pullout Testing

Expansion and chemically bonded anchors shall be tested by applying a pullout load using a hydraulic ram attached to the anchor bolt. At least 5 percent of the anchors, but not less than 3 per day shall be tested. The load shall be applied to the anchor without removing the nut; when that is not possible, the nut shall be removed and a threaded coupler shall be installed of the same tightness as the original nut. The test setup shall be checked to verify that the anchor is not restrained from withdrawing by the baseplate, the test fixture, or any other fixtures. The support for the testing apparatus shall be at least 1.5 times the embedment length away from the bolt being tested. Each tested anchor shall be loaded to 1 times the design tension value for the anchor. The anchor shall have no observable movement at the test load. If any anchor fails the test, similar anchors not previously tested shall be tested until 20 consecutive anchors pass. Failed anchors shall be retightened and retested to the specified load; if the anchor still fails the test it shall be replaced.

3.4 RESILIENT VIBRATION ISOLATION DEVICES

Where the need for these devices is determined, based on the magnitude of the design seismic forces, selection of anchor bolts for vibration isolation devices and/or snubbers for equipment base and foundations shall follow the same procedure as in paragraph ANCHOR BOLTS, except that an equipment weight equal to five times the actual equipment weight shall be used.

3.4.1 Resilient and Spring-Type Vibration Devices

Vibration isolation devices shall be selected so that the maximum movement of equipment from the static deflection point shall be 13 mm.

3.4.2 Multidirectional Seismic Snubbers

Multidirectional seismic snubbers employing elastomeric pads shall be installed on floor- or slab-mounted equipment. These snubbers shall provide 6 mm free vertical and horizontal movement from the static deflection point. Snubber medium shall consist of multiple pads of cotton duct and neoprene or other suitable materials arranged around a flanged steel trunnion so both horizontal and vertical forces are resisted by the snubber medium.

3.5 SWAY BRACES FOR PIPING

Transverse sway bracing for steel and copper pipe shall be provided at intervals not to exceed those shown on the drawings. Transverse sway bracing for pipes of materials other than steel and copper shall be provided at intervals not to exceed the hanger spacing as specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE. Bracing shall consist of at least one vertical angle 50 by 50 mm by 16 gauge and one diagonal angle of

the same size.

3.5.1 Longitudinal Sway Bracing

Longitudinal sway bracing shall be provided in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.5.2 Anchor Rods, Angles, and Bars

Anchor rods, angles, and bars shall be bolted to either pipe clamps or pipe flanges at one end and cast-in-place concrete or masonry insert or clip angles bolted to the steel structure on the other end. Rods shall be solid metal or pipe as specified below. Anchor rods, angles, and bars shall not exceed lengths given in the tabulation below.

3.5.3 Maximum Length for Anchor Braces

Type	Size (millimeters)	Maximum Length* (meters)
Angles	38 x 38 x 6	1.5
	50 x 50 x 6	2.0
	64 x 38 x 6	2.5
	75 x 64 x 6	2.5
	75 x 75 x 6	3.0
Rods	91	1.0
	22	1.0
Flat Bars	38 x 6	0.4
	50 x 6	0.4
	50 x 10	0.5
Pipes (40s)	25	2.0
	32	2.8
	40	3.2
	50	4.0

3.5.4 Bolts

Bolts used for attachment of anchors to pipe and structure shall be not less than 13 mm diameter.

3.6 EQUIPMENT SWAY BRACING

3.6.1 Suspended Equipment and Light Fixtures

Equipment sway bracing shall be provided for items supported from overhead floor or roof structural systems, including light fixtures. Braces shall consist of angles, rods, wire rope, bars, or pipes arranged as shown and secured at both ends with not less than 13 mm bolts. Sufficient braces shall be provided for equipment to resist a horizontal force as specified in Chapter 10 of UFC 3-310-03A without exceeding safe working stress of bracing components. The Contractor shall provide, for approval, specific force calcualtions in accordance with Chapter 10 of UFC 3-310-03A for the equipment in the project. Details of equipment bracing shall be submitted for acceptance. In lieu of bracing with vertical supports, these items may be supported with hangers inclined at 45 degrees directed up and radially away from equipment and oriented symmetrically in 90-degree intervals on

the horizontal plane, bisecting the angles of each corner of the equipment, provided that supporting members are properly sized to support operating weight of equipment when hangers are inclined at a 45-degree angle.

3.6.2 Floor or Pad Mounted Equipment

3.6.2.1 Shear Resistance

Floor mounted equipment shall be bolted to the floor. Requirements for the number and installation of bolts to resist shear forces shall be in accordance with paragraph ANCHOR BOLTS.

3.6.2.2 Overturning Resistance

The ratio of the overturning moment from seismic forces to the resisting moment due to gravity loads shall be used to determine if overturning forces need to be considered in the sizing of anchor bolts. Calculations shall be provided to verify the adequacy of the anchor bolts for combined shear and overturning.

-- End of Section --

SECTION 22 00 00

PLUMBING, GENERAL PURPOSE
04/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B16.15	(2006) Cast Bronze Threaded Fittings Classes 125 and 250
ASME B16.18	(2001; R 2005) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.3	(2006) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.39	(1998) Standard for Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300

ASTM INTERNATIONAL (ASTM)

ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM B 828	(2002) Standard Practice for Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings
ASTM A 733	(2003) Standard Specification for Welded and Seamless Carbon Steel and Austenitic Stainless Steel Pipe Nipples
ASTM D 1785	(2006) Standard Specification for Poly(Vinyl Chloride) (PVC), Plastic Pipe, Schedules 40, 80, and 120
ASTM D 2241	(2005) Standard Specification for Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)
ASTM D 2464	(2006) Standard Specification for Threaded Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D 2466	(2006) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40

ASTM D 2467	(2006) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D 2672	(1996a; R 2003) Joints for IPS PVC Pipe Using Solvent Cement

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-44	(2006) Steel Pipeline Flanges
MSS SP-83	(2006) Standard for Class 3000 Steel Pipe Unions Socket Welding and Threaded

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals having a "FIO" designation are For Information only and for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Plumbing System; GA

Detail drawings consisting of schedules, performance charts, instructions, diagrams, and other information to illustrate the requirements and operations of systems that are not covered by the Plumbing Code. Detail drawings for the complete plumbing system including piping layouts and locations of connections; dimensions for roughing-in, foundation, and support points; schematic diagrams and wiring diagrams or connection and interconnection diagrams. Detail drawings shall indicate clearances required for maintenance and operation. Where piping and equipment are to be supported other than as indicated, details shall include loadings and proposed support methods. Mechanical drawing plans, elevations, views, and details, shall be drawn to scale.

SD-03 Product Data

Fixtures

For the following equipment to be provided under this contract the contractor shall submit the manufacturer's standard catalog data, installation, operation and maintenance manuals:

Water closets; GA
Faucets and trim, all locations; GA
Utility sinks; GA
Water heaters; GA
Hose bibs and wall hydrants; GA
Backflow prevention assemblies; GA
Emergency eyewashes; GA
Shower Faucets; GA
Valves; GA

Drains and Cleanouts; GA
Pipe Insulation; GA
Propane Storage Tanks; GA
Welding; FIO

A copy of qualified procedures and a list of names and identification symbols of qualified welders and welding operators.

Vibration-Absorbing Features; FIO

Details of vibration-absorbing features, including arrangement, foundation plan, dimensions and specifications.

Plumbing System

Diagrams, instructions, and other sheets proposed for posting. Manufacturer's recommendations for the installation of bell and spigot and hubless joints for cast iron soil pipe.

SD-06 Test Reports

Tests, Flushing and Disinfection; FIO

Test reports in booklet form showing all field tests performed to adjust each component and all field tests performed to prove compliance with the specified performance criteria, completion and testing of the installed system. Each test report shall indicate the final position of controls.

Test of Backflow Prevention Assemblies; GA

Certification of proper operation shall be as accomplished in accordance with state regulations by an individual certified by the state to perform such tests. If no state requirement exists, the Contractor shall have the manufacturer's representative test the device, to ensure the unit is properly installed and performing as intended. The Contractor shall provide written documentation of the tests performed and signed by the individual performing the tests.

SD-07 Certificates

Materials and Equipment

Where equipment is specified to conform to requirements of the ASME Boiler and Pressure Vessel Code, the design, fabrication, and installation shall conform to the code.

Bolts

Written certification by the bolt manufacturer that the bolts furnished comply with the specified requirements.

SD-10 Operation and Maintenance Data

Valves, Faucets, Hydrants, and Fixtures - Submit Data Package 2 in accordance with Section 01 78 23 "OPERATION AND MAINTENANCE DATA".

Water Heaters - Submit Data Package 3 in accordance with Section 01 78 23 "OPERATION AND MAINTENANCE DATA".

1.3 STANDARD PRODUCTS

Specified materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacture of such products. Specified equipment shall essentially duplicate equipment that has performed satisfactorily at least two years prior to bid opening. Standard products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

1.3.1 Alternative Qualifications

Products having less than a two-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.3.2 Service Support

The equipment items shall be supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. These service organizations shall be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.3.3 Manufacturer's Nameplate

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.3.4 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.3.4.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions shall be considered mandatory, the word "should" shall be interpreted as "shall." Reference to the "code official" shall be interpreted to mean the "Contracting Officer." For Navy owned property, references to the "owner" shall be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" shall be interpreted to mean the "lessor." References to the "permit holder" shall be interpreted to mean the "Contractor."

1.3.4.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of

Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, shall be applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.4 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.5 PERFORMANCE REQUIREMENTS

1.5.1 Welding

Piping shall be welded in accordance with qualified procedures using performance-qualified welders and welding operators. Procedures and welders shall be qualified in accordance with ASME BPVC SEC IX. Welding procedures qualified by others, and welders and welding operators qualified by another employer, may be accepted as permitted by ASME B31.1. The Contracting Officer shall be notified 24 hours in advance of tests, and the tests shall be performed at the work site if practicable. Welders or welding operators shall apply their assigned symbols near each weld they make as a permanent record. Structural members shall be welded in accordance with Section 05 12 00 STRUCTURAL STEEL.

1.5.2 Cathodic Protection and Pipe Joint Bonding

Cathodic protection and pipe joint bonding systems shall be in accordance with paragraph 3.1.4.

1.5.3 Plumbing Fixtures

Water flow and consumption rates shall at a minimum comply with requirements in PL 102-486.

1.6 REGULATORY REQUIREMENTS

Unless otherwise required herein, plumbing work shall be in accordance with ICC IPC.

1.7 PROJECT/SITE CONDITIONS

The Contractor shall become familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.8 INSTRUCTION TO GOVERNMENT PERSONNEL

When specified in other sections, furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Instructors shall be thoroughly familiar with all parts of the installation and shall be trained in operating theory as well as practical operation and maintenance work.

Instruction shall be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.9 ACCESSIBILITY OF EQUIPMENT

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

PART 2 PRODUCTS

2.1 MATERIALS

Materials for various services shall be in accordance with TABLES I and II. PVC pipe shall contain a minimum of 25 percent recycled content, with a minimum of 15 percent post-consumer recycled content. Steel pipe shall contain a minimum of 25 percent recycled content, with a minimum of 16 percent post-consumer recycled content. Pipe schedules shall be selected based on service requirements. Pipe fittings shall be compatible with the applicable pipe materials. Plastic pipe, fittings, and solvent cement shall meet NSF 14 and shall be NSF listed for the service intended. Plastic pipe, fittings, and solvent cement used for potable hot and cold water service shall bear the NSF seal "NSF-PW." Pipe threads (except dry seal) shall conform to ASME B1.20.1. Grooved pipe couplings and fittings shall be from the same manufacturer. Material or equipment containing lead shall not be used in any potable water system. In line devices such as building valves, check valves, valves, fittings and back flow preventers shall comply with PL 93-523 and NSF 61, Section 8. End point devices such as lavatory faucets, supply stops and end point control valves used to dispense water for drinking must meet the requirements of NSF 61, Section 9. Hubless cast-iron soil pipe shall not be installed underground, under concrete floor slabs, or in crawl spaces below kitchen floors. Cast-iron pipe shall contain a minimum of 100 percent recycled content. Plastic pipe shall not be installed in air plenums. Plastic pipe shall not be installed in a pressure piping system in buildings greater than three stories including any basement levels.

2.1.1 Pipe Joint Materials

Grooved pipe and hubless cast-iron soil pipe shall not be used under ground. Solder containing lead shall not be used with copper pipe. Cast iron soil pipe and fittings shall be marked with the collective trademark of the Cast Iron Soil Institute. Joints and gasket materials shall conform to the following:

a. Coupling for Cast-Iron Pipe: for hub and spigot type ASTM A 74, AWWA C606. For hubless type: CISPI 310.

b. Coupling for Steel Pipe: AWWA C606.

c. Flange Gaskets: Gaskets shall be made of non-asbestos material in accordance with ASME B16.21. Gaskets shall be flat, 1.6 mm thick, and contain Aramid fibers bonded with Styrene Butadiene Rubber (SBR) or Nitro Butadiene Rubber (NBR). Gaskets shall be the full face or self centering flat ring type. Gaskets used for hydrocarbon service shall be bonded with NBR.

d. PTFE Tape: PTFE Tape, for use with Threaded Metal or Plastic Pipe.

e. Flexible Elastomeric Seals: ASTM D 3139, ASTM D 3212 or ASTM F 477.

f. Plastic Solvent Cement for PVC Plastic Pipe: ASTM D 2564 and ASTM D 2855.

g. Flanged fittings including flanges, bolts, nuts, bolt patterns, etc., shall be in accordance with ASME B16.5 class 150 and shall have the manufacturer's trademark affixed in accordance with MSS SP-25. Flange material shall conform to ASTM A 105/A 105M. Blind flange material shall conform to ASTM A 516/A 516M cold service and ASTM A 515/A 515M for hot service. Bolts shall be high strength or intermediate strength with material conforming to ASTM A 193/A 193M.

2.1.2 Miscellaneous Materials

Miscellaneous materials shall conform to the following:

a. Copper, Sheet and Strip for Building Construction: ASTM B 370.

b. Hose Clamps: SAE J1508.

c. Supports for Off-The-Floor Plumbing Fixtures: ASME A112.6.1M.

d. Metallic Cleanouts: ASME A112.36.2M.

e. Hypochlorites: AWWA B300.

f. Liquid Chlorine: AWWA B301.

g. Gauges - Pressure and Vacuum Indicating Dial Type - Elastic Element: ASME B40.100.

h. Thermometers: ASTM E 1. Mercury shall not be used in thermometers.

2.1.3 Pipe Insulation Material

Insulation shall be as specified in Section 22 07 19.00 40 PLUMBING PIPING INSULATION.

2.2 PIPE HANGERS, INSERTS, AND SUPPORTS

Pipe hangers, inserts, and supports shall conform to MSS SP-58 and MSS SP-69.

2.3 VALVES

Valves shall be provided on supplies to equipment and fixtures. Valves 65 mm and smaller shall be bronze with threaded bodies for pipe and

solder-type connections for tubing. Valves 80 mm and larger shall have flanged iron bodies and bronze trim. Pressure ratings shall be based upon the application. Grooved end valves may be provided if the manufacturer certifies that the valves meet the performance requirements of applicable MSS standard. Valves shall conform to the following standards:

Description	Standard
Butterfly Valves	MSS SP-67
Cast-Iron Gate Valves, Flanged and Threaded Ends	MSS SP-70
Cast-Iron Swing Check Valves, Flanged and Threaded Ends	MSS SP-71
Ball Valves with Flanged Butt-Welding Ends for General Service	MSS SP-72
Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends	MSS SP-110
Cast-Iron Plug Valves, Flanged and Threaded Ends	MSS SP-78
Steel Valves, Socket Welding and Threaded Ends	ASME B16.34
Cast-Iron Globe and Angle Valves, Flanged and Threaded Ends	MSS SP-85
Water Heater Drain Valves	ASSE 1005
Temperature and Pressure Relief Valves for Hot Water Supply Systems	ANSI Z21.22
Temperature and Pressure Relief Valves for Automatically Fired Hot Water Boilers	ASME CSD-1 Safety Code No. Part W, Article 5

2.3.1 Wall Faucets (HB-1)

Wall faucets with vacuum-breaker backflow preventer shall be brass with 20 mm male inlet threads, hexagon shoulder, and 20 mm hose connection. Faucet handle shall be securely attached to stem.

2.3.2 Wall Hydrants (Frostproof)(WH-1)

ASSE 1019 with vacuum-breaker backflow preventer shall have a nickel-brass or nickel-bronze wall plate or flange with nozzle and detachable key handle. A brass or bronze operating rod shall be provided within a galvanized iron casing of sufficient length to extend through the wall so that the valve is inside the building, and the portion of the hydrant between the outlet and valve is self-draining. A brass or bronze valve with coupling and union elbow having metal-to-metal seat shall be provided. Valve rod and seat washer shall be removable through the face of the hydrant. The hydrant shall have 20 mm exposed hose thread on spout and 20 mm male pipe thread on inlet.

2.3.3 Relief Valves

Water heaters shall have a combination pressure and temperature (P&T) relief valve. The pressure relief element of a P&T relief valve shall have adequate capacity to prevent excessive pressure buildup in the system when the system is operating at the maximum rate of heat input. The temperature element of a P&T relief valve shall have a relieving capacity which is at least equal to the total input of the heaters when operating at their maximum capacity. Relief valves shall be rated according to ANSI Z21.22. Relief valves for systems where the maximum rate of heat input is less than 59 kW (200,000 Btuh) shall have 20 mm minimum inlets, and 20 mm outlets. Relief valves for systems where the maximum rate of heat input is greater than 59 kW (200,000 Btuh) shall have 25 mm minimum inlets, and 25 mm outlets. The discharge pipe from the relief valve shall be the size of the valve outlet.

2.3.4 Thermostatic Mixing Valves

Provide thermostatic mixing valve for storage water heaters. Mixing valves, thermostatic type, pressure-balanced or combination thermostatic and pressure-balanced shall be line size and shall be constructed with rough or finish bodies either with or without plating. Each valve shall he constructed to control the mixing of hot and cold water and to deliver water at a desired temperature regardless of pressure or input temperature changes. The control element shall be of an approved type. The body shall be of heavy cast bronze, and interior parts shall be brass, bronze, corrosion-resisting steel or copper. The valve shall be equipped with necessary stops, check valves, unions, and sediment strainers on the inlets. Mixing valves shall maintain water temperature within 2 degrees C of any setting.

2.4 FIXTURES

Fixtures shall be water conservation type, in accordance with ICC IPC. Porcelain enameled ware shall have specially selected, clear white, acid-resisting enamel coating evenly applied on surfaces. No fixture will be accepted that shows cracks, crazes, blisters, thin spots, or other flaws. Fixtures shall be equipped with appurtenances such as traps, faucets, stop valves, and drain fittings. Each fixture and piece of equipment requiring connections to the drainage system shall be equipped with a trap. Brass expansion or toggle bolts capped with acorn nuts shall be provided for supports, and polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Internal parts of flush and/or flushometer valves, shower mixing valves, shower head face plates, pop-up stoppers of lavatory waste drains, may contain acetal resin, fluorocarbon, nylon, acrylonitrile-butadiene-styrene (ABS) or other plastic material, if the material has provided satisfactory service under actual commercial or industrial operating conditions for not less than 2 years. Plastic in contact with hot water shall be suitable for 82 degrees C (180 degrees F) water temperature.

The following plumbing fixtures shall be provided:

Eastern Water Closet (W-1) with low consumption (6.1 Liter/Flush) flush valve assembly. Provide acid resisting fired porcelain enameled cast iron water closet complete with rotating No-Hub 'P' trap and No-Hub coupling to meet piping requirements. Eastern Style water closet shall be furnished with integral non-skid foot pads and bowl wash down non-splashing flushing rim. The water closet shall be completely self supporting requiring no

external mounting hardware and shall be flush with floor. The Eastern Style water closet shall incorporate waterproofing membrane flashing flange. Provide a cold water spigot 300mm above finished floor on the right (from a perspective of standing inside of the cubicle and looking out) sidewall of the cubicle. Toilets shall be oriented north and south. Toilets shall not face east or west.

Lavatories (L-1). All sinks shall be trough type constructed of block and concrete with ceramic tile exterior and lining capable of withstanding abuse.

Lavatories (L-2). Enameled cast iron, wall mounted. Brass fittings provided for water supplies. Faucets shall be chrome plated brass single lever mixing type.

Shower (SH-1). Showerhead and faucet handles shall be copper alloy. Provide for manual mixing with hot and cold water valves. In addition to a shower head, provide each shower stall with a threaded faucet approximately 1.2 m AFF with hot and cold-water controls, mixing valve and a diverter type valve so water can be directed to either the shower or to the lower faucet. Diverter valve shall be factory made for this specific package, by the mixing valve manufacturer. Shower shall be provided with low (9.5 LPM) flow shower head. The shower head shall be surface mounted, heavy duty type and securely fastened to the wall. Shower pan membrane shall be "elastomeric sheet waterproofing membrane" as specified in section 07 13 53 ELASTOMERIC SHEET WATERPROOFING. Pans shall be field fabricated as indicated in section 22 00 00, Part 3 Execution.

Medical Clinic & DFAC:
Sink (S-1): Single bowl, wall mounted, type 302, 18-8, 18 gauge stainless steel, 559 mm x 495 mm x 190 mm deep, three (3) hole punching. Two (2) stainless steel wall support brackets, also wall hanger. Sound deadened. Chrome gooseneck faucet with rigid/swing, wrist blade handles, and aerator. Stainless steel drain and tailpiece assembly; P-trap; and stops.

DFAC Only:
Sink (S-2): Two (2) bowl kitchen sink, complete with trim, furnished and installed by Plumbing Contractor. Completely connected by this contractor.

Sink (S-3): Two (2) bowl kitchen sink, complete with trim, furnished and installed by Plumbing Contractor. Completely connected by this contractor.

Pot Wash (PW-1): Pot wash sink faucet, provide hot and cold water valves with manual mixing. Faucet handles shall be copper alloy.

Pot Fill (PF-1): Pot fill faucet, provide hot water valve. Wok style faucet, chrome plated. Completely connected by this contractor.

Emergency Eye and Face Wash Assembly (EW-1). Provide emergency eye and face wash assembly in facilities where appropriate. Provide a drain at each area. Emergency eye and face wash assembly shall be ISEA Z358.1, wall-mounted, self-cleaning, nonclogging eye and face wash with quick opening, full-flow valves, stainless steel eye and face wash receptor. Unit shall deliver 0.19 L/S of aerated water at 207 kPa (gage) flow pressure, with eye and face wash nozzles 838 to 1143 mm above finished floor. Provide copper alloy control valves. Provide an air-gap with the lowest potable eye and face wash water outlet located above the overflow rim by not less than the International Plumbing Code minimum.

Floor or Shower Drain (FD-1). Cast iron construction with galvanized body, integral seepage pan, and adjustable perforated or slotted chromium plated bronze, nickel-bronze, or nickel brass strainer consisting of a grate and threaded collar. Toilet room floor drains are similar except are provided with built-in, solid, hinged grate.

Funnel/Floor Drain (FD-2). Cast iron construction with galvanized body, with slotted cast iron gate. Drain shall be factory furnished with a cast iron oval funnel assembly, 229 mm diameter.

Trench Drain (TR-1). Cast iron construction with galvanized body, integral seepage and adjustable perforated or slotted chromium plated bronze, nickel-bronze, or nickel brass strainer consisting of a grate and threaded collar. This style of drain shall be employed in the kitchen area of the DFACs in response to kitchen cleaning practices of the local national staff. Also, access needs to be provided to the solids collector for routine emptying.

Room hose bibs and floor drains shall be provided as required. Afghan dining facility area clean-up hose bib (HB-2) to be supplied with connecting hose on reel including approximately 12 meters of hose. Provide clean-up spray nozzle on end of hose assembly.

Provide P-Traps per International Plumbing Code IPC for all fixture drains, floor and trench drains, and shower drains. P-traps shall have minimum of 50 mm water seal.

2.5 BACKFLOW PREVENTERS

Backflow preventers shall be approved and listed by the Foundation For Cross-Connection Control & Hydraulic Research. Reduced pressure principle assemblies, double check valve assemblies, atmospheric (nonpressure) type vacuum breakers, and pressure type vacuum breakers shall be tested, approved, and listed in accordance with FCCCHR Manual. Backflow preventers with intermediate atmospheric vent shall conform to ASSE 1012. Reduced pressure principle backflow preventers shall conform to ASSE 1013. Hose connection vacuum breakers shall conform to ASSE 1011. Pipe applied atmospheric type vacuum breakers shall conform to ASSE 1001. Pressure vacuum breaker assembly shall conform to ASSE 1020. Air gaps in plumbing systems shall conform to ASME A112.1.2.

2.6 TRAPS

Unless otherwise specified, traps shall be plastic per ASTM F 409. Traps shall be with a cleanout. Provide traps with removable access panels for easy clean-out at sinks and lavatories. Inlets shall have rubber washer and copper alloy nuts for slip joints above the discharge level. Swivel joints shall be below the discharge level and shall be of metal-to-metal or metal-to-plastic type as required for the application. Nuts shall have flats for wrench grip. Outlets shall have internal pipe thread, except that when required for the application, the outlets shall have sockets for solder-joint connections. The depth of the water seal shall be not less than 50 mm. The interior diameter shall be not more than 3.2 mm over or under the nominal size, and interior surfaces shall be reasonably smooth throughout.

2.7 WATER HEATERS

Water heater types and capacities shall be as indicated. Each water heater

shall have replaceable anodes. Each primary water heater shall have controls with an adjustable range that includes 32 to 71 degrees C. The thermal efficiencies and standby heat losses shall conform to TABLE III for each type of water heater specified. Plastic materials polyetherimide (PEI) and polyethersulfone (PES) are forbidden to be used for vent piping of combustion gases. A factory pre-charged expansion tank shall be installed on the cold water supply to each water heater. Expansion tanks shall be specifically designed for use on potable water systems and shall be rated for 93 degrees C water temperature and 1034 kPa working pressure. The expansion tank size and acceptance volume shall be as indicated.

2.7.1 Automatic Storage Type

Heaters shall be complete with control system, temperature gauge, and pressure gauge, and shall have ASME rated combination pressure and temperature relief valve.

2.7.1.1 Electric Type (HWH-1)

Electric type water heaters shall conform to UL 174 with dual heating elements. Each element shall be of KW noted. The elements shall be wired so that only one element can operate at a time. A phenolic resin coating shall be provided as specified herein.

2.7.2 Phenolic Resin Coatings

The phenolic resin coating shall be applied at coating manufacturer's factory. The coating shall be a product specifically intended for use on water heaters and shall be acceptable for use in potable water systems. Steel, copper, copper alloy, or stainless steel coatings shall be capable of withstanding temperatures up to 204 degrees C dry bulb; and meet the requirements of 21 CFR 175. The entire exterior surface shall be coated with three component phenolic resin coating system. The system shall consist of the following: wash primer, pigmented base coat, and the clear top coat. Immediate and final cure times and temperatures shall be as recommended by the coating manufacturer.

2.7.2.1 Sub Title

The wash primer shall be composed of a combination of polyvinyl butyral and a heat hardening phenolic resin. The weight per liter shall be between 0.8388 kg per liter minimum and 0.8867 kg per liter maximum.

2.7.2.2 Pigmented Base Coat

The pigmented baking phenolic base coat shall consist of heat hardening phenolic resins, suitable pigments of the earth type, and softening agents, and shall not contain drying oils or cellulose material. The weight per liter shall be between 1.2 kg per liter minimum and 1.3 kg per liter maximum. The non-volatile solids content shall be between 60 percent minimum and 64 percent maximum by weight.

2.7.2.3 Clear Top Coat

The clear non-pigmented baking phenolic top coat shall have a weight per liter of between 1.0 kg per liter minimum and 1.1 kg per liter maximum. The non-volatile solids content shall be between 48 percent minimum and 52 percent maximum by weight.

2.7.2.4 Certificate of Compliance

A certificate of compliance shall be submitted by the coating manufacturer that documents successful use of coating system under service conditions indicated on the drawings for a minimum of 2 years at three different locations, and that the coating material and application comply with the testing procedures outlined.

2.7.2.5 Test Panels

Steel test panel substrate shall be 0.607 mm in thickness. The panels shall be coated with one coat wash primer, then pigmented baking phenolic to a dry film thickness of 0.10 to 0.15 mm, then clear baking phenolic to a total dry film thickness of 0.13 to 0.18 mm. The panels shall then be subjected to the tests specified below:

a. Heat Test: Test panel shall be minimum 70 x 150 mm in size. A coated test panel shall show no cracking, flaking, or other failure after the panel has been tested in accordance with ASTM D 2485, with a furnace temperature of 204 degrees C.

b. Abrasion Test: A coated test panel shall show no more than a 40 milligram loss when tested in accordance with ASTM D 4060, utilizing a Tabor Abraser CS-17F wheel with a 1000 g weight for 1000 cycles.

c. Corrosion Test: A coated test panel shall show no corrosion after being subjected to a 500 hour salt spray test in accordance with ASTM B 117.

2.7.2.6 Hot Water Storage Tank

Hot-water storage tank shall be constructed by one manufacturer; ASME stamped for the working pressure, and shall have the National Board (ASME) registration. The tank shall be cement-lined or glass-lined steel type in accordance with AWWA D100. The heat loss shall conform to TABLE III as determined by the requirements of ASHRAE 90.1. Tank shall be equipped with a thermometer, conforming to ASTM E 1, Type I, Class 3, Range C, style and form as required for the installation, and with 7 inch scale. Thermometer shall have a separable socket suitable for a 3/4 inch tapped opening. Tank shall be equipped with a pressure gauge 6 inch minimum diameter face. Tank shall include a factory-insulated jacket, with an "R" value of not less than 14. Jacket shall be prime-coated steel or PVC. Storage tank capacity shall be as shown.

2.8 ELECTRICAL WORK

Provide electrical equipment specified complete with controls as specified herein and in Section 26 20 00, INTERIOR DISTRIBUTION SYSTEM. Provide internal wiring for components of packaged equipment as an integral part of the equipment.

Controllers shall have auxiliary contacts for use with the controls provided. Manual or automatic control and protective or signal devices required for the operation specified and any control wiring required for controls and devices specified, but not shown, shall be provided. For packaged equipment, the manufacturer shall provide controllers, including the required monitors and timed restart.

Power wiring and conduit for field installed equipment shall be provided

under and conform to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.9 MISCELLANEOUS PIPING ITEMS

2.9.1 Escutcheon Plates

Provide one piece or split hinge metal plates for piping entering floors, walls, and ceilings in exposed spaces. Provide chromium-plated on copper alloy plates or polished stainless steel finish in finished spaces. Provide paint finish on plates in unfinished spaces.

2.9.2 Pipe Sleeves

Provide where piping passes entirely through walls, ceilings, roofs, and floors. Secure sleeves in position and location during construction. Provide sleeves of sufficient length to pass through entire thickness of walls, ceilings, roofs, and floors. Provide 25 mm minimum clearance between exterior of piping or pipe insulation, and interior of sleeve or core-drilled hole. Firmly pack space with mineral wool insulation. Seal space at both ends of sleeve or core-drilled hole with plastic waterproof cement which will dry to a firm but pliable mass, or provide a mechanically adjustable segmented elastomeric seal. In fire walls and fire floors, seal both ends of sleeves or core-drilled holes with UL listed fill, void, or cavity material.

2.9.2.1 Sleeves in Masonry and Concrete

Provide steel pipe sleeves or schedule 40 PVC plastic pipe sleeves. Sleeves are not required where drain, waste, and vent (DWV) piping passes through concrete floor slabs located on grade. Core drilling of masonry and concrete may be provided in lieu of pipe sleeves when cavities in the core-drilled hole are completely grouted smooth.

2.9.3 Sleeves Not in Masonry and Concrete

Provide 26 gage galvanized steel sheet or PVC plastic pipe sleeves.

2.9.4 Pipe Hangers (Supports)

Provide MSS SP-58 and MSS SP-69, Type 1 with adjustable type steel support rods, except as specified or indicated otherwise. Attach to steel joists with Type 19 or 23 clamps and retaining straps. Attach to Steel W or S beams with Type 21, 28, 29, or 30 clamps. Attach to steel angles and vertical web steel channels with Type 20 clamp with beam clamp channel adapter. Attach to horizontal web steel channel and wood with drilled hole on centerline and double nut and washer. Attach to concrete with Type 18 insert or drilled expansion anchor. Provide Type 40 insulation protection shield for insulated piping.

2.9.5 Nameplates

Provide 3.2 mm thick melamine laminated plastic nameplates, black matte finish with white center core, for equipment, gages, thermometers, and valves; valves in supplies to faucets will not require nameplates. Accurately align lettering and engrave minimum of 6.4 mm high normal block lettering into the white core. Minimum size of nameplates shall be 25 by 63 mm. Key nameplates to a chart and schedule for each system. Frame charts and schedules under glass and place where directed near each

system. Furnish two copies of each chart and schedule.

2.10 SPARE PARTS

2.10.1 General Requirements

The contractor shall furnish to the Contracting Officer, fifteen per cent (15%) spare parts of total items installed, as directly coordinated with the Contracting Officer. Spare parts shall include such items as: faucets, flush valves, shower heads, shower mixing valves, hoses, hose valves, spray nozzles, wall hydrant and hose bibb components, backflow preventer parts of each type, fixture stops and traps, heater relief valves, internal valve components for each type of valve, hangers, pipe hammer arrestors, hose clamps, PVC solvent cement, pipe couplings, gaskets, flanges, nuts, bolts, faucet cartridges, pump bearings, pump micro switches, and floor drain and cleanout tops.

2.10.2 Itemizing and Tagging Spare Parts

All spare parts shall be itemized, tagged for future use, and stored by the contractor where directed by the Contracting Officer. Spare parts shall be handled, loaded, unloaded, and stored by the contractor. Final decision of spare part items shall be directly coordinated with the Contracting Officer.

2.11 PROPANE TANKS, PIPING, AND VALVES

Propane tanks (cylindrical bottles), piping, and valve installations shall be furnished and installed under this Contract, including sleeve vent piping, in accordance with NFPA 58. Provide standard tank regulating equipment for the bottles. Propane tanks shall be secured in such a manner that they do not move or topple over. The Project will require that the Contractor provide fuel tanks filled with propane fuel at time of completion.

The Contractor shall furnish and install propane gas piping/manifold from service entrance tank equipment to the various propane gas-consuming equipment shown. Make final connections to the tanks. Surface mounted piping shall not be susceptible to damage or cause any safety hazards. Piping passing through exterior walls shall be provided with pipe sleeves.

Propane tanks (bottles) shall be of number shown, 100 lb. (45 kilograms) steel construction, with automatic MIG/submerged arc welded gas containment welds. 100% leak tested before/after mechanical valve installation. Large collars, heavy duty footrings, and powder coated finish, free-of-scale interiors. Size of bottle, 1200 mm H. with 163 mm x 128 mm H. collar and 363 mm diameter footring (1238 mm H. overall with cap and flange); providing 89 liters LPG capacity. Manufactured to Department of Transportation specifications.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Piping located in air plenums shall conform to NFPA 90A requirements. Plastic pipe shall not be installed in air plenums. Piping located in shafts that constitute air ducts or that enclose air ducts shall be noncombustible in accordance with NFPA 90A. Installation of plastic pipe where in compliance with NFPA may be installed in accordance with PPFA-01. The plumbing system shall be installed complete with necessary fixtures,

fittings, traps, valves, and accessories. Water and drainage piping shall be extended 1.5 m outside the building, unless otherwise indicated. A ball valve and drain shall be installed on the water service line inside the building approximately 150 mm above the floor from point of entry. Piping shall be connected to the exterior service lines or capped or plugged if the exterior service is not in place. Sewer and water pipes shall be laid in separate trenches, except when otherwise shown. Exterior underground utilities shall be at least 300 mm below the average local frost depth or as indicated on the drawings. If trenches are closed or the pipes are otherwise covered before being connected to the service lines, the location of the end of each plumbing utility shall be marked with a stake or other acceptable means. Valves shall be installed with control no lower than the valve body.

3.1.1 Water Pipe, Fittings, and Connections

3.1.1.1 Utilities

The piping shall be extended to fixtures, outlets, and equipment. The hot-water and cold-water piping system shall be arranged and installed to permit draining. The supply line to each item of equipment or fixture, except faucets, flush valves, or other control valves which are supplied with integral stops, shall be equipped with a shutoff valve to enable isolation of the item for repair and maintenance without interfering with operation of other equipment or fixtures. Supply piping to fixtures, faucets, hydrants, shower heads, and flushing devices shall be anchored to prevent movement.

3.1.1.2 Cutting and Repairing

The work shall be carefully laid out in advance, and unnecessary cutting of construction shall be avoided. Damage to building, piping, wiring, or equipment as a result of cutting shall be repaired by mechanics skilled in the trade involved.

3.1.1.3 Protection of Fixtures, Materials, and Equipment

Pipe openings shall be closed with caps or plugs during installation. Fixtures and equipment shall be tightly covered and protected against dirt, water, chemicals, and mechanical injury. Upon completion of the work, the fixtures, materials, and equipment shall be thoroughly cleaned, adjusted, and operated. Safety guards shall be provided for exposed rotating equipment.

3.1.1.4 Mains, Branches, and Runouts

Piping shall be installed as indicated. Pipe shall be accurately cut and worked into place without springing or forcing. Structural portions of the building shall not be weakened. Aboveground piping shall run parallel with the lines of the building, unless otherwise indicated. Branch pipes from service lines may be taken from top, bottom, or side of main, using crossover fittings required by structural or installation conditions. Supply pipes, valves, and fittings shall be kept a sufficient distance from other work and other services to permit not less than 12 mm between finished covering on the different services. Bare and insulated water lines shall not bear directly against building structural elements so as to transmit sound to the structure or to prevent flexible movement of the lines. Water pipe shall not be buried in or under floors unless specifically indicated or approved. Changes in pipe sizes shall be made

with reducing fittings. Use of bushings will not be permitted except for use in situations in which standard factory fabricated components are furnished to accommodate specific accepted installation practice. Change in direction shall be made with fittings, except that bending of pipe 100 mm and smaller will be permitted, provided a pipe bender is used and wide sweep bends are formed. The center-line radius of bends shall be not less than six diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be acceptable.

3.1.1.5 Pipe Drains

Pipe drains indicated shall consist of 20 mm (3/4 inch) hose bibb with renewable seat and ball valve ahead of hose bibb. At other low points, 20 mm (3/4 inch) brass plugs or caps shall be provided. Disconnection of the supply piping at the fixture is an acceptable drain.

3.1.1.6 Expansion and Contraction of Piping

Allowance shall be made throughout for expansion and contraction of water pipe. Each hot-water riser shall have expansion loops or other provisions such as offsets, changes in direction, etc., where indicated and/or required. Risers shall be securely anchored as required or where indicated to force expansion to loops. Branch connections from risers shall be made with ample swing or offset to avoid undue strain on fittings or short pipe lengths. Horizontal runs of pipe over 15 m in length shall be anchored to the wall or the supporting construction about midway on the run to force expansion, evenly divided, toward the ends. Sufficient flexibility shall be provided on branch runouts from mains and risers to provide for expansion and contraction of piping. Flexibility shall be provided by installing one or more turns in the line so that piping will spring enough to allow for expansion without straining. If mechanical grooved pipe coupling systems are provided, the deviation from design requirements for expansion and contraction may be allowed pending approval of Contracting Officer.

3.1.1.7 Thrust Restraint

Plugs, caps, tees, valves and bends deflecting 11.25 degrees or more, either vertically or horizontally, in waterlines 100 mm in diameter or larger shall be provided with thrust blocks, to prevent movement. Thrust blocking shall be concrete of a mix not leaner than: 1 cement, 2-1/2 sand, 5 gravel; and having a compressive strength of not less than 14 MPa after 28 days. Blocking shall be placed between solid ground and the fitting to be anchored. The base and thrust bearing sides of the thrust block shall be poured against undisturbed earth. The side of the thrust block not subject to thrust shall be poured against forms. The area of bearing will be as shown. Blocking shall be placed so that the joints of the fitting are accessible for repair. Steel rods and clamps, protected by galvanizing or by coating with bituminous paint, shall be used to anchor vertical down bends into gravity thrust blocks.

3.1.2 Joints

Installation of pipe and fittings shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints shall be made up with fittings of compatible material and made for the specific purpose intended.

3.1.2.1 Threaded

Threaded joints shall have American Standard taper pipe threads conforming to ASME B1.20.1. Only male pipe threads shall be coated with graphite or with an approved graphite compound, or with an inert filler and oil, or shall have a polytetrafluoroethylene tape applied.

3.1.2.2 Unions and Flanges

Unions, flanges and mechanical couplings shall not be concealed in walls, ceilings, or partitions. Unions shall be used on pipe sizes 65 mm and smaller; flanges shall be used on pipe sizes 80 mm and larger.

3.1.2.3 Cast Iron Soil, Waste and Vent Pipe

Bell and spigot compression and hubless gasketed clamp joints for soil, waste and vent piping shall be installed per the manufacturer's recommendations.

3.1.2.4 Plastic Pipe

PVC pipe shall have joints made with solvent cement elastomeric, threading, (threading of Schedule 80 Pipe is allowed only where required for disconnection and inspection; threading of Schedule 40 Pipe is not allowed), or mated flanged.

3.1.3 Dissimilar Pipe Materials

Connections between ferrous and non-ferrous copper water pipe shall be made with dielectric unions or flange waterways. Dielectric waterways shall have temperature and pressure rating equal to or greater than that specified for the connecting piping. Waterways shall have metal connections on both ends suited to match connecting piping. Dielectric waterways shall be internally lined with an insulator specifically designed to prevent current flow between dissimilar metals. Dielectric flanges shall meet the performance requirements described herein for dielectric waterways. Connecting joints between plastic and metallic pipe shall be made with transition fitting for the specific purpose.

3.1.4 Corrosion Protection for Buried Pipe and Fittings

Ductile iron, cast iron, and steel pipe, fittings, and joints shall have a protective coating. Additionally, ductile iron, cast iron, and steel pressure pipe shall have a cathodic protection system and joint bonding. Coatings shall be selected, applied, and inspected in accordance with NACE RP0169 and as otherwise specified. The pipe shall be cleaned and the coating system applied prior to pipe tightness testing. Joints and fittings shall be cleaned and the coating system applied after pipe tightness testing. For tape coating systems, the tape shall conform to AWWA C203 and shall be applied with a 50 percent overlap. Primer utilized with tape type coating systems shall be as recommended by the tape manufacturer.

3.1.5 Pipe Sleeves and Flashing

Pipe sleeves shall be furnished and set in their proper and permanent location.

3.1.5.1 Sleeve Requirements

Pipes passing through concrete or masonry walls or concrete floors or roofs shall be provided with pipe sleeves fitted into place at the time of construction. Sleeves are not required for supply, drainage, waste and vent pipe passing through concrete slab on grade, except where penetrating a membrane waterproof floor. A modular mechanical type sealing assembly may be installed in lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve. The seals shall consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe and sleeve using galvanized steel bolts, nuts, and pressure plates. The links shall be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tightening of the bolt shall cause the rubber sealing elements to expand and provide a watertight seal between the pipe and the sleeve. Each seal assembly shall be sized as recommended by the manufacturer to fit the pipe and sleeve involved. Sleeves shall not be installed in structural members, except where indicated or approved. Rectangular and square openings shall be as detailed. Each sleeve shall extend through its respective floor, or roof, and shall be cut flush with each surface, except for special circumstances. Pipe sleeves passing through floors in wet areas such as mechanical equipment rooms, lavatories, kitchens, and other plumbing fixture areas shall extend a minimum of 100 mm above the finished floor. Unless otherwise indicated, sleeves shall be of a size to provide a minimum of 6 mm clearance between bare pipe or insulation and inside of sleeve or between insulation and inside of sleeve. Sleeves in bearing walls and concrete slab on grade floors shall be steel pipe or cast-iron pipe. Sleeves in nonbearing walls or ceilings may be steel pipe, cast-iron pipe, galvanized sheet metal with lock-type longitudinal seam, or plastic. Except as otherwise specified, the annular space between pipe and sleeve, or between jacket over insulation and sleeve, shall be sealed as indicated with sealants conforming to ASTM C 920 and with a primer, backstop material and surface preparation as specified in Section 07 92 00 JOINT SEALANTS. The annular space between pipe and sleeve, between bare insulation and sleeve or between jacket over insulation and sleeve shall not be sealed for interior walls which are not designated as fire rated. Sleeves through below-grade walls in contact with earth shall be recessed 12 mm from wall surfaces on both sides. Annular space between pipe and sleeve shall be filled with backing material and sealants in the joint between the pipe and concrete or masonry wall as specified above. Sealant selected for the earth side of the wall shall be compatible with dampproofing/waterproofing materials that are to be applied over the joint sealant. Pipe sleeves in fire-rated walls shall conform to the requirements in Section 07 84 00 FIRESTOPPING.

3.1.5.2 Flashing Requirements

Pipes passing through roof shall be installed through a 4.9 kg per square meter copper flashing, each within an integral skirt or flange. Flashing shall be suitably formed, and the skirt or flange shall extend not less than 200 mm from the pipe and shall be set over the roof or floor membrane in a solid coating of bituminous cement. The flashing shall extend up the pipe a minimum of 250 mm. For cleanouts, the flashing shall be turned down into the hub and caulked after placing the ferrule. Pipes passing through pitched roofs shall be flashed, using lead or copper flashing, with an adjustable integral flange of adequate size to extend not less than 200 mm from the pipe in all directions and lapped into the roofing to provide a watertight seal. The annular space between the flashing and the bare pipe

or between the flashing and the metal-jacket-covered insulation shall be sealed. Flashing for dry vents shall be turned down into the pipe to form a waterproof joint. Pipes, up to and including 250 mm in diameter, passing through roof or floor waterproofing membrane may be installed through a cast-iron sleeve with caulking recess, anchor lugs, flashing-clamp device, and pressure ring with brass bolts. Flashing shield shall be fitted into the sleeve clamping device. Pipes passing through wall waterproofing membrane shall be sleeved as described above. A waterproofing clamping flange shall be installed.

3.1.5.3 Waterproofing

Waterproofing at floor-mounted water closets shall be accomplished by forming a flashing guard from soft-tempered sheet copper. The center of the sheet shall be perforated and turned down approximately 40 mm to fit between the outside diameter of the drainpipe and the inside diameter of the cast-iron or steel pipe sleeve. The turned-down portion of the flashing guard shall be embedded in sealant to a depth of approximately 40 mm; then the sealant shall be finished off flush to floor level between the flashing guard and drainpipe. The flashing guard of sheet copper shall extend not less than 200 mm from the drainpipe and shall be lapped between the floor membrane in a solid coating of bituminous cement. If cast-iron water closet floor flanges are used, the space between the pipe sleeve and drainpipe shall be sealed with sealant and the flashing guard shall be upturned approximately 40 mm to fit the outside diameter of the drainpipe and the inside diameter of the water closet floor flange. The upturned portion of the sheet fitted into the floor flange shall be sealed.

3.1.5.4 Optional Counterflashing

Instead of turning the flashing down into a dry vent pipe, or caulking and sealing the annular space between the pipe and flashing or metal-jacket-covered insulation and flashing, counterflashing may be accomplished by utilizing the following:

a. A standard roof coupling for threaded pipe up to 150 mm in diameter.

b. A tack-welded or banded-metal rain shield around the pipe.

3.1.5.5 Pipe Penetrations of Slab on Grade Floors

Where pipes, fixture drains, floor drains, cleanouts or similar items penetrate slab on grade floors, except at penetrations of floors with waterproofing membrane as specified in paragraphs Flashing Requirements and Waterproofing, a groove 6 to 13 mm wide by 6 to 10 mm deep shall be formed around the pipe, fitting or drain. The groove shall be filled with a sealant as specified in Section 07 92 00 JOINT SEALANTS.

3.1.5.6 Pipe Penetrations

Provide sealants for all pipe penetrations. All pipe penetrations shall be sealed to prevent infiltration of air, insects, and vermin.

3.1.6 Fire Seal

Where pipes pass through fire walls, fire-partitions, fire-rated pipe chase walls or floors above grade, a fire seal shall be provided as specified in Section 07 84 00 FIRESTOPPING.

3.1.7 Supports

3.1.7.1 General

Hangers used to support piping 50 mm and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors shall be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures shall be supported by variable spring hangers and supports or by constant support hangers. In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support members shall not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run. Threaded sections of rods shall not be formed or bent.

3.1.7.2 Pipe Supports and Structural Bracing, Seismic Requirements

Piping and attached valves shall be supported and braced to resist seismic loads. Design for vibration isolation using NEBB TABLES, NEBB Procedural Standards ASHRAE-05, Chapter 42, as applicable. Structural steel required for reinforcement to properly support piping, headers, and equipment, but not shown, shall be provided. Material used for supports shall be as specified in Section 05 12 00 STRUCTURAL STEEL.

Pipe Vibration Isolation

Isolators shall be devices with contained chloroprene-elastomer elements for connecting to building-structure attachments. Devices shall be loaded by supported system during operating conditions to produce a minimum elastomer static deflection of 10 millimeter.

3.1.7.3 Pipe Hangers, Inserts, and Supports

Installation of pipe hangers, inserts and supports shall conform to MSS SP-58 and MSS SP-69, except as modified herein.

a. Types 5, 12, and 26 shall not be used.

b. Type 3 shall not be used on insulated pipe.

c. Type 18 inserts shall be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustment may be used if they otherwise meet the requirements for type 18 inserts.

d. Type 19 and 23 C-clamps shall be torqued per MSS SP-69 and shall have both locknuts and retaining devices furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.

e. Type 20 attachments used on angles and channels shall be furnished with an added malleable-iron heel plate or adapter.

f. Type 24 may be used only on trapeze hanger systems or on fabricated frames.

g. Type 39 saddles shall be used on insulated pipe 100 mm and larger when the temperature of the medium is 15 degrees C or higher. Type 39

saddles shall be welded to the pipe.

h. Type 40 shields shall:

(1) Be used on insulated pipe less than 100 mm.

(2) Be used on insulated pipe 100 mm and larger when the temperature of the medium is 15 degrees C or less.

(3) Have a high density insert for all pipe sizes. High density inserts shall have a density of 128 kg per cubic meter (8 pcf) or greater.

i. Horizontal pipe supports shall be spaced as specified in MSS SP-69 and a support shall be installed not over 300 mm from the pipe fitting joint at each change in direction of the piping. Pipe supports shall be spaced not over 1.5 m apart at valves. Operating temperatures in determining hanger spacing for PVC pipe shall be 49 degrees C for PVC. Horizontal pipe runs shall include allowances for expansion and contraction.

j. Vertical pipe shall be supported at each floor, except at slab-on-grade, at intervals of not more than 4.5 m nor more than 2 m from end of risers, and at vent terminations. Vertical pipe risers shall include allowances for expansion and contraction.

k. Type 35 guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided to allow longitudinal pipe movement. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered. Lateral restraints shall be provided as needed. Where steel slides do not require provisions for lateral restraint the following may be used:

(1) On pipe 100 mm and larger when the temperature of the medium is 15 degrees C or higher, a Type 39 saddle, welded to the pipe, may freely rest on a steel plate.

(2) On pipe less than 100 mm a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.

(3) On pipe 100 mm and larger carrying medium less that 15 degrees C a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.

l. Pipe hangers on horizontal insulated pipe shall be the size of the outside diameter of the insulation. The insulation shall be continuous through the hanger on all pipe sizes and applications.

m. Where there are high system temperatures and welding to piping is not desirable, the type 35 guide shall include a pipe cradle, welded to the guide structure and strapped securely to the pipe. The pipe shall be separated from the slide material by at least 100 mm or by an amount adequate for the insulation, whichever is greater.

n. Hangers and supports for plastic pipe shall not compress, distort, cut or abrade the piping, and shall allow free movement of pipe except where otherwise required in the control of expansion/contraction.

3.1.7.4 Structural Attachments

Attachment to building structure concrete and masonry shall be by cast-in concrete inserts, built-in anchors, or masonry anchor devices. Inserts and anchors shall be applied with a safety factor not less than 5. Supports shall not be attached to metal decking. Supports shall not be attached to the underside of concrete filled floor or concrete roof decks unless approved by the Contracting Officer. Masonry anchors for overhead applications shall be constructed of ferrous materials only.

3.1.8 Welded Installation

Plumbing pipe weldments shall be as indicated. Changes in direction of piping shall be made with welding fittings only; mitering or notching pipe to form elbows and tees or other similar type construction will not be permitted. Branch connection may be made with either welding tees or forged branch outlet fittings. Branch outlet fittings shall be forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Beveling, alignment, heat treatment, and inspection of weld shall conform to ASME B31.1. Weld defects shall be removed and repairs made to the weld, or the weld joints shall be entirely removed and rewelded. After filler metal has been removed from its original package, it shall be protected or stored so that its characteristics or welding properties are not affected. Electrodes that have been wetted or that have lost any of their coating shall not be used.

3.1.9 Pipe Cleanouts

Pipe cleanouts shall be the same size as the pipe except that cleanout plugs larger than 100 mm will not be required. A cleanout installed in connection with cast-iron soil pipe shall consist of a long-sweep 1/4 bend or one or two 1/8 bends extended to the place shown. An extra-heavy cast-brass or cast-iron ferrule with countersunk cast-brass head screw plug shall be caulked into the hub of the fitting and shall be flush with the floor. Cleanouts in connection with other pipe, where indicated, shall be T-pattern, 90-degree branch drainage fittings with cast-brass screw plugs, except plastic plugs shall be installed in plastic pipe. Plugs shall be the same size as the pipe up to and including 100 mm. Cleanout tee branches with screw plug shall be installed at the foot of soil and waste stacks, and on each building drain outside the building. Cleanout tee branches may be omitted on stacks in single story buildings with slab-on-grade construction or where less than 450 mm of crawl space is provided under the floor. Cleanouts on pipe concealed in partitions shall be provided with chromium plated bronze, nickel bronze, nickel brass or stainless steel flush type access cover plates. Round access covers shall be provided and secured to plugs with securing screw. Square access covers may be provided with matching frames, anchoring lugs and cover screws. Cleanouts in finished walls shall have access covers and frames installed flush with the finished wall. Cleanouts installed in finished floors subject to foot traffic shall be provided with a chrome-plated cast brass, nickel brass, or nickel bronze cover secured to the plug or cover frame and set flush with the finished floor. Heads of fastening screws shall not project above the cover surface. Where cleanouts are provided with adjustable heads, the heads shall be cast iron.

3.2 WATER HEATERS

3.2.1 Relief Valves

No valves shall be installed between a relief valve and its water heater. The P&T relief valve shall be installed where the valve actuator comes in contact with the hottest water in the heater. Whenever possible, the relief valve shall be installed directly in a tapping in the tank or heater; otherwise, the P&T valve shall be installed in the hot-water outlet piping. A vacuum relief valve shall be provided on the cold water supply line to the water heater and mounted above and within 150 mm above the top of the water heater.

3.2.2 Installation of Electric Water Heaters

Shall conform to the National Electrical Code Standards.

3.2.3 Phenolic Resin Application Process

The phenolic resin coating shall be applied at the coating manufacturer's factory. The exterior surface shall be coated with the three-component coating system in the following sequence and manner. For immediate and final cure times and temperature, the recommendations of the coating manufacturer shall be followed.

a. Wash Primer. One coat of wash primer shall be applied by flooding.

b. Pigmented Base Coat. Pigmented baking phenolic coating shall be applied in several coats by immersion or flooding to a dry film thickness of 0.10 to 0.15 mm.

c. Clear Top Coat. Clear non-pigmented baking phenolic top coat shall be applied in several coats by immersion or flooding. The final coat may be applied by spraying. The dry film thickness of the total coating system shall be between 0.13 and 0.18 mm.

3.2.4 Heat Traps

Piping to and from each water heater shall be routed horizontally and downward a minimum of 600 mm before turning in an upward direction.

3.2.5 Connections to Water Heaters

Connections of metallic pipe to water heaters shall be made with dielectric unions or flanges.

3.2.6 Expansion Tanks

A pre-charged expansion tank shall be installed on the cold water supply between each water heater inlet and the cold water supply shut-off valve. The Contractor shall adjust the expansion tank air pressure, as recommended by the tank manufacturer, to match incoming water pressure. Valve inlet to each tank.

3.3 FIXTURES AND FIXTURE TRIMMINGS

Polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Angle stops, straight stops, stops integral with the faucets, or concealed type of lock-shield, and loose-key pattern stops for

supplies with threaded, sweat or solvent weld inlets shall be furnished and installed with fixtures. Where connections between copper tubing and faucets are made by rubber compression fittings, a beading tool shall be used to mechanically deform the tubing above the compression fitting. Exposed traps and supply pipes for fixtures and equipment shall be connected to the rough piping systems at the wall, unless otherwise specified under the item. Floor and wall escutcheons shall be as specified. Plumbing fixtures and accessories shall be installed within the space shown.

3.3.1 Fixture Connections

Where space limitations prohibit standard fittings in conjunction with the cast-iron floor flange, special short-radius fittings shall be provided. Connections between earthenware fixtures and flanges on soil pipe shall be made gastight and watertight with a closet-setting compound or neoprene gasket and seal. Use of natural rubber gaskets or putty will not be permitted. Fixtures with outlet flanges shall be set the proper distance from floor or wall to make a first-class joint with the closet-setting compound or gasket and fixture used.

3.3.2 Flushometer Valves

Flushometer valves shall be secured to prevent movement by anchoring the long finished top spud connecting tube to wall adjacent to valve with approved metal bracket. Flushometer valves for water closets shall be installed 1 m above the floor as directed by the Contracting Officer.

3.3.3 Height of Fixture Rims Above Floor

Lavatories and treatment sinks shall be mounted with rim 775 mm above finished floor. Wall-hung utility sinks shall be mounted with rim 700 mm above the floor.

3.3.4 Shower Bath Outfits

The area around the water supply piping to the mixing valves and behind the escutcheon plate shall be made watertight by caulking or gasketing.

3.3.5 Fixture Supports

Fixture supports for off-the-floor lavatories and other fixtures of similar size, design, and use, shall be of the chair-carrier type. The carrier shall provide the necessary means of mounting the fixture, with a foot or feet to anchor the assembly to the floor slab. Adjustability shall be provided to locate the fixture at the desired height and in proper relation to the wall. Support plates, in lieu of chair carrier, shall be fastened to the wall structure only where it is not possible to anchor a floor-mounted chair carrier to the floor slab.

3.3.5.1 Support for Solid Masonry Construction

Chair carrier shall be anchored to the floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate shall be imbedded in the masonry wall.

3.3.5.2 Support for Concrete-Masonry Wall Construction

Chair carrier shall be anchored to floor slab. Where a floor-anchored

chair carrier cannot be used, a suitable wall plate shall be fastened to the concrete wall using through bolts and a back-up plate.

3.3.6 Backflow Prevention Devices

Plumbing fixtures, equipment, and pipe connections shall not cross connect or interconnect between a potable water supply and any source of nonpotable water. Backflow preventers shall be installed where indicated and in accordance with ICC IPC at all other locations necessary to preclude a cross-connect or interconnect between a potable water supply and any nonpotable substance. In addition backflow preventers shall be installed at all locations where the potable water outlet is below the flood level of the equipment, or where the potable water outlet will be located below the level of the nonpotable substance. Backflow preventers shall be located so that no part of the device will be submerged. Backflow preventers shall be of sufficient size to allow unrestricted flow of water to the equipment, and preclude the backflow of any nonpotable substance into the potable water system. Bypass piping shall not be provided around backflow preventers. Access shall be provided for maintenance and testing. Each device shall be a standard commercial unit.

3.3.7 Access Panels

Access panels shall be provided for concealed valves and controls, or any item requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced, maintained, or replaced. Access panels shall be as specified in Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS.

3.3.8 Sight Drains

Sight drains shall be installed so that the indirect waste will terminate 50 mm above the flood rim of the funnel to provide an acceptable air gap.

3.3.9 Traps

Each trap shall be placed as near the fixture as possible, and no fixture shall be double-trapped. Traps installed on cast-iron soil pipe shall be cast iron. Traps installed on steel pipe shall be recess-drainage pattern, or brass-tube type. Traps installed on plastic pipe may be plastic conforming to ASTM D 3311.

3.3.10 Shower Pans

3.3.10.1 General

The floor of each individual shower, the shower-area portion of combination shower and drying room, and the entire shower and drying room where the two are not separated by curb or partition, shall be made watertight with a shower pan fabricated in place. The shower pan material shall be cut to size and shape of the area indicated, in one piece to the maximum extent practicable, allowing a minimum of 150 mm for turnup on walls or partitions, and shall be folded over the curb with an approximate return of 1/4 of curb height. The upstands shall be placed behind any wall or partition finish. Subflooring shall be smooth and clean, with nailheads driven flush with surface, and shall be sloped to drain. Shower pans shall be clamped to drains with the drain clamping ring.

3.3.10.2 Nonplasticized Polyvinyl Chloride (PVC) Shower Pans

Nonplasticized PVC shall be turned up behind walls or wall surfaces a distance of not less than 150 mm in room areas and 75 mm above curb level in curbed spaces with sufficient material to fold over and fasten to outside face of curb. Corners shall be pig-ear type and folded between pan and studs. Only top 25 mm of upstand shall be nailed to hold in place. Nails shall be galvanized large-head roofing type. Approved duct tape shall be used on metal framing or studs to secure pig-ear fold and membrane. Where no backing is provided between studs, the membrane slack shall be taken up by pleating and stapling or nailing to studding at top inch of upstand. To adhere the membrane to vertical surfaces, the back of the membrane and the surface to which it is to be applied shall be coated with adhesive that becomes dry to the touch in 5 to 10 minutes, after which the membrane shall be pressed into place. Trim for drain shall be exactly the size of drain opening. Bolt holes shall be pierced to accommodate bolts with a tight fit. Adhesive shall be used between pan and subdrain. Clamping ring shall be bolted firmly. A small amount of gravel or porous materials shall be placed at weepholes so that holes remain clear when setting bed is poured. Membrane shall be solvent welded with PVC solvent cement. Surfaces to be solvent welded shall be clean (free of grease and grime). Sheets shall be laid on a flat surface with an overlap of about 50 mm. Top edge shall be folded back and surface primed with a PVC primer. PVC cement shall be applied and surfaces immediately placed together, while still wet. Joint shall be lightly rolled with a paint roller, then as the joint sets shall be rolled firmly but not so hard as to distort the material. In long lengths, about 600 or 900 mm at a time shall be welded. On wood subflooring, two layers of 0.73 kg per square meter (15 pound) felt shall be installed prior to installation of shower pan to ensure a smooth surface installation.

3.4 VIBRATION-ABSORBING FEATURES

Mechanical equipment, shall be isolated from the building structure by approved vibration-absorbing features, unless otherwise shown.

3.5 IDENTIFICATION SYSTEMS

3.5.1 Identification Tags

Identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and valve number shall be installed on valves, except those valves installed on supplies at plumbing fixtures. Tags shall be 35 mm minimum diameter, and marking shall be stamped or engraved. Indentations shall be black, for reading clarity. Tags shall be attached to valves with No. 12 AWG, copper wire, chrome-plated beaded chain, or plastic straps designed for that purpose.

3.5.2 Pipe Color Code Marking

Color code marking of piping shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.5.3 Color Coding Scheme for Locating Hidden Utility Components

Scheme shall be provided in buildings having suspended grid ceilings. The color coding scheme shall identify points of access for maintenance and operation of operable components which are not visible from the finished space and installed in the space directly above the suspended grid ceiling.

The operable components shall include valves, dampers, switches, linkages and thermostats. The color coding scheme shall consist of a color code board and colored metal disks. Each colored metal disk shall be approximately 12 mm in diameter and secured to removable ceiling panels with fasteners. The fasteners shall be inserted into the ceiling panels so that the fasteners will be concealed from view. The fasteners shall be manually removable without tools and shall not separate from the ceiling panels when panels are dropped from ceiling height. Installation of colored metal disks shall follow completion of the finished surface on which the disks are to be fastened. The color code board shall have the approximate dimensions of 1 m width, 750 mm height, and 12 mm thickness. The board shall be made of wood fiberboard and framed under glass or 1.6 mm transparent plastic cover. Unless otherwise directed, the color code symbols shall be approximately 20 mm in diameter and the related lettering in 12 mm high capital letters. The color code board shall be mounted and located in the mechanical or equipment room. The color code system shall be as shown.

3.6 ESCUTCHEONS

Escutcheons shall be provided at finished surfaces where bare or insulated piping, exposed to view, passes through floors, walls, or ceilings, except in boiler, utility, or equipment rooms. Escutcheons shall be fastened securely to pipe or pipe covering and shall be satin-finish, corrosion-resisting steel, polished chromium-plated zinc alloy, or polished chromium-plated copper alloy. Escutcheons shall be either one-piece or split-pattern, held in place by internal spring tension or setscrew.

3.7 PAINTING

Painting of pipes, hangers, supports, and other iron work, either in concealed spaces or exposed spaces, is specified in Section 09 90 00 PAINTS AND COATINGS.

3.7.1 PAINTING OF NEW EQUIPMENT

New equipment painting shall be factory applied or shop applied, and shall be as specified herein, and provided under each individual section.

3.7.1.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors shall withstand 500 hours in a salt-spray fog test. Salt-spray fog test shall be in accordance with ASTM B 117, and for that test the acceptance criteria shall be as follows: immediately after completion of the test, the paint shall show no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen shall show no signs of rust creepage beyond 3 mm on either side of the scratch mark.

The film thickness of the factory painting system applied on the equipment shall not be less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 50 degrees C, the factory painting system shall be designed for the temperature service.

3.7.1.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 50 degrees C shall be cleaned to bare metal.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat shall be aluminum or light gray.

a. Temperatures Less Than 50 Degrees C: Immediately after cleaning, the metal surfaces subject to temperatures less than 50 degrees C shall receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.0076 mm, one coat of primer applied to a minimum dry film thickness of 0.0255 mm; and two coats of enamel applied to a minimum dry film thickness of 0.0255 mm per coat.

b. Temperatures Between 50 and 205 Degrees C: Metal surfaces subject to temperatures between 50 and 205 degrees C shall receive two coats of 205 degrees C heat-resisting enamel applied to a total minimum thickness of 0.05 mm.

c. Temperatures Greater Than 205 Degrees C: Metal surfaces subject to temperatures greater than 205 degrees C shall receive two coats of 315 degrees C heat-resisting paint applied to a total minimum dry film thickness of 0.05 mm.

3.8 TESTS, FLUSHING AND DISINFECTION

3.8.1 Plumbing System

The following tests shall be performed on the plumbing system in accordance with ICC IPC except that the drainage and vent system final test shall include the smoke test. The Contractor has the option to perform a peppermint test in lieu of the smoke test. If a peppermint test is chosen, the Contractor must submit a testing procedure to the Contracting Officer for approval.

a. Drainage and Vent Systems Tests. The final test shall include a smoke test.

b. Building Sewers Tests.

c. Water Supply Systems Tests.

e. Propane Gas Supply, Sleeve, and Vent Systems Tests.

3.8.1.1 Test of Backflow Prevention Assemblies

Backflow prevention assembly shall be tested using gauges specifically designed for the testing of backflow prevention assemblies. Gauges shall be tested annually for accuracy in accordance with the University of Southern California's Foundation of Cross Connection Control and Hydraulic Research or the American Water Works Association Manual of Cross Connection (Manual M-14). Report form for each assembly shall include, as a minimum,

the following:

Data on Device	Data on Testing Firm
Type of Assembly	Name
Manufacturer	Address
Model Number	Certified Tester
Serial Number	Certified Tester No.
Size	Date of Test
Location	
Test Pressure Readings	Serial Number and Test Data of Gauges

If the unit fails to meet specified requirements, the unit shall be repaired and retested.

3.8.1.2 Shower Pans

After installation of the pan and finished floor, the drain shall be temporarily plugged below the weep holes. The floor area shall be flooded with water to a minimum depth of 25 mm for a period of 24 hours. Any drop in the water level during test, except for evaporation, will be reason for rejection, repair, and retest.

3.8.1.3 Eastern Toilet Pans

After installation of the pan and finished floor, the toilet drain outlet shall be temporarily plugged and floor area flooded as described for shower pans, with rejection, repair, or retest as a result in water level drop as described for shower pans.

3.8.2 Defective Work

If inspection or test shows defects, such defective work or material shall be replaced or repaired as necessary and inspection and tests shall be repeated. Repairs to piping shall be made with new materials. Caulking of screwed joints or holes will not be acceptable.

3.8.3 System Flushing

3.8.3.1 During Flushing

Before operational tests or disinfection, potable water piping system shall be flushed with potable water. Sufficient water shall be used to produce a water velocity that is capable of entraining and removing debris in all portions of the piping system. This requires simultaneous operation of all fixtures on a common branch or main in order to produce a flushing velocity of approximately 1.2 meters per second (4 fps) through all portions of the piping system. In the event that this is impossible due to size of system, the Contracting Officer (or the designated representative) shall specify the number of fixtures to be operated during flushing. Contractor shall provide adequate personnel to monitor the flushing operation and to ensure that drain lines are unobstructed in order to prevent flooding of the facility. Contractor shall be responsible for any flood damage resulting from flushing of the system. Flushing shall be continued until entrained dirt and other foreign materials have been removed and until discharge water shows no discoloration. All faucets and drinking water fountains, to include any device considered as an end point device by NSF 61, Section 9, shall be flushed a minimum of 1 L per 24 hour period, ten times over a 14 day period.

3.8.3.2 After Flushing

System shall be drained at low points. Strainer screens shall be removed, cleaned, and replaced. After flushing and cleaning, systems shall be prepared for testing by immediately filling water piping with clean, fresh potable water. Any stoppage, discoloration, or other damage to the finish, furnishings, or parts of the building due to the Contractor's failure to properly clean the piping system shall be repaired by the Contractor. When the system flushing is complete, the hot-water system shall be adjusted for uniform circulation. Flushing devices and automatic control systems shall be adjusted for proper operation according to manufacturer's instructions. Comply with ASHRAE 90.1 - SI for minimum efficiency requirements.Lead levels shall not exceed limits established by 40 CFR 50.12 Part 141.80(c)(1). The water supply to the building shall be tested separately to ensure that any lead contamination found during potable water system testing is due to work being performed inside the building.

3.8.4 Operational Test

Upon completion of flushing and prior to disinfection procedures, the Contractor shall subject the plumbing system to operating tests to demonstrate satisfactory installation, connections, adjustments, and functional and operational efficiency. Such operating tests shall cover a period of not less than 8 hours for each system and shall include the following information in a report with conclusion as to the adequacy of the system:

a. Time, date, and duration of test.

b. Water pressures at the most remote and the highest fixtures.

c. Operation of each fixture and fixture trim.

d. Operation of each valve, hydrant, and faucet.

e. Temperature of each domestic hot-water supply.

f. Operation of each floor drain, shower, and Eastern closet by flooding with water.

g. Operation of each vacuum breaker and backflow preventer.

3.8.5 Disinfection

After operational tests are complete, the entire domestic hot- and cold-water distribution system shall be disinfected. System shall be flushed as specified, before introducing chlorinating material. The chlorinating material shall be hypochlorites or liquid chlorine. Except as herein specified, water chlorination procedure shall be in accordance with AWWA C651 and AWWA C652. The chlorinating material shall be fed into the water piping system at a constant rate at a concentration of at least 50 parts per million (ppm). A properly adjusted hypochlorite solution injected into the main with a hypochlorinator, or liquid chlorine injected into the main through a solution-feed chlorinator and booster pump, shall be used. If after the 24 hour and 6 hour holding periods, the residual solution contains less than 25 ppm and 50 ppm chlorine respectively, flush the piping and tank with potable water, and repeat the above procedures until the required residual chlorine levels are satisfied. The system including the tanks shall then be flushed with clean water until the

residual chlorine level is reduced to less than one part per million. During the flushing period each valve and faucet shall be opened and closed several times. Samples of water in disinfected containers shall be obtained from several locations selected by the Contracting Officer. The samples of water shall be tested for total coliform organisms (coliform bacteria, fecal coliform, streptococcal, and other bacteria) in accordance with AWWA 10084. The testing method used shall be either the multiple-tube fermentation technique or the membrane-filter technique. Disinfection shall be repeated until tests indicate the absence of coliform organisms (zero mean coliform density per 100 milliliters) in the samples for at least 2 full days. The system will not be accepted until satisfactory bacteriological results have been obtained.

3.9 WASTE MANAGEMENT

Place materials defined as hazardous or toxic waste in designated containers. Return solvent and oil soaked rags for contaminant recovery and laundering or for proper disposal. Close and seal tightly partly used sealant and adhesive containers and store in protected, well-ventilated, fire-safe area at moderate temperature. Place used sealant and adhesive tubes and containers in areas designated for hazardous waste. Separate copper and ferrous pipe waste in accordance with the Waste Management Plan and place in designated areas for reuse.

3.10 POSTED INSTRUCTIONS

Framed instructions under glass or in laminated plastic, including wiring and control diagrams showing the complete layout of the entire system, shall be posted where directed. Condensed operating instructions explaining preventive maintenance procedures, methods of checking the system for normal safe operation, and procedures for safely starting and stopping the system shall be prepared in typed form, framed as specified above for the wiring and control diagrams and posted beside the diagrams. The framed instructions shall be posted before acceptance testing of the systems.

3.11 PERFORMANCE OF WATER HEATING EQUIPMENT

Standard rating condition terms are as follows:

EF = Energy factor, overall efficiency.

ET = Thermal efficiency with 21 degrees C delta T.

SL = Standby loss in W/0.093 sq. m. based on 27 degrees C delta T, or in percent per hour based on nominal 38 degrees C delta T.

HL = Heat loss of tank surface area.

V = Storage volume in liters

3.11.1 Storage Water Heaters

3.11.1.1 Electric

a. Storage capacity of 454 liters or less, and input rating of 12 kW or less: minimum energy factor (EF) shall be 0.95-0.00132V per 10 CFR 430.

b. Storage capacity of more than 454 liters or input rating more than 12

kW: maximum SL shall be 1.9 w/0.093 sq. m. per ASHRAE 90.1 - SI, Addenda B.

3.12 TABLES

TABLE I
PIPE AND FITTING MATERIALS FOR
DRAINAGE, WASTE, AND VENT PIPING SYSTEMS

		SERVICE			
Item #	Pipe and Fitting Materials	A	B	C	D
1	Cast iron soil pipe and fittings, hub and spigot, ASTM A 74 with compression gaskets. Pipe and fittings shall be marked with the CISPI trademark.	X	X	X	X
2	Cast iron soil pipe and fittings hubless, CISPI 301 and ASTM A 888. Pipe and fittings shall be marked with the CISPI trademark.		X	X	X
3	Cast iron drainage fittings, threaded, ASME B16.12	X		X	X
4	Cast iron screwed fittings (threaded) ASME B16.4				X
5	Polyvinyl Chloride plastic drain, waste and vent pipe and fittings, ASTM D 2665, ASTM F 891, (Sch 40) ASTM F 1760	X	X	X	X

SERVICE:
A - Underground Building Soil, Waste and Drain
B - Aboveground Soil, Waste, Drain In Buildings
C - Underground Vent
D - Aboveground Vent

TABLE II
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

Item No.	Pipe and Fitting Materials	SERVICE A	B	C	D
1	Malleable-iron threaded fittings,	X	X	X	X
	a. Galvanized, ASME B16.3 for use with Item 4a				
	b. Same as "a" but not galvanized for use with Item 4b			X	
2	Steel pipe:	X	X	X	X
	a. Seamless, galvanized, ASTM A 53/A 53M, Type S, Grade B				
	b. Seamless, black, ASTM A 53/A 53M, Type S, Grade B			X	
3	Polyvinyl chloride (PVC) plastic pipe, Schedules 40, 80, and 120, ASTM D 1785	X			X
4	Polyvinyl chloride (PVC) pressure-rated pipe (SDR Series), ASTM D 2241	X			X
5	Polyvinyl chloride (PVC) plastic pipe fittings, Schedule 40, ASTM D 2466	X			X
6	Socket-type polyvinyl chloride (PVC) plastic pipe fittings, schedule 80, ASTM D 2467 for use with Items 26 and 27	X			X
7	Threaded polyvinyl chloride (PVC) plastic pipe fittings, schedule 80, ASTM D 2464	X			X
8	Joints for IPS pvs pipe using solvent cement, ASTM D 2672	X			X
9	Steel pipeline flanges, MSS SP-44	X	X		
10	Fittings: brass or bronze; ASME B16.15, and ASME B16.18 ASTM B 828	X	X		
11	Fittings: forged, threaded or socket weld ASME B16.11		X	X	
12	Carbon steel pipe unions, socket-welding and threaded, MSS SP-83	X	X	X	
13	Fittings: butt weld		X	X	

TABLE II
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

		SERVICE			
Item No.	Pipe and Fitting Materials	A	B	C	D
14	Malleable-iron threaded pipe unions ASME B16.39	X	X		
15	Nipples, pipe threaded ASTM A 733	X	X	X	
16	Wrought Iron Pipe ASTM B36.10M			X	

A - Cold Water Service Aboveground
B - Hot and Cold Water Distribution 82 degrees C Maximum Aboveground
C - Compressed Air Lubricated
D - Cold Water Service Belowground
Indicated types are minimum wall thicknesses.
** - Type L - Hard
*** - Type K - Hard temper with brazed joints only or type K-soft temper without joints in or under floors
**** - In or under slab floors only brazed joints

TABLE III
STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING EQUIPMENT

A. STORAGE WATER HEATERS

FUEL	STORAGE CAPACITY LITERS	INPUT RATING	TEST PROCEDURE	REQUIRED PERFORMANCE
Elect.	100 max.	12 kW max.	10 CFR 430	EF = 0.95-0.00132V minimum
Elect.	50 min. OR	12 kW min.	ASHRAE 90.1 - SI (Addenda B)	SL = 1.9 W/0.09 sq.m. maximum

TERMS:

EF = Energy factor, overall efficiency.
ET = Thermal efficiency with 21 degrees C delta T.
EC = Combustion efficiency, 100 percent - flue loss when smoke = 0 (trace is permitted).
SL = Standby loss in W/0.09 sq. m. based on 27 degrees C delta T, or in percent per hour based on nominal 32 degrees C delta T.
HL = Heat loss of tank surface area
V = Storage volume in gallons

-- End of Section --

SECTION 22 07 19.00 40

PLUMBING PIPING INSULATION
07/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B 209M	(2007) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM C 1136	(2006) Standard Specification for Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C 195	(2000) Standard Specification for Mineral Fiber Thermal Insulating Cement
ASTM C 449/C 449M	(2000) Standard Specification for Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement
ASTM C 592	(2004) Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type)
ASTM C 795	(2003) Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel
ASTM C 916	(1985; R 2007) Standard Specification for Adhesives for Duct Thermal Insulation
ASTM C 920	(2008) Standard Specification for Elastomeric Joint Sealants
ASTM C 921	(2003a) Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation
ASTM D 579	(2004) Standard Specification for Greige Woven Glass Fabrics
ASTM E 84	(2009c) Standard Test Method for Surface Burning Characteristics of Building Materials

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 220	(2006) Standard on Types of Building

Construction

NFPA 255	(2005; Errata 2006) Standard Method of Test of Surface Burning Characteristics of Building Materials

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE AMS 3779	(1990; Rev A; R 1994) Tape Adhesive, Pressure Sensitive Thermal Radiation Resistant, Aluminum Foil/Glass Cloth

1.2 PERFORMANCE REQUIREMENTS

Thermal-insulation system materials shall be noncombustible, as defined by NFPA 220. Adhesives, coatings, sealants, facings, jackets, and thermal-insulation materials, except cellular elastomers, shall have a flame-spread classification (FSC) of 25, and a smoke-developed classification (SDC) of 50. These maximum values shall be determined in accordance with ASTM E 84, NFPA 255. Coatings and sealants shall be nonflammable in their wet state.

Adhesives, coatings, and sealants shall have published or certified temperature ratings suitable for the entire range of working temperatures normal for the surfaces to which they are to be applied.

1.3 SUBMITTALS

Government approval is required for submittals with a "GA" designation; submittals having a "FIO" designation are For Information only and for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation Drawings for pipe insulation shall be submitted in accordance with paragraph entitled, "Installation," of this section.

SD-03 Product Data

Manufacturer's catalog data shall be submitted for the following items:

Adhesives; FIO
Coatings; FIO
Insulating Cement; FIO
Insulation Materials; FIO
Jacketing; FIO
Tape; FIO

PART 2 PRODUCTS

2.1 MATERIALS

Materials shall be compatible and shall not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either the wet or

dry state. Materials to be used on stainless steel surfaces shall meet ASTM C 795 requirements. Materials shall be asbestos free and conform to the following.

2.1.1 Adhesives

2.1.1.1 Cloth Adhesives

Adhesives for adhering, sizing, and finishing lagging cloth, canvas, and open-weave glass cloth shall be a pigmented polyvinyl acetate emulsion and shall conform to the requirements of ASTM C 916, Type I.

2.1.1.2 Vapor-Barrier Material Adhesives

Adhesives for attaching laps of vapor-barrier materials and presized glass cloth and for attaching insulation to itself, to metal, and to various other substrates, shall be solvent-base, synthetic-rubber type and shall conform to the requirements of ASTM C 916, Type I, for attaching fibrous-glass insulation to metal surfaces. Solvent shall be nonflammable.

2.1.1.3 Cellular Elastomer Insulation Adhesive

Adhesive for cellular elastomer insulation shall be a solvent cutback chloroprene elastomer conforming to ASTM C 916, Type I, and shall be of a type approved by the manufacturer of the cellular elastomer for the intended use.

2.1.2 Coatings

2.1.2.1 Vapor-Barrier Finishing

Coatings for indoor vapor-barrier finishing of insulation surfaces shall be a pigmented resin and solvent compound and shall conform to ASTM C 1136, Type II.

2.1.2.2 Nonvapor-Barrier Finishing

Coatings for outdoor and indoor nonvapor-barrier finishing of insulation surfaces shall be pigmented polymer-emulsion type recommended by the insulation material manufacturer for the surface to be coated and shall be applied to specified dry-film thickness.

2.1.2.3 Cellular-Elastomer Insulation Coating

Finish coating for cellular-elastomer insulation shall be a polyvinylchloride lacquer approved by the manufacturer of the cellular elastomer.

2.1.3 Insulating Cement

2.1.3.1 General Purpose Insulating Cement

General purpose insulating cement shall be mineral fiber and shall conform to ASTM C 195. Composite shall be rated for 982 degrees C service and shall have a thermal-conductivity maximum of .123 watt per meter per degree Kelvin temperature differential at 93 degrees C mean temperature for 25 millimeter thickness.

2.1.3.2 Finishing Insulating Cement

Finishing insulating cement shall be mineral-fiber, hydraulic-setting type conforming to ASTM C 449/C 449M.

2.1.4 Caulking

Caulking used with specified insulation materials shall be an elastomeric joint sealant in accordance with ASTM C 920, Type S, Grade NS, Class 25, Use A.

2.1.5 Corner Angles

Corner angle piping insulation shall be nominal 0.41 millimeter aluminum 25 by 25 millimeter with factory applied kraft backing. Aluminum shall be in accordance with ASTM B 209M, Alloy 3003.

2.1.6 Insulation Materials

Insulation conductances shall be maximum values, as tested at any point, not an average. Insulation conductance found by test to exceed the specified maximum shall either be replaced or augmented by an additional thickness to bring it to the required maximum conductance and a complete finishing system.

2.1.6.1 Mineral Fiber

Mineral fiber shall conform to ASTM C 592, shall be suitable for surface temperatures up to 188 degrees C, and shall be of not less than 64.1 kilograms per cubic meter density. Thermal conductivity shall be not greater than 0.037 watt per meter per degree Kelvinat 66 degrees C mean.

2.1.6.2 Pipe Fittings

Pipe fitting insulation shall be molded pipe fitting covering for use at temperatures up to and including 650 degrees C.

2.1.6.3 Flexible Blankets

Flexible blankets shall be blankets and felts for use at temperatures up to and including 177 degrees Cminimum 16 kilogram per cubic meter density. Thermal conductivity shall be not greater than 0.038 watt per meter per degree Kat 24 degrees Cmean.

2.1.7 Jacketing

2.1.7.1 Glass Cloth Jackets

Glass cloth shall be plain-weave glass cloth conforming to ASTM D 579, Style 141 and shall weigh not less than 0.25 kilogram/square meter before sizing. Cloth shall be factory applied wherever possible.

Glass reinforcing cloth shall be a leno weave, 26-end and 12-pick thread conservation, with a warp and fill tensile strength of 7.9 and 5.3 kilonewton per meter of width, respectively, and with a weight of not less than 0.51 kilogram per square meter. At the Contractor's option, Style 191 leno-weave glass cloth conforming to ASTM D 579 may be provided.

2.1.8 Tape

Glass lagging shall be a knitted elastic cloth specifically suitable for continuous spiral wrapping of insulated pipe bends and fittings and shall produce a smooth, tight, wrinkle-free surface. Tape shall conform to requirements of SAE AMS 3779, SAE AMS 3779, ASTM D 579, and ASTM C 921, and shall weigh not less than 0.339 kilogram per square meter.

2.2 PIPING SYSTEMS

Insulation thickness and pipe sizes are in millimeter. Pipe size is inclusive dimensionally, and includes pipe nominal pipe size (NPS) and tubing outside diameter.

2.2.1 Hot-Water Piping

Insulation shall be mineral fiber with glass cloth jacket, Type T-2. Thickness shall be not less than that given in the following list. Aboveground pipes, valve bodies, fittings, unions, flanges, and miscellaneous surfaces shall be insulated.

PIPE SIZE (MILLIMETER)	INSULATION THICKNESS (MILLIMETER)
Up to 100	25
100 to 250	38
250 to 300	50

2.2.2 Cold-Water and Condensate-Drain Piping

Aboveground pipe, valve bodies, fittings, unions, flanges, and miscellaneous surfaces shall be insulated. Insulation shall be 10 millimeter mineral fiber with glass cloth jacket, Type T-2.

2.2.3 Refrigerant Suction Piping

Insulation shall be cellular-elastomer, Type T-3. Thickness shall be nominal 20 millimeter. Surfaces, including valve, fittings, unions, and flanges, shall be insulated.

PART 3 EXECUTION

3.1 INSTALLATION OF INSULATION SYSTEMS

Contours on exposed work shall be smooth and continuous. Cemented laps, flaps, bands, and tapes shall be smoothly and securely pasted down. Adhesives shall be applied on a full-coverage basis.

Insulation shall be applied only to system or component surfaces that have been tested and approved.

Joints shall be tight with insulation lengths tightly butted against each other. Where lengths are cut, cuts shall be smooth and square and without breakage of end surfaces. Where insulation terminates, ends shall be neatly tapered and effectively sealed, or finished as specified. Longitudinal seams of exposed insulation shall be directed away from normal view.

Materials shall be applied in conformance with the recommendations of the manufacturer.

Surfaces shall be clean and free of oil and grease before insulation adhesives or mastics are applied. Solvent cleaning required to bring metal surfaces to such condition shall be provided.

Installation Drawings for pipe insulation shall be in accordance with the adhesive manufacturer's written instructions for installation.

3.2 SYSTEM TYPES

3.2.1 Type T-2, Mineral Fiber with Glass Cloth Jacket

Piping shall be covered with a mineral-fiber, pipe insulation with factory-attached, presized, white, glass cloth. Jackets, jacket laps, flaps, and bands shall be securely cemented in place with vapor-barrier adhesive. Jacket overlap shall be not less than 40 millimeter. Jacketing bands for butt joints shall be 75 millimeter wide.

Exposed-to-view fittings shall be covered with preformed mineral-fiber fitting insulation of the same thickness as the pipe insulation and temporarily secured in place with light cord ties. Impregnated glass lagging tape shall be installed with indoor vapor-barrier on 50 percent overlap basis and the tape shall be blended smoothly into the adjacent jacketing. Additional coating shall be applied as needed, and rubber gloved to a smooth contour. Ends of insulation shall be taped to the pipe at valves DN50 and smaller. On-the-job fabricated insulation for concealed fittings and special configurations shall be built up from mineral fiber and a mixture of insulating cement and lagging adhesive, diluted with 3 parts water. Surfaces shall be finished with glass cloth or tape lagging.

In lieu of materials and methods specified above, fittings may be wrapped with a twine-secured, mineral-wool blanket to the required thickness and covered with premolded polyvinylchloride jackets. All jacket ends shall be held in place with AISI 300 series corrosion-resistant steel straps, 0.381 millimeter thick by 15 millimeter wide. Fitting insulation shall be thermally equivalent to pipe-barrel insulation to preclude surface temperatures detrimental to polyvinylchloride.

3.2.2 Type T-3, Cellular Elastomer

Piping-system surfaces shall be covered with flexible cellular-elastomer sheet or preformed insulation. Vapor seal shall be maintained. Insulation shall be cemented into continuous material with a solvent cutback chloroprene adhesive recommended by the manufacturer for the specific purpose. Adhesive shall be applied to both of the surfaces on a 100-percent coverage basis to a minimum thickness of 0.254 millimeter wet or approximately 4 square meter per liter of undiluted adhesive.

At pipe hangers or supports where the insulation rests on the pipe hanger strap, the insulation shall be cut with a brass cork borer and a No. 3 superior grade cork inserted. Seams shall be sealed with approved adhesive. Sweat fitting shall be insulated with miter-cut pieces of cellular elastomer insulation of the same nominal pipe size and thickness as the insulation on the adjacent piping or tubing. Miter-cut pieces shall be joined with approved adhesive. Covers shall be slit and snapped over the fitting, and joints shall be sealed with approved adhesive.

3.3 ACCEPTANCE

Final acceptance will depend upon providing construction (Record Drawings) details to the Contracting Officer. Construction details shall include, by building area, the insulation material type, amount, and installation method. An illustration or map of the duct routing locations may serve this purpose. Data shall have a cover letter/sheet clearly marked with the system name, date, and the words "Record Drawings insulation/material." Forward to the Systems Engineer/Condition Monitoring Office/Predictive Testing Group for inclusion in the Maintenance Database."

-- End of Section --

SECTION 23 00 00

AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
11/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)

AMCA 201	(2002) Fans and Systems
AMCA 210	(2007) Laboratory Methods of Testing Fans for Aerodynamic Performance Rating
AMCA 300	(2005) Reverberant Room Method for Sound Testing of Fans
AMCA 301	(2006; INT 2007; Errata 2008) Methods for Calculating Fan Sound Ratings from Laboratory Test Data

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)

ABMA 11	(1990; R 1999) Load Ratings and Fatigue Life for Roller Bearings
ABMA 9	(1990; R 2000) Load Ratings and Fatigue Life for Ball Bearings

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 62.1	(2007; INT 2007; INT 2-15 2008; Errata 2008; Addenda a, b, e, f and h 2008) Ventilation for Acceptable Indoor Air Quality

ASTM INTERNATIONAL (ASTM)

ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM C 553	(2008) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
ASTM E 2016	(2006) Standard Specification for Industrial Woven Wire Cloth

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1	(2007; Errata 2008) Standard for Motors and Generators
NEMA MG 10	(2001; R 2007) Energy Management Guide for Selection and Use of Fixed Frequency Medium AC Squirrel-Cage Polyphase Induction Motors
NEMA MG 11	(1977; R 2007) Energy Management Guide for Selection and Use of Single Phase Motors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 96	(2007) Ventilation Control and Fire Protection of Commercial Cooking Operations

UNDERWRITERS LABORATORIES (UL)

UL 214	(1997; Rev thru Aug 2001) Tests for Flame-Propagation of Fabrics and Films
UL 705	(2004; Rev thru Oct 2009) Standard for Power Ventilators
UL Bld Mat Dir	(2009) Building Materials Directory

1.2 COORDINATION OF TRADES

Furnish ductwork, piping offsets, fittings, and accessories as required to provide a complete installation and to eliminate interference with other construction.

1.3 DELIVERY AND STORAGE

Store equipment at the jobsite so that it is protected from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, cap or plug all pipes until installed.

1.4 FIELD MEASUREMENTS

After becoming familiar with all details of the work, the Contractor shall verify all dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing the work.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals having a "FIO" designation are For Information only and for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Drawings; GA

Drawings showing equipment layout, including assembly and installation details and electrical connection diagrams; ductwork layout showing the location of all supports and hangers, typical hanger details, gauge reinforcement, reinforcement spacing rigidity classification, and static pressure and seal classifications. Include any information required to demonstrate that the system has been coordinated and will properly function as a unit on the drawings and shall show equipment relationship to other parts of the work, including clearances required for operation and maintenance.

SD-03 Equipment Submittals

For the following equipment to be provided under this contract the contractor shall submit the manufacturer's standard catalog data, installation, operation and maintenance manuals:

Duct Connectors; FIO
Duct Access Doors; FIO
Manual Balancing Dampers; FIO
Registers and Grilles; FIO
Louvers; GA
Centrifugal Fans; GA
Centrifugal Type Power Wall Ventilators; GA
Centrifugal Type Power Roof Ventilators; GA
Filtered Supply Fans; GA
Heat Pumps; GA
Electric Resistant Heat; GA
Test Procedures; FIO
Duct Insulation; GA
Kitchen Hoods; GA
Make up Air; GA

SD-06 Test Reports

Performance Tests; FIO

Test reports for the ductwork leak test, and performance tests in booklet form, upon completion of testing. Document phases of tests performed including initial test summary, repairs/adjustments made, and final test results in the reports.

Damper Acceptance Test; FIO

Proposed schedule, at least 2 weeks prior to the start of test.

SD-10 Operation and Maintenance Data

Dampers, Diffusers, Louvers, and Grilles - Submit Data Package 2 in accordance with Section 01 78 23 "OPERATION AND MAINTENANCE DATA".

Proposed on-site training schedule, submitted concurrently with the operation and maintenance manuals.

Powered Equipment - Submit Data Package 3 in accordance with Section 01 78 23 "OPERATION AND MAINTENANCE DATA".

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide Components and equipment that are "standard products" of a manufacturer regularly engaged in the manufacturing of products that are of a similar material, design and workmanship. "Standard products" is defined as being in satisfactory commercial or industrial use for 2 years before bid opening. The 2-year manufacturer's experience shall include applications of components and equipment under similar circumstances and of similar size. The 2 years must be satisfactorily completed by a product that is sold on the commercial market through advertisements, manufacturers' catalogs, or brochures. Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown. The equipment items shall be supported by a service organization.

2.2 ASBESTOS PROHIBITION

Asbestos and asbestos-containing products shall not be used.

2.3 NAMEPLATES

All equipment shall have a nameplate, installed by the manufacturer, that identifies the manufacturer's name, address, type or style, and model or serial number.

2.4 EQUIPMENT GUARDS AND ACCESS

Belts, pulleys, chains, gears, couplings, projecting setscrews, keys, and other rotating parts exposed to personnel contact shall be fully enclosed or guarded according to OSHA requirements. High temperature equipment and piping exposed to contact by personnel or where it creates a potential fire hazard shall be properly guarded or covered with insulation of a type specified.

2.5 ELECTRICAL WORK

a. Provide motors, controllers, integral disconnects, contactors, and controls with their respective pieces of equipment, except controllers indicated as part of motor control centers. Provide electrical equipment, including motors and wiring, as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Manual or automatic control and protective or signal devices required for the operation specified and control wiring required for controls and devices specified, but not shown, shall be provided. For packaged equipment, the manufacturer shall provide controllers including the required monitors and timed restart.

b. For single-phase motors, provide high-efficiency type, fractional-horsepower alternating-current motors, including motors that are part of a system, in accordance with NEMA MG 11.

c. For polyphase motors, provide squirrel-cage medium induction motors, including motors that are part of a system, and that meet the efficiency ratings for premium efficiency motors in accordance with NEMA MG 1. Select premium efficiency polyphase motors in accordance with NEMA MG 10.

d. Provide motors in accordance with NEMA MG 1 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor. Motors shall be rated for continuous duty with the enclosure specified. Motor duty requirements shall allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motor torque shall be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Provide motor starters complete with thermal overload protection and other necessary appurtenances. Motor bearings shall be fitted with grease supply fittings and grease relief to outside of the enclosure.

e. Where two-speed or variable-speed motors are indicated, solid-state variable-speed controllers may be provided to accomplish the same function. Use solid-state variable-speed controllers for motors rated 7.45 kW or less and adjustable frequency drives for larger motors.

2.6 INDOOR AIR QUALITY

All equipment and components furnished as part of this Section shall comply with the requirements of ASHRAE 62.1 unless more stringent requirements are specified herein.

2.7 DUCT SYSTEMS

2.7.1 Metal Ductwork

All aspects of metal ductwork construction, including all fittings and components, shall comply with SMACNA HVAC Duct Const Stds unless otherwise specified. Elbows shall be radius type with a centerline radius of 1.5 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes may be used. Ductwork shall meet the requirements of Seal Class A. Sealants shall conform ASTM E8 and shall be suitable for the range of air distribution and ambient temperatures that it will be exposed to. Do not use pressure sensitive tape as a sealant. Apply the sealant to the exposed male part of the fitting collar so that the sealer will be on the inside of the joint and fully protected by the metal of the duct fitting. Apply one brush coat of the sealant over the outside of the joint to at least 50 mm band width covering all screw heads and joint gap. Dents in the male portion of the slip fitting collar will not be acceptable.

2.7.1.1 General Service Duct Connectors

Provide a flexible duct connector approximately 150 mm in width where sheet metal connections are made to fans or where ducts of dissimilar metals are connected. For round/oval ducts, secure the flexible material by stainless steel or zinc-coated, iron clinch-type draw bands. For rectangular ducts, install the flexible material locked to metal collars using normal duct construction methods. The composite connector system shall comply with UL 214 and be classified as "flame-retarded fabrics" in UL Bld Mat Dir.

2.7.1.2 Aluminum Ducts

Provide aluminum ducts at all areas carrying moisture laden air as indicated on the drawings. Ducts shall be ASTM B 209M, alloy 3003-H14 for

aluminum sheet and alloy 6061-T6 or equivalent strength for aluminum connectors and bar stock.

2.7.2 Ductwork Accessories

2.7.2.1 Duct Access Doors

Provide hinged access doors conforming to SMACNA HVAC Duct Const Stds in ductwork and plenums where indicated and at all air flow measuring primaries, automatic dampers, fire dampers, coils, thermostats, and other apparatus requiring service and inspection in the duct system. Provide access doors upstream and downstream of air flow measuring primaries and heating and cooling coils. Doors shall be minimum 375 x 450 mm, unless otherwise shown. Where duct size will not accommodate this size door, the doors shall be made as large as practicable. Equip doors 600 x 600 mm or larger with fasteners operable from inside and outside the duct. Use insulated type doors in insulated ducts.

2.7.2.2 Manual Balancing Dampers

Furnish manual balancing dampers with accessible operating mechanisms. Use chromium plated operators (with all exposed edges rounded) in finished portions of the building. Manual volume control dampers shall be operated by locking-type quadrant operators. Dampers shall be 2 gauges heavier than the duct in which installed. Unless otherwise indicated, multileaf dampers shall be opposed blade type with maximum blade width of 300 mm. Provide access doors or panels for all concealed damper operators and locking setscrews. Unless otherwise indicated, the locking-type quadrant operators for dampers, when installed on ducts to be thermally insulated, shall be provided with stand-off mounting brackets, bases, or adapters to provide clearance between the duct surface and the operator not less than the thickness of the insulation. Stand-off mounting items shall be integral with the operator or standard accessory of the damper manufacturer.

2.7.3 Registers, and Grilles

Units shall be factory-fabricated of steel or aluminum and shall distribute the specified quantity of air evenly over space intended without causing noticeable drafts, air movement faster than 0.25 m/s in occupied zone, or dead spots anywhere in the conditioned area. Outlets for diffusion, spread, throw, and noise level shall be as required for specified performance. Performance shall be certified according to ASHRAE 70. Inlets and outlets shall be sound rated and certified according to ASHRAE 70. Sound power level shall be no more than 30 NC or better. Registers shall be provided with volume damper with accessible operator, unless otherwise indicated; or if standard with the manufacturer, an automatically controlled device will be acceptable. Volume dampers shall be opposed blade type for all diffusers and registers. Where the inlet and outlet openings are located less than 2 m above the floor, they shall be protected by a grille or screen according to NFPA 90A. Units shall be fixed horizontal or vertical louver type. Furnish registers with sponge-rubber gasket between flanges and wall or ceiling. Locate exhaust registers 150 mm above the floor unless otherwise indicated. Grilles shall be as specified for registers, without volume control damper. Exhaust registers shall have a single set of non-directional face bars or vanes. Set face bars or vanes at 30 degrees.

2.7.4 Insulation

All supply air ducts shall be insulated with Duct Wrap, with vapor retarder facing. The insulation shall have a k-value of 0.24 respectively at 24 degrees C mean temperature. Thickness and R-value of the insulation shall be as installed. Installed thicknesses and R-values shall be based on 25% compression of the wrap. Duct wrap shall be minimum 50 mm thick.

2.8 AIR SYSTEMS EQUIPMENT

2.8.1 Fans

Fans shall be tested and rated according to AMCA 210. Calculate system effect on air moving devices in accordance with AMCA 201 where installed ductwork differs from that indicated on drawings. Install air moving devices to minimize fan system effect. Where system effect is unavoidable, determine the most effective way to accommodate the inefficiencies caused by system effect on the installed air moving device. The sound power level of the fans shall not exceed 85 dBA when tested per AMCA 300 and rated per AMCA 301. All fans shall have an AMCA seal. Connect fans to the motors directly. Fan motors located in hazardous areas, as indicated in schedule, shall have motor installed out of air stream, fans shall be explosion proof. Motor sheaves shall be variable pitch for 11 kW and below and fixed pitch as defined by ARI Guideline D. Select variable pitch sheaves to drive the fan at a speed which will produce the specified capacity when set at the approximate midpoint of the sheave adjustment. When fixed pitch sheaves are furnished, provide a replaceable sheave when needed to achieve system air balance. Provide fans with personnel screens or guards on both suction and supply ends, except that the screens need not be provided, unless otherwise indicated, where ducts are connected to the fan. For discharge air provide fans with manufactures standard low leakage gravity discharge louvers with security bars. Provide fan and motor assemblies with vibration-isolation supports or mountings as indicated. Use vibration-isolation units that are standard products with published loading ratings. Select each fan to produce the capacity required at the fan static pressure indicated. Sound power level shall be as indicated. Obtain the sound power level values according to AMCA 300. Standard AMCA arrangement, rotation, and discharge shall be as indicated. Power ventilators shall conform to UL 705 and shall have a UL label.

2.8.1.1 Centrifugal Fans

Centrifugal fans shall be fully enclosed, single-width single-inlet, or double-width double-inlet, AMCA Pressure Class I, II, or III as required or indicated for the design system pressure. Impeller wheels shall be rigidly constructed, accurately balanced both statically and dynamically. Fan blades may be forward curved or backward-inclined airfoil design in wheel sizes up to 750 mm. Fan blades for wheels over 750 mm in diameter shall be backward-inclined airfoil design. Fan wheels over 900 mm in diameter shall have overhung pulleys and a bearing on each side of the wheel. Fan wheels 900 mm or less in diameter may have one or more extra long bearings between the fan wheel and the drive. Bearings shall be sleeve type, self-aligning and self-oiling with oil reservoirs, or precision self-aligning roller or ball-type with accessible grease fittings or permanently lubricated type. Grease fittings shall be connected to tubing and serviceable from a single accessible point. Bearing life shall be L50 rated at not less than 200,000 hours as defined by ABMA 9 and ABMA 11. Fan shafts shall be steel, accurately finished, and shall be provided with key seats and keys for impeller hubs and fan pulleys. Each fan outlet shall be of ample

proportions and shall be designed for the attachment of angles and bolts for attaching flexible connections. Manually operated inlet vanes shall be provided on suction inlets. Manually operated outlet dampers shall be provided. Motors, unless otherwise indicated, shall not exceed 1800 rpm and shall have open drip proof enclosures. Motor starters shall be manual type with weather-resistant enclosure.

2.8.1.2 Centrifugal Type Power Wall Ventilators

Fans shall be direct driven centrifugal type with backward inclined, non-overloading wheel. Motor housing shall be removable and weatherproof. Unit housing shall be designed for sealing to building surface and for discharge and condensate drippage away from building surface. Construct housing of heavy gauge aluminum. Equip unit with an aluminum or plated steel wire discharge bird screen, disconnect switch, anodized aluminum wall grille, manufacturer's standard gravity damper, an airtight and liquid-tight metallic wall sleeve. Motor enclosure shall be totally enclosed fan cooled & explosion-proof (where indicated) type. Use only lubricated bearings.

2.8.1.3 Centrifugal Type Power Roof Ventilators

Fans shall be direct driven centrifugal type with backward inclined, non-overloading wheel. Motor compartment housing shall be hinged or removable and weatherproof, constructed of heavy gauge aluminum. Provide fans with birdscreen, disconnect switch, gravity dampers, roof curb, and extended base. Motors enclosure shall be dripproof type. Kitchen exhaust fans shall be centrifugal type according to UL 705 with direct drive, round hood, and windband upblast discharge configuration, integral residue trough and collection device, motor and power transmission components located in outside positively air ventilated compartment. Use only lubricated bearings.

2.8.1.4 In-line Centrifugal Fans

Welded steel casings, centrifugal backward inclined blades, stationary discharge conversion vanes, internal and external belt guards and adjustable motor mounts. Inlet and outlet connections for fan casings to duct work and equipment casings, may be of the slip fit or flanged type. Provide guards for discharges. Air shall enter and leave the fan axially. Inlet shall be streamlined and conversion vanes shall eliminate turbulence and provide smooth discharge air flow. Enclose fan bearings and drive shafts, and isolate from the air stream. Fan bearings shall be mechanically sealed against dust and dirt and shall be self-aligning, pillow block ball or roller type. Motor and drive shall be provided by fan manufacturer.

2.8.1.5 Filtered Supply Fan

For kitchen supply fan. Roof mounted, filtered supply fans shall be direct drive axial type. Propeller construction shall be cast aluminum, airfoil. Propellers shall be statically and dynamically balanced. Fan Hood and base construction shall be aluminum. Hood panels shall be arched with interlocking seams for weather protection. Fan bases shall be tall to allow for low leakage backdraft dampers. Welded galvanized mesh birdscreens shall be mounted horizontally across the intake area of the hood. Support members shall be heavy gauge galvanized steel angles. Motors shall be heavy duty ball bearing type carefully matched to the fan load and furnished at the specified voltage, phase and enclosure. A standard square

key and set screws or tapered locking bushing shall attaché the propeller securely to the motor shaft. Motor support frame assemblies shall be constructed of heavy gauge steel angles. Fan panels shall be heavy gauge steel with formed flanges and double venture. Safety guards of heavy welded wire construction shall be attached to the underside of the fan panel.

2.8.1.6 Prefabricated Roof Curb

For kitchen hood exhaust and supply fan. Curb shall be galvanized steel, with continuous welded corner seams, 50 mm wall thickness, treated wood nailer, .38 mm thick, 48 kg per cubic meter density rigid mineral fiberboard insulation with metal liner, built-in cant strip. Curbs shall be built for pitched roof as required to keep top of curb level. Curb Height shall be 450 mm above finished roof or as required to comply with NFPA 96.

2.8.1.7 Special Construction for Hazardous Area

Explosion Proof:

Construct fans to AMCA 99-0401, Type A spark-resistant requirements where explosion-proof electrical components are specified on drawings or indicated to conform to NFPA 70, Chapter 5 requirements.

2.9 UNITARY EQUIPMENT, SPLIT SYSTEM

Unit shall be an air-cooled, split system which employs a remote condensing unit, a separate indoor unit, and interconnection refrigeration piping. Unit shall be the heat pump type conforming to applicable Underwriters Laboratories (UL) standards including UL 1995. Unit shall be provided with necessary fans, air filters, internal dampers, mixing boxes, outdoor connections and cabinet construction as specified. Evaporator or supply fans shall be double-width, double inlet, forward curved, backward inclined, or airfoil blade, centrifugal scroll type. Condenser or outdoor fans shall be the manufacture's standard for the unit specified and may be either propeller or centrifugal scroll type. Fan and condenser motors shall have totally enclosed enclosures. Thermostat and controls shall be integral with the unit.

2.9.1 Construction

The cabinet and chassis shall be constructed of heavy gauge galvanized steel and designed for easy installation and service access from one side and bottom of unit only (water cooled units require end access). Mounting holes shall be factory attached to the cabinet. Unit shall be wall mounted.

2.9.2 Air Distribution

The air distribution system shall be constructed with a direct-drive fan assembly equipped with double-inlet blower, self-aligning ball bearings, and lifetime lubrication. Fan motor shall be permanent-split capacitor, high efficiency type, equipped with two speeds for air flow modulation.

2.9.3 Filters

The filters shall be rated not less than 20% efficiency based on ASHRAE Dust Weight Arrestance Test. They shall be removable without shutting down the system.

2.9.4 Outdoor Unit, Heat Pump

A. Direct Expansion Coil: The evaporator coil shall have 0.23 sq.m face area. It shall be constructed of copper tubes and aluminum fins. The coil shall be provided with a stainless steel drain pan.

B. Refrigeration System: The refrigeration system shall consist of a scroll (rotary hermetic on 1-ton) compressor with vibration isolating grommets, high pressure safety switch, and externally equalized expansion valve.

C. Air-Cooled Condenser: The condenser coil shall be constructed of copper tubes and aluminum fins and a direct-drive centrifugal fan. No piping, brazing, dehydration or charging shall be required. Condenser electrical connection to the cooling chassis shall be by a factory wired plug. Fan shall be sized to provide full rated cooling capacity at 35°C entering air from plenum space. The system shall be provided with a fan speed control system to permit operation at -28.9°C ambient temperature with low ambient controls and unit frost protection.

2.10 ELECTRIC UNIT HEATERS

UL 1025; Electric unit heaters shall be of the KW rating, voltage and phase specified in the schedule. They shall be fan-forced type, UL approved. Provide control-circuit terminals and single source of power supply. Limit leaving air temperature to 60 degrees C with entering air of 15 degrees C. Include limit controls for overheat protection of heaters. Heating wire element shall be nickel chromium. Provide tamper resistant integral thermostat. Completely factory-prewired to terminal strips, ready to receive branch circuit and control connections for 60°C copper or aluminum wiring. Provide factory-installed safety disconnect switch in the housing with "off" position marking on the face plate. Size of units shall be limited to 5kW only, units over 5kW are not allowed. Provide multiple units to meet needs above 5kW.

2.10.1 Enclosure

Standard unit shall be Minimum 20 gage steel. Explosion proof, corrosion resistant heater shall be NEMA 7, 9 cast aluminum enclosure.

2.10.2 Heating Element (Standard Unit)

Nickel chromium heating wire element, free from expansion noise and hum. Embed element in magnesium-oxide insulating refractory. Seal element in corrosion-resisting metallic sheath with fins. Enclose element ends in terminal box. Provide not more than six fins per 25 mm. Limit fin surface temperature 285 degrees C at any point during normal operation.

2.10.3 Heat Exchanger (Explosion proof/Corrosion Resistant Units)

Nickel Heat exchanger shall be liquid to air design, utilizing a steel tube core with integral aluminum fins. Nontoxic, inhibited, propylene glycol heat transfer fluid shall be used that provides freeze protection down to -45 degrees C. A pressure relief plug shall be utilized to provide overpressure protection. The heat exchanger shall include industrial grade electric heating elements. Heat exchanger and aluminum fan blade to be enclosed in an industrial grade, corrosion-resistant cabinet. Provide at high hazard areas as indicated on plans.

2.10.4 Thermostat

Thermostats shall be the adjustable electric or electronic type. Control wiring required to complete the space temperature control system shall be included. Thermostats shall have a 2 degree C (3 degree F) differential and a set point range of plus 5 to 38 degrees C (35 to 100 degrees F). Thermostats shall be the single stage type.

2.11 SENSORS

2.11.1 Hydrogen Sensor

Hydrogen sensor shall automatically sense increased levels of hydrogen, should the concentration of hydrogen gas in the air surrounding the sensor reach 1% by volume, the "1% Caution" yellow LED will light and the 1% internal relay will close. Should the hydrogen gas concentration reach 2% by volume, the "2% Warning" red LED will flash and an 80 db alarm will sound; the 1% relay will remain closed and, if a Dual-Relay model, the 2% internal relay will close. Either relay shall activate a remote exhaust fan, turn off battery chargers and alarm. Sensor shall be mounted as high as possible.

2.12 SUPPLEMENTAL COMPONENTS/SERVICES

2.12.1 Condensate Drain Lines

Provide and install condensate drainage for each item of equipment that generates condensate in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE except as modified herein.

2.13 SEISMIC RESTRAINT

2.13.1 Type of Vibration-Isolation Provisions

Design for vibration isolation using NEBB TABLES, NEBB Procedural Standards ASHRAE-05, Chapter 42.

2.13.2 Mountings

Combination spring and rubber-in-shear steel framed for hanger-rod mounting. Minimum total static deflection shall be 25 millimeter. Air spring with body constructed of reinforced elastomer specifically suitable for application environment. Air spring shall be selected to provide a natural frequency equal to 127 millimeter of deflection of conventional specified steel springs. Facilities shall be provided for dead-level adjustment and height-control of supported equipment.

2.13.3 Duct Vibration Isolation

Isolators shall be devices with contained chloroprene-elastomer elements for connecting to building-structure attachments. Devices shall be loaded by supported system during operating conditions to produce a minimum elastomer static deflection of 10 millimeter.

2.14 SPARE PARTS

2.14.1 General Requirements

The Contractor shall furnish to the Contracting Officer, fifteen per cent

(15%) spare parts of total items installed, as directly coordinated with the Contracting Officer. Spare parts shall include but not be limited to such items as: fan motors, filters, thermostats, diffusers, registers, grilles, actuators, damper motors.

2.14.2 Itemizing and Tagging Spare Parts

All spare parts shall be itemized, tagged for future use, and stored by the Contractor where directed by the Contracting Officer. Spare parts shall be handled, loaded, unloaded, and stored by the Contractor. Final design of spare part items shall be directly coordinated with the Contracting Officer.

2.15 EXHAUST HOODS OVER COOKING EQUIPMENT

Conform to NFPA 96 and UL 710. Conform to SMACNA HVAC Duct Const Stds. Provide seismic restraints in accord with SMACNA KEFG. The hood must not vary from design listing of air requirements or static pressure by more than five percent. Fabricate from 1.2 mm thick 18 gage stainless steel. Run electrical wiring in conduit or raceways. When total hood length is more than 3600 mm 12 feet long, provide hoods individually complete in all respects, of approximately equal length less than 3600 mm 12 feet long, and mounted end to end.

2.15.1 Hoods with face supply

Fabricate in factory. Hood shall be full compensating wall canopy with the capability to replace up to 95% of the exhausted air with fresh outside air. Air shall be supplied through perforated panels in a manner that does not interfere with the cooking operations beneath the hood. Perforated panels shall be located on the face to ensure precise volume control and shall limit the throw to within several feet of the hood.

The hood shall include a filter housing constructed of the same material as the hood. The filters shall be aluminum baffle type (stainless optional), U. L. Classified, and in sufficient number and sizes to ensure optimum performance. The filter housing shall terminate in a pitched, full length grease trough which shall drain into a removable grease container.

2.15.1.1 Types of Hoods

Provide the following hood types as indicated:

a. Wall-Mounted: Provide over ranges located along wall. Mount at height indicated.

2.15.1.2 Features

Provide the following:

a. Fan control.
b. Damper controls.
c. UL classified washable grease filters.
d. Vapor-proof lights.

2.15.1.3 Fan Control

Provide delay-time starter on starter leg of exhaust fan so supply fan starts first and run 5 seconds before exhaust fan starts, to insure the required balance in exhausted and make-up air flow. Provide the following

operations:

a. Operation by manual push buttons labeled "start" and "stop".

2.15.1.4 Fire Damper

Provide mechanically driven damper and damper control. Activate by heat-sensing thermostat set to react to temperature of 176 degrees C 350 degrees F in exhaust duct at hood. Activation of damper must cause the following additional actions:

a. Shut off exhaust and supply fans of hood.
b. Shut off fuel source and electric power to equipment under hood.

2.15.1.5 Vapor proof Lights

Provide incandescent or fluorescent lights in accord with UL 1598 or UL 1598. Locate switches for operating hood lights on face of hood in lower right corner.

2.16 LOUVERS

Weather resistant type, with bird screens and made to withstand a wind load of not less than 1.44 kilopascals. Wall louvers shall bear the AMCA certified ratings program seal for air performance and water penetration in accordance with AMCA 500 and AMCA 511. The rating shall show a water penetration of 0.06 kilograms or less per square meter of free area at a free velocity of 244 meters. Finish shall be a factory-applied coating. Clean and phosphate treat exposed surfaces and apply rust-inhibitive primer and baked enamel finish coat, 0.025 mm minimum total dry film thickness, color as directed by architect. Install using stops or moldings, flanges, strap anchors, or jamb fasteners as appropriate for the wall construction and in accordance with manufacturer's recommendations. Mount screens in removable, rewirable frames of same material and finish as the louvers. Provide zinc-coated or stainless steel screws and fasteners for louvers. Provide other accessories as required for complete and proper installation. Provide 12.5 mm square mesh, 1.5 mm thick zinc-coated steel or copper bird screening.

2.16.1 Bird Screens and Frames

Bird screens shall conform to ASTM E 2016, No. 2 mesh, aluminum or stainless steel. Aluminum screens shall be rated "medium-light". Stainless steel screens shall be rated "light". Frames shall be removable type, and fabricated from either stainless steel or extruded aluminum.

2.16.2 Sand Trap Louver

Extruded aluminum frame and blades 1.5 mm and 1.2 mm thick, composed of two sets of inverted U - channels mounted vertically on two opposite rows. Channels shall be fixed with a removable volume control damper to ensure control of air stream. Louver shall be provided with 2 rows of 20 mm dia. self draining holes for emptying filtered sand and dust. Volume damper shall be low leakage, galvanized steel with extruded aluminum blades. Bird screen shall be 12 mm x 12 mm x 1.5 mm dia aluminum wire mesh. Aluminum filters with washable expanded aluminum media, 50 mm thickness, designed to separate and dust from the air stream. Louver shall be capable of filtering sand particles at high intake velocities up to 4m/sec, standard design shall maintain velocities at 2.5m/sec and below with sand rejection

efficiencies of 42% and higher.

2.17 Electric Heat Make-Up Air Unit

Make up air units shall be self-contained packaged with a permanent washable) air filter, electric heating element, modulating element temperature control, and blower, designed specifically for outside air inlet. Heaters shall conform to the requirements of UL 1996. Units shall be factory prewired, ready for field terminal connections. Cabinet enclosure shall be galvanized insulated sheet metal sealed tight. Provide unit with finned rod modulating electric elements, high temperature limit switch, airflow proving switch and an outlet temperature sensing control. Unit shall include adjustable speed blower with PSC motor. Outside air inlet shall include a sand-trap type intake louver with washable pre filter. Include remote mounted thermostat with Auto, Fan and Heat modes. Unit shall be mounted tight to structure above with vibration isolators.

PART 3 EXECUTION

3.1 INSTALLATION

Installation shall be as shown and according to the manufacturer's diagrams, recommendations and manufacturer's installation instructions.

3.1.1 Condensate Drain Lines

Water seals shall be provided in the condensate drain from all units. The depth of each seal shall be 50 mm plus 0.1 mm for each Pa, of the total static pressure rating of the unit to which the drain is connected. Water seals shall be constructed of 2 tees and an appropriate U-bend with the open end of each tee plugged. Pipe cap or plug cleanouts shall be provided where indicated. Drains indicated to connect to the sanitary waste system shall be connected by an indirect waste fitting.

3.1.2 Equipment and Installation

Provide frames and supports for tanks, compressors, pumps, valves, air handling units, fans, coils, dampers, and other similar items requiring supports.

3.1.3 Access Panels

Install access panels for concealed valves, vents, controls, dampers, and items requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced and maintained or completely removed and replaced. Access panels shall be as specified in Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS.

3.1.4 Metal Ductwork

Installation shall be according to SMACNA HVAC Duct Const Stds unless otherwise indicated. Duct supports for sheet metal ductwork shall be according to SMACNA HVAC Duct Const Stds, unless otherwise specified. Friction beam clamps indicated in SMACNA HVAC Duct Const Stds shall not be used. Risers on high velocity ducts shall be anchored in the center of the vertical run to allow ends of riser to move due to thermal expansion. Supports on the risers shall allow free vertical movement of the duct. Supports shall be attached only to structural framing members and concrete slabs. Supports shall not be anchored to metal decking unless a means is

provided and approved for preventing the anchor from puncturing the metal decking. Where supports are required between structural framing members, suitable intermediate metal framing shall be provided. Where C-clamps are used, retainer clips shall be provided.

3.1.5 Kitchen Exhaust Ductwork

3.1.5.1 Ducts Conveying Smoke and Grease Laden Vapors

Ducts conveying smoke and grease laden vapors shall conform to requirements of NFPA 96. Seams, joints, penetrations, and duct-to-hood collar connections shall have a liquid tight continuous external weld. Duct material shall be minimum 1.3 mm, Type 304L or 316L, stainless steel Duct construction shall include external perimeter angle sized in accordance with SMACNA HVAC Duct Const Stds, except welded joint reinforcement shall be on maximum of 600 mm centers; continuously welded companion angle bolted flanged joints with flexible ceramic cloth gaskets where indicated; pitched to drain at low points; welded pipe coupling-plug drains at low points; welded fire protection and detergent cleaning penetration; steel framed, stud bolted, and flexible ceramic cloth gasketed cleaning access provisions where indicated. Angles, pipe couplings, frames, bolts, etc., shall be same material as that specified for the duct unless indicated otherwise.

3.1.5.2 Exposed Ductwork

Exposed ductwork shall be fabricated from minimum 1.3 mm, Type 304L or 316L, stainless steel with continuously welded joints and seams. Ducts shall be pitched to drain at hoods and low points indicated. Surface finish shall match hoods.

3.1.5.3 Concealed Ducts Conveying Moisture Laden Air

Concealed ducts conveying moisture laden air shall be fabricated from minimum 1.3 mm, Type 300 series, stainless steel Joints shall be continuously welded, brazed, or soldered to be liquid tight. Duct shall be pitched to drain at points indicated. Transitions to other metals shall be liquid tight, companion angle bolted and gasketed.

3.1.6 Dust Control

To prevent the accumulation of dust, debris and foreign material during construction, temporary dust control protection shall be provided. The distribution system (supply and return) shall be protected with temporary seal-offs at all inlets and outlets at the end of each day's work. Temporary protection shall remain in place until system is ready for startup.

3.1.7 Insulation

Sheet metal ductwork shall be clean, dry and sealed tightly prior to insulating with Duct Wrap. To ensure installed thermal performance, Duct Wrap shall be cut to "stretch-out" dimensions. This requires measurement of the duct perimeter, then cutting the duct wrap to the dimension (perimeter + add-on) indicated in the manufactures' stretch-out chart. A 50 mm piece of insulation shall be removed from the facing at the end of the piece of insulation to form an overlapping stapling and taping flap. The duct wrap is installed with the facing out. Adjacent sections of duct wrap shall be tightly butted with the 50mm stapling and taping flap overlapping. Seams shall be stapled approximately 150 mm o.c. with 13 mm

min. steel outward clinching staples. Seams shall be sealed with vapor retarder mastic or pressure-sensitive tape matching the insulation facing. Seal all tears, punctures, and/or other penetrations of the duct wrap facing with tape or mastic to provide a vapor-tight system.

3.1.8 Duct Test Holes

Holes with closures or threaded holes with plugs shall be provided in ducts and plenums as indicated or where necessary for the use of pitot tube in balancing the air system. Extensions, complete with cap or plug, shall be provided where the ducts are insulated.

3.1.9 Power Roof Ventilator Mounting

Foamed 13 mm thick, closed-cell, flexible elastomer insulation shall cover width of roof curb mounting flange. Where wood nailers are used, holes shall be pre-drilled for fasteners.

3.1.10 Exhaust Hoods Over Cooking Equipment Installation

Install in accordance with manufacturer's printed instructions.

3.1.11 Installation of Hoods

Install in accord with NFPA 96. Install hoods to remain free from vibration under all conditions of operation.

Upon completion perform operational tests on each piece of equipment to determine that equipment and components, including controls, safety devices, and attachments, operate as specified and are properly installed and adjusted. Notify the Contracting Officer 14 calendar days prior to testing. Submit 6 copies of the Exhaust Hood Air-Balance Report to the Contracting Officer.

3.2 PENETRATIONS

Provide sleeves and prepared openings for duct mains, branches, and other penetrating items, and install during the construction of the surface to be penetrated. Cut sleeves flush with each surface. Provide sleeves for round duct 380 mm and smaller. Provide framed prepared openings for round duct larger than 380 mm and square, rectangular or oval ducts. Sleeves and framed openings are also required where grilles, registers, and diffusers are installed at the openings. Provide 25 mm clearance between penetrating and penetrated surfaces except at grilles, registers, and diffusers. Pack spaces between sleeve or opening and duct or duct insulation with mineral fiber conforming with ASTM C 553, Type 1, Class B-2.

a. Sleeves: Fabricate sleeves, except as otherwise specified or indicated, from 1 mm thick mill galvanized sheet metal. Where sleeves are installed in bearing walls or partitions, provide black steel pipe conforming with ASTM A 53/A 53M, Schedule 20.

b. Framed Prepared Openings: Fabricate framed prepared openings from 1 mm galvanized steel, unless otherwise indicated.

c. Insulation: Provide duct insulation in accordance with Article 2.17 continuous through sleeves and prepared openings except firewall penetrations. Terminate duct insulation at fire dampers and flexible connections. For duct handling air at or below 16 degrees C, provide

insulation continuous over the damper collar and retaining angle of fire dampers, which are exposed to unconditioned air.

d. Closure Collars: Provide closure collars of a minimum 100 mm wide, unless otherwise indicated, for exposed ducts and items on each side of penetrated surface, except where equipment is installed. Install collar tight against the surface and fit snugly around the duct or insulation. Grind sharp edges smooth to prevent damage to penetrating surface. Fabricate collars for round ducts 380 mm in diameter or less from 1 mm galvanized steel. Fabricate collars for square and rectangular ducts, or round ducts with minimum dimension over 380 mm from 1.40 mm galvanized steel. Fabricate collars for square and rectangular ducts with a maximum side of 380 mm or less from 1 mm galvanized steel. Install collars with fasteners a maximum of 150 mm on center. Attach to collars a minimum of 4 fasteners where the opening is 300 mm in diameter or less, and a minimum of 8 fasteners where the opening is 500 mm in diameter or less.

e. Firestopping: Where ducts pass through fire-rated walls, fire partitions, and fire rated chase walls, seal the penetration with fire stopping materials as specified in Section 07 84 00 FIRESTOPPING.

3.3 DUCTWORK LEAK TEST

Perform ductwork leak test for the entire air distribution and exhaust system, including fans, coils, filters, etc. Test procedure, apparatus, and report shall conform to SMACNA Leakage Test Mnl. Ductwork leak test shall be completed with satisfactory results prior to applying insulation to ductwork exterior.

3.4 DAMPER ACCEPTANCE TEST

Operate all fire dampers and smoke dampers under normal operating conditions, prior to the occupancy of a building to determine that they function properly. Test each fire damper equipped with fusible link by having the fusible link cut in place. Test dynamic fire dampers with the air handling and distribution system running. Reset all fire dampers with the fusible links replaced after acceptance testing. To ensure optimum operation and performance, install the damper so it is square and free from racking.

3.5 TESTING, ADJUSTING, AND BALANCING

The requirements for testing, adjusting, and balancing are specified in Section 23 05 93.00 10 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS Testing, adjusting, and balancing shall begin only when the air supply and distribution, including controls, has been completed, with the exception of performance tests.

3.6 PERFORMANCE TESTS

After testing, adjusting, and balancing is complete as specified, test each system as a whole to see that all items perform as integral parts of the system and temperatures and conditions are evenly controlled throughout the building. Make corrections and adjustments as necessary to produce the conditions indicated or specified. Capacity tests and general operating tests shall be conducted by an experienced engineer. Tests shall cover a period of not less than 10 days for each system and shall demonstrate that the entire system is functioning according to the specifications. Make

coincidental chart recordings at points indicated on the drawings for the duration of the time period and record the temperature at space thermostats or space sensors, the humidity at space humidistats or space sensors and the ambient temperature and humidity in a shaded and weather protected area.

3.7 CLEANING AND ADJUSTING

Inside of ducts, plenums, and casing shall be thoroughly cleaned of debris and blown free of small particles of rubbish and dust and then shall be vacuum cleaned before installing outlet faces. Wipe equipment clean, with no traces of oil, dust, dirt, or paint spots. Maintain system in this clean condition until final acceptance. Properly lubricate bearings with oil or grease as recommended by the manufacturer. Adjust control valves and other miscellaneous equipment requiring adjustment to setting indicated or directed. Adjust fans to the speed indicated by the manufacturer to meet specified conditions.

3.8 OPERATION AND MAINTENANCE TRAINING

The Contractor shall conduct a training course for the members of the operating staff as designated by the Contracting Officer. The training period shall consist of a total of 16 hours of normal working time and shall start after all work specified herein is functionally completed and the Performance Tests have been approved. The field instruction shall cover all of the items contained in the Operation and Maintenance Manuals as well as demonstrations of routine maintenance operations. Notify the Contracting Officer at least 14 days prior to the date of proposed conduct of the training course.

-- End of Section --

SECTION 23 05 93.00 10

TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1	(2002) National Standards for Total System Balance

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB TABES	(2005) Procedural Standards for Testing, Adjusting and Balancing of Environmental Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA HVACTAB	(2002, 3rd Ed) HVAC Systems - Testing, Adjusting and Balancing

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Testing Adjusting and Balancing Submittals (TAB); GA

The contractor shall provide the following; GA
1) Two copies of the TAB Schematic Drawings and Report Forms, no later than 7 days prior to the start of the TAB field.
2) A list of TAB related HVAC submittals no later than seven days prior to the start TAB field measurments.
3) Proposed procedures for TAB, submitted with the TAB schematic drawings and report forms.
4) Proposed date and time to begin the systems readiness check, no later than seven days prior to the start of the system readiness check.
5) Proposed date and time to begin field measurement, making adjustments, etc., for the TAB report, submitted with the TAB report.
6) Proposed date and time to begin the TAB verification, submitted with the TAB report.
7) A copy of completed checklists for each system in the contract

scope, each signed by the contractor's representative, at least seven days prior to the start of TAB execution.
8) Two copies of the completed TAB reports, no later than seven days after the execution of TAB signed by the contractors representative.

SD-07 Certificates

Ductwork Leak Testing; FIO

A written statement signed by the TAB Specialist certifying that the TAB Specialist witnessed the Ductwork Leak Testing, it was successfully completed, and that there are no known deficiencies related to the ductwork installation that will prevent TAB from producing satisfactory results.

TAB Firm; GA

Certification of the proposed TAB Firm's qualifications by either AABC, NEBB, or TABB to perform the duties specified herein and in other related Sections, no later than (21) days after the Notice to Proceed. The documentation shall include the date that the Certification was initially granted and the date that the current Certification expires. Any lapses in Certification of the proposed TAB Firm or disciplinary action taken by AABC, NEBB or TABB against the proposed TAB Firm shall be described in detail.

TAB Specialist; GA

Certification of the proposed TAB Specialist's qualifications by either AABC, NEBB, or TABB to perform the duties specified herein and in other related Sections, no later than (21) days after the Notice to Proceed. The documentation shall include the date that the Certification was initially granted and the date that the current Certification expires. Any lapses in Certification of the proposed TAB Specialist or disciplinary action taken by AABC, NEBB, or TABB against the proposed TAB Specialist shall be described in detail.

1.3 SIMILAR TERMS

In some instances, terminology differs between the Contract and the TAB Standard primarily because the intent of this Section is to use the industry standards specified, along with additional requirements listed herein to produce optimal results. The following table of similar terms is provided for clarification only. Contract requirements take precedent over the corresponding AABC, NEBB, or TABB requirements where differences exist.

SIMILAR TERMS

Contract Term	AABC Term	NEBB Term	TABB Term
TAB Standard	National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems	Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems.	SMACNA's Procedures

SIMILAR TERMS

TAB Specialist	TAB Engineer	TAB Supervisor	TAB Supervisor
Systems Readiness Check	Construction Phase Inspection	Field Readiness Check & Preliminary Field Procedures.	Field Readiness Check & Prelim. Field Procedures

1.4 TAB STANDARD

TAB shall be performed in accordance with the requirements of the standard under which the TAB Firm's qualifications are approved, i.e., AABC MN-1, NEBB TABES, or SMACNA HVACTAB unless otherwise specified herein. All recommendations and suggested practices contained in the TAB Standard shall be considered mandatory. The provisions of the TAB Standard, including checklists, report forms, etc., shall, as nearly as practical, be used to satisfy the Contract requirements. The TAB Standard shall be used for all aspects of TAB, including qualifications for the TAB Firm and Specialist and calibration of TAB instruments. Where the instrument manufacturer calibration recommendations are more stringent than those listed in the TAB Standard, the manufacturer's recommendations shall be adhered to. All quality assurance provisions of the TAB Standard such as performance guarantees shall be part of this contract. For systems or system components not covered in the TAB Standard, TAB procedures shall be developed by the TAB Specialist. Where new procedures, requirements, etc., applicable to the Contract requirements have been published or adopted by the body responsible for the TAB Standard used (AABC, NEBB, or TABB), the requirements and recommendations contained in these procedures and requirements shall be considered mandatory.

1.5 QUALIFICATIONS

1.5.1 TAB Firm

The TAB Firm shall be either a member of AABC or certified by the NEBB or the TABB and certified in all categories and functions where measurements or performance are specified on the plans and specifications, including building systems commissioning. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the firm loses subject certification during this period, the Contractor shall immediately notify the Contracting Officer and submit another TAB Firm for approval. Any firm that has been the subject of disciplinary action by either the AABC, the NEBB, or the TABB within the five years preceding Contract Award shall not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections to be performed by the TAB Firm shall be considered invalid if the TAB Firm loses its certification prior to Contract completion and must be performed by an approved successor. These TAB services are to assist the prime Contractor in performing the quality oversight for which it is responsible. The TAB Firm shall be a subcontractor of the prime Contractor and shall be financially and corporately independent of the mechanical subcontractor, and shall report to and be paid by the prime Contractor.

1.5.2 TAB Specialist

The TAB Specialist shall be either a member of AABC, an experienced technician of the Firm certified by the NEBB, or a Supervisor certified by the TABB. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the Specialist loses subject certification during this period, the Contractor shall immediately notify the Contracting Officer and submit another TAB Specialist for approval. Any individual that has been the subject of disciplinary action by either the AABC, the NEBB, or the TABB within the five years preceding Contract Award shall not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections performed by the TAB Specialist shall be considered invalid if the TAB Specialist loses its certification prior to Contract completion and must be performed by the approved successor.

1.6 TAB SPECIALIST RESPONSIBILITIES

All TAB work specified herein and in related sections shall be performed under the direct guidance of the TAB Specialist. The TAB specialist is required to be onsite on a daily basis to direct TAB efforts.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 DESIGN REVIEW

The TAB Specialist shall review the Contract Plans and Specifications and advise the Contracting Officer of any deficiencies that would prevent the effective and accurate TAB of the system. The TAB Specialist shall provide a Design Review Report individually listing each deficiency and the corresponding proposed corrective action necessary for proper system operation.

3.2 TAB RELATED HVAC SUBMITTALS

The TAB Specialist shall prepare a list of the submittals from the Contract Submittal Register that relate to the successful accomplishment of all HVAC TAB. The submittals identified on this list shall be accompanied by a letter of approval signed and dated by the TAB Specialist when submitted to the Government. The TAB Specialist shall also ensure that the location and details of ports, terminals, connections, etc., necessary to perform TAB are identified on the submittals.

3.3 TAB SCHEMATIC DRAWINGS AND REPORT FORMS

A schematic drawing showing each system component, including balancing devices, shall be provided for each system. Each drawing shall be accompanied by a copy of all report forms required by the TAB Standard used for that system. Where applicable, the acceptable range of operation or appropriate setting for each component shall be included on the forms or as an attachment to the forms. The schematic drawings shall identify all testing points and cross reference these points to the report forms and procedures.

3.4 DUCTWORK LEAK TESTING

The TAB Specialist shall witness the Ductwork Leak Testing specified in

Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEM and approve the results as specified in Paragraph TAB RELATED HVAC SUBMITTALS.

3.5 TESTING, ADJUSTING, AND BALANCING

3.5.1 TAB Procedures

Step by step procedures for each measurement required during TAB Execution shall be provided. The procedures shall be oriented such that there is a separate section for each system. The procedures shall include measures to ensure that each system performs as specified in all operating modes, interactions with other components (such as exhaust fans, kitchen hoods, fume hoods, relief vents, etc.) and systems, and with all seasonal operating differences, diversity, simulated loads, and pressure relationships required.

3.5.2 Systems Readiness Check

The TAB Specialist shall inspect each system to ensure that it is complete, including installation and operation of controls, and that all aspects of the facility that have any bearing on the HVAC systems, including installation of ceilings, walls, windows, doors, and partitions, are complete to the extent that TAB results will not be affected by any detail or touch-up work remaining. The TAB Specialist shall also verify that all items such as ductwork and piping ports, terminals, connections, etc., necessary to perform TAB shall be complete during the Systems Readiness Check.

3.5.3 Preparation of TAB Report

Preparation of the TAB Report shall begin only when the Systems Readiness Report has been approved. The Report shall be oriented so that there is a separate section for each system. The Report shall include a copy of the appropriate approved Schematic Drawings and TAB Related Submittals, such as pump curves, fan curves, etc., along with the completed report forms for each system. The operating points measured during successful TAB Execution and the theoretical operating points listed in the approved submittals shall be marked on the performance curves and tables. Where possible, adjustments shall be made using an "industry standard" technique which would result in the greatest energy savings, such as adjusting the speed of a fan instead of throttling the flow. Any deficiencies outside of the realm of normal adjustments and balancing during TAB Execution shall be noted along with a description of corrective action performed to bring the measurement into the specified range. If, for any reason, the TAB Specialist determines during TAB Execution that any Contract requirement cannot be met, the TAB Specialist shall immediately provide a written description of the deficiency and the corresponding proposed corrective action necessary for proper system operation to the Contracting Officer.

3.5.4 TAB Verification

The TAB Specialist shall recheck ten percent of the measurements listed in the Tab Report and prepare a TAB Verification Report. The measurements selected for verification and the individuals that witness the verification will be selected by the Contracting Officer's Representative (COR). The measurements will be recorded in the same manner as required for the TAB Report. All measurements that fall outside the acceptable operating range specified shall be accompanied by an explanation as to why the measurement

does not correlate with that listed in the TAB Report and a description of corrective action performed to bring the measurement into the specified range. The TAB Specialist shall update the original TAB report to reflect any changes or differences noted in the TAB verification report and submit the updated TAB report. If over 20 percent of the measurements selected by the COR for verification fall outside of the acceptable operating range specified, the COR will select an additional ten percent for verification. If over 20 percent of the total tested (including both test groups) fall outside of the acceptable range, the TAB Report shall be considered invalid and all contract TAB work shall be repeated beginning with the Systems Readiness Check.

3.5.5 Marking of Setting

Following approval of TAB Verification Report, the setting of all HVAC adjustment devices including valves, splitters, and dampers shall be permanently marked by the TAB Specialist so that adjustment can be restored if disturbed at any time.

3.5.6 Identification of Test Ports

The TAB Specialist shall permanently and legibly identify the location points of duct test ports. If the ductwork has exterior insulation, the identification shall be made on the exterior side of the insulation. All penetrations through ductwork and ductwork insulation shall be sealed to prevent air leakage or to maintain integrity of vapor barrier.

-- End of Section --

SECTION 23 11 13.00 20

FUEL OIL PIPING
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN PETROLEUM INSTITUTE (API)

API RP 1110	(1997) Pressure Testing of Liquid Petroleum Pipelines
API Std 600	(2001; R 2006) Bolted Bonnet Steel Gate Valves for Petroleum and Natural Gas Industries

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M	(2004; Errata 2004) Specification for Filler Metals for Brazing and Braze Welding
AWS Z49.1	(2005) Safety in Welding, Cutting and Allied Processes

ASME INTERNATIONAL (ASME)

ASME A13.1	(2007) Scheme for the Identification of Piping Systems
ASME B1.1	(2003) Unified Inch Screw Threads (UN and UNR Thread Form)
ASME B16.11	(2009) Forged Fittings, Socket-Welding and Threaded
ASME B16.21	(2005) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.3	(2006) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.39	(1998) Standard for Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300
ASME B16.5	(2009) Standard for Pipe Flanges and Flanged Fittings: NPS 1/2 Through NPS 24
ASME B16.9	(2003) Standard for Factory-Made Wrought Steel Buttwelding Fittings
ASME B18.2.2	(1987; R 2005) Standard for Square and Hex

	Nuts
ASME B18.52.1	(1996; R 2005) Square and Hex Bolts and Screws Inch Series
ASME B31.1	(2007; Addenda 2008; Addenda 2009) Power Piping
ASME B31.3	(2004) Process Piping
ASME B31.4	(2006) Pipeline Transportation Systems for Liquid Hydrocarbons and Other Liquid
ASME B40.100	(2006) Pressure Gauges and Gauge Attachments
ASME BPVC SEC IX	(2007; Addenda 2008) Boiler and Pressure Vessel Code; Section IX, Welding and Brazing Qualifications
ASME BPVC SEC VIII D1	(2007; Addenda 2008) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels Division 1 - Basic Coverage

ASTM INTERNATIONAL (ASTM)

ASTM A 194/A 194M	(2006a Standard Specification for) Carbon and Alloy Steel Nuts for Bolts for High Pressure or High Temperature Service or Both
ASTM A 307	(2007b) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A 36/A 36M	(2008) Standard Specification for Carbon Structural Steel
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-110	(1996) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends
MSS SP-58	(2002) Standard for Pipe Hangers and Supports - Materials, Design and Manufacture
MSS SP-69	(2003; R 2004) Standard for Pipe Hangers and Supports - Selection and Application
MSS SP-72	(1999) Standard for Ball Valves with Flanged or Butt-Welding Ends for General Service

MSS SP-80	(2008) Bronze Gate, Globe, Angle and Check Valves

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 30	(2007; Errata 2008) Flammable and Combustible Liquids Code
NFPA 31	(2006; Errata 2006) Installation of Oil Burning Equipment
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 780	(2007) Standard for the Installation of Lightning Protection Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA Seismic Restraint Mnl	(1998; Addendum 2000, 2nd Ed) Seismic Restraint Manual: Guidelines for Mechanical Systems

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 20	(2002; E 2004) Paint Specification No. 20 Zinc-Rich Coating Type I Inorganic and Type II Organic
SSPC SP 10	(2000; E 2004) Near-White Blast Cleaning

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-P-24441	(Rev C; Supp 1; INT Am 1) Paint, Epoxy-Polyamide
MIL-PRF-907	(Rev F) Antiseize Thread Compound, High Temperature

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS A-A-1689	(Rev B) Tape, Pressure-Sensitive Adhesive, (Plastic Film)
FS A-A-50568	(Basic) Gages, Liquid Level Measuring, Tank
FS A-A-58092	(Basic) Tape, Antiseize, Polytetrafluoroethylene
FS A-A-59313	(Basic; Notice 1) Thread, Compound, Antiseize, Zinc Dust-Petrolatum
FS WW-S-2739	(Basic) Strainers, Sediment: Pipeline, Water, Air, Gas, Oil, or Steam

UNDERWRITERS LABORATORIES (UL)

UL 842	(1997; Rev thru Aug 2005) Standard for Valves for Flammable Fluids
UL Gas&Oil Dir	(2006) Flammable and Combustible Liquids and Gases Equipment Directory

1.2 DEFINITIONS

1.2.1 Carrier Piping

Piping which contains diesel fuel or MOGAS, exclusively.

1.2.2 Secondary Containment System

System which contains carrier piping and prevents fuel leakage from carrier piping into surrounding soil and/or water. System to be double-walled piping.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings; GA

Diesel Fuel Storage Tanks

SD-03 Product and Catalog Data; GA

Pipe and fittings

Valves

Flexible hose

Dielectric unions

Strainers

Instruments

Secondary containment system for piping

SD-06 Testing of Fuel Oil Tanks and Fuel Oil Pumps Including Instrumentation and Fuel Oil Piping Including Prefabricated Joints; GA

The contractor shall provide the following: Six copies of each test containing the information described below (items 1-7) in bound letter-size booklets; individual reports shall be provided for the storage tank tests, the piping tests, the system performance tests, the high level alarm test, and the system leak tests. Drawings shall be folded blue lines, with the title block visible. 1) The date the tests were performed. 2) A list of equipment used, with calibration certifications. 3) A copy of

measurements taken. 4) The parameters to be verified. 5) The condition specified for the parameter. 6) The inspection results, signed, dated, and certified by the installer. The certification shall state that required procedures were accomplished, that the procedures were conducted in compliance the plans and specifications. 7) A description of adjustments performed.

SD-07 Certificates; GA

Welding procedure

Qualification of welders

List of welder's names and symbols

Flexible hose

Dielectric unions

Tank surface preparation

Coating materials

Coating application procedure

SD-08 Manufacturer's Instructions

Secondary containment system for piping

Flexible pipe

SD-10 Installation, Operation and Maintenance Manuals

Diesel Fuel Tank

Submit Data Package 3 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.4 QUALITY ASSURANCE

1.4.1 Welding Procedure

Before performing welding, submit three copies of welding procedure specification for metals included in the work, together with proof of its qualifications as outlined in ASME B31.1.

1.4.2 Qualification of Welders

Before welder or operator performs welding, submit to the Contracting Officer three copies of the Welder's Performance Qualification Record in conformance with ASME B31.1 showing that the welder was tested under the approved procedure specification submitted by the Contractor.

1.4.3 List of Welder's Names and Symbols

Submit each welder's assigned number, letter, or symbol which shall be used to identify the work of the welder and shall be affixed immediately upon completion of the weld.

1.4.4 Defective Welds

Welders making defective welds after passing a qualification test shall be required to take a re-qualification test. Welders failing the re-qualification tests will not be permitted to work under this contract.

1.4.5 Previous Welder Qualifications

Welding procedures, welders, and welding operators previously qualified by test may be accepted for this contract without re-qualification, subject to approval by the Contracting Officer provided that all the conditions specified in ASME B31.1 are met before a procedure can be used.

1.5 WELDING SAFETY

AWS Z49.1.

1.6 REGISTRATION

Contractor shall obtain required tank registration or permit/approval application forms from governing regulatory agencies. Furnish completed forms to the Contracting Officer and the installation environmental office within 10 days after contract award for their submission to the regulatory agency.

PART 2 PRODUCTS

Fuel oil system including equipment, materials, installation, workmanship, fabrication, assembly, erection, examination, inspection, and testing shall be in accordance with ASME B31.1, NFPA 70 and SMACNA Seismic Restraint Mnl, as modified and supplemented by the contract specifications and drawings.

2.1 MATERIALS AND EQUIPMENT

2.1.1 Steel Pipe and Fittings

2.1.1.1 Secondary Containment System for Piping

Provide double-walled steel secondary containment piping for diesel fuel and MOGAS piping systems. Secondary containment piping systems shall be an engineered and prefabricated double pipe type containment system. Carrier pipe shall be standard weight carbon steel, ASTM A-53, Grade B, ERW or seamless. Joints shall be socket or buttweld. Secondary containment pipe shall be carbon steel ASTM A-139, Grade B, ASTM A-135, Grade B or ASTM A-53, Grade B. Thickness for pipe diameters under 125 mm shall be schedule 40. Provide a fiberglass reinforced polyester external cladding to outer pipe for corrosion resistance. Secondary containment shall allow for complete inspection of carrier pipe connections, during carrier pipe hydrostatic testing, before the secondary containment system is sealed. The secondary containment system shall be:

a. Compatible with diesel fuel and MOGAS fuel.

b. Non-corrosive, di-electric, non-degradable and resistant to attack from microbial growth.

2.1.1.2 Socket-Welding Fittings

ASME B16.11, forged steel, Class 2000.

2.1.1.3 Butt-Welding Fittings

ASME B16.9, Class 150. Backing rings shall conform to ASME B31.3 and be compatible with materials being welded.

2.1.1.4 Flanges and Flange Fittings

ASME B16.5, steel flanges or convoluted steel flanges which meet the criteria of ASME BPVC SEC VIII D1. Flange faces shall have integral grooves of rectangular cross section which afford containment for self-energizing gasket material.

2.1.2 Flexible Pipe

2.1.2.1 Pipe

Flexible pipe shall be approved by the Underwriters Laboratories for the service intended and listed in UL Gas&Oil Dir. Use of flexible piping is limited to connection at generator only and at pressures not exceeding that marked on the pipe.

2.1.2.2 Flexible Pipe Fittings

Bronze mechanical coupling shall be supplied by the same manufacturer as the pipe.

2.1.3 Vent Piping

ASTM A 53/A 53M standard weight, zinc-coated steel with zinc-coated malleable iron fittings ASME B16.3.

2.1.4 Valves

2.1.4.1 Bronze Gate Valves

MSS SP-80 Class 125, 50 mm and smaller, wedge disk, nonrising stem.

2.1.4.2 Steel Gate Valves

API Std 600, oil service, Class 150.

2.1.4.3 Ball Valves

MSS SP-72 for flanged or butt-welding ends and MSS SP-110 for socket-welding.

2.1.4.4 Relief Valves

UL 842, steel or bronze bodies, corrosion-resistant valve seats, and positive closing to prevent leakage.

2.1.4.5 Check Valves

Metal body, Class 200, suited for use in diesel fuel and gasoline applications.

2.1.5 Piping Accessories

2.1.5.1 Flexible Hose

Flexible metal hose, corrugated type with braided wire sheath covering, close-pitch annular corrugations, rated for a working pressure of at least 862 kPa (gage), 200 mm minimum live length, screwed end connections, UL listed for flammable liquid service. Metal for hose and braided wire sheath shall be stainless steel, any type of ASTM 300-series.

2.1.5.2 Unions

ASME B16.39, Class 150 pound.

a. Dielectric Unions: Union comprised of steel female pipe thread end and copper solder-joint end conforming to dimensional, strength, and pressure requirements of ASME B16.39, Class 1. Steel parts shall be galvanized or plated. Union shall have a water-impervious insulation barrier capable of limiting galvanic current to one percent of the short-circuit current in a corresponding bimetallic joint. When dry, it shall be able to withstand a 600-volt breakdown test.

2.1.5.3 Welding Filler Metal

ASME B31.4 and compatible with the materials to be welded.

2.1.5.4 Brazing Filler Metal

AWS A5.8/A5.8M, silver base alloy, with melting point not less than 593 degrees C.

2.1.5.5 Hangers, Supports, and Shields

Design, selection, fabrication, installation, and spacing shall conform to MSS SP-58 and MSS SP-69. Hangers, supports, rods, anchors, nuts, bolts, and washers shall be hot-dip galvanized. Hangers and supports shall be of the adjustable type.

2.1.5.6 Strainers

FS WW-S-2739 single basket type, with inlet and outlet on the same center line. Cast steel or fabricated steel body, 40 by 40 mesh ASTM 300-series stainless steel baskets. Open area of one basket shall be 2 1/2-times inlet or outlet piping area. Furnish one spare basket.

2.1.5.7 Gaskets

Provide one piece, factory cut, 1.60 mm thick, gaskets resistant to the effects of fuel oil and manufactured of fire-resistant materials. Provide full-face gaskets for flat-face flanged joints, and ring gaskets for raised-face flanged joints. Dimensions for gaskets shall be in accordance with ASME B16.21.

2.1.5.8 Bolting

Material for bolts and studs ASTM A 307, Grade-B and for nuts ASTM A 194/A 194M, Grade-2. Dimensions of bolts, studs and nuts ASME B18.52.1 and ASME B18.2.2 with threads conforming to ASME B1.1 coarse

type, with Class 2A fit for bolts and studs, and Class 2B for nuts.

2.1.5.9 Sleeves in Stone,Masonry and Concrete Walls, Floors,

Provide ASTM A 53/A 53M, Schedule 40 or Standard Weight, zinc-coated steel pipe sleeves.

2.1.5.10 Sleeves in Other Wall, and Floor Materials

Provide minimum 26 gage zinc-coated steel sheet sleeves in partitions and other than masonry and concrete walls, floors, and roof.

2.1.5.11 Floor, Walls, and Ceiling Plates

Plates shall be painted cast-iron, malleable iron, or steel.

2.1.5.12 Identification for Piping Aboveground

Labels for pipes 20 mm diameter and larger shall bear printed legends to identify contents of pipes and arrows to show direction of flow. Labels shall have color coded background to signify levels of hazard in accordance with ASME A13.1. Legends and type and size of characters shall also conform to ASME A13.1. Make labels of plastic sheet FS A-A-1689 with pressure sensitivity suitable for intended applications, or they may be premolded of plastic to fit over pipe. For pipes smaller than 20 mm diameter, provide brass identification tags 40 mm in diameter with legends in depressed black filled characters.

2.1.5.13 Miscellaneous Metal

ASTM A 36/A 36M, standard mill finished structural shapes, hot-dip galvanized after fabrication.

2.1.6 Instruments

2.1.6.1 Tank Gages

FS A-A-50568, buoyant force type with direct reading dial.

2.1.6.2 Thermometers

Thermometers shall be bi-metal dial type with stainless steel case, stem, and fixed thread connection; 125 mm diameter dial with glass face gasketed within the case; accuracy within one percent of scale range. Provide scale range suitable for the intended service.

2.1.6.3 Pressure Gages

ASME B40.100, single style with 115 mm diameter dial for fuel, brass or aluminum case, bronze tube; accuracy within 2 percent of scale range. Provide scale range suitable for the intended service.

2.1.7 Protective Coating Materials for Aboveground Pipe and Tanks

Coatings shall be the products of one manufacturer and coating application procedure shall be in accordance with manufacturer's instruction. Tank surface preparation shall be abrasive blast clean steel surfaces in accordance with SSPC SP 10 to a surface profile of 0.013 to 0.051 mm.

2.1.7.1 External Coatings

Protect aboveground piping and steel tanks against atmospheric corrosion with a coat of organic, lead and chromate free, zinc-rich primer conforming to SSPC Paint 20, Type II applied to a minimum dry film thickness of 0.102 mm and finish with two coats of epoxy-polyamide topcoat conforming to MIL-P-24441. Apply a gray first topcoat conforming to MIL-P-24441/2, Formula 151 applied to a minimum dry film thickness of 0.076 mm and finish with a white second topcoat conforming to MIL-P-24441/3, Formula 152 applied to a minimum dry film thickness of 0.076 mm resulting in a total system minimum dry film thickness of 0.28 mm.

PART 3 EXECUTION

3.1 INSTALLATION

Contractor shall provide installation of fuel oil piping system in accordance with applicable Federal, State, regional or local regulations.

3.1.1 Fuel Oil Piping System

Install piping in out-of-the-way locations, in a manner that will minimize cutting of beams, girders, columns, or load-bearing members. Installation of oil piping and equipment in buildings shall conform to NFPA 30 and NFPA 31, except as indicated or specified herein.

3.1.2 Pipe Sleeves and Plates

Provide sleeves where piping passes through walls, floors, and partitions. Secure sleeves in proper position and location during construction. Provide sleeves of sufficient length to pass through entire thickness of walls, floors, and partitions. Extend sleeves in floor slabs 80 mm above the finished floor. Provide not less than 6 mm space between exterior of piping or pipe insulation and interior of sleeve. Firmly pack space with insulation and calk at both ends of the sleeve with plastic waterproof cement which will dry to a firm but pliable mass, or provide a segmented elastomeric seal. Secure plates to pipes at sleeves.

3.1.3 Steel Piping

Steel piping 50 mm and smaller shall be threaded or socket-welded. Steel piping 65 mm and larger shall be buttwelded. Flanges may be used for valves and equipment installation. Piping joints shall conform to ASME B31.3.

3.1.4 Threaded Joints in Piping

Provide lubricant or polytetrafluoroethylene tape conforming to FS A-A-58092 on male threads of screwed joints. Red or white lead and zinc compound conforming to FS A-A-59313 may be used. Lubricate threaded pipe joints, as well as bolts and studs used on high temperature pipe joints up to 566 degrees C, with anti-seize compound in accordance with MIL-PRF-907. Piping shall be free from fins and burrs. Ream or file out pipe ends to size of bore and remove chips. Attach screwed flanges by screwing the pipe through the flange, and reface pipe and flange accurately.

3.1.5 Welding

3.1.5.1 Welding of Piping

Welding of joints in piping, butt welds, fillet welds, bends, loops, offsets, and cleaning of pipe shall be in accordance with ASME B31.1. Welds shall be visually examined and meet acceptance standards specified in Chapter VI of ASME B31.1.

3.1.5.2 Quality of Welds

Quality of welds, correction of defects, stress relieving, and preheating shall be in accordance with ASME B31.1.

3.1.5.3 Arc Welding and Gas Welding

In accordance with ASME BPVC SEC IX.

3.1.6 Unions and Flanges

Place unions and flanges where necessary to permit easy disconnection of piping and apparatus. Each connection having a threaded end valve shall have a union.

3.1.7 Valves

Install valves in positions accessible for operation and repair.

3.1.8 Thermometers

Provide thermometers and thermal sensing elements of control valves with separable sockets. Install separable sockets in pipe lines in such a manner to sense the temperature of flowing fluid and minimize obstruction to flow.

3.1.9 Diesel Fuel Storage Tanks

Install storage tanks, vents and other connections in accordance with NFPA 30, NFPA 31, recommendations and published instructions of the manufacturer, and as indicated. Provide grounding of tanks directly through ground rods or through bonding to grounded network in accordance with NFPA 780. Fasten aboveground fuel oil tanks on a firm reinforced concrete foundation. Provide fireproofed steel supports between tank and foundation. Concrete shall have a compressive strength of 2.8 kPa, 20 mm maximum aggregate size and 80 to 100 mm slump. Materials for sand, gravel, and concrete shall meet requirements specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.2 FIELD QUALITY CONTROL

Prior to application of test pressure, remove or valve off piping components which may be damaged by test and install a calibrated test gage in the system. Maintain test pressure for at least one hour. In the event of leakage, locate and repair leak by rewelding and repeat test. Materials and equipment shall be subject to inspection at the installation site by the Contracting Officer.

3.2.1 Piping Test

Before final acceptance of the work, test each system as in service to demonstrate compliance with contract requirements. Furnish electricity, instruments, connecting devices, and personnel for the tests. Correct defects in work provided by the Contractor and repeat tests until work is in compliance with contract requirements. Government will furnish fuel for piping testing and flushing provided by the Contractor. Contractor shall be responsible for test fuel losses greater than 10 percent.

3.2.1.1 Pneumatic Test

Pneumatically test each piping system to 172 kPa (gage), examine joints with soap solution. Gradually increase to 345 kPa (gage) and hold for 1 hour. The pneumatic test is more hazardous than a hydrostatic test, therefore, special safety measures, including the wearing of face masks, shall be taken during testing under pressure. Only authorized personnel shall be permitted in the area during pneumatic and hydrostatic testing.

3.2.1.2 Hydrostatic Tests

Upon completion of pneumatic testing, hydrostatically test each piping system at 1.5 times maximum system operating pressure but in no case more than 1896 kPa (gage) in accordance with ASME B31.3 and API RP 1110, with no leakage or reduction in gage pressure for 4 hours.

3.2.1.3 Flushing

Thoroughly flush piping before placing in operation. Flush piping, including branch piping, at a minimum velocity of 2.40 meters per second.

3.2.2 Secondary Containment Piping Test

The secondary containment piping system shall undergo a 34 kPa minimum air-pressure/soap test upon completion of installation to confirm the secondary containment integrity. This testing shall be in compliance with the manufacturer's published installation instructions.

3.2.3 Protective Coating Systems

Inspect protective coating systems, with a holiday tester just prior to placement. Holidays revealed shall be promptly repaired. Steel piping coating system shall be given a holiday test with a voltage of 100 to 200 times the mm thickness of the coating.

3.2.4 Steel Fuel Oil Storage Tanks

Test tanks for leaks by applying internal air pressure and using soapsuds, linseed oil or equivalent material on external welds. For horizontal tanks, test pressure shall be not less than 34 nor more than 48 kPa (gage). For vertical tanks, test pressure shall be not less than 10 kPa (gage) nor more than that pressure which first causes visible deformation of the tank. During testing, tank shall be provided with a suitable pressure relief device.

-- End of Section --

SECTION 26 00 00.00 20

BASIC ELECTRICAL MATERIALS AND METHODS
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 709	(2001; R 2007) Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

1.2 RELATED REQUIREMENTS

This section applies to certain sections of Division 13, SPECIAL CONSTRUCTION, and Divisions 22, 23, 27 and 28, PLUMBING and HEATING VENTILATING AND AIR CONDITIONING COMMUNICATIONS AND ELECTRICAL SAFETY. This section applies to all sections of Division 26, 27, 28 and 33, ELECTRICAL and UTILITIES, of this project specification unless specified otherwise in the individual sections. This section has been incorporated into, and thus, does not apply to, and is not referenced in the following sections.

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM
Section 26 51 00 INTERIOR LIGHTING
Section 26 56 00 EXTERIOR LIGHTING

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. The technical sections referred to herein are those specification sections that describe products, installation procedures, and equipment operations and that refer to this section for detailed description of submittal types.

c. The technical paragraphs referred to herein are those paragraphs in PART 2 - PRODUCTS and PART 3 - EXECUTION of the technical sections that describe products, systems, installation procedures, equipment, and test methods.

1.4 ELECTRICAL CHARACTERISTICS

Electrical characteristics for this project shall be 12.47 kV primary, three phase, three wire, 60 Hz, and 380 volts secondary, three phase, four wire.

1.5 ADDITIONAL SUBMITTALS INFORMATION

Submittals required in other sections that refer to this section must conform to the following additional requirements as applicable.

1.5.1 Shop Drawings (SD-02)

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices.

1.5.2 Product Data (SD-03)

Submittal shall include performance and characteristic curves.

1.6 QUALITY ASSURANCE

1.6.1 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.6.2 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or

brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in the technical section.

1.6.2.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.6.2.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site shall not be used, unless specified otherwise.

1.7 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.8 POSTED OPERATING INSTRUCTIONS

Provide for each system and principal item of equipment as specified in the technical sections for use by operation and maintenance personnel. The operating instructions shall include the following:

a. Wiring diagrams, control diagrams, and control sequence for each principal system and item of equipment.

b. Start up, proper adjustment, operating, lubrication, and shutdown procedures.

c. Safety precautions.

d. The procedure in the event of equipment failure.

e. Other items of instruction as recommended by the manufacturer of each system or item of equipment.

Print or engrave operating instructions and frame under glass or in approved laminated plastic. Post instructions where directed. For operating instructions exposed to the weather, provide weather-resistant materials or weatherproof enclosures. Operating instructions shall not fade when exposed to sunlight and shall be secured to prevent easy removal or peeling.

1.9 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.10 FIELD FABRICATED NAMEPLATES

ASTM D 709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified in the technical sections or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 3 mm thick, white with black center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be 25 by 65 mm. Lettering shall be a minimum of 6.35 mm high normal block style.

1.11 ELECTRICAL REQUIREMENTS

Electrical installations shall conform to IEEE C2, NFPA 70, and requirements specified herein.

1.12 INSTRUCTION TO GOVERNMENT PERSONNEL

Where specified in the technical sections, furnish the services of competent instructors to give full instruction to designated Government personnel in the adjustment, operation, and maintenance of the specified systems and equipment, including pertinent safety requirements as required. Instructors shall be thoroughly familiar with all parts of the installation and shall be trained in operating theory as well as practical operation and maintenance work. Instruction shall be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with equipment or system. When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instructions to acquaint the operating personnel with the changes or modifications.

PART 2 PRODUCTS

2.1 FACTORY APPLIED FINISH

Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA 250 corrosion-resistance test.

PART 3 EXECUTION

3.1 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side, but space the signs a maximum of 9 meters apart.

-- End of Section --

SECTION 26 05 00.00 40

COMMON WORK RESULTS FOR ELECTRICAL
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 709	(2001; R 2007) Laminated Thermosetting Materials

ELECTRONIC INDUSTRIES ALLIANCE (EIA)

EIA 480	(1981) Toggle Switches

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C57.12.28	(2005) Standard for Pad-Mounted Equipment - Enclosure Integrity
IEEE C57.12.29	(2005) Pad-Mounted Equipment - Enclosure Integrity for Coastal Environments
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1	(2003; R 2004) Standard for Accessible and Usable Buildings and Facilities

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA FB 1	(2007) Standard for Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable
NEMA KS 1	(2001; R 2006) Enclosed and Miscellaneous Distribution Equipment Switches (600 Volts Maximum)
NEMA OS 1	(2008) Standard for Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports
NEMA PB 1	(2006; Errata 2008) Standard for Panelboards

NEMA RN 1	(2005) Standard for Polyvinyl Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA TC 2	(2003) Standard for Electrical Polyvinyl Chloride (PVC) Tubing and Conduit
NEMA TC 3	(2004) Standard for Polyvinyl Chloride PVC Fittings for Use With Rigid PVC Conduit and Tubing
NEMA VE 1	(2009) Standard for Metallic Cable Tray Systems
NEMA WD 1	(1999; R 2005) Standard for General Requirements for Wiring Devices
NEMA WD 6	(2002; R 2008) Standard for Wiring Devices - Dimensional Requirements
NEMA Z535.1	(2006) Standard for Safety Colors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 1	(2005; Rev thru Jul 2007) Standard for Flexible Metal Conduit
UL 1242	(2006; Rev thru Jul 2007) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 489	(2009) Standard for Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 506	(2000; Rev thru May 2006) Standard for Specialty Transformers
UL 6	(2007) Standard for Electrical Rigid Metal Conduit-Steel
UL 797	(2007) Standard for Electrical Metallic Tubing -- Steel
UL 870	(1995; Rev thru Jul 2003) Standard for Wireways, Auxiliary Gutters, and Associated Fittings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office

that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submit Material, Equipment, and Fixture Lists for the following:

Conduits, Raceways and Fittings	Medium Voltage Cable
Wire and Cable	Oil Filled
Splices and Connectors	Distribution Transformers
Switches	Switchgear
Receptacles	Generators
Outlets, Outlet Boxes, and Pull Boxes	Fire Alarm System
Circuit Breakers	
Panelboards	
Lamps and Lighting Fixtures	
Dry-Type Distribution Transformers	

SD-03 Product Data

Submit manufacturer's catalog data for the following items:

Conduits, Raceway sand Fittings
Wire and Cable
Splices and Connectors
Switches
Receptacles
Outlets, Outlet Boxes, and Pull Boxes
Circuit Breakers
Panelboards and Distribution Panelboards
Lamps and Lighting Fixtures
Dry-Type Distribution Transformers
Spare Parts

SD-06 Test Reports

Continuity Test
Phase-Rotation Tests
Insulation Resistance Test

SD-08 Manufacturer's Instructions

Submit Manufacturer's Instructions.

1.3 PREVENTION OF CORROSION

Protect metallic materials against corrosion. Provide equipment enclosures with the standard finish by the manufacturer when used for most indoor installations. For harsh indoor environments (any area subjected to chemical and/or abrasive action), and all outdoor installations, refer to Section 09 90 00 PAINTS AND COATINGS. Do not use aluminum when in contact with earth or concrete and, where connected to dissimilar metal, protect by approved fittings and treatment. Ferrous metals such as, but not limited to, anchors, bolts, braces, boxes, bodies, clamps, fittings, guards, nuts, pins, rods, shims, thimbles, washers, and miscellaneous spare parts not of corrosion-resistant steel shall be hot-dip galvanized except where other equivalent protective treatment is specifically approved in writing.

1.4 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. The technical sections referred to herein are those specification sections that describe products, installation procedures, and equipment operations and that refer to this section for detailed description of submittal types.

1.5 GENERAL REQUIREMENTS

Submit Material, Equipment, and Fixture Lists for the following items showing manufacturer's style or catalog numbers, specification and drawing reference numbers, warranty information, and fabrication site.

Submit Manufacturer's Instructions including special provisions required to install equipment components and system packages. Special notices shall detail impedances, hazards and safety precautions.

Submit Certification required to install equipment components and system packages.

1.6 POSTED OPERATING INSTRUCTIONS

Provide for each system and principal item of equipment as specified in the technical sections for use by operation and maintenance personnel. The operating instructions shall include the following:

a. Wiring diagrams, control diagrams, and control sequence for each principal system and item of equipment.

b. Start up, proper adjustment, operating, lubrication, and shutdown procedures.

c. Safety precautions.

d. The procedure in the event of equipment failure.

e. Other items of instruction as recommended by the manufacturer of each system or item of equipment.

Print or engrave operating instructions and frame under glass or in approved laminated plastic. Post instructions where directed. For operating instructions exposed to the weather, provide weather-resistant materials or weatherproof enclosures. Operating instructions shall not fade when exposed to sunlight and be secured to prevent easy removal or peeling.

1.7 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.8 FIELD FABRICATED NAMEPLATES

ASTM D 709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified in the technical sections or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 3 mm thick, white with black center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be 25 by 65 mm. Lettering shall be a minimum of 6.35 mm high normal block style.

1.9 WARNING SIGNS

Provide warning signs for the enclosures of electrical equipment including substations, pad-mounted transformers, pad-mounted switches, generators, and switchgear having a nominal rating exceeding 600 volts.

a. When the enclosure integrity of such equipment is specified to be in accordance with IEEE C57.12.28 or IEEE C57.12.29, such as for pad-mounted transformers and pad-mounted SF6 switches, provide self-adhesive warning signs on the outside of the high voltage compartment door(s). Sign shall be a decal and have nominal dimensions of 178 by 255 mm with the legend "DANGER HIGH VOLTAGE" printed in two lines of nominal 50 mm high letters. The word "DANGER" shall be in white letters on a red background and the words "HIGH VOLTAGE" shall be in black letters on a white background. Decal shall be Panduit No. PPSO710D72 or approved equal.

b. When such equipment is guarded by a fence, mount signs on the fence. Provide metal signs having nominal dimensions of 355 by 255 mm with the legend "DANGER HIGH VOLTAGE KEEP OUT" printed in three lines of nominal 75 mm high white letters on a red and black field.

PART 2 PRODUCTS

2.1 MATERIALS

Materials and equipment to be provided shall be the standard cataloged products of manufacturers regularly engaged in the manufacture of the products.

2.1.1 Rigid Steel Conduit

Rigid steel conduit shall comply with UL 6 and be galvanized by the hot-dip process. Rigid steel conduit shall be polyvinylchloride (PVC) coated in accordance with NEMA RN 1, where underground and in corrosive areas, or must be painted with bitumastic.

Fittings for rigid steel conduit shall be threaded.

Gaskets shall be solid. Conduit fittings with blank covers shall have gaskets, except in clean, dry areas or at the lowest point of a conduit run where drainage is required.

Covers shall have captive screws and be accessible after the work has been completed.

2.1.2 Electrical Metallic Tubing (EMT)

EMT shall be in accordance with UL 797 and be zinc coated steel. Couplings and connectors shall be zinc-coated, raintight, gland compression with insulation throat. Crimp, spring, or setscrew type fittings are not acceptable.

2.1.3 Flexible Metallic Conduit

Flexible metallic conduit shall comply with UL 1 and be galvanized steel.

Fittings for flexible metallic conduit shall be specifically designed for such conduit.

Provide liquidtight flexible metallic conduit with a protective jacket of PVC extruded over a flexible interlocked galvanized steel core to protect wiring against moisture, oil, chemicals, and corrosive fumes.

Specifically design fittings for liquidtight flexible metallic conduit for such conduit.

2.1.4 Intermediate Metal Conduit

Intermediate metal conduit shall comply with UL 1242 and be galvanized.

2.1.5 Rigid Nonmetallic Conduit

Rigid nonmetallic conduit shall comply with NEMA TC 2 and NEMA TC 3 with wall thickness not less than Schedule 40.

2.1.6 Wireways and Auxiliary Gutters

Wireway and auxiliary gutters shall be a minimum 100 by 100 millimeter trade size conforming to UL 870.

2.1.7 Surface Raceways and Assemblies

Surface metal raceways and multi-outlet assemblies shall conform to NFPA 70. Receptacles shall conform to NEMA WD 1, Type 5-15R.

2.1.8 Cable Trays

Provide ladder type cable trays conforming to NEMA VE 1.

2.2 WIRE AND CABLE

Conductors installed in conduit shall be copper 600-volt type THHN, THWN, or XHHW as indicated. All conductors 3.15 millimeter diameter and larger, shall be stranded. All conductors smaller than 3.15 millimeter diameter shall be solid.

Flexible cable shall be Type SO and contain a grounding conductor with green insulation.

Conductors installed in plenums shall be marked plenum rated.

2.3 SPLICES AND CONNECTORS

Make all splices in 3.15 millimeter diameter and smaller with approved insulated electrical type.

Make all splices in 4.1 millimeter diameter and larger with indentor crimp-type connectors and compression tools. Joints shall be wrapped with an insulating tape that has an insulation and temperature rating equivalent to that of the conductor.

2.4 SWITCHES

2.4.1 Safety Switches

Safety switches shall comply with NEMA KS 1, and be the heavy-duty type with enclosure, voltage, current rating, number of poles, and fusing as indicated. Switch construction shall be such that, when the switch handle in the "ON" position, the cover or door cannot be opened. Cover release device shall be coinproof and be so constructed that an external tool shall be used to open the cover. Make provisions to lock the handle in the "OFF" position, but the switch shall not be capable of being locked in the "ON" position.

Provide switches of the quick-make, quick-break type. Approve terminal lugs for use with copper conductors.

Safety color coding for identification of safety switches shall conform to NEMA Z535.1.

2.4.2 Toggle Switches

Toggle switches shall comply with EIA 480, control incandescent, mercury, and fluorescent lighting fixtures and be of the heavy duty, general purpose, noninterchangeable flush-type.

Toggle switches shall be commercial grade toggle type, single, double-pole, three or four-way two-position devices rated 20 amperes at 277 volts, 60 hertz alternating current (ac) only.

All toggle switches shall be products of the same manufacturer.

2.5 RECEPTACLES

Receptacles shall be commercial grade, 20A, 125 VAC, 2-pole, 3-wire duplex conforming to NEMA WD 6, NEMA 5-20R.

2.6 OUTLETS, OUTLET BOXES, AND PULL BOXES

Outlet boxes for use with conduit systems shall be in accordance with NEMA FB 1 and NEMA OS 1 and be not less than 40 millimeter deep. Furnish all pull and junction boxes with screw-fastened covers.

2.7 PANELBOARDS

Lighting and appliance branch circuit panelboards shall be the circuit-breaker type in accordance with NEMA PB 1. Bolt circuit breakers to the bus. Plug-in circuit breakers are not acceptable. Buses shall be copper of the rating indicated, with main lugs or main circuit breaker as indicated. Provide all panelboards for use on grounded ac systems with a

full-capacity isolated neutral bus and a separate grounding bus bonded to the panelboard enclosure. Panelboard enclosures shall be NEMA 250, Type 1, in accordance with NEMA PB 1. Provide enclosure fronts with latchable hinged doors.

2.8 CIRCUIT BREAKERS

Circuit-breaker interrupting rating shall be not less than those indicated and in no event less than 10,000 amperes root-mean-square (rms) symmetrical at 240 volts, respectively. Multipole circuit breakers shall be the common-trip type with a single handle. Molded case circuit breakers shall be bolt-on type conforming to UL 489.

2.9 LAMPS AND LIGHTING FIXTURES

Manufacturers and catalog numbers shown are indicative of the general type desired and are not intended to restrict the selection to fixtures of any particular manufacturer. Fixtures with the same salient features and equivalent light distribution and brightness characteristics, of equal finish and quality, are acceptable. Provide lamps of the proper type and wattage for each fixture.

Ballasts shall be high power factor and be energy efficient. Ballasts shall have a Class P terminal protective device for 220-volt operation as indicated and be rapid-start fluorescent. Ballasts shall be "A" sound rated. Fluorescent lamps shall be standard reduced wattage type.

High intensity discharge (HID) lighting fixtures shall have prewired integral ballasts and cast aluminum housings complete with tempered glass lenses suitable for installation in damp or wet locations. Provide fixtures and lamps.

2.10 DRY-TYPE DISTRIBUTION TRANSFORMERS

General purpose dry-type transformers with windings 600 volts or less shall be two-winding, 60 hertz, self-cooled in accordance with UL 506. Windings shall have a minimum of two 2-1/2-percent taps above and below nominal voltage.

PART 3 EXECUTION

3.1 CONDUITS, RACEWAYS AND FITTINGS

Conduit runs between outlet and outlet, between fitting and fitting, or between outlet and fitting shall not contain more than the equivalent of three 90-degree bends, including those bends located immediately at the outlet or fitting.

Do not install crushed or deformed conduit. Avoid trapped conduit runs where possible. Take care to prevent the lodgment of foreign material in the conduit, boxes, fittings, and equipment during the course of construction. Clear any clogged conduit of obstructions or be replaced.

Conduit and raceway runs concealed in or behind walls, above ceilings, or exposed on walls and ceilings 1470 millimeter or more above finished floors and not subject to mechanical damage may be electrical metallic tubing (EMT).

3.1.1 Rigid Steel Conduit

Make field-made bends and offsets with approved hickey or conduit bending machine. Conduit elbows larger than 65 millimeter shall be long radius.

Provide all conduit stubbed-up through concrete floors for connections to free-standing equipment with the exception of motor-control centers, cubicles, and other such items of equipment, with a flush coupling when the floor slab is of sufficient thickness. Otherwise,provide a floor box set flush with the finished floor. Conduits installed for future use shall be terminated with a coupling and plug set flush with the floor.

3.1.2 Electrical Metallic Tubing (EMT)

EMT shall be grounded in accordance with NFPA 70, using pressure grounding connectors especially designed for EMT.

3.1.3 Flexible Metallic Conduit

Use flexible metallic conduit to connect recessed fixtures from outlet boxes in ceilings, transformers, and other approved assemblies.

Bonding wires shall be used in flexible conduit as specified in NFPA 70, for all circuits. Flexible conduit shall not be considered a ground conductor.

Electrical connections to vibration-isolated equipment shall be made with flexible metallic conduit.

Liquidtight flexible metallic conduit shall be used in wet and oily locations and to complete the connection to motor-driven equipment.

3.1.4 Intermediate Conduit

Make all field-made bends and offsets with approved hickey or conduit bending machine. Use intermediate metal conduit only for indoor installations.

3.1.5 Rigid Nonmetallic Conduit

Rigid PVC conduit shall be direct buried.

A green insulated copper grounding conductor shall be in conduit with conductors and be solidly connected to ground at each end. Grounding wires shall be sized in accordance with NFPA 70.

3.1.6 Wireway and Auxiliary Gutter

Straight sections and fittings shall be bolted together to provide a rigid, mechanical connection and electrical continuity. Dead ends of wireways and auxiliary gutters shall be closed. Plug all unused conduit openings.

Wireways for overhead distribution and control circuits shall be supported at maximum 1500 millimeter intervals.

Auxiliary gutters used to supplement wiring spaces for equipment not contained in a single enclosure shall contain no switches, overcurrent devices, appliances, or apparatus and be not more than 9000 millimeter long.

3.2 WIRING

Feeder and branch circuit conductors shall be color coded as follows:

CONDUCTOR	COLOR AC
Phase A	Black
Phase B	Red
Phase C	Blue
Neutral	White
Equipment Grounds	Green

Conductors up to and including 6.5 millimeter diameter shall be manufactured with colored insulating materials. Conductors larger than 6.5 millimeter diameter shall have ends identified with color plastic tape in outlet, pull, or junction boxes.

Splice in accordance with the NFPA 70. Provide conductor identification within each enclosure where a tap, splice, or termination is made and at the equipment terminal of each conductor. Terminal and conductor identification shall match as indicated.

Where several feeders pass through a common pullbox, the feeders shall be tagged to clearly indicate the electrical characteristics, circuit number, and panel designation.

3.3 SAFETY SWITCHES

Securely fasten switches to the supporting structure or wall, utilizing a minimum of four 6 millimeter bolts. Do not use sheet metal screws and small machine screws for mounting. Do not mount switches in an inaccessible location or where the passageway to the switch may become obstructed. Mounting height shall be 1500 millimeter above floor level, when possible.

3.4 WIRING DEVICES

3.4.1 Wall Switches and Receptacles

Install wall switches and receptacles so that when device plates are applied, the plates will be aligned vertically to within 2 millimeter.

Ground terminal of each flush-mounted receptacle shall be bonded to the outlet box with an approved green bonding jumper when used with dry wall type construction.

3.4.2 Device Plates

Device plates for switches that are not within sight of the loads controlled shall be suitably engraved with a description of the loads.

Device plates and receptacle cover plates for receptacles other than 125-volt, single-phase, duplex, convenience outlets shall be suitably marked, showing the circuit number, voltage, frequency, phasing, and amperage available at the receptacle. Required marking shall consist of a

self-adhesive label having 6 millimeter embossed letters.

Device plates for convenience outlets shall be similarly marked indicating the supply panel and circuit number.

3.5 BOXES AND FITTINGS

Furnish and install pullboxes where necessary in the conduit system to facilitate conductor installation. Conduit runs longer than 30 meter or with more than three right-angle bends shall have a pullbox installed at a convenient intermediate location.

Securely mount boxes and enclosures to the building structure with supporting facilities independent of the conduit entering or leaving the boxes.

Mounting height of wall-mounted outlet and switch boxes, measured between the bottom of the box and the finished floor, shall be in accordance with ICC A117.1 and as follows:

LOCATION	MOUNTING HEIGHT
Receptacles in offices	450 millimeter
Receptacles in corridors	450 millimeter
Receptacles in shops & laboratories	1200 millimeter
Receptacles in rest rooms	1200 millimeter
Switches for light control	1200 millimeter

3.6 LAMPS AND LIGHTING FIXTURES

Install new lamps of the proper type and wattage in each fixture. Securely fasten fixtures and supports to structural members and install parallel and perpendicular to major axes of structures.

3.7 PANELBOARDS

Securely mount panelboards so that the top operating handle does not exceed 1800 millimeter above the finished floor. Do not mount equipment within 914 millimeter of the front of the panel. Directory card information shall be complete and legible.

3.8 DRY-TYPE DISTRIBUTION TRANSFORMERS

Connect dry-type transformers with flexible metallic conduit.

Mount all dry-type transformers on vibration isolators in accordance with Section 13 48 00 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT.

3.9 IDENTIFICATION PLATES AND WARNINGS

Furnish and install identification plates for lighting and power panelboards, motor control centers, all line voltage heating and ventilating control panels, fire detector and sprinkler alarms, door bells, pilot lights, disconnect switches, manual starting switches, and magnetic starters. Process control devices and pilot lights shall have

identification plates.

Furnish identification plates for all line voltage enclosed circuit breakers, identifying the equipment served, voltage, phase(s) and power source. Circuits 480 volts and above shall have conspicuously located warning signs in accordance with OSHA requirements.

3.10 PAINTING

Exposed conduit, supports, fittings, cabinets, pull boxes, and racks shall be thoroughly cleaned and painted as specified in Section 09 90 00 PAINTS AND COATINGS.

3.11 FIELD TESTING

Submit Test Reports in accordance with referenced standards in this section.

After completion of the installation and splicing, and prior to energizing the conductors, perform wire and cable continuity and insulation tests as herein specified before the conductors are energized.

Contractor shall provide all necessary test equipment, labor, and personnel to perform the tests, as herein specified.

Isolate completely all wire and cable from all extraneous electrical connections at cable terminations and joints. Substation and switchboard feeder breakers, disconnects in combination motor starters, circuit breakers in panel boards, and other disconnecting devices shall be used to isolate the circuits under test.

Perform Insulation-Resistance Test on each field-installed conductor with respect to ground and adjacent conductors. Applied potential shall be 500 volts dc for 300 volt rated cable and 1000 volts dc for 600 volt rated cable. Take readings after 1 minute and until the reading is constant for 15 seconds. Minimum insulation-resistance values shall not be less than 25 Megohms for 300 volt rated cable and 100 Megohms for 600 volt rated cable. For circuits with conductor sizes 8AWG and smaller insulation resistance testing is not required.

Perform Continuity Test to insure correct cable connection (i.e correct phase conductor, grounded conductor, and grounding conductor wiring) end-to end. Any damages to existing or new electrical equipment resulting from contractor mis-wiring will be repaired and re-verified at contractor's expense. All repairs shall be approved by the CO prior to acceptance of the repair.

Conduct Phase-Rotation Tests on all three-phase circuits using a phase-rotation indicating instrument. Perform phase rotation of electrical connections to connected equipment clockwise, facing the source.

Final acceptance will depend upon the successful performance of wire and cable under test. Do not energize any conductor until the final test reports are reviewed and approved by the CO.

-- End of Section --

SECTION 26 05 13.00 40

MEDIUM-VOLTAGE CABLES
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

AEIC C8	(2000) Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV
AEIC CS1	(1990e11) Impregnated-Paper-Insulated, Metallic Sheathed Cable, Solid Type

ASTM INTERNATIONAL (ASTM)

ASTM B 3	(2001; R 2007) Standard Specification for Soft or Annealed Copper Wire
ASTM D 746	(2007) Standard Test Method for Brittleness Temperature of Plastics and Elastomers by Impact

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE Std 383	(2003) Standard for Qualifying Class 1E Electric Cables and, Field Splices for Nuclear Power Generating Stations 2004
IEEE Std 400.2	(2004) Guide for Field Testing of Shielded Power Cable Systems Using Very Low Frequency (VLF)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA WC 70	(2009) Standard for Non-Shielded Power Cable 2000 V or Less for the Distribution of Electrical Energy
NEMA WC 71	(1999) Standard for Nonshielded Cables Rated 2001-5000 Volts for use in the Distribution of Electric Energy
NEMA WC 74	(2006) Standard for 5-46 kV Shielded Power Cable for use in the Transmission and Distribution of Electric Energy

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-228	(2000) Cable and Wire, Insulated; Methods of Testing

1.2 DEFINITIONS

Medium voltage power cables includes all cables rated above 600 to 35,000 volts.

1.3 GENERAL REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to work specified in this section.

Provide Certificates for the following showing that the cable manufacturer has made factory-conducted tests on each shipping length of cable. Provide certified copies of test data that shows conformance with the referenced standards and is approved prior to delivery of cable.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that reviews the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Provide equipment and performance data and manufacturer's catalog data for the following items:

Single-Conductor Shielded Cables

SD-06 Test Reports

Provide test reports for the following in accordance with the paragraph entitled, "Field Testing," of this section.

Dielectric Absorption Tests
High-Voltage Tests
Radiographic Tests

SD-07 Certificates

Provide listing of products installed showing qualifications of Cable Splicers to the Contracting Officer prior to specified work.

Provide Certificates for the following:

Flammability
Minimum Bending Radius
High-Voltage Tests
Dielectric Absorption Tests
Cable Splicers

SD-08 Manufacturer's Instructions

Provide manufacturer's instructions showing the recommended sequence and method of installation for the following:

Medium-Voltage Power Cables
High-Voltage Power Cables
Pothead Terminations

1.5 QUALIFICATIONS

Cable splicers performing splicing are required to have 5 years experience in cable splicing and terminations. Once a termination or splice has been started by a worker, the same person completes that particular splice. Start and complete each termination and splice in one continuous work period.

1.6 CABLE VOLTAGE RATINGS

Provide Medium-voltage power cables single-conductor cables rated as follows, phase-to-phase, for grounded and ungrounded neutral systems:

Use cables rated 15,000 volts, ungrounded neutral, on 12,470-volt, three-phase, 60-hertz distribution systems.

1.7 SHIPMENT

Ship cables on reels such that the cable is protected from mechanical injury. Hermetically seal and securely attach each end of each length of cable to the reel.

Make minimum reel drum diameter 14 times the overall diameter of the cable. Provide a pulling eye that is installed by the manufacturer for each length of cable supplied for installation in ducts, manholes, and utility tunnels.

PART 2 PRODUCTS

2.1 CONDUCTORS

Provide conductors that are solid copper conforming to ASTM B 3.

2.2 CABLE IDENTIFICATION

Provide cables that have a tape placed immediately under the lead sheath or outer jacket showing the name of the manufacturer, the year in which the cable was manufactured, and a unique number for identification purposes. Closely group information on the tape at 300 millimeter intervals to permit complete identification.

2.3 FLAMMABILITY

Test cables not to be enclosed in metallic conduit for flammability in accordance with FED-STD-228, Method 5221 vertical, IEEE Std 383,20000 watt per hour vertical tray flame test.

2.4 MULTIPLE-CONDUCTOR SHIELDED CABLES

2.4.1 Cross-Linked Polyethylene with PVC Jacket

Provide multiple-conductor, cross-linked polyethylene-insulated, polyvinylchloride-jacketed, shielded cable that conforms to NEMA WC 70, NEMA WC 71, NEMA WC 74 and AEIC C8. Provide taped shielding that consists of 0.13 millimeter thick copper shielding lap applied over 0.30 millimeter thick semiconducting tape. Wrap both helically with 10-percent overlap, providing 100-percent coverage.

2.5 SINGLE-CONDUCTOR SHIELDED CABLES

2.5.1 Cross-Linked Polyethylene with PVC Jacket

Provide single-conductor, polyethylene-insulated, polyvinylchloride-jacketed, shielded cable that conforms to NEMA WC 70, NEMA WC 71, NEMA WC 74 and AEIC C8.

2.6 NONMETALLIC JACKET

2.6.1 Terminations

Provide potheads with grounding terminals and cast-aluminum bells that is rated as follows:

Indoor - 15 kilovolts (kV) rating, to withstand 45 kV ac for 10 seconds, minimum

Outdoor - 25 kV rating, to withstand 60 kV ac for 10 seconds, minimum

2.7 CABLE SUPPORTS AND FITTINGS

Provide cable supports, related fittings, and accessories for use in corrosive underground locations, such as manholes and utility tunnels, with a factory applied coating of polyvinylchloride of at least 0.51 millimeter thick. Provide polyvinylchloride (PVC) coated items that have a uniform thickness and be free of blisters, breaks, and holidays. Provide PVC compound that conforms to ASTM D 746.

Provide cable racks, cable tray supports and related fittings that are UL listed standard.

PART 3 EXECUTION

3.1 INSTALLATION

Install medium-voltage cables in accordance with NFPA 70.

Install cable in underground duct banks; in conduit above and below grade.

When field cuts or other damage occurs to the PVC coating, apply a liquid PVC patch to maintain the integrity of the coating. After the installation is complete, perform an inspection to ensure the absence of voids, pinholes, or cuts.

3.1.1 Protection During Splicing Operations

Provide blower to force fresh air into manholes or confined areas where

free movement or circulation of air is obstructed. Make waterproof protective coverings available on the work site to provide protection against moisture while a splice is being made. Use pumps to keep manholes dry during splicing operations. Never make a splice or termination with the interior of a cable exposed to moisture. Moisture-test conductor insulation paper before the splice is made. Use a manhole ring at least 150 millimeter above ground around the manhole entrance to keep surface water from entering the manhole. Plug unused ducts and stop water seepage through ducts in use before the splice is started.

3.1.2 Pulling Cables in Ducts, Manholes and Utility Tunnels

Pull medium-voltage cables into ducts and utility tunnels with equipment designed for this purpose, including power-driven winch, cable-feeding flexible tube guide, cable grips, and lubricants. Employ a sufficient number of trained personnel and equipment to ensure the careful and proper installation of the cable.

Set up cable reel at the side of the manhole or tunnel hatch opening and above the duct or hatch level, allowing the cable to enter through the opening without reverse bending. Install flexible tube guide through the opening in a manner that prevents the cable from rubbing on the edges of any structural member.

Allow for a pulling force for a cable grip on lead-sheathed cable that does not exceed 6700 newton per 650 square millimeter of sheath cross-sectional area. Use a dynamometer in the pulling line to ensure that the pulling force is not exceeded. Allow for a pulling force for a nonmetallic-sheathed cable that does not exceed the smaller of 4400 newton or a value computed from the following equation:

TM = 0.008 X N X CM

Where: TM = maximum allowable pulling tension in newton

N = number of conductors in the cable

CM = cross-sectional area of each conductor in square millimeter

Unreel cable from the top of the reel. Carefully control payout. Make cable to be pulled be attached through a swivel to the main pulling wire by means of a pulling eye suitable cable grip permitted only on cables less than 60 meter long and less than 50 millimeter in diameter.

Use woven-wire cable grips to grip the cable end when pulling small cables and short straight lengths of heavier cables.

Attach pulling eyes to the cable conductors to prevent damage to the cable structure.

Use pulling eyes and cable grips together for nonmetallic sheathed cables to prevent damage to the cable structure.

Provide a Minimum bending radius in accordance with the following:

CABLE TYPE	MINIMUM BENDING RADIUS MULTIPLIER TIMES CABLE DIAMETER
RUBBER- AND PLASTIC-IN-	

CABLE TYPE	MINIMUM BENDING RADIUS MULTIPLIER TIMES CABLE DIAMETER
SULATED CABLE WITH OR WITHOUT INTERLOCKED ARMOR	
Shielded cables with shielding wire	8

Liberally coat cables with a suitable cable-pulling lubricant as it enters the tube guide or duct. Use grease and oil lubricants only on lead-sheathed cables. Cover nonmetallic sheathed cables with wire-pulling compounds when required which have no deleterious effects on the cable. Provide rollers, sheaves, or tube guides around which the cable is pulled that conform to the minimum bending radius of the cable.

Pull cables into ducts at a speed not to exceed 50 feet per minute and not in excess of maximum permissible pulling tension specified by the cable manufacturer. Cable pulling using a vehicle is not permitted. Stop pulling operations immediately with any indication of binding or obstruction and do not resume until such difficulty is corrected. Provide sufficient slack for free movement of cable due to expansion or contraction.

Make cable splices made up in manholes or utility tunnels that are firmly supported on cable racks as indicated. Do not pull cable splices in ducts. Overlap cable ends at the ends of a section to provide sufficient undamaged cable for splicing. Make cables to be spliced in manholes or utility tunnels overlap the centerline of the proposed joint by not less than 600 millimeter.

Provide cables cut in the field that have the cut ends immediately sealed to prevent entrance of moisture. Seal nonleaded cables with rubber tape wrapped down to 75 millimeter from the cable end. Cover-wrap rubber tape with polyvinylchloride tape.

3.1.3 Splices and Terminations

Make splices in manholes or tunnels except where cable terminations are specifically indicated. Expedite splicing and terminating of cables to minimize exposure and cable deterioration.

Terminate cables in potheads. Dry terminations with medium voltage pennants, preformed, and hand wrapped stress cones are allowed for terminating cables. Provide potheads with adequate means for making external connections to the cable conductors of single- conductor cables; protecting the cable insulation against moisture, oil, or other contaminant; physically protecting and supporting cables, and maintaining the insulation level of the cable.

Field-fabricate Pothead terminations from termination kits supplied by and in accordance with the pothead manufacturer's recommendations for the type, size, and electrical characteristics of the cable.

Installation includes built-up or prefabricated heat or cold shrink stress-relief cones at the terminals of all shielded cables and at the terminals of single-conductor lead-covered cables rated 15 kV and above, ungrounded.

Field fabricate cable splices from splicing kits supplied by and in

accordance with the cable manufacturer's recommendations for the type, size, and electrical characteristics of the cable specified. Locate cable splices in manholes midway between cable racks on walls of manholes and supported with cable arms at approximately the same elevation as the enclosing duct.

Cable splices in the tunnel which are not installed in cable trays, install on cable racks or by other approved methods which minimize physical stress on the splice connections. Support splices at approximately the same elevation as the installed cable except where space limitations or existing cable length limitations make this method impractical or impossible.

Support all universal demountable splices in such manner so as to minimize physical stress on the splice connections. Support each cable end termination using a pair of saddle type supports under the cable end termination and/or cable with a minimum 300 millimeter and a maximum 750 millimeter separation between the supports. Secure cable end termination and cable to the supports in such a manner as to prevent movement of termination or cable at the support. Install saddle type supports on galvanized steel framing channel anchored to the wall or securely fastened to the cable tray or installed by other approved methods.

3.1.4 Multiple-Conductor Potheads

Provide multiple-conductor potheads that are hermetically sealed capnut type and that are suitable for the type, size, and electrical characteristics of the cable. Provide potheads that consist of bells or bodies with bell caps, bushing, cable connectors, lugs, and entrance fittings.

Provide bushings that are glazed wet-process electrical porcelain insulators, factory assembled and hermetically sealed to bell cap.

Provide cable connectors that are high-conductivity copper accurately machined and threaded for internal and external electrical connections. Provide cross-sectional and contact areas that are adequate to carry the full-load current rating of the conductors. Provide solder type cable connectors with gasket seal between the connector and bushing.

Provide cable-entrance fittings that are cast-bronze wiping-sleeve type for lead-covered cable, and cast-aluminum positive-sealed stuffing boxes for nonlead-covered cables. Provide cast iron conduit couplings and armor base fittings.

Three-conductor potheads with a neutral stud and lug are allowed in lieu of four-conductor potheads in four-wire grounded neutral systems.

Provide completely filled potheads, leaving no gaps or voids, with an insulating compound suitable for the type of cable, insulation, voltage rating, and ambient operating temperatures in accordance with the pothead manufacturer's recommendations. Ground pothead parts that do not carry current.

3.2 FIELD TESTING

Subject each to dielectric-absorption tests and high-voltage tests after the installation of high-voltage power cables has been completed, including splices, joints, and terminations, and before the cable is energized.

Provide test equipment, labor, and technical personnel as necessary to perform the electrical acceptance tests.

Make arrangements to have tests witnessed and approved by the Contracting Officer.

Completely isolate each power-cable installation from extraneous electrical connections at cable terminations and joints. Observe safety precautions.

First give each power cable a full dielectric-absorption test with 5000-volt insulation-resistance test set. Apply test for a long enough time to fully charge the cable. Record readings every 15 seconds during the first 3 minutes of test and at 1 minute intervals thereafter. Continue test until three equal readings, 1 minute apart, are obtained. Minimum reading is 200 megohms at an ambient temperature of 20 degrees C. Correct readings taken at other than 20 degrees C ambient temperatures.

Upon successful completion of the dielectric absorption tests, subject the cable to a direct-current high-potential test for 5 minutes with test voltages applied in accordance with AEIC CS1 and IEEE Std 400.2 for paper-impregnated, lead-covered cable; AEIC C8 and IEEE Std 400.2 for cross-linked, polyethylene-insulated cable; and AEIC C8 and IEEE Std 400.2 for ethylene propylene rubber-insulated cable.

Record leakage current readings every 30 seconds during the first 2 minutes and every minute thereafter for the remainder of the test. When the leakage current continues to increase after the first minute, immediately terminate the test and take steps to find and correct the fault. When a second test becomes necessary, repeat this test procedure.

Upon satisfactory completion of the high-potential test, give the cable a second dielectric-absorption test as before.

Provide results of the second dielectric-absorption test that agree with the first test and that indicate no evidence of permanent injury to the cable caused by the high-potential test.

Record test data and include identification of cable and location, megohm readings versus time, leakage current readings versus time, and cable temperature versus time.

Final acceptance depends upon the satisfactory performance of the cable under test. Do not energize cable until recorded test data has been approved by the Contracting Officer Provide final test reports to the Contracting Officer. Provide reports with a cover letter/sheet clearly marked with the System name, Date, and the words "Final Test Report - Forward to the Systems Engineer/Condition Monitoring Office/Predictive Testing Group for inclusion in the Maintenance Database."

Perform Radiographic tests on all potheads at the discretion of the Contracting Officer to determine if voids exist in the pothead. Rework unacceptable terminations at no additional expense to the Government.

-- End of Section --

SECTION 26 05 19.00 10

INSULATED WIRE AND CABLE
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

AEIC C8	(2000) Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV
AEIC CS8	(2000) Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE Std 383	(2003) Standard for Qualifying Class 1E Electric Cables and, Field Splices for Nuclear Power Generating Stations 2004

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA WC 70	(2009) Standard for Non-Shielded Power Cable 2000 V or Less for the Distribution of Electrical Energy

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Installation Instructions

Cable manufacturing data as requested.

SD-06 Test Reports

Tests, Inspections, and Verifications

____ certified copies of test reports.

1.3 DELIVERY, STORAGE, AND HANDLING

Furnish cables on reels or coils. Each cable and the outside of each reel

or coil, shall be plainly marked or tagged to indicate the cable length, voltage rating, conductor size, and manufacturer's lot number and reel number. Each coil or reel of cable shall contain only one continuous cable without splices. Reels shall remain the property of the Contractor.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Rated Circuit Voltages

All wire and cable shall have minimum rated circuit voltages in accordance with NEMA WC 70.

2.1.2 Conductors

2.1.2.1 Material for Conductors

Conductors shall conform to all the applicable requirements of NEMA WC 70, as applicable, and shall be annealed copper. Copper conductors may be bare, or tin- or lead-alloy-coated, if required by the type of insulation used.

2.1.2.2 Size

Minimum wire size shall be No. 12 AWG for power and lighting circuits; No. 10 AWG for current transformer secondary circuits; No. 14 AWG for potential transformer, relaying, and control circuits; No. 16 AWG for annunciator circuits; and No. 19 AWG for alarm circuits. Minimum wire sizes for rated circuit voltages of 2,001 volts and above shall not be less than those listed for the applicable voltage in NEMA WC 70, as applicable.

2.1.2.3 Stranding

Conductor stranding classes cited herein shall be as defined in NEMA WC 70, as applicable. Lighting conductors No. 10 AWG and smaller shall be solid or have Class B stranding. Any conductors used between stationary and moving devices, such as hinged doors or panels, shall have Class H or K stranding. All other conductors shall have Class B or C stranding, except that conductors shown on the drawings, or in the schedule, as No. 12 AWG may be 19 strands of No. 25 AWG, and conductors shown as No. 10 AWG may be 19 strands of No. 22 AWG.

2.1.2.4 Conductor Shielding

Use conductor shielding conforming to NEMA WC 70, as applicable, on power cables having a rated circuit voltage above 2,000 volts. In addition, conductor shielding for shielded cables shall also comply with Section C of AEIC C8 or AEIC CS8. Strict precautions shall be taken after application of the conductor shielding to prevent the inclusion of voids or contamination between the conductor shielding and the subsequently applied insulation.

2.1.2.5 Separator Tape

Where conductor shielding, strand filling, or other special conductor treatment is not required, a separator tape between conductor and insulation is permitted.

2.1.3 Insulation

2.1.3.1 Insulation Thickness

The insulation thickness for each conductor shall be based on its rated circuit voltage.

Power Cables/Single-Conductor Control Cables, 2,000 Volts and Below - The insulation thickness for single-conductor cables rated 2,000 volts and below shall be as required by NEMA WC 70, as applicable. Some thicknesses of NEMA WC 70 will be permitted only for single-conductor cross-linked thermosetting polyethylene insulated cables without a jacket. NEMA WC 70 ethylene-propylene rubber-insulated conductors shall have a jacket.

2.1.4 Jackets

2.1.4.1 Jacket Thickness

The minimum thickness of the jackets at any point shall be not less than 80 percent of the respective nominal thicknesses specified below.

a. Multiple-Conductor Cables - Thickness of the jackets of the individual conductors of multiple-conductor cables shall be as required by NEMA WC 70, and shall be in addition to the conductor insulation thickness required by Column B of Table 3-1 of the applicable NEMA publication for the insulation used. Thickness of the outer jackets or sheaths of the assembled multiple-conductor cables shall be as required by NEMA WC 70.

b. Single-Conductor Cables - Single-conductor cables, if nonshielded, shall have a jacket thickness as specified in NEMA WC 70. If shielded, the jacket thickness shall be in accordance with the requirements of NEMA WC 70.

2.1.5 Metal-Clad Cable

2.1.5.1 General

The metallic covering shall be interlocked steel tape, conforming to the applicable requirements of NEMA WC 70. If the covering is of ferrous metal, it shall be galvanized. Copper grounding conductor(s) conforming to NEMA WC 70 shall be furnished for each multiple-conductor metal-clad cable. Assembly and cabling shall be as specified in paragraph CABLING. The metallic covering shall be applied over an inner jacket or filler tape. The cable shall be assembled so that the metallic covering will be tightly bound over a firm core.

2.1.5.2 Jackets

Metal-clad cables may have a jacket under the armor, and shall have a jacket over the armor. Jackets shall comply with the requirements of NEMA WC 70. The outer jacket for the metal-clad cable may be of polyvinyl chloride only if specifically approved.

2.2 CABLE IDENTIFICATION

2.2.1 Color-Coding

Insulation of individual conductors of multiple-conductor cables shall be color-coded in accordance with NEMA WC 70, except that colored braids will not be permitted. Only one color-code method shall be used for each cable construction type. Control cable color-coding shall be in accordance with NEMA WC 70. Power cable color-coding shall be black for Phase A, red for Phase B, blue for Phase C, white for grounded neutral, and green for an insulated grounding conductor, if included. Other individual conductors shall be color-coded as indicated on the contract drawings but such color-coding may be accomplished by applying colored plastic tapes or sleeving at terminations.

2.2.2 Shielded Cables Rated 2,001 Volts and Above

Marking shall be in accordance with Section H of AEIC C8 or AEIC CS8, as applicable.

2.2.3 Cabling

Individual conductors of multiple-conductor cables shall be assembled with flame-and moisture-resistant fillers, binders, and a lay conforming to NEMA WC 70, except that flat twin cables will not be permitted. Fillers shall be used in the interstices of multiple-conductor round cables with a common covering where necessary to give the completed cable a substantially circular cross section. Fillers shall be non-hygroscopic material, compatible with the cable insulation, jacket, and other components of the cable. The rubber-filled or other approved type of binding tape shall consist of a material that is compatible with the other components of the cable and shall be lapped at least 10 percent of its width.

2.2.4 Dimensional Tolerance

The outside diameters of single-conductor cables and of multiple-conductor cables shall not vary more than 5 percent and 10 percent, respectively, from the manufacturer's published catalog data.

PART 3 EXECUTION

3.1 INSTALLATION INSTRUCTIONS

The following information shall be provided by the cable manufacturer for each size, conductor quantity, and type of cable furnished:

a. Minimum bending radius, in inches - For multiple-conductor cables, this information shall be provided for both the individual conductors and the multiple-conductor cable.

b. Pulling tension and sidewall pressure limits, in newtons.

c. Instructions for stripping semiconducting insulation shields, if furnished, with minimum effort without damaging the insulation.

d. Upon request, compatibility of cable materials and construction with specific materials and hardware manufactured by others shall be stated. Also, if requested, recommendations shall be provided for various cable operations, including installing, splicing, terminating,

etc.

3.2 TESTS, INSPECTIONS, AND VERIFICATIONS

3.2.1 Cable Data

Manufacture of the wire and cable shall not be started until all materials to be used in the fabrication of the finished wire or cable have been approved by the Contracting Officer. Cable data shall be submitted for approval including dimensioned sketches showing cable construction, and sufficient additional data to show that these specifications will be satisfied.

3.2.2 Inspection and Tests

Inspection and tests of wire and cable furnished under these specifications shall be made by and at the plant of the manufacturer, and shall be witnessed by the Contracting Officer or his authorized representative, unless waived in writing. The Government may perform further tests before or after installation. Testing in general shall comply with NEMA WC 70. Specific tests required for particular materials, components, and completed cables shall be as specified in the sections of the above standards applicable to those materials, components, and cable types. Tests shall also be performed in accordance with the additional requirements specified below.

3.2.2.1 High-Voltage Test Source

Where the applicable standards allow a choice, high-voltage tests for cables to be used exclusively on dc circuits shall be made with dc test voltages. Cables to be used exclusively on ac circuits shall be tested with ac test voltages. If both ac and dc will be present, on either the same or separate conductors of the cable, ac test voltages shall be used.

3.2.2.2 Shielded Cables Rated 2,001 Volts or Greater

The following tests shall be performed in addition to those specified above. Section or paragraph references are to AEIC C8 or AEIC CS8 as applicable, unless otherwise stated.

a. High potential test voltages shall be as required by Table B1 of AEIC C8 or AEIC CS8 as applicable, rather than by NEMA WC 70.

b. If high potential testing is done with an ac test voltage as specified in paragraph HIGH-VOLTAGE TEST SOURCE, an additional test shall be made using a dc test voltage rated at 75 percent of the specified full dc test voltage, for 5 consecutive minutes.

c. Production sampling tests shall be performed in accordance with Section D. Sampling frequency and failure contingencies shall be in accordance with paragraph G.3. Unless otherwise approved, samples shall not be taken from the middle of extruder runs of insulation or shielding made only for one continuous shipping length of cable, if such sampling will result in the need to repair the sampled area.

d. Partial discharge tests shall be performed in accordance with Section E, paragraph E.2, and Section F.

3.2.2.3 Flame Tests

All multiple-conductor and single-conductor cable assemblies shall pass IEEE Std 383 flame tests, paragraph 2.5, using the ribbon gas burner. Single-conductor cables and individual conductors of multiple-conductor cables shall pass the flame test of NEMA WC 70. If such tests, however, have previously been made on identical cables, these tests need not be repeated. Instead, certified reports of the original qualifying tests shall be submitted. In this case the reports furnished under paragraph REPORTS, shall verify that all of each cable's materials, construction, and dimensions are the same as those in the qualifying tests.

3.2.2.4 Independent Tests

The Government may at any time make visual inspections, continuity or resistance checks, insulation resistance readings, power factor tests, or dc high-potential tests at field test values. A cable's failure to pass these tests and inspections, or failure to produce readings consistent with acceptable values for the application, will be grounds for rejection of the cable.

3.2.2.5 Reports

Furnish results of tests made. No wire or cable shall be shipped until authorized. Lot number and reel or coil number of wire and cable tested shall be indicated on the test reports.

-- End of Section --

SECTION 26 05 48.00 10

SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 325 (2005e13) Manual of Steel Construction

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-310-03A (2005) Seismic Design for Buildings

UNDERWRITERS LABORATORIES (UL)

UL 1598 (2004; Rev thru May 2006) Luminaires

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Lighting Fixtures in Buildings
Equipment Requirements

Detail drawings along with catalog cuts, templates, and erection and installation details, as appropriate, for the items listed. Submittals shall be complete in detail; shall indicate thickness, type, grade, class of metal, and dimensions; and shall show construction details, reinforcement, anchorage, and installation with relation to the building construction.

SD-03 Product Data

Lighting Fixtures in Buildings
Equipment Requirements

Copies of the design calculations with the detail drawings. Calculations shall be stamped by a registered engineer and shall verify the capability of structural members to which bracing is attached for carrying the load from the brace.

Contractor Designed Bracing

Copies of the Design Calculations with the Drawings.

Calculations shall be approved, certified, stamped and signed by a Registered Professional Engineer. Calculations shall verify the capability of structural members to which bracing is attached for carrying the load from the brace.

1.3 SYSTEM DESCRIPTION

1.3.1 General Requirements

The requirements for seismic protection measures described in this section shall be applied to the electrical equipment and systems listed below. Structural requirements shall be in accordance with Section 13 48 00 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT.

1.3.2 Electrical Equipment

Electrical equipment shall include the following items to the extent required on the drawings or in other sections of these specifications:

Control Panels	Air Handling Units
Pumps with Motors	Light Fixtures
Motor Control Centers	Transformers
Switchboards (Floor Mounted)	

1.3.3 Electrical Systems

The following electrical systems shall be installed as required on the drawings and other sections of these specifications and shall be seismically protected in accordance with this specification:

1.3.4 Contractor Designed Bracing

The Contractor shall design the bracing in accordance with UFC 3-310-03A and additional data furnished by the Contracting Officer. Resistance to lateral forces induced by earthquakes shall be accomplished without consideration of friction resulting from gravity loads. UFC 3-310-03A uses parameters for the building, not for the equipment in the building; therefore, corresponding adjustments to the formulas shall be required. Loadings determined using UFC 3-310-03A are based on strength design; therefore, AISC 325 shall be used for the design. The bracing for the following electrical equipment and systems shall be developed by the Contractor.

1.3.5 Conduits Requiring No Special Seismic Restraints

Seismic restraints may be omitted from electrical conduit less than 64 mm trade size. All other interior conduit, shall be seismically protected as specified.

1.4 EQUIPMENT REQUIREMENTS

1.4.1 Rigidly Mounted Equipment

The following specific items of equipment are to be furnished under this contract shall be constructed and assembled to withstand the seismic forces specified in UFC 3-310-03A, Chapter 10. Each item of rigid electrical equipment shall be entirely located and rigidly attached on one side only of a building expansion joint. Piping, electrical conduit, etc., which cross the expansion joint shall be provided with flexible joints that are

capable of accommodating displacements equal to the full width of the joint in both orthogonal directions.

Transformers
Switch Boards

PART 2 PRODUCTS

2.1 LIGHTING FIXTURE SUPPORTS

Lighting fixtures and supports shall conform to UL 1598.

2.2 SWAY BRACING MATERIALS

Sway bracing materials (e.g. rods, plates, rope, angles, etc.) shall be as specified in Section 13 48 00 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT.

PART 3 EXECUTION

3.1 SWAY BRACES FOR CONDUIT

Conduit shall be braced as for an equivalent weight pipe in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.2 LIGHTING FIXTURES IN BUILDINGS

Lighting fixtures and supports shall conform to the following:

3.2.1 Pendant Fixtures

Pendant fixtures shall conform to the requirements of UFC 3-310-03A, Chapter 10.

3.2.2 Ceiling Attached Fixtures

3.2.2.1 Recessed Fluorescent Fixtures

Recessed fluorescent individual or continuous-row mounted fixtures shall be supported by a seismic-resistant suspended ceiling support system built in accordance with ASTM E580. Seismic protection for the fixtures shall conform to the requirements of UFC 3-310-03A, Chapter 10. Recessed lighting fixtures not over 25 kg in weight may be supported by and attached directly to the ceiling system runners using screws or bolts, number and size as required by the seismic design. Fixture accessories, including louvers, diffusers, and lenses shall have lock or screw attachments.

3.2.2.2 Surface-Mounted Fluorescent Fixtures

Surface-mounted fluorescent individual or continuous-row fixtures shall be attached to a seismic-resistant ceiling support system built in accordance with ASTM E580. Seismic protection for the fixtures shall conform to the requirements of UFC 3-310-03A, Chapter 10.

3.2.3 Assembly Mounted on Outlet Box

A supporting assembly, that is intended to be mounted on an outlet box, shall be designed to accommodate mounting features on 100 mm boxes, plaster rings, and fixture studs.

3.2.4 Wall-Mounted Emergency Light Unit

Attachments for wall-mounted emergency light units shall be designed and secured for the worst expected seismic disturbance at the site.

3.2.5 Lateral Force

Structural requirements for light fixture bracing shall be in accordance with Section 13 48 00 SEISMIC PROTECTION FOR MISCELLANIOUS EQUIPMENT.

-- End of Section --

SECTION 26 05 70.00 40

HIGH VOLTAGE OVERCURRENT PROTECTIVE DEVICES
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C39.1	(1981; R 1992) Requirements for Electrical Analog Indicating Instruments

ASTM INTERNATIONAL (ASTM)

ASTM D 877	(2002; R 2007) Standard Test Method for Dielectric Breakdown Voltage of Insulating Liquids Using Disk Electrodes

ELECTRONIC INDUSTRIES ALLIANCE (EIA)

EIA 443	(1979) Standard for Solid-State Relay Service, EIA/NARM

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C37.09	(1999; Corrigendum 2007; Errata 2007) IEEE Standard Test Procedure for AC High-Voltage Circuit Breakers Rated on a Symmetrical Current Basis
IEEE C37.17	(1997) Standard for Trip Devices for AC and General-Purpose DC Low-Voltage Power Circuit Breakers
IEEE C37.121	(1989; R 2006) American National Standard for Switchgear Unit Substations Requirements
IEEE C37.90	(2005) Standard for Relays and Relay Systems Associated With Electric Power Apparatus
IEEE C57.13	(2008) Standard Requirements for Instrument Transformers
IEEE C63.2	(1996) Standard for Electromagnetic Noise and Field Strength Instrumentation, 10 Hz to 40 GHz - Specifications
IEEE C63.4	(2009) American National Standard for Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and

	Electronic Equipment in the Range of 9 kHz to 40 GHz

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 107	(1998; R 1993) Methods of Measurement of Radio Influence Voltage (RIV) of High-Voltage Apparatus
NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA AB 1	(2002) Molded-Case Circuit Breakers, Molded Case Switches, and Circuit-Breaker Enclosures
NEMA AB 3	(2001) Molded Case Circuit Breakers and Their Application
NEMA C12.1	(2008) Electric Meters; Code for Electricity Metering
NEMA C78.23	(1995; R 2003) Standard for Incandescent Lamps - Miscellaneous Types
NEMA FU 1	(2002; R 2007) Low Voltage Cartridge Fuses
NEMA ICS 1	(2000; R 2005; R 2008) Standard for Industrial Control and Systems General Requirements
NEMA ICS 2	(2000; Errata 2002; R 2005; Errata 2006) Standard for Industrial Control and Systems: Controllers, Contactors, and Overload Relays Rated Not More than 2000 Volts AC or 750 Volts DC: Part 8 - Disconnect Devices for Use in Industrial Control Equipment
NEMA ICS 3	(2005) Standard for Industrial Control and Systems: Medium Voltage Controllers Rated 2001 to 7200 Volts AC
NEMA ICS 6	(1993; R 2006) Standard for Industrial Controls and Systems Enclosures
NEMA SG 2	(1993) Standard for High-Voltage Fuses

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 489	(2009) Standard for Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that reviews the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Prior to the beginning of construction submit manufacturer's equipment and performance data for the following items including use life, system functional flows, safety features, and mechanical automated details.

Fuses

SD-02 Shop Drawings

Submit Connection Diagrams and Fabrication Drawings for the following items in accordance with paragraph entitled, "General Requirements," of this section.

Submit Installation drawings for the following items in accordance with the paragraph entitled, "Installation," of this section.

Control Devices
Protective Devices

SD-03 Product Data

Submit manufacturer's equipment and performance data for the following items including use life, system functional flows, safety features, and mechanical automated details.

Instrument Transformers
Enclosures
Circuit Breakers; G
Control Devices
Protective Relays
Indicating Instruments
Indicating Lights

SD-06 Test Reports

Submit Factory Test Reports for Power, High Voltage, and Oil Circuit Breakers in accordance with IEEE C37.09.

Dielectric Tests
Timing Test
Insulation Power Factor Test

SD-07 Certificates

Submit certificates for Circuit Tests on similar motor-control or submit motor-circuit protector (MCP) units under actual conditions in lieu of factory tests on the actual units provided.

SD-08 Manufacturer's Instructions

Submit manufacturer's instructions for the following items, including special provisions required to install equipment components and system packages. Provide detail on resistance impedances, hazards and safety precautions within the special notices.

Control Devices
Protective Devices

SD-10 Operation and Maintenance Data

Submit Operation and Maintenance Manuals for the following equipment:

Circuit Breakers
Protective Relays
Indicating Instruments

1.3 GENERAL REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to work specified in this section.

Submit Connection Diagrams showing the relations and connections of control devices and protective devices by showing the general physical layout of all controls, the interconnection of one system (or portion of system) with another, and internal tubing, wiring, and other devices.

Submit Fabrication Drawings for control devices and protective devices consisting of fabrication and assembly details to be performed in the factory.

PART 2 PRODUCTS

2.1 INSTRUMENT TRANSFORMERS

Comply with the interference requirements listed below, measured in accordance with IEEE C63.2, IEEE C63.4, and NEMA 107 for Instrument transformers.

Insulation Class, kV	Basic Insulation Level, kV	Preferred Nominal System Voltage, kV	Test Voltage for Potential Transformers, kV	Test Voltage for Current Transformers, kV	Radio Influence Voltage Level, Microvolts Dry Type	Radio Influence Voltage Level, Microvolts Oil Filled
0.6	10	.....	.....	0.76	250	250
1.2	30	0.208 0.416 0.832 1.04	0.132 0.264 0.528 0.66	0.76	250	250
2.5	45	2.40	1.52	1.67	250	250
5.0	60	4.16 4.80	2.64 3.04	3.34	250	250

Insulation Class, kV	Basic Insulation Level, kV	Preferred Nominal System Voltage, kV	Test Voltage for Potential Transformers, kV	Test Voltage for Current Transformers, kV	Radio Influence Voltage Level, Microvolts Dry Type	Radio Influence Voltage Level, Microvolts Oil Filled
8.7	75	7.20 8.32	4.57 5.28	5.77	250	250
15L or 15H	95-110	12.00 12.47 14.40	7.62 7.92 9.14	9.41	1000	250

2.1.1 Current Transformers

Provide current transformers that conform to IEEE C57.13 for installation in metal-clad switchgear. Use standard 3-A secondary transformer.

Provide window type transformers.

Provide transformers that have single secondary winding.

Provide transformers that are complete with secondary short-circuiting device.

For window-type current transformers, provide indoor dry type construction with secondary current ratings as indicated with specified burden, frequency, and accuracy.

2.1.2 Potential Transformers

For potential transformers, conform to IEEE C57.13 for installation in metal-clad switchgear. Use standard 120-volt secondary transformers.

Provide transformers that have single secondary.

Provide burden, frequency, and accuracy as required.

For disconnecting potential transformers with integral fuse mountings and current-limiting fuses provide indoor dry type two-winding construction with primary and secondary voltage ratings as required.

2.2 ENCLOSURES

2.2.1 Equipment Enclosures

Provide enclosures for equipment in accordance with NEMA 250.

Contain equipment installed in wet locations in NEMA Type 4 watertight, corrosion-resistant sheet-steel enclosure, constructed to prevent entrance of water when tested in accordance with NEMA ICS 6 for Type 4 enclosures.

2.3 CIRCUIT BREAKERS

Provide circuit breakers that conform to UL 489, NEMA AB 1, and NEMA AB 3.

2.3.1 Air Circuit Breakers

Provide circuit breakers that include a ground-fault system or ground-sensing relays.

2.3.1.1 Stored-Energy-Operated Type

For air circuit breakers with stored-energy-operated mechanisms, conform to IEEE C37.121 for metal-clad switchgear rated above 14.4 kilovolts grounded.

Mount metal-clad air circuit breakers on a mobile frame with primary and secondary disconnecting devices, automatic shutters, and mechanical interlocks to allow complete removal of the unit for inspection and maintenance. Provide three-pole, single-throw, electrically operated circuit breakers, with a motor-charged spring, stored-energy mechanism, and electric release coils for tripping and closing operations.

Provide a motor-operated position-changing mechanism that moves the breaker between the test and operating position by means of a levering device. Provide interlocks to prevent the complete withdrawal of the circuit breaker from its compartment when the stored-energy mechanism is in the fully charged position. Design circuit breakers to prevent the release of stored energy unless the mechanism is fully charged.

Provide circuit breakers that have mechanically trip-free mechanisms with direct-current potential trip coils of the voltage indicated, auxiliary switches, latch-checking switches, control relays, and operation counters.

2.4 FUSES

Provide a complete set of fuses for all switches and switchgear. Provide fuses that have a voltage rating of not less than the circuit voltage.

Make no change in continuous-current rating, interrupting rating, and clearing or melting time of fuses unless written permission has first been secured.

Provide nonrenewable cartridge type fuses for ratings 30 amperes, 125 volts or less. Provide renewable cartridge type fuses for ratings above 30 amperes 600 volts or less with time-delay dual elements, except where otherwise indicated. Conform to NEMA FU 1 for fuses.

Install special fuses such as extra-high interrupting-capacity fuses, fuses for welding machines, and capacitor fuses where required. Plug fuses are not permitted.

Provide power fuses on ac systems above 600 volts in accordance with NEMA SG 2.

Label fuses showing UL class, interrupting rating, and time-delay characteristics, when applicable. Additionally, clearly list fuse information on equipment drawings.

Provide porcelain fuse holders when field-mounted in a cabinet or box. Do not use fuse holders made of such materials as ebony asbestos, Bakelite, or pressed fiber for field installation.

2.5 PROTECTIVE RELAYS

2.5.1 Overcurrent Relays

Conform to IEEE C37.90 for overcurrent relays.

For protection against phase and ground faults provide single-phase nondirectional removable induction type overcurrent relays with built-in testing facilities designed for operation on the dc or ac control circuit indicated.

Provide ground-fault overcurrent relays with short-time inverse time characteristics with adjustable current tap range as required.

Provide phase-fault overcurrent relays with varied inverse-time characteristics with adjustable current tap range as required and indicating instantaneous-trip attachments with adjustable current range as required.

Semiflush-mount case with matching cover to the hinged instrument panel.

Provide solid-state static-type trips for low-voltage power circuit breakers in accordance with EIA 443 and IEEE C37.17.

Provide a trip unit that employs a combination of discreet components and integrated circuits to provide the time-current protection functions required in a modern selectively coordinated distribution system.

Provide complete system selective coordination by utilizing a combination of the following time-current curve-shaping adjustments: ampere setting; long-time delay; short-time pickup; short-time delay; instantaneous pickup; and ground fault.

Provide switchable or easily defeatable instantaneous and ground fault trips.

Make all adjustments using non-removable, discrete step, highly reliable switching plugs for precise settings. Provide a sealable, transparent cover over the adjustments to prevent tampering.

Furnish trip devices with three visual indicators to denote the automatic tripping mode of the breaker including: overload; short circuit; and ground fault.

Wire trip unit to appropriate terminals whereby an optional remote automatic trip accessory can be utilized to provide the same indication.

Make available for use a series of optional automatic trip relays for use with the trip unit to provide remote alarm and lockout circuits.

Provide all trip units with test jacks for in-service functional testing of the long-time instantaneous and ground fault circuits using a small hand-held test kit.

2.6 INDICATING INSTRUMENTS

2.6.1 Ammeters

For ammeters, conform to ANSI C39.1.

Provide switchboard indicating ammeters of approximately 115 millimeter square with 250-degree scale and recessed cases suitable for flush mounting. Furnish white dials with black figures and black pointers. Mount instruments on the hinged front panel of the switchgear compartment completely isolated from high-voltage circuits. Provide standard 5-ampere type meter for a zero to full-scale normal movement, 60 hertz.

2.6.2 Voltmeters

For voltmeters, conform to ANSI C39.1.

Provide a switchboard indicating voltmeters that is approximately 115 millimeter square with 250-degree scale and recessed cases suitable for flush mounting. Furnish white dials with black figures and black pointers. Mount instruments on the hinged front panel of the switchgear compartment completely isolated from high-voltage circuits. Provide standard 120-volt type voltmeter for a zero to full-scale normal movement, 60 hertz.

2.7 FACTORY TESTING

Perform factory tests on control and low voltage protective devices in accordance with the manufacturer's recommendations.

Conduct short-circuit tests in accordance with Section 2 of NEMA ICS 1.

Perform factory tests on power, high-voltage, and oil circuit breakers in accordance with IEEE C37.09.

2.8 INDICATING LIGHTS

2.8.1 General-Purpose Type

For indicating lights, provide oiltight instrument devices with threaded base and collar for flush-mounting, translucent convex lens, candelabra screw-base lampholder, and 120-volt, 6-watt, Type S-6 incandescent lamp in accordance with NEMA C78.23. Provide indicating lights color coded in accordance with NEMA ICS 6.

2.8.2 Switchboard Indicating Lights

For switchboard indicating lights, provide the manufacturer's standard transformer type units 120-volt input utilizing low-voltage lamps and convex lenses of the colors indicated. Provide indicating lights that are capable of being relamped from the switchboard front. Indicating lights utilizing resistors in series with the lamps are not permitted, except in direct-current control circuits. Provide lights that have a press-to-test feature.

2.9 FINISH

Protect metallic materials against corrosion. For harsh indoor environments (any area subjected to chemical and/or abrasive action), and all outdoor installations, refer to Section 09 90 00 PAINTS AND COATINGS.

PART 3 EXECUTION

3.1 INSTALLATION

Install Control devices and protective devices that are not factory installed in equipment in accordance with the manufacturer's recommendations and field adjusted and operation tested. Conform to NFPA 70, NEMA ICS 1, NEMA ICS 2, and NEMA ICS 3 requirements for installation of control and protective devices.

3.2 FIELD TESTING

Demonstrate to operate as indicated control and protective devices not factory installed in equipment.

Ratio and verify tap settings of instrumentation, potential, and current transformers.

Give circuit breakers rated 15KV and above a timing test to verify proper contact speed, travel, bounce, and wipe.

Give oil and high-voltage circuit breakers and their bushings an insulation power factor test to establish condition monitoring baselines.

Perform dielectric tests on insulating oil in oil circuit breakers before the breakers are energized. Test oil in accordance with ASTM D 877, and provide breakdown voltage that is not less than 25,000 volts. Provide manufacturer certification that the oil contains no PCB's and affix a label to that effect on each breaker tank and on each oil drum containing the insulating oil.

Field adjust reduced-voltage starting devices to obtain optimum operating conditions. Provide test meters and instrument transformers that conform to NEMA C12.1 and IEEE C57.13.

Do not energize control and protective devices until recorded test data has been approved. Provide final test reports with a cover letter/sheet clearly marked with the System name, Date, and the words "Final Test Reports - Forward to the Systems Engineer/Condition Monitoring Office/Predictive Testing Group for inclusion in the Maintenance Database."

-- End of Section --

SECTION 26 08 00

APPARATUS INSPECTION AND TESTING
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2009) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

1.2 RELATED REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to this section with additions and modifications specified herein.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Acceptance tests and inspections

SD-07 Certificates

Qualifications of organization, and lead engineering technician

Acceptance test and inspections procedure

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

Contractor shall engage the services of a qualified testing organization to provide inspection, testing, calibration, and adjustment of the electrical distribution system and generation equipment listed in paragraph entitled "Acceptance Tests and Inspections" herein. Organization shall be independent of the supplier, manufacturer, and installer of the equipment. The organization shall be a first tier subcontractor. No work required by this section of the specification shall be performed by a second tier subcontractor.

a. Submit name and qualifications of organization. Organization shall have been regularly engaged in the testing of electrical

materials, devices, installations, and systems for a minimum of 5 years. The organization shall have a calibration program, and test instruments used shall be calibrated in accordance with NETA ATS.

b. Submit name and qualifications of the lead engineering technician performing the required testing services. Include a list of three comparable jobs performed by the technician with specific names and telephone numbers for reference. Testing, inspection, calibration, and adjustments shall be performed by an engineering technician, certified by NETA or the National Institute for Certification in Engineering Technologies (NICET) with a minimum of 5 years' experience inspecting, testing, and calibrating electrical distribution and generation equipment, systems, and devices.

1.4.2 Acceptance Tests and Inspections Reports

Submit certified copies of inspection reports and test reports. Reports shall include certification of compliance with specified requirements, identify deficiencies, and recommend corrective action when appropriate. Type and neatly bind test reports to form a part of the final record. Submit test reports documenting the results of each test not more than 10 days after test is completed.

1.4.3 Acceptance Test and Inspections Procedure

Submit test procedure reports for each item of equipment to be field tested at least 45 days prior to planned testing date. Do not perform testing until after test procedure has been approved.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 ACCEPTANCE TESTS AND INSPECTIONS

Testing organization shall perform acceptance tests and inspections. Test methods, procedures, and test values shall be performed and evaluated in accordance with NETA ATS, the manufacturer's recommendations, and paragraph entitled "Field Quality Control" of each applicable specification section. Tests identified as optional in NETA ATS are not required unless otherwise specified. Equipment shall be placed in service only after completion of required tests and evaluation of the test results have been completed. Contractor shall supply to the testing organization complete sets of shop drawings, settings of adjustable devices, and other information necessary for an accurate test and inspection of the system prior to the performance of any final testing. Contracting Officer shall be notified at least 14 days in advance of when tests will be conducted by the testing organization. Perform acceptance tests and inspections on applicable equipment and systems specified in the following sections:

a. Section 26 12 19.00 40 PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS

b. Section 33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION

c. Section 26 13 13 MEDIUM VOLTAGE SWITCHGEAR

3.2 SYSTEM ACCEPTANCE

Final acceptance of the system is contingent upon satisfactory completion of acceptance tests and inspections.

3.3 PLACING EQUIPMENT IN SERVICE

A representative of the approved testing organization shall be present when equipment tested by the organization is initially energized and placed in service.

-- End of Section --

SECTION 26 12 19.00 40

PAD-MOUNTED, LIQUID-FILLED, MEDIUM-VOLTAGE TRANSFORMERS
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE C37.47	(2000) High Voltage Current-Limiting Type Distribution Class Fuses and Fuse Disconnecting Switches
IEEE C57.12.00	(2006) Standard General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers
IEEE C57.12.28	(2005) Standard for Pad-Mounted Equipment - Enclosure Integrity
IEEE C57.12.34	(2004; Errata 2005) Pad-Mounted, Compartmental-Type, Self-Cooled, Three-Phase Distribution Transformers, 2500 kVA and Smaller—High-Voltage: 34 500 GrdY/19 920 Volts and Below; Low Voltage: 480 Volts and Below
IEEE C57.12.80	(2002) Standard Terminology for Power and Distribution Transformers
IEEE C57.12.90	(2006; INT 2009) Standard Test Code for Liquid-Immersed Distribution, Power, and Regulating Transformers
IEEE C57.98	(1993; R 1999) Guide for Transformer Impulse Tests
IEEE C62.11	(2005; Amendment A 2008) Standard for Metal-Oxide Surge Arresters for Alternating Current Power Circuits (>1kV)
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms
IEEE Std 386	(2006) Standard for Separable Insulated Connector Systems for Power Distribution Systems Above 600V

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2009) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA C12.1	(2008) Electric Meters; Code for Electricity Metering

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 467	(2007) Standard for Grounding and Bonding Equipment

1.2 RELATED REQUIREMENTS

Section 26 08 00 APPARATUS INSPECTION AND TESTING applies to this section, with the additions and modifications specified herein.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Transformers manufactured by ABB in Jefferson City, MO; by Cooper Power Systems in Waukesha, WI; by ERMCO in Dyersburg, TN; or by Howard Industries in Laurel, MS need not submit the entire submittal package requirements of this contract. Instead, submit the following items:

a. A certification, from the manufacturer, that the technical requirements of this specification shall be met.

b. An outline drawing of the transformer with devices identified (paragraph entitled "Pad-Mounted Transformer Drawings", item a).

c. ANSI nameplate data of the transformer (paragraph entitled "Pad-Mounted Transformer Drawings", item b).

d. Manufacturer's published time-current curves (on full size logarithmic paper) of the transformer high side fuses (paragraph entitled "Pad-Mounted Transformer Drawings", item e).

e. Routine and other tests (in PART 2, see paragraph entitled "Routine and Other Tests"), shall be conducted by the manufacturer and may be witnessed by the government (in Part 2, see paragraph entitled "Source Quality Control"). Provide transformer test schedule required by submittal item "SD-11 Closeout Submittals". Provide certified copies of the tests.

f. Provide acceptance test reports required by submittal item "SD-06 Test Reports".

g. Provide operation and maintenance manuals required by submittal item "SD-10 Operation and Maintenance Data".

SD-02 Shop Drawings

Pad-mounted transformer drawings; G

SD-03 Product Data

Pad-mounted transformers; G

Submittal shall include manufacturer's information for each component, device, and accessory provided with the transformer.

SD-06 Test Reports

Acceptance checks and tests; G

SD-07 Certificates

Transformer losses; G

Submit certification from the manufacturer indicating conformance with the paragraph entitled "Specified Transformer Losses."

SD-09 Manufacturer's Field Reports

Pad-mounted transformer design tests; G

Pad-mounted transformer routine and other tests; G

SD-10 Operation and Maintenance Data

Transformer(s), Data Package 5

Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein.

SD-11 Closeout Submittals

Transformer test schedule

Submit report of test results as specified by paragraph entitled "Field Quality Control."

1.5 QUALITY ASSURANCE

1.5.1 Pad-Mounted Transformer Drawings

Drawings shall indicate, but not be limited to the following:

a. An outline drawing, with front, top, and side views.

b. ANSI nameplate data.

c. Elementary diagrams and wiring diagrams with terminals identified of watthour meter and current transformers.

d. One-line diagram, including switch(es), current transformers, meters, and fuses.

e. Manufacturer's published time-current curves (on full size logarithmic paper) of the transformer high side fuses.

1.5.2 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.5.3 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.3.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.3.2 Material and Equipment Manufacturing Date

Do not use products manufactured more than 3 years prior to date of delivery to site, unless specified otherwise.

1.6 MAINTENANCE

1.6.1 Additions to Operation and Maintenance Data

In addition to requirements of Data Package 5, include the following on the actual transformer(s) provided:

a. An instruction manual with pertinent items and information highlighted

b. An outline drawing, front, top, and side views

c. Prices for spare parts and supply list

d. Routine and field acceptance test reports

e. Fuse curves for primary fuses

f. Information on watthour demand meter, CT's, and fuse block

g. Actual nameplate diagram

h. Date of purchase

1.7 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 THREE-PHASE PAD-MOUNTED TRANSFORMERS

IEEE C57.12.34, IEEE C57.12.28 and as specified herein.

2.1.1 Compartments

Separate the high- and low-voltage compartments with steel isolating barriers extending the full height and depth of the compartments. Compartment doors: hinged lift-off type with stop in open position and three-point latching.

2.1.1.1 High Voltage, Dead-Front

High-voltage compartment shall contain the incoming line, insulated high-voltage load-break connectors, bushing well inserts, load-break switch handle(s), access to oil-immersed fuses, dry-well fuse canisters, tap changer handle, connector parking stands with insulated standoff bushings, protective caps, and ground pad.

a. Insulated high-voltage load-break connectors: IEEE Std 386, rated 15 kV, 95 kV BIL. Current rating: 200 amperes rms continuous. Short time rating: 10,000 amperes rms symmetrical for a time duration of 0.17 seconds. Connector shall have a steel reinforced hook-stick eye, grounding eye, test point, and arc-quenching contact material.

c. Load-break switch

Radial-feed oil-immersed type rated at 15 kV, 95 kV BIL, with a continuous current rating and load-break rating of 200 amperes, and a make-and-latch rating of 10,000 rms amperes symmetrical. Locate the switch handle in the high-voltage compartment.

ARRANGEMENT NO.	DESCRIPTION OF SWITCH ARRANGEMENT	SWITCH POSITION LINE A SW. OPEN	LINE A SW. CLOSE	LINE B SW OPEN	LINE B SW CLOSE	XFMR. SW OPEN	XFMR. SW CLOSE
1	Line A connected to Line B and both lines connected to transformer		X		X		X
2	Transformer connected to Line A only		X	X			X
3	Transformer connected to Line B only	X			X		X
4	Transformer open and loop closed		X		X	X	
5	Transformer open and loop open	X		X		X	

d. Provide bayonet type, oil-immersed, expulsion fuses in series with oil-immersed, partial-range, current-limiting fuses. Bayonet fuse links shall sense both high currents and high oil temperature in order to provide thermal protection to the transformer. Coordinate transformer protection with expulsion fuse clearing low-current faults and current-limiting fuse clearing high-current faults beyond the interrupting rating of the expulsion fuse. In order to eliminate or minimize oil spills, the bayonet fuse assembly shall include an oil retention valve inside the housing which closes when the fuse holder is removed and an external drip shield. Conspicuously display warning within the high-voltage compartment cautioning against removing or inserting fuses unless the load-break switch is in the open position and the tank pressure has been released.

Bayonet fuse assembly: 150 kV BIL.

e. Current-limiting fuses, dry-well mount: IEEE C37.47. Provide fuses in air-insulated, oil-sealed, dead-front, non-load-break dry-well fuse canisters, on the load side of the load-break switch serving the transformer. Interlock fuse canisters with the load-break switch so that the fuses may be removed and inserted only when the switch is in the "Off" position. Fuses shall remove the transformer from service in case of an internal fault. Size fuses to approximately 150 percent of the transformer primary full load current rating and in accordance with fuse manufacturer's recommendations for dry-well mounting. Fuses shall

have an interrupting rating of 50,000 rms amperes symmetrical at the system voltage specified. Furnish a spare fuse for each fuse provided.

f. Surge arresters: IEEE C62.11, rated 15 kV, fully shielded, dead-front, metal-oxide-varistor, elbow type with resistance-graded gap, suitable for plugging into inserts. Provide three arresters for radial feed circuits.

g. Parking stands: Provide a parking stand near each bushing well. Provide insulated standoff bushings for parking of energized load-break connectors on parking stands.

h. Protective caps: IEEE Std 386, 200 amperes, 15 kV Class. Provide insulated protective caps (not shipping caps) for insulating and sealing out moisture from unused bushing well inserts and insulated standoff bushings.

2.1.1.2 Low Voltage

Low-voltage compartment shall contain low-voltage bushings with NEMA spade terminals, accessories, stainless steel or laser-etched anodized aluminum diagrammatic transformer nameplate, and ground pad.

a. Accessories shall include drain valve with sampler device, fill plug, pressure relief device, liquid level gage, pressure-vacuum gage, and dial type thermometer with maximum temperature indicator.

2.1.2 Compartment Construction

b. Two compartment: Separate the high- and low-voltage compartments with steel isolating barriers extending the full height and depth of the compartments. Compartment doors: hinged lift-off type with stop in open position and three-point latching.

2.1.3 Transformer

a. Oil-insulated, two winding, 60 hertz, 65 degrees C rise above a 30 degrees C average ambient, self-cooled type.

b. Transformer shall be rated as noted on the plans. Note: The two 2,000 kVA 380 volt primary to 12.47 are connected in parallel. Impedance must be the same., 95 kV BIL.

c. Transformer voltage ratings: See schedule on plans.

d. Tap changer shall be externally operated, manual type for changing tap setting when the transformer is de-energized. Provide four 2.5 percent full capacity taps, two above and two below rated primary voltage. Tap changers shall clearly indicate which tap setting is in use.

e. Minimum tested impedance shall not be less than 5.5 percent at 85 degrees C on Three-Phase transformers.

f. Audible sound levels shall comply with the following:

kVA	DECIBELS (MAX)
75	51
112.5	55

kVA	DECIBELS (MAX)
150	55
225	55
300	55
500	56
750	57
1000	58
1500	60

g. Transformer shall include lifting lugs and provisions for jacking under base. The transformer base construction shall be suitable for using rollers or skidding in any direction. Provide transformer top with an access handhole. Transformer shall have its kVA rating conspicuously displayed on its enclosure. The transformer shall have an insulated low-voltage neutral bushing with NEMA spade terminal, and with removable ground strap.

2.2 WARNING SIGNS

Provide warning signs for the enclosures of pad-mounted transformers having a nominal rating exceeding 600 volts.

a. When the enclosure integrity of such equipment is specified to be in accordance with IEEE C57.12.28, such as for pad-mounted transformers, provide self-adhesive warning signs on the outside of the high voltage compartment door(s). Sign shall be a decal and have nominal dimensions of 178 by 255 mm with the legend "DANGER HIGH VOLTAGE" printed in two lines of nominal 50 mm high letters. The word "DANGER" shall be in white letters on a red background and the words "HIGH VOLTAGE" shall be in black letters on a white background. Decal shall be Panduit No. PPSO710D72 or approved equal.

2.3 GROUNDING AND BONDING

UL 467. Provide grounding and bonding as specified in Section 33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION.

2.4 PADLOCKS

Provide padlocks for pad-mounted equipment. Padlocks shall be keyed as directed by the Contracting Officer. Padlocks shall comply with Section 08 71 00 DOOR HARDWARE.

2.5 CAST-IN-PLACE CONCRETE

Concrete associated with electrical work for other than encasement of underground ducts shall be 30 MPa minimum 28-day compressive strength unless specified otherwise. All concrete shall conform to the requirements of Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

2.6 SOURCE QUALITY CONTROL

2.6.1 Transformer Test Schedule

The Government reserves the right to witness tests. Provide transformer test schedule for tests to be performed at the manufacturer's test facility. Submit required test schedule and location, and notify the

Contracting Officer 30 calendar days before scheduled test date. Notify Contracting Officer 15 calendar days in advance of changes to scheduled date.

a. Test Instrument Calibration

1. The manufacturer shall have a calibration program which assures that all applicable test instruments are maintained within rated accuracy.

2. The accuracy shall be directly traceable to the National Institute of Standards and Technology.

3. Instrument calibration frequency schedule shall not exceed 12 months for both test floor instruments and leased specialty equipment.

4. Dated calibration labels shall be visible on all test equipment.

5. Calibrating standard shall be of higher accuracy than that of the instrument tested.

6. Keep up-to-date records that indicate dates and test results of instruments calibrated or tested. For instruments calibrated by the manufacturer on a routine basis, in lieu of third party calibration, include the following:

(a) Maintain up-to-date instrument calibration instructions and procedures for each test instrument.

(b) Identify the third party/laboratory calibrated instrument to verify that calibrating standard is met.

2.6.2 Design Tests

IEEE C57.12.00, and IEEE C57.12.90. Section 5.1.2 in IEEE C57.12.80 states that "design tests are made only on representative apparatus of basically the same design." Submit design test reports (complete with test data, explanations, formulas, and results), in the same submittal package as the catalog data and drawings for each of the specified transformer(s). Perform design tests prior to the award of this contract.

a. Tests shall be certified and signed by a registered professional engineer.

b. Temperature rise: "Basically the same design" for the temperature rise test means a pad-mounted transformer with the same coil construction (such as wire wound primary and sheet wound secondary), the same kVA, the same cooling type (ONAN), the same temperature rise rating, and the same insulating liquid as the transformer specified.

c. Lightning impulse: "Basically the same design" for the lightning impulse dielectric test means a pad-mounted transformer with the same BIL, the same coil construction (such as wire wound primary and sheet wound secondary), and a tap changer, if specified. Design lightning impulse tests shall include the primary windings only of that transformer.

1. IEEE C57.12.90, paragraph 10.3 entitled "Lightning Impulse Test

Procedures," and IEEE C57.98.

2. State test voltage levels.

3. Provide photographs of oscilloscope display waveforms or plots of digitized waveforms with test report.

d. Lifting and moving devices: "Basically the same design" requirement for the lifting and moving devices test means a test report confirming that the lifting device being used is capable of handling the weight of the specified transformer in accordance with IEEE C57.12.34.

e. Pressure: "Basically the same design" for the pressure test means a pad-mounted transformer with a tank volume within 30 percent of the tank volume of the transformer specified.

f. Short circuit: "Basically the same design" for the short circuit test means a pad-mounted transformer with the same kVA as the transformer specified.

2.6.3 Routine and Other Tests

IEEE C57.12.00. Routine and other tests shall be performed by the manufacturer on the actual transformer(s) prepared for this project to ensure that the design performance is maintained in production. Submit test reports, by serial number and receive approval before delivery of equipment to the project site. Required tests and testing sequence shall be as follows:

a. Cold resistance measurements (provide reference temperature)

b. Phase relation

c. Ratio

d. No-load losses (NLL) and excitation current

e. Load losses (LL) and impedance voltage

f. Dielectric

1. Impulse

2. Applied voltage

3. Induced voltage

g. Leak

h. Dissolved gas analysis (DGA)

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations shall conform to IEEE C2, NFPA 70, and to the requirements specified herein. Provide new equipment and materials unless indicated or specified otherwise.

3.2 GROUNDING

NFPA 70 and IEEE C2, except that grounding systems shall have a resistance to solid earth ground not exceeding 5 ohms.

3.2.1 Grounding Electrodes

Provide driven ground rods as specified in Section 33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION. Connect ground conductors to the upper end of ground rods by exothermic weld or compression connector. Provide compression connectors at equipment end of ground conductors.

3.2.2 Pad-Mounted Transformer Grounding

Provide separate copper grounding conductors and connect them to the ground loop as indicated. When work in addition to that indicated or specified is required to obtain the specified ground resistance, the provision of the contract covering "Changes" shall apply.

3.2.3 Connections

Make joints in grounding conductors and loops by exothermic weld or compression connector. Install exothermic welds and compression connectors as specified in Section 33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION.

3.2.4 Grounding and Bonding Equipment

UL 467, except as indicated or specified otherwise.

3.3 INSTALLATION OF EQUIPMENT AND ASSEMBLIES

Install and connect pad-mounted transformers furnished under this section as indicated on project drawings, the approved shop drawings, and as specified herein.

3.3.1 Meters and Current Transformers

NEMA C12.1.

3.4 FIELD APPLIED PAINTING

Where field painting of enclosures is required to correct damage to the manufacturer's factory applied coatings, provide manufacturer's recommended coatings and apply in accordance with manufacturer's instructions.

3.5 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side, but space the signs a maximum of 9 meters apart.

3.6 FOUNDATION FOR EQUIPMENT AND ASSEMBLIES

Mount transformer on concrete slab. Unless otherwise indicated, the slab shall be at least 200 mm thick, reinforced with a 152 mm x 152 mm - MW19 by MW19 (6 by 6 - W2.9 by W2.9) mesh, placed uniformly 100 mm from the top of the slab. Place the slab on a 150 mm thick, well-compacted gravel base. Top of concrete slab shall be approximately 100 mm above finished grade with gradual slope for drainage. Edges above grade shall have 15 mm chamfer. Slab shall be of adequate size to project at least 200 mm beyond

the equipment.

Stub up conduits, with bushings, 50 mm into cable wells in the concrete pad. Coordinate dimensions of cable wells with transformer cable training areas.

3.6.1 Cast-In-Place Concrete

Cast-in-place concrete work shall conform to the requirements of Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.6.2 Sealing

When the installation is complete, the Contractor shall seal all conduit and other entries into the equipment enclosure with an approved sealing compound. Seals shall be of sufficient strength and durability to protect all energized live parts of the equipment from rodents, insects, or other foreign matter.

3.7 FIELD QUALITY CONTROL

3.7.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.7.1.1 Pad-Mounted Transformers

a. Visual and mechanical inspection

1. Compare equipment nameplate information with specifications and approved shop drawings.

2. Inspect physical and mechanical condition. Check for damaged or cracked insulators and leaks.

3. Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

4. Verify correct liquid level in tanks.

5. Perform specific inspections and mechanical tests as recommended by manufacturer.

6. Verify correct equipment grounding.

7. Verify the presence of transformer surge arresters.

b. Electrical tests

1. Perform resistance measurements through all bolted connections with low-resistance ohmmeter.

2. Verify that the tap-changer is set at specified ratio.

3. Verify proper secondary voltage phase-to-phase and

phase-to-neutral after energization and prior to loading.

3.7.1.2 Grounding System

a. Visual and mechanical inspection

1. Inspect ground system for compliance with contract plans and specifications.

b. Electrical tests

1. Perform ground-impedance measurements utilizing the fall-of-potential method. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable ground testing megger in accordance with manufacturer's instructions to test each ground or group of grounds. Equip the instrument with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test.

2. Submit the measured ground resistance of each ground rod and grounding system, indicating the location of the rod and grounding system. Include the test method and test setup (i.e., pin location) used to determine ground resistance and soil conditions at the time the measurements were made.

3.7.2 Follow-Up Verification

Upon completion of acceptance checks and tests, the Contractor shall show by demonstration in service that circuits and devices are in good operating condition and properly performing the intended function. As an exception to requirements stated elsewhere in the contract, the Contracting Officer shall be given 5 working days advance notice of the dates and times of checking and testing.

-- End of Section --

SECTION 26 13 13

MEDIUM VOLTAGE SWITCHGEAR
01/10

PART 1 GENERAL

1.1 SCOPE

Furnish and install the medium voltage metal enclosed switchgear equipment as specified herein and as shown on the drawings.

1.2 REFERENCES

The medium voltage metal-enclosed switchgear and all components shall be designed, manufactured and tested in accordance with the latest applicable standards as follows:

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C37.20.3	(2001; R 2006) Metal-Enclosed Interrupter Switchgear
IEEE C37.20.4	Indoor AC Switches (1 kV - 38 kV) for Use in Metal-Enclosed Switchgear
IEEE C37.20.3	(2001; R 2006) Metal-Enclosed Interrupter Switchgear

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA SG 6	(2000) Standard for Power Switching Equipment

1.3 SUBMITTALS

SD-02 Shop Drawings

Switchgear Drawings; G

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation.

Master drawing index
Front view elevation
Floor plan
Top view
Single line
Nameplate schedule
Component list
Conduit entry/exit locations
Assembly ratings including:
a. Short-circuit rating
b. Voltage
c. Continuous current
d. Basic Impulse Level

Major component ratings including:
a. Voltage
b. Continuous current
c. Interrupting ratings
Cable terminal sizes
Wiring Diagrams
Bus duct connection.
Connection details between close-coupled assemblies.
Composite floor plan of close-coupled assemblies.
Key interlock scheme drawing and sequence of operations.

Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices. Drawings shall include the nameplate data, size, and capacity. Drawings shall also include applicable federal, military, industry, and technical society publication references.

SD-03 Product Data

Switchgear; G

Switchgear product data sheets

SD-06 Test Reports

Switchgear design tests; G

Switchgear production tests; G

Acceptance checks and tests; G

SD-11 Closeout Submittals

Final as-built drawings incorporating changes made during the manufacturing process.
Installation information including equipment anchorage provisions.
Seismic certification as specified.
Operation and Maintenance Manuals
Equipment Test Schedule69+

1.4 QUALIFICATIONS

The manufacturer of the assembly shall be the manufacturer of the major components within the assembly.

For the equipment specified herein, the manufacturer shall be ISO 9001 or 9002 certified.

The manufacturer of this equipment shall have produced similar electrical equipment for a minimum period of five (5) years.

Provide Seismic tested equipment as follows:

The equipment and major components shall be suitable for and certified to meet all applicable seismic requirements of the International Building Code (IBC) for zone 4 application. Guidelines for the

installation consistent with these requirements shall be provided by the switchgear manufacturer and be based upon testing of representative equipment. The test response spectrum shall be based upon a 5% minimum damping factor, IBC: a peak of 2.45g's (3.2-11 Hz), and a ZPA of 0.98g's applied at the base of the equipment. The tests shall fully envelop this response spectrum for all equipment natural frequencies up to at least 35 Hz.

1.5 REGULATORY REQUIREMENTS (NOT USED)

1.6 DELIVERY, STORAGE AND HANDLING

Equipment shall be handled and stored in accordance with manufacturer's instructions. One (1) copy of these instructions shall be included with the equipment at time of shipment.

Each switchgear assembly shall be split into shipping groups for handling. Shipping groups shall be bolted to skids. Accessories shall be packaged and shipped separately. Each switchgear shipping group shall be equipped with lifting eyes for handling solely by crane.

1.7 OPERATION AND MAINTENANCE MANUALS

Equipment operation and maintenance manuals shall be provided with each assembly shipped, and shall include instruction leaflets and instruction bulletins for the complete assembly and each major component.

PART 2 PRODUCTS

2.1 RATINGS - SWITCHGEAR, SWITCH AND CIRCUIT BREAKER

The 15 kV switchgear assembly ratings shall be as follows:

Maximum Design Voltage	15 kV
Basic Impulse Level	95 kV
Nominal System Voltage	12.47 kV three-phase, three-wire
System Grounding	Solid
Main Cross Bus	
Continuous Current Rating	600 Amperes

The 15 kV breaker ratings shall be as follows:

Circuit Breaker Nominal 3-Phase MVA Class	500 MVA
Circuit Breaker Rated Short-Circuit Current at Rated Maximum kV	18 kA Symmetrical RMS
Short-Time (2-Second) Current	23 kA Asymmetrical RMS
Circuit Breaker Closing and Latching Capability (and assembly momentary)	37 kA Asymmetrical RMS

Load Interrupter Switches:

1. Fuse Rating	100 Amperes
2. Type of Fuse	CLE
3. Fuse Interrupting Rating	63 kA Sym RMS
4. Fused Switch Fault Close	101 kA Asym RMS

2.2 CONSTRUCTION

The switchgear assembly shall consist of deadfront, completely metal-enclosed vertical sections each containing drawout vacuum circuit breakers and where shown, furnish additional vertical sections containing load interrupter switches and fuses or miscellaneous auxiliary apparatus of the number, rating and type noted on the drawings or specified herein.

The following feature shall be supplied on every vertical section containing a drawout vacuum circuit breaker:
High voltage parts within circuit breaker compartments shall be isolated with grounded metal barriers.

Vertical section construction shall be of the universal frame type using die-formed and bolted parts. All enclosing covers and doors shall be fabricated from steel whose thickness shall be equal to or greater than those specified in ANSI/IEEE C37.20.3. No removable hardware for covers or doors shall be thread forming type. To facilitate installation and maintenance of cables and bus in each vertical section, a split removable top cover and hinged, bolted rear door with padlock provisions shall be provided. A high quality G90 grade galvanized base will isolate equipment from contact with the concrete pad providing protection from rust. Heavy-duty hot dipped galvanized anchor clips shall be provided to anchor the switchgear to the concrete pad.

Each vertical section shall be ventilated at the top and bottom, both front and rear, to allow airflow to help prevent buildup of moisture within the structure. For dust-resistant or outdoor applications, the ventilated covers shall be externally removable to allow safe maintenance of the filter media without providing access to live parts.

Each vertical section containing a switch shall have a single, full-length, flanged front door and shall be equipped with two rotary latch-type padlockable handles. A nameplate shall be mounted on the front door of each vertical section.

2.3 BUS

All buses shall be tin-plated copper. Ground bus shall be silver-plated copper and be directly fastened to a galvanized metal surface of each vertical section, and be of a size sufficient to carry the rated (2-second) current of the switchgear assembly. A neutral bus shall be provided when indicated on the drawings. It shall be insulated for 1000 Vac to ground. The current rating of the neutral bus shall be 600 amperes.

2.4 BUS SUPPORTING SYSTEMS

All bus shall be supported utilizing a high strength and high creep, support providing a minimum of 1 mm of creep between phases and ground. The molded fins shall be constructed of high track-resistantaramid nylon. All standoff insulators on the primary switches and fuse mountings shall be glass polyester.

2.5 WIRING/TERMINATIONS

One terminal pad per phase shall be provided for attaching supplied cable terminal lugs for a maximum of two conductors per phase of the sizes indicated on the drawings. Sufficient space shall be allowed for supplied electrical stress relief termination devices.

Small wiring, fuse blocks and terminal blocks within the vertical section shall be furnished as indicated on the drawings. Each control wire shall be labeled with wire markers. Terminal blocks shall be provided for owner connections to other apparatus.

2.6 CIRCUIT BREAKER

Each circuit breaker shall be operated by a motor-charged spring stored energy mechanism. The spring may be charged manually in an emergency or during maintenance procedures.

Each circuit breaker shall have three (3) vacuum interrupter assemblies that are separately mounted on glass polyester insulators. Each vacuum interrupter shall have a contact wear indicator which does not require any tools to indicate the contact wear. The current transfer from the vacuum interrupter moving stem to the breaker main conductor shall be a non-sliding design. The breaker front panel shall be removable when the compartment door is open for ease of inspection and maintenance of the mechanism.

The breakers shall be electrically operated by:

1. 120-Vac close and AC Capacitor Trip.
2. Each breaker shall be complete with control switch and red and green indicating lights to indicate breaker contact position.

The control voltage shall be derived from a control power transformer mounted in the switchgear.

2.7 PROTECTIVE RELAYS

The switchgear manufacturer shall furnish and install, in the metal-enclosed switchgear, the quantity, type and rating of protection relays as described hereinafter in this specification.

2.8 LOAD INTERRUPTER SWITCHES

Each load interrupter switch shall have a manual over-toggle type mechanism that does not require the use of a chain or a cable for operation, and utilizes a heavy-duty coil spring to provide opening and closing action. The speed of opening and closing the switch shall be independent of the operator, and it shall be impossible to tease the switch into any intermediate position.

The interrupter switch shall have separate main and break contacts to provide maximum endurance for fault close and load interrupting duty.

The interrupter switch shall have insulating barriers between each phase and between the outer phases and the enclosure.

A maintenance provision shall be provided for slow closing the switch to check switch-blade engagement and slow opening the switch to check operation of the arc interrupting contacts.

For fused switch cubicles, fault protection shall be furnished by fuses with continuous ratings as shown in the contract documents. The fuses shall be type CLE current limiting type with three (3) spare fuses.

The following features shall be supplied on every vertical section containing a three-pole, two-position open-closed switch or switch and fuse:

1. The door shall be interlocked with the switch so that:
   a. The switch must be opened before the door can be opened
   b. The door must be closed before the switch can be closed

2. A minimum 1.82 M x 4.87 M high-impact viewing window that permits full view of the position of all three switch blades through the closed door. The window shall not be more than 17.67 M above the switch pad level to allow ease of inspection

3. A hinged grounded metal barrier bolted closed in front of every switch to prevent inadvertent contact with any live part, yet allow for a full-view inspection on the switch blade position

4. Provision for padlocking the switch in the open or closed position

5. Green OPEN, Red CLOSED switch position indicators with the words "Open" and "Closed" in French, Spanish and English

6. A hinged cover with rustproof quarter turn nylon latches over the switch operating mechanism to discourage casual tampering

7. The switch shall be removable as a complete operational component

8. Provision shall be made for operating the switch and storing the removable handle without opening the full-length door.

2.9 SIGNS

Signs shall be installed on all medium voltage equipment. Signs shall identify the voltage of the equipment.

2.10 METERING

Furnish and install in the switchboard a microprocessor-based metering system to read system voltage, amperes, power factor, demand and frequency.

2.11 ENCLOSURES

Enclosures shall be constructed per IEEE/ANSI C37.20.3 Outdoor specifications. (Exceeds NEMA 3R.)

Each vertical section shall have a sloped weatherproof roof with labyrinth shaped joints. Use of gasket or caulking to make roof joints weatherproof shall not be permitted. All exterior openings shall be screened to prevent the entrance of small animals and barriered to inhibit the entrance of snow, sand, etc. A minimum of one (1) 250-watt, 220-volt space heater shall be provided in each vertical section. Power for the space heater(s) shall be furnished by a control power transformer mounted in the switchgear.

Each vertical section shall be ventilated at the top and bottom, both front and rear, to allow airflow to provide cooling and help prevent buildup of moisture within the structure. The ventilated covers shall be externally removable to allow safe maintenance of the filter media without providing access to live parts.

Enclosure shall be Dust Resistant. All ventilated openings shall be

filtered to inhibit the ingress of dust. The ventilated covers shall be externally removable to allow safe maintenance of the filter media without providing access to live parts. All external doors and covers shall be gasketed.

2.12 NAMEPLATES

A nameplate shall be mounted on the front door of each switch vertical section and circuit breaker.

2.13 Sub Title

Prior to assembly, all enclosing steel shall be thoroughly cleaned and phosphatized. A powder coating shall be applied electrostatically, then fused on by baking in an oven. The coating is to have a thickness of not less than 1.5 mils. The finish shall have the following properties:

Impact resistance (ASTM D-2794)	60 direct/60 indirect
Pencil hardness (ASTM D-3363)	H
Flexibility (ASTM D-522)	Pass .08 mm mandrel
Salt spray (ASTM B117-85 20)	600 hours
Color	ANSI 61 gray

PART 3 EXECUTION

3.1 FACTORY TESTING

The following standard factory tests shall be performed on the circuit breaker element provided under this section. All tests shall be in accordance with the latest version of ANSI and NEMA standards.

1. Circuit breaker operated over the range of minimum to maximum control voltage
2. Factory setting of contact gap
3. One (1) minute dielectric test per ANSI standards
4. Final inspections and quality checks.

The following production test shall be performed on the circuit breaker housing:

1. One (1) minute dielectric test per ANSI standards on primary and secondary circuits
2. Operation of wiring, relays and other devices verified by an operational sequence test
3. Final inspection and quality check.

The manufacturer shall provide three (3) certified copies of factory test reports.

3.2 INSTALLATION

Install all equipment per the manufacturer's recommendations and the drawings. All necessary hardware to secure the assembly in place shall be provided.

3.3 FIELD ADJUSTMENTS

The relays shall be set in the field in accordance with settings designated in a coordination study of the system.

3.4 FIELD TESTING

Field testing shall be performed in the presence of the Contracting Officer. Notify the Contracting Officer 20 days prior to conducting tests. Furnish all materials, labor, and equipment necessary to conduct field tests. Perform all tests and inspections recommended by the manufacturer unless specifically waived by the Contracting Officer. Maintain a written record of all tests which includes date, test performed, personnel involved, devices tested, serial number and name of test equipment, and test results. All field test reports will be signed and dated by the Contractor.

-- End of Section --

SECTION 26 20 00

INTERIOR DISTRIBUTION SYSTEM
07/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B 1	(2001; R 2007) Standard Specification for Hard-Drawn Copper Wire
ASTM B 8	(2004) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D 709	(2001; R 2007) Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms
IEEE Std 81	(1983) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System (Part 1) Normal Measurements

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA C80.1	(2005) Standard for Electrical Rigid Steel Conduit (ERSC)
NEMA C80.3	(2005) Standard for Electrical Metallic Tubing (EMT)
NEMA ICS 1	(2000; R 2005; R 2008) Standard for Industrial Control and Systems General Requirements
NEMA FU 1	(2002; R 2007) Low Voltage Cartridge Fuses
NEMA ICS 4	(2005) Industrial Control and Systems:

	Terminal Blocks
NEMA ICS 6	(1993; R 2006) Standard for Industrial Controls and Systems Enclosures
NEMA ICS 2	(2000; Errata 2002; R 2005; Errata 2006) Standard for Industrial Control and Systems: Controllers, Contactors, and Overload Relays Rated Not More than 2000 Volts AC or 750 Volts DC: Part 8 - Disconnect Devices for Use in Industrial Control Equipment
NEMA KS 1	(2001; R 2006) Enclosed and Miscellaneous Distribution Equipment Switches (600 Volts Maximum)
NEMA MG 1	(2007; Errata 2008) Standard for Motors and Generators
NEMA MG 11	(1977; R 2007) Energy Management Guide for Selection and Use of Single Phase Motors
NEMA TC 3	(2004) Standard for Polyvinyl Chloride PVC Fittings for Use With Rigid PVC Conduit and Tubing
NEMA WD 1	(1999; R 2005) Standard for General Requirements for Wiring Devices

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 70E	(2004; AMD 2004) Electrical Safety in the Workplace

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.147	Control of Hazardous Energy (Lock Out/Tag Out)

UNDERWRITERS LABORATORIES (UL)

UL 1063	(2006) Standard for Safety Machine-Tools Wires and Cables
UL 1	(2005; Rev thru Jul 2007) Standard for Flexible Metal Conduit
UL 1242	(2006; Rev thru Jul 2007) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 1660	(2004; Rev thru Jan 2005) Liquid-Tight Flexible Nonmetallic Conduit
UL 198E	(1988; Rev Jul 1988) Class R Fuses

UL 20	(2004) Standard for General-Use Snap Switches
UL 360	(2003) Liquid-Tight Flexible Steel Conduit
UL 44	(2005; Rev thru Nov 2005) Thermoset-Insulated Wires and Cables
UL 467	(2007) Standard for Grounding and Bonding Equipment
UL 486A-486B	(2003; Rev thru Apr 2009) Standard for Wire Connectors
UL 486C	(2004; Rev thru Aug 2006) Standard for Splicing Wire Connectors
UL 489	(2009) Standard for Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 506	(2000; Rev thru May 2006) Standard for Specialty Transformers
UL 508	(1999; Rev thru Sep 2008) Standard for Industrial Control Equipment
UL 50	(2007) Standard for Enclosures for Electrical Equipment
UL 510	(2005; Rev thru Aug 2005) Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape
UL 512	(1993; Rev thru Jan 2008) Fuseholders
UL 514A	(2004; Rev thru Aug 2007) Standard for Metallic Outlet Boxes
UL 514B	(2004; Rev thru Aug 2007) Standard for Conduit, Tubing and Cable Fittings
UL 6	(2007) Standard for Electrical Rigid Metal Conduit-Steel
UL 67	(2009) Standard for Panelboards
UL 797	(2007) Standard for Electrical Metallic Tubing -- Steel
UL 83	(2008) Standard for Thermoplastic-Insulated Wires and Cables
UL 854	(2004; Rev thru Oct 2007) Service-Entrance Cables
UL 869A	(2006) Reference Standard for Service Equipment

UL 943	(2006) Ground-Fault Circuit-Interrupters
UL 984	(1996; Rev thru Sept 2005) Hermetic Refrigerant Motor-Compressors

1.2 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Panelboards; G

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices.

Wireways

Marking strips drawings

SD-03 Product Data

Receptacles; G

Circuit breakers; G

Switches; G

Enclosed circuit breakers; G

Motor controllers; G

Combination motor controllers; G

Manual motor starters; G

Telecommunications Grounding Busbar

Surge protective devices; G

Submittals shall include performance and characteristic curves.

SD-06 Test Reports

600-volt wiring test; G

Grounding system test; G

Ground-fault receptacle test

SD-07 Certificates

Fuses

1.4 QUALITY ASSURANCE

1.4.1 Fuses

Submit coordination data as specified in paragraph, FUSES of this section.

1.4.2 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.4.3 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.3.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.3.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site shall not be used, unless specified otherwise.

1.5 MAINTENANCE

1.5.1 Electrical Systems

Submit operation and maintenance manuals for electrical systems that provide basic data relating to the design, operation, and maintenance of the electrical distribution system for the building. This shall include:

a. Single line diagram of the "as-built" building electrical system.

b. Schematic diagram of electrical control system (other than HVAC, covered elsewhere).

c. Manufacturers' operating and maintenance manuals on active electrical equipment.

1.6 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Materials, equipment, and devices shall, as a minimum, meet requirements of UL, where UL standards are established for those items, and requirements of NFPA 70.

2.2 CONDUIT AND FITTINGS

Shall conform to the following:

2.2.1 Rigid Metallic Conduit

2.2.1.1 Rigid, Threaded Zinc-Coated Steel Conduit

NEMA C80.1, UL 6.

2.2.2 Intermediate Metal Conduit (IMC)

UL 1242, zinc-coated steel only.

2.2.3 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797, NEMA C80.3.

2.2.4 Flexible Metal Conduit

UL 1.

2.2.4.1 Liquid-Tight Flexible Metal Conduit, Steel

UL 360.

2.2.5 Fittings for Metal Conduit, EMT, and Flexible Metal Conduit

UL 514B. Ferrous fittings shall be cadmium- or zinc-coated in accordance with UL 514B.

2.2.5.1 Fittings for Rigid Metal Conduit and IMC

Threaded-type. Split couplings unacceptable.

2.2.5.2 Fittings for EMT

Steel compression type.

2.2.6 Fittings for Rigid Nonmetallic Conduit

NEMA TC 3 for PVC, and UL 514B.

2.2.7 Liquid-Tight Flexible Nonmetallic Conduit

UL 1660.

2.2.8 Fittings for CFNC

UL 514B

2.3 OUTLET BOXES AND COVERS

UL 514A, cadmium- or zinc-coated, if ferrous metal.

2.3.1 Outlet Boxes for Telecommunications System

Provide standard type 100 mm square by 54 mm deep. Depth of boxes shall be large enough to allow manufacturers' recommended conductor bend radii.

2.4 CABINETS, JUNCTION BOXES, AND PULL BOXES

Volume greater than 1640 mL, UL 50, hot-dip, zinc-coated, if sheet steel.

2.5 WIRES AND CABLES

Wires and cables shall meet applicable requirements of NFPA 70 and UL for type of insulation, jacket, and conductor specified or indicated. Wires and cables manufactured more than 12 months prior to date of delivery to site shall not be used.

2.5.1 Conductors

Conductors No. $8MM^2$ and larger diameter shall be stranded. Conductors No. $6MM^2$ and smaller diameter shall be solid, except that conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3, shall be stranded unless specifically indicated otherwise. Conductor sizes and ampacities shown are based on copper, unless indicated otherwise. All conductors shall be copper.

2.5.1.1 Minimum Conductor Sizes

Minimum size for branch circuits shall be No. $4MM^2$; for Class 1 remote-control and signal circuits, No. $2.5MM^2$; for Class 2 low-energy,

remote-control and signal circuits, No. 1.5MM^2; and for Class 3 low-energy, remote-control, alarm and signal circuits, No. .5MM^2.

2.5.2 Color Coding

Provide for service, feeder, branch, control, and signaling circuit conductors. Color shall be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in same raceway or box, other neutrals shall be white with a different colored (not green) stripe for each. Color of ungrounded conductors in different voltage systems shall be as follows:

a. 380/220 volt, three-phase

(1) Phase A - black

(2) Phase B - red

(3) Phase C - blue

b. 220 volt, single phase: Black and red

2.5.3 Insulation

Unless specified or indicated otherwise or required by NFPA 70, power and lighting wires shall be 600-volt, Type THWN/THHN conforming to UL 83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits shall be Type TW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.5.4 Bonding Conductors

ASTM B 1, solid bare copper wire for sizes No. 10MM^2 and smaller diameter; ASTM B 8, Class B, stranded bare copper wire for sizes No. 16MM^2 and larger diameter.

2.5.5 Service Entrance Cables

Service Entrance (SE) and Underground Service Entrance (USE) Cables, UL 854.

2.6 SPLICES AND TERMINATION COMPONENTS

UL 486A-486B for wire connectors and UL 510 for insulating tapes. Connectors for No. 6MM^2 and smaller diameter wires shall be insulated, pressure-type in accordance with UL 486A-486B or UL 486C (twist-on splicing connector). Provide solderless terminal lugs on stranded conductors.

2.7 DEVICE PLATES

Provide UL listed, one-piece device plates for outlets to suit the devices installed. For metal outlet boxes, plates on unfinished walls shall be of zinc-coated sheet steel or cast metal having round or beveled edges. Plates on finished walls shall be nylon or lexan, minimum 0.792 mm wall thickness. Plates shall be same color as receptacle or toggle switch with which they are mounted. Screws shall be machine-type with countersunk heads in color to match finish of plate. Sectional type device plates will not be permitted. Plates installed in wet locations shall be gasketed and

UL listed for "wet locations."

2.8 SWITCHES

2.8.1 Toggle Switches

NEMA WD 1, UL 20, single pole, double pole, three-way, and four-way, totally enclosed with bodies of thermoplastic or thermoset plastic and mounting strap with grounding screw. Handles shall be brown thermoplastic. Wiring terminals shall be screw-type, side-wired. Contacts shall be silver-cadmium and contact arm shall be one-piece copper alloy. Switches shall be rated quiet-type ac only, 220 volts, with current rating and number of poles indicated.

2.8.2 Breakers Used as Switches

For 220-Volt fluorescent fixtures, mark breakers "SWD" in accordance with UL 489.

2.8.3 Disconnect Switches

NEMA KS 1. Provide heavy duty-type switches where indicated, where switches are rated higher than 240 volts, and for double-throw switches. Fused switches shall utilize Class R fuseholders and fuses, unless indicated otherwise. Switches serving as motor-disconnect means shall be horsepower rated. Provide switches in NEMA 1, 3R enclosure as indicated per NEMA ICS 6.

2.9 FUSES

NEMA FU 1. Provide complete set of fuses for each fusible switch. Time-current characteristics curves of fuses serving motors or connected in series with circuit breakers or other circuit protective devices shall be coordinated for proper operation. Submit coordination data for approval. Fuses shall have voltage rating not less than circuit voltage.

2.9.1 Fuseholders

Provide in accordance with UL 512.

2.9.2 Cartridge Fuses, Current Limiting Type (Class R)

UL 198E, Class RK-1 RK-5 time-delay type. Associated fuseholders shall be Class R only.

2.9.3 Cartridge Fuses, High-Interrupting Capacity, Current Limiting Type (Classes J, L, and CC)

UL 198C, Class J for zero to 600 amperes, Class L for 601 to 6,000 amperes, and Class CC for zero to 30 amperes.

2.9.4 Cartridge Fuses, Current Limiting Type (Class T)

UL 198H, Class T for zero to 1,200 amperes, 300 volts; and zero to 800 amperes, 600 volts.

2.10 SOCKET

Socket shall be British Standard and shall conform to BS 546:1950. Socket

outlet shall be patented 3 pin safety shutter mechanism 15 amp 250 volt. Install in a flush back box minimum 35 mm deep. Provide with 89x89 mm silver satin finish cover plate. Sockets shall be ASTA certified.

2.10.1 Weatherproof Receptacles

Provide in cast metal box with gasketed, weatherproof, cast-metal cover plate and gasketed cap over each receptacle opening. Provide caps with a spring-hinged flap. Receptacle shall be UL listed for use in "wet locations with plug in use."

2.10.2 Ground-Fault Socket

Provide a RCD socket 13A, 250 volts conforming to BS-7288:1990 and BS 1363 Part 2: 1995. Socket shall have earth pin release shutter with test and reset button. Socket shall have mechanical latching that does not trip on power failure (Passive) RCD unit 2 gang OP 30 MA. Flush box shall be a minimum of 25 MM deep. Cover plate shall be stainless steel 86x146 MM.

2.10.3 Special Purpose Receptacles

Special Purpose Receptacles will be specified on plans. Furnish one matching plug with each receptacle.

2.11 PANELBOARDS

UL 67 and UL 50 having a short-circuit current rating as indicated of 10,000 amperes symmetrical minimum. Panelboards for use as service disconnecting means shall additionally conform to UL 869A. Panelboards shall be circuit breaker-equipped unless indicated otherwise. Design shall be such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL. "Specific breaker placement" is required in panelboards to match the breaker placement indicated in the panelboard schedule on the drawings. Use of "Subfeed Breakers" is not acceptable unless specifically indicated otherwise. Main breaker shall be "separately" mounted "above" branch breakers. Where "space only" is indicated, make provisions for future installation of breakers. Directories shall indicate load served by each circuit in panelboard. Directories shall also indicate source of service to panelboard (e.g., Panel PA served from Panel MDP). Type directories and mount in holder behind transparent protective covering. Panelboard shall have nameplates in accordance with paragraph FIELD FABRICATED NAMEPLATES.

UL 67 and UL 50. Panelboards for use as service disconnecting means shall additionally conform to UL 869A. Panelboards shall be circuit breaker-equipped. Design shall be such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL. Where "space only" is indicated, make provisions for future installation of breaker sized as indicated. Directories shall indicate load served by each circuit of panelboard. Directories shall also indicate source of service (upstream panel, switchboard, etc.) to panelboard. Type directories and mount in holder behind transparent protective covering. Panelboard shall have nameplates in accordance with paragraph FIELD FABRICATED NAMEPLATES.

2.11.1 Enclosure

Enclosures shall meet the requirements of UL 50. All cabinets shall be fabricated from sheet steel of not less than 3.5 millimeters if flush-mounted or mounted outdoors, and not less than 2.7 millimeters if surface-mounted indoors, with full seam-welded box ends. Cabinets mounted outdoors or flush-mounted shall be hot-dipped galvanized after fabrication. Cabinets shall be painted in accordance with paragraph PAINTING. Outdoor cabinets shall be of NEMA 3R raintight with conduit hubs welded to the cabinet. Front edges of cabinets shall be form-flanged or fitted with structural shapes welded or riveted to the sheet steel, for supporting the panelboard front. All cabinets shall be so fabricated that no part of any surface on the finished cabinet shall deviate from a true plane by more than 3 millimeters. Holes shall be provided in the back of indoor surface-mounted cabinets, with outside spacers and inside stiffeners, for mounting the cabinets with a 15 millimeter clear space between the back of the cabinet and the wall surface. Flush doors shall be mounted on hinges that expose only the hinge roll to view when the door is closed. Each door shall be fitted with a combined catch and lock, except that doors over 600 millimeters long shall be provided with a three-point latch having a knob with a T-handle, and a cylinder lock. Two keys shall be provided with each lock, and all locks shall be keyed alike. Finished-head cap screws shall be provided for mounting the panelboard fronts on the cabinets.

2.11.2 Panelboard Buses

Support bus bars on bases independent of circuit breakers. Main buses and back pans shall be designed so that breakers may be changed without machining, drilling, or tapping. Provide isolated neutral bus in each panel for connection of circuit neutral conductors. Provide separate ground bus identified as equipment grounding bus per UL 67 for connecting grounding conductors; bond to steel cabinet.

2.11.3 Circuit Breakers

UL 489, thermal magnetic-type having a minimum short-circuit current rating equal to the short-circuit current rating of the panelboard in which the circuit breaker shall be mounted. Breaker terminals shall be UL listed as suitable for type of conductor provided. Where indicated on the drawings, provide circuit breakers with shunt trip devices. Provide earth leakage circuit breakers, three pole for 2 and 3 wire circuits and four pole for 3 phase circuits.

2.11.3.1 Multipole Breakers

Provide common trip-type with single operating handle. Breaker design shall be such that overload in one pole automatically causes all poles to open. Maintain phase sequence throughout each panel so that any three adjacent breaker poles are connected to Phases A, B, and C, respectively.

2.11.3.2 Circuit Breaker With GFI

UL 943 and NFPA 70. Provide with "push-to-test" button, visible indication of tripped condition, and ability to detect and trip on current imbalance of 6 milliamperes or greater per requirements of UL 943 for Class A GFI devices, for personnel protection

2.11.3.3 Circuit Breakers for HVAC Equipment

Circuit breakers for HVAC equipment having motors (group or individual) shall be marked for use with HACR type and UL listed as HACR type.

2.12 ENCLOSED CIRCUIT BREAKERS

UL 489. Individual molded case circuit breakers with voltage and continuous current ratings, number of poles, overload trip setting, and short circuit current interrupting rating as indicated. Enclosure type as indicated. Provide solid neutral.

2.13 MOTOR SHORT-CIRCUIT PROTECTOR (MSCP)

Motor short-circuit protectors, also called motor circuit protectors (MCPs); shall conform to UL 508 and UL 489 and shall be provided as shown. MSCPs shall consist of an adjustable instantaneous trip circuit breaker used only in conjunction with a combination motor controller which provides coordinated motor branch-circuit overload and short-circuit protection. MSCPs shall be rated in accordance with the requirements of NFPA 70.

2.14 MOTORS

NEMA MG 1; hermetic-type sealed motor compressors shall also comply with UL 984. Provide the size in terms of kW, or kVA, or full-load current, or a combination of these characteristics, and other characteristics, of each motor as indicated or specified. Determine specific motor characteristics to ensure provision of correctly sized starters and overload heaters. Motors for operation on 380-volt, 3-phase circuits shall have terminal voltage rating of 380 volts. Motors shall be designed to operate at full capacity with voltage variation of plus or minus 10 percent of motor voltage rating. Unless otherwise indicated, motors rated 745 Watts (1 HP) and above shall be continuous duty type.

Where fuse protection is specifically recommended by the equipment manufacturer, provide fused switches in lieu of non-fused switches indicated.

2.14.1 High Efficiency Single-Phase Motors

Single-phase fractional-horsepower alternating-current motors shall be high efficiency types corresponding to the applications listed in NEMA MG 11. In exception, for motor-driven equipment with a minimum seasonal or overall efficiency rating, such as a SEER rating, provide equipment with motor to meet the overall system rating indicated.

2.14.2 Motor Sizes

Provide size for duty to be performed, not exceeding the full-load nameplate current rating when driven equipment is operated at specified capacity under most severe conditions likely to be encountered. When motor size provided differs from size indicated or specified, make adjustments to wiring, disconnect devices, and branch circuit protection to accommodate equipment actually provided. Provide controllers for motors rated 1-hp and above with electronic phase-voltage monitors designed to protect motors from phase-loss, undervoltage, and overvoltage. Provide protection for motors from immediate restart by a time adjustable restart relay.

2.14.3 Wiring and Conduit

Provide internal wiring for components of packaged equipment as an integral part of the equipment. Provide power wiring and conduit for field-installed equipment as specified herein. Power wiring and conduit shall conform to the requirements specified herein. Control wiring shall be provided under, and conform to the requirements of the section specifying the associated equipment.

2.15 MOTOR CONTROLLERS

UL 508, NEMA ICS 1, and NEMA ICS 2. Controllers shall have thermal overload protection in each phase and shall have one spare normally open and one spare normally closed auxiliary contact. Provide controllers for motors rated 1-hp and above with electronic phase-voltage monitors designed to protect motors from phase-loss, undervoltage, and overvoltage. Provide protection for motors from immediate restart by a time adjustable restart relay. Magnetic-type motor controllers shall have undervoltage protection when used with momentary-contact pushbutton stations or switches and shall have undervoltage release when used with maintained-contact pushbutton stations or switches. When used with pressure, float, or similar automatic-type or maintained-contact switch, controller shall have hand/off/automatic selector switch. Connections to selector switch shall be such that only normal automatic regulatory control devices are bypassed when switch is in "hand" position. Safety control devices, such as low and high pressure cutouts, high temperature cutouts, and motor overload protective devices, shall be connected in motor control circuit in "hand" and "automatic" positions. Control circuit connections to hand/off/automatic selector switch or to more than one automatic regulatory control device shall be made in accordance with indicated or manufacturer's approved wiring diagram.For each motor not in sight of controller or where controller disconnecting means is not in sight of motor location and driven machinery location, controller disconnecting means shall be capable of being locked in open position. As an alternative, provide a manually operated, lockable, nonfused switch which disconnects motor from supply source within sight of motor. Overload protective devices shall provide adequate protection to motor windings; be thermal inverse-time-limit type; and include manual reset-type pushbutton on outside of motor controller case. Cover of combination motor controller and manual switch or circuit breaker shall be interlocked with operating handle of switch or circuit breaker so that cover cannot be opened unless handle of switch or circuit breaker is in "off" position. Minimum short circuit withstand rating of combination motor controller shall be 10,000 rms symmetrical amperes. Provide controllers in hazardous locations with classifications as indicated.

2.15.1 Control Wiring

All control wire shall be stranded tinned copper switchboard wire with 600-volt flame-retardant insulation Type SIS meeting UL 44, or Type MTW meeting UL 1063, and shall pass the VW-1 flame tests included in those standards. Hinge wire shall have Class K stranding. Current transformer secondary leads shall be not smaller than No. $6MM^2$. The minimum size of control wire shall be No. $2.5MM^2$. Power wiring for 480-volt circuits and below shall be of the same type as control wiring and the minimum size shall be No. $4MM^2$. Special attention shall be given to wiring and terminal arrangement on the terminal blocks to permit the individual conductors of each external cable to be terminated on adjacent terminal points.

2.15.2 Control Circuit Terminal Blocks

NEMA ICS 4. Control circuit terminal blocks for control wiring shall be molded or fabricated type with barriers, rated not less than 600 volts. The terminals shall be removable binding, fillister or washer head screw type, or of the stud type with contact and locking nuts. The terminals shall be not less than No. $6MM^2$ in size and shall have sufficient length and space for connecting at least two indented terminals for $6MM^2$ conductors to each terminal. The terminal arrangement shall be subject to the approval of the Contracting Officer and not less than four (4) spare terminals or 10 percent, whichever is greater, shall be provided on each block or group of blocks. Modular, pull apart, terminal blocks will be acceptable provided they are of the channel or rail-mounted type. The Contractor shall submit data showing that the proposed alternate will accommodate the specified number of wires, are of adequate current-carrying capacity, and are constructed to assure positive contact between current-carrying parts.

2.15.2.1 Types of Terminal Blocks

a. Short-Circuiting Type: Short-circuiting type terminal blocks shall be furnished for all current transformer secondary leads and shall have provision for shorting together all leads from each current transformer without first opening any circuit. Terminal blocks shall meet the requirements of paragraph CONTROL CIRCUIT TERMINAL BLOCKS above.

b. Load Type: Load terminal blocks rated not less than 600 volts and of adequate capacity shall be provided for the conductors for NEMA Size 3 and smaller motor controllers and for other power circuits, except those for feeder tap units. The terminals shall be of either the stud type with contact nuts and locking nuts or of the removable screw type, having length and space for at least two indented terminals of the size required on the conductors to be terminated. For conductors rated more than 50 amperes, screws shall have hexagonal heads. Conducting parts between connected terminals shall have adequate contact surface and cross-section to operate without overheating. Each connected terminal shall have the circuit designation or wire number placed on or near the terminal in permanent contrasting color.

2.15.3 Control Circuits

Control circuits shall have maximum voltage of 220 volts derived from control transformer in same enclosure. Transformers shall conform to UL 506, as applicable. Transformers, other than transformers in bridge circuits, shall have primaries wound for voltage available and secondaries wound for correct control circuit voltage. Size transformers so that 80 percent of rated capacity equals connected load. Provide disconnect switch on primary side. Provide fuses in each ungrounded primary feeder. One secondary lead shall be fused; other shall be grounded.

2.15.4 Enclosures for Motor Controllers

NEMA ICS 6.

2.15.5 Multiple-Speed Motor Controllers and Reversible Motor Controllers

Across-the-line-type, electrically and mechanically interlocked.

Multiple-speed controllers shall have compelling relays and shall be multiple-button, station-type with pilot lights for each speed.

2.15.6 Pushbutton Stations

Provide with "start/stop" momentary contacts having one normally open and one normally closed set of contacts, and red lights to indicate when motor is running. Stations shall be heavy duty, oil-tight design.

2.15.7 Pilot and Indicating Lights

Provide LED cluster lamps.

2.15.8 Reduced-Voltage Controllers

Reduced-voltage starters shall be single-step, closed transition solid state-type, or as indicated, and shall have adjustable time interval between application of reduced and full voltages to motors. Wye-delta reduced voltage starter or part winding increment starter having adjustable time delay between application of voltage to first and second winding of motor may be used in lieu of the reduced-voltage starters for starting of centrifugally operated equipment.

2.16 MANUAL MOTOR STARTERS (MOTOR RATED SWITCHES)

Single Double Three pole designed for flush surface mounting with overload protection and pilot lights.

2.16.1 Pilot Lights

Provide yoke-mounted, seven element LED cluster light module. Color shall be green, red, amber in accordance with NEMA ICS 2.

2.17 LOCKOUT REQUIREMENTS

Provide disconnecting means capable of being locked out for machines and other equipment to prevent unexpected startup or release of stored energy in accordance with 29 CFR 1910.147. Mechanical isolation of machines and other equipment shall be in accordance with requirements of Division 23, Heating Ventilation and Air Conditioning"; Division 22, "Plumbing"; and Division 33."

2.17.1 Other Equipment-Ceiling Fans

Wobble-free canopy,52" blade span (except for models with feather blades (54"), min. 188 mm x 15 mm diameter motor, 14° (degree) blade pitch for maximum air flow, 3 speeds (high, medium, low), reversible air flow whisper-quiet operation (no hum), top quality finishes and plating, wall-mounted switch.

2.18 GROUNDING AND BONDING EQUIPMENT

2.18.1 Ground Rods

UL 467. Ground rods shall be copper-clad steel, with minimum diameter of 19 mm and minimum length of 3050 mm.

2.18.2 Ground Bus

A copper ground bus shall be provided in the electrical equipment rooms as indicated.

2.19 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.20 FIELD FABRICATED NAMEPLATES

ASTM D 709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 3 mm thick, white with black center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be 25 by 65 mm. Lettering shall be a minimum of 6.35 mm high normal block style.

2.21 FIRESTOPPING MATERIALS

Provide firestopping around electrical penetrations in accordance with Section 07 84 00, FIRESTOPPING .

2.22 FACTORY APPLIED FINISH

Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA 250 corrosion-resistance test and the additional requirements as specified herein. Interior and exterior steel surfaces of equipment enclosures shall be thoroughly cleaned and then receive a rust-inhibitive phosphatizing or equivalent treatment prior to painting. Exterior surfaces shall be free from holes, seams, dents, weld marks, loose scale or other imperfections. Interior surfaces shall receive not less than one coat of corrosion-resisting paint in accordance with the manufacturer's standard practice. Exterior surfaces shall be primed, filled where necessary, and given not less than two coats baked enamel with semigloss finish. Equipment located indoors shall be ANSI Light Gray, and equipment located outdoors shall be ANSI Dark Gray. Provide manufacturer's coatings for touch-up work and as specified in paragraph FIELD APPLIED PAINTING.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations, including weatherproof and hazardous locations and ducts, plenums and other air-handling spaces, shall conform to requirements of NFPA 70 and IEEE C2 and to requirements specified herein.

3.1.1 Underground Service

Underground service conductors and associated conduit shall be continuous from service entrance equipment to outdoor power system connection.

3.1.2 Service Entrance Identification

Service entrance disconnect devices, switches, and enclosures shall be labeled and identified as such.

3.1.2.1 Labels

Wherever work results in service entrance disconnect devices in more than one enclosure, as permitted by NFPA 70, each enclosure, new and existing, shall be labeled as one of several enclosures containing service entrance disconnect devices. Label, at minimum, shall indicate number of service disconnect devices housed by enclosure and shall indicate total number of enclosures that contain service disconnect devices. Provide laminated plastic labels conforming to paragraph FIELD FABRICATED NAMEPLATES. Use lettering of at least 6.35 mm in height, and engrave on black-on-white matte finish. Service entrance disconnect devices in more than one enclosure, shall be provided only as permitted by NFPA 70.

3.1.3 Wiring Methods

Provide insulated conductors installed in rigid steel conduit, IMC, rigid nonmetallic conduit, or EMT, except where specifically indicated or specified otherwise or required by NFPA 70 to be installed otherwise. Grounding conductor shall be separate from electrical system neutral conductor. Provide insulated green equipment grounding conductor for circuit(s) installed in conduit and raceways. Minimum conduit size shall be 21 mm in diameter for low voltage lighting and power circuits. Metal conduit shall extend through shafts for minimum distance of 150 mm. Conduit which penetrates fire-rated walls, fire-rated partitions, or fire-rated floors shall be firestopped in accordance with Section 07 84 00, FIRESTOPPING.

3.1.3.1 Pull Wire

Install pull wires in empty conduits. Pull wire shall be plastic having minimum 890-N (200-pound) force tensile strength. Leave minimum 915 mm of slack at each end of pull wire.

3.1.4 Conduit Installation

Unless indicated otherwise, conceal conduit under floor slabs and within finished walls, ceilings, and floors. Keep conduit minimum 150 mm away from parallel runs of flues and steam or hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where located above accessible ceilings and where conduit will be visible after completion of project.

3.1.4.1 Restrictions Applicable to EMT

a. Do not install underground.

b. Do not encase in concrete, mortar, grout, or other cementitious materials.

c. Do not use in areas subject to severe physical damage including but not limited to equipment rooms where moving or replacing equipment could physically damage the EMT.

d. Do not use in hazardous areas.

e. Do not use outdoors.

3.1.4.2 Restrictions Applicable to Nonmetallic Conduit

a. PVC Schedule 40 and PVC Schedule 80

(1) Do not use in areas where subject to severe physical damage, including but not limited to, mechanical equipment rooms, electrical equipment rooms.

(2) Do not use in hazardous (classified) areas.

(3) Do not use in penetrating fire-rated walls or partitions, or fire-rated floors.

(4) Do not use above grade, except where allowed in this section for rising through floor slab or indicated otherwise.

3.1.4.3 Restrictions Applicable to Flexible Conduit

Use only as specified in paragraph FLEXIBLE CONNECTIONS.

3.1.4.4 Service Entrance Conduit, Underground

PVC, Type-EPC 40, galvanized rigid steel or steel IMC. Underground portion shall be encased in minimum of 75 mm of concrete and shall be installed minimum 460 mm below slab or grade.

3.1.4.5 Conduit Installed Under Floor Slabs

Conduit run under floor slab shall be located a minimum of 305 mm below the vapor barrier. Seal around conduits at penetrations thru vapor barrier.

3.1.4.6 Conduit Through Floor Slabs

Where conduits rise through floor slabs, curved portion of bends shall not be visible above finished slab.

3.1.4.7 Conduit Installed in Concrete Floor Slabs

Rigid steel; steel IMC; or PVC, Type EPC-40, e unless indicated otherwise. Locate so as not to adversely affect structural strength of slabs. Install conduit within middle one-third of concrete slab. Do not stack conduits. Space conduits horizontally not closer than three diameters, except at cabinet locations. Curved portions of bends shall not be visible above finish slab. Increase slab thickness as necessary to provide minimum 25 mm cover over conduit. Where embedded conduits cross building and/or expansion joints, provide suitable watertight expansion/deflection fittings and bonding jumpers. Expansion/deflection fittings shall allow horizontal and vertical movement of raceway. Conduit larger than 27 mm trade size shall be parallel with or at right angles to main reinforcement; when at right angles to reinforcement, conduit shall be close to one of supports of slab.

3.1.4.8 Stub-Ups

Provide conduits stubbed up through concrete floor for connection to free-standing equipment with adjustable top or coupling threaded inside for

plugs, set flush with finished floor. Extend conductors to equipment in rigid steel conduit, except that flexible metal conduit may be used 150 mm above floor. Where no equipment connections are made, install screwdriver-operated threaded flush plugs in conduit end.

3.1.4.9 Conduit Support

Support conduit by pipe straps, wall brackets, hangers, or ceiling trapeze. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit only. Do not weld conduits or pipe straps to steel structures. Load applied to fasteners shall not exceed one-fourth proof test load. Fasteners attached to concrete ceiling shall be vibration resistant and shock-resistant. Holes cut to depth of more than 40 mm in reinforced concrete beams or to depth of more than 20 mm in concrete joints shall not cut main reinforcing bars. Fill unused holes. In partitions of light steel construction, use sheet metal screws. Supporting means shall not be shared between electrical raceways and mechanical piping or ducts. Installation shall be coordinated with above-ceiling mechanical systems to assure maximum accessibility to all systems. Spring-steel fasteners may be used for lighting branch circuit conduit supports in suspended ceilings in dry locations. Where conduit crosses building expansion joints, provide suitable expansion fitting that maintains conduit electrical continuity by bonding jumpers or other means. For conduits greater than 63 mm inside diameter, provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.4.10 Directional Changes in Conduit Runs

Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with hickey or conduit-bending machine. Do not install crushed or deformed conduits. Avoid trapped conduits. Prevent plaster, dirt, or trash from lodging in conduits, boxes, fittings, and equipment during construction. Free clogged conduits of obstructions.

3.1.4.11 Locknuts and Bushings

Fasten conduits to sheet metal boxes and cabinets with two locknuts where required by NFPA 70, where insulated bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, use at least minimum single locknut and bushing. Locknuts shall have sharp edges for digging into wall of metal enclosures. Install bushings on ends of conduits, and provide insulating type where required by NFPA 70.

3.1.4.12 Flexible Connections

Provide flexible steel conduit between 915 and 1830 mm in length for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for motors. Install flexible conduit to allow 20 percent slack. Minimum flexible steel conduit size shall be 16 mm diameter. Provide liquidtight flexible conduit in wet and damp locations for equipment subject to vibration, noise transmission, movement or motors. Provide separate ground conductor across flexible connections.

3.1.5 Boxes, Outlets, and Supports

Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures. Boxes for metallic raceways shall be cast-metal, hub-type when located in wet locations, when surface mounted on outside of exterior surfaces, when surface mounted on interior walls exposed up to 2135 mm above floors and walkways, and when specifically indicated. Boxes in other locations shall be sheet steel, except that aluminum boxes may be used with aluminum conduit. Each box shall have volume required by NFPA 70 for number of conductors enclosed in box. Boxes for mounting lighting fixtures shall be minimum 100 mm square, or octagonal, except that smaller boxes may be installed as required by fixture configurations, as approved. Boxes for use in masonry-block or tile walls shall be square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers. Provide gaskets for cast-metal boxes installed in wet locations and boxes installed flush with outside of exterior surfaces. Provide separate boxes for flush or recessed fixtures when required by fixture terminal operating temperature; fixtures shall be readily removable for access to boxes unless ceiling access panels are provided. Support boxes and pendants for surface-mounted fixtures on suspended ceilings independently of ceiling supports. Fasten boxes and supports with wood screws on wood, with bolts and expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screws or welded studs on steel or nail-type. In open overhead spaces, cast boxes threaded to raceways need not be separately supported except where used for fixture support; support sheet metal boxes directly from building structure or by bar hangers. Where bar hangers are used, attach bar to raceways on opposite sides of box, and support raceway with approved-type fastener maximum 610 mm from box. When penetrating reinforced concrete members, avoid cutting reinforcing steel.

3.1.5.1 Boxes

Boxes for use with raceway systems shall be minimum 40 mm deep, except where shallower boxes required by structural conditions are approved. Boxes for other than lighting fixture outlets shall be minimum 100 mm square, except that 100 by 50 mm boxes may be used where only one raceway enters outlet. Telecommunications outlets shall be a minimum of 120 mm square by 54 mm deep. Mount outlet boxes flush in finished walls.

3.1.5.2 Pull Boxes

Construct of at least minimum size required by NFPA 70 of code-gauge galvanized sheet steel, except where cast-metal boxes are required in locations specified herein. Provide boxes with screw-fastened covers. Where several feeders pass through common pull box, tag feeders to indicate clearly electrical characteristics, circuit number, and panel designation.

3.1.6 Mounting Heights

Mount panelboards, enclosed circuit breakers, motor controller and disconnecting switches so height of operating handle at its highest position is maximum 1980 mm above floor. Mount receptacles and telecommunications outlets 460 mm above finished floor, unless otherwise indicated. Wall-mounted telecommunications outlets shall be mounted at height 1525 mm above finished floor. Measure mounting heights of wiring devices and outlets to center of device or outlet.

3.1.7 Conductor Identification

Provide conductor identification within each enclosure where tap, splice, or termination is made. For conductors No. 16MM^2 and smaller diameter, color coding shall be by factory-applied, color-impregnated insulation. For conductors No. 25MM^2 and larger diameter, color coding shall be by plastic-coated, self-sticking markers; colored nylon cable ties and plates; or heat shrink-type sleeves. Identify control circuit terminations in accordance with manufacturer's recommendations

3.1.7.1 Marking Strips

White or other light-colored plastic marking strips, fastened by screws to each terminal block, shall be provided for wire designations. The wire numbers shall be made with permanent ink. The marking strips shall be reversible to permit marking both sides, or two marking strips shall be furnished with each block. Marking strips shall accommodate the two sets of wire numbers. Each device to which a connection is made shall be assigned a device designation in accordance with NEMA ICS 1 and each device terminal to which a connection is made shall be marked with a distinct terminal marking corresponding to the wire designation used on the Contractor's schematic and connection diagrams. The wire (terminal point) designations used on the Contractor's wiring diagrams and printed on terminal block marking strips may be according to the Contractor's standard practice; however, additional wire and cable designations for identification of remote (external) circuits shall be provided for the Government's wire designations. Prints of the marking strips drawings submitted for approval will be so marked and returned to the Contractor for addition of the designations to the terminal strips and tracings, along with any rearrangement of points required.

3.1.8 Splices

Make splices in accessible locations. Make splices in conductors No. 6MM^2 and smaller diameter with insulated, pressure-type connector. Make splices in conductors No. 10MM^2 and larger diameter with solderless connector, and cover with insulation material equivalent to conductor insulation.

3.1.9 Covers and Device Plates

Install with edges in continuous contact with finished wall surfaces without use of mats or similar devices. Plaster fillings are not permitted. Install plates with alignment tolerance of 0.58 mm. Use of sectional-type device plates are not permitted. Provide gasket for plates installed in wet locations.

3.1.10 Electrical Penetrations

Seal openings around electrical penetrations through fire resistance-rated walls, partitions, floors, or ceilings in accordance with Section 07 84 00, FIRESTOPPING.

3.1.11 Grounding and Bonding

Provide In accordance with NFPA 70. Ground exposed, non-current-carrying metallic parts of electrical equipment, metallic raceway systems, grounding conductor in metallic and nonmetallic raceways, telecommunications system grounds, and neutral conductor of wiring systems. Make ground connection

at main service equipment, and extend grounding conductor to point of entrance of metallic water service. Make connection to water pipe by suitable ground clamp or lug connection to plugged tee. If flanged pipes are encountered, make connection with lug bolted to street side of flanged connection. Supplement metallic water service grounding system with additional made electrode in compliance with NFPA 70. Make ground connection to driven ground rods on exterior of building. Interconnect all grounding media in or on the structure to provide a common ground potential. This shall include lightning protection, electrical service, telecommunications system grounds, as well as underground metallic piping systems. Use main size lightning conductors for interconnecting these grounding systems to the lightning protection system.

3.1.11.1 Ground Rods

Provide cone pointed ground rods. The resistance to ground shall be measured using the fall-of-potential method described in IEEE Std 81. The maximum resistance of a driven ground shall not exceed 25 ohms under normally dry conditions. If this resistance cannot be obtained with a single rod, additional rods not less than 1830 mm on centers. In high-ground-resistance, UL listed chemically charged ground rods may be used. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, notify the Contracting Officer who will decide on the number of ground rods to add.

3.1.11.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, by exothermic weld or compression connector.

a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.

b. Make compression connections using a hydraulic compression tool to provide the correct circumferential pressure. Tools and dies shall be as recommended by the manufacturer. An embossing die code or other standard method shall provide visible indication that a connector has been adequately compressed on the ground wire.

3.1.11.3 Ground Bus

A copper ground bus shall be provided in the electrical equipment rooms as indicated. Noncurrent-carrying metal parts of electrical equipment shall be effectively grounded by bonding to the ground bus. The ground bus shall be bonded to both the entrance ground, and to a ground rod or rods as specified above having the upper ends terminating approximately 100 mm above the floor. Connections and splices shall be of the brazed, welded, bolted, or pressure-connector type, except that pressure connectors or bolted connections shall be used for connections to removable equipment.

3.1.12 Equipment Connections

Provide power wiring for the connection of motors and control equipment under this section of the specification. Except as otherwise specifically noted or specified, automatic control wiring, control devices, and protective devices within the control circuitry are not included in this

section of the specifications but shall be provided under the section specifying the associated equipment.

3.1.13 Government-Furnished Equipment

Contractor shall rough-in for Government-furnished equipment to make equipment operate as intended, including providing miscellaneous items such as plugs, receptacles, wire, cable, conduit, flexible conduit, and outlet boxes or fittings.

3.1.14 Workmanship

Lay out work in advance. Exercise care where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceilings, or other surfaces is necessary for proper installation, support, or anchorage of conduit, raceways, or other electrical work. Repair damage to buildings, piping, and equipment using skilled craftsmen of trades involved.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side. Space the signs in accordance with NFPA 70E.

3.4 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00, PAINTS AND COATINGS.

3.5 FIELD QUALITY CONTROL

Furnish test equipment and personnel and submit written copies of test results. Give Contracting Officer 5 working days notice prior to each test.

3.5.1 Devices Subject to Manual Operation

Each device subject to manual operation shall be operated at least five times, demonstrating satisfactory operation each time.

3.5.2 600-Volt Wiring Test

Test wiring rated 600 volt and less to verify that no short circuits or accidental grounds exist. Perform insulation resistance tests on wiring No. $16MM^2$ and larger diameter using instrument which applies voltage of approximately 500 volts to provide direct reading of resistance. Minimum resistance shall be 250,000 ohms.

3.5.3 Grounding System Test

Test grounding system to ensure continuity, and that resistance to ground is not excessive. Test each ground rod for resistance to ground before making connections to rod; tie grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not

earlier than 48 hours after rainfall. Submit written results of each test to Contracting Officer, and indicate location of rods as well as resistance and soil conditions at time measurements were made.

-- End of Section --

SECTION 26 24 16.00 40

PANELBOARDS
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA AB 1	(2002) Molded-Case Circuit Breakers, Molded Case Switches, and Circuit-Breaker Enclosures
NEMA PB 1	(2006; Errata 2008) Standard for Panelboards

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-595	(Rev B; Am 1) Colors Used in Government Procurement

UNDERWRITERS LABORATORIES (UL)

UL 67	(2009) Standard for Panelboards

1.2 GENERAL REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to work specified in this section.

Submit Detail Drawings for the panelboards consisting of fabrication and assembly drawings for all parts of the work in sufficient detail to enable the Government to check conformity with the requirements of the contract documents. Include within drawings details of bus layout.

Ensure Outline Drawings for panelboards indicate overall physical features, dimensions, ratings, service requirements, and weights of equipment.

Statements signed by responsible officials of a manufacturer of a product, system, or material attesting that the product, system or material meet specified requirements. Statements must be dated after the award of this contract, name the project, and list the specific requirements which it is intended to address.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation

identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

UPS System, G

Submit Detail Drawings and Outline Drawings for panelboards in accordance with paragraph entitled, "General Requirements," of this section.

SD-03 Product Data

Submit Manufacturer's catalog data for the following items:

Panelboards, G
Directory Card and Holder
Filtered Panelboard
Performance Requirements; G

SD-04 Samples

Ensure that keys are properly tagged and delivered to the Contracting Officer.

SD-06 Test Reports

Submit test reports for the following tests in accordance with the paragraph entitled, "Site Testing," of this section. Do not energize panelboards until the recorded test data has been submitted to and approved by the Contracting Officer.

Continuity Tests
Insulation Tests

SD-07 Certificates

Submit Statements in accordance with paragraph entitled, "General Requirements," of this section.

SD-08 Manufacturer's Instructions

Submit Manufacturer's instructions for Panelboards including special provisions required to install equipment components and system packages. Special notices shall detail impedances, hazards and safety precautions.

PART 2 PRODUCTS

2.1 PANELBOARDS

Totally enclose power-distribution panelboards and lighting and appliance branch-circuit panelboards in a steel cabinet, dead-front circuit breaker type with copper buses, surface- or flush-mounted as indicated. Ensure panelboards conform to NEMA PB 1 and NEMA AB 1. Branch circuit panels shall have buses fabricated for bolt-on type circuit breakers.

An outer door or cover, hinged on one side, shall be provided on

surface-mounted panelboards to provide gutter space access. Provide a center door for circuit breaker access only.

Voltage and current rating, number of phases, and number of wires shall be as indicated. Provide four-wire distribution panelboards and lighting and appliance branch-circuit panelboards with an isolated full-capacity neutral bus. Ensure panelboards are rated for 380-volt (maximum), 220/380-volt, three-phase, 60-hertz current.

Provide three-phase, 4-wire and distribution lighting and branch circuit panelboards with an isolated full-capacity bus providing spaces for single-pole circuit breakers/switches and spaces indicated as spare.

Provide panelboards with a separate grounding bus bonded to the enclosure. Grounding bus shall be a solid bus bar of rectangular cross section equipped with binding screws for the connection of equipment grounding conductors.

Each panelboard, as a complete unit, shall have a short-circuit current rating equal to or greater than the integrated equipment rating shown on the panelboard schedule or as indicated.

Ensure panelboards and main lugs or main breaker have current ratings as shown on the panelboard schedule.

Bus bar connections to the branch circuit breakers shall be the "distributed phase" or "phase sequence" type. Single-phase, three-wire panelboard busing shall be such that when any two adjacent single-pole breakers are connected to opposite phases, two-pole breakers can be installed in any location. Three-phase, four-wire busing shall be such that when any three adjacent single-pole breakers are individually connected to each of the three different phases, two- or three-pole breakers can be installed at any location. Current-carrying parts of the bus assembly shall be plated. Mains ratings shall be as shown.

Mechanical lugs furnished with panelboards shall be cast copper or copper alloys of sizes suitable for the conductors indicated to be connected thereto.

Boxes shall have the manufacturer's standard knockouts and shall be galvanized code-gage sheet steel. Fronts shall be of code-gage sheet steel furnished with hinged doors with adjustable trim clamps for securing the fronts to the boxes.

Panelboard box shall be galvanized code-gage sheet steel without knockouts. Ensure entire panelboard front is hinged on one side with a piano hinge for the full height and has captive screws opposite the hinged side. Where panelboards are installed flush with the walls, the installation details shall be such that the hinged front can be opened without damage to the adjacent wall surfaces. Ensure that the color of the finished coat of trim and front matches the adjacent walls except when the box is installed in electrical closets or equipment rooms, the gray finish as specified is acceptable.

Panelboard enclosures shall be NEMA 250, Type 1. Provide enclosures with hinged fronts and corrosion-resistant steel pin-tumbler cylinder locks. Key locks alike and provide two keys for each enclosure.

Exterior panelboards and distribution panels shall be provided with larger

cabinets. These cabinets shall be provided with strip heaters and thermostats same as specified for switchgear. Provide weatherproof cabinets as specified.

Finish panelboards with baked enamel. Finish color is to be No. 61 gray conforming to FED-STD-595.

2.2 CIRCUIT BREAKERS

Circuit breakers shall be the molded-case type as specified in Section 26 05 70.00 40 HIGH VOLTAGE OVERCORRECT PROTECTIVE DEVICES. Frame and trip ratings shall be as indicated.

Interrupting rating of circuit breakers shall be as indicated. For breakers in 220/380-volt panelboards shall be not less than 18,000 amperes rms symmetrical.

Circuit breakers shall be bolt-on type. Plug-in type is not acceptable.

Provide shunt trips where indicated.

In branch circuit panelboards, branch circuit breakers feeding convenience outlets shall have sensitive instantaneous trip settings of not more than 10 times the trip rating of the breaker to prevent repeated arcing shorts resulting from frayed appliance cords. Single-pole 15- and 20-ampere circuit breakers shall be UL listed as "Switching Breakers" at 220 volts ac. Provide UL Class A (5-milliampere sensitivity) ground fault circuit protection on 220-volt ac branch circuit as indicated. This protection is an integral part of the branch circuit breaker that also provides overload and short-circuit protection for branch circuit wiring. Tripping of a branch circuit breaker containing ground fault circuit interruption is not to disturb the feeder circuit to the panelboard. A single-pole circuit breaker with integral ground fault circuit interruption requires no more panelboard branch circuit space than a conventional slide pole circuit breaker.

Ensure connections to the bus are bolt-on type.

When multiple wires per phase are specified, furnish the circuit breakers with connectors made to accommodate multiple wires.

Ensure circuit breaker spaces called out on the drawings are complete with mounting hardware to permit ready installation of the circuit breakers.

2.3 DIRECTORY CARD AND HOLDER

Mount a directory card on the inside of hinged fronts and doors 0.76 millimeter thick minimum plastic in a metal frame, with spaces for circuit numbers, outlets controlled, and room numbers. Where hinged fronts or doors are not required, provide the directory card 0.76 millimeterthick minimum plastic in a metal frame mounted on the left-hand side of the front trim. Directory card shall identify each branch circuit with its respective and numbered circuit breaker.

2.4 FACTORY TESTING

Test complete panelboards in accordance with UL 67.

2.5 PRECAUTIONARY LABEL

To ensure persons are aware of immediate or potential hazard in the application, installation, use, or maintenance of panelboards, each panelboard shall be conspicuously marked on the trim or dead front shield with the text (or equivalent) **DANGER** symbol. If the panel is supplied with a door, ensure the label is visible when the door is in the open position.

PART 3 EXECUTION

3.1 INSTALLATION

Install panelboards as indicated and in accordance with the manufacturer's instructions. Fully align and mount panels so that the height of the top operating handle does not exceed 1800 millimeter above the finished floor.

Directory-card information shall be typewritten in capital letters to indicate outlets controlled and final room numbers served by each circuit and shall be mounted in holders behind protective covering.

3.2 SITE TESTING

Each panelboard enclosure key shall be shown to operate the enclosure locks in the presence of the Contracting Officer.

Panelboards shall be given continuity and insulation tests after the installation has been completed and before the panelboard is energized.

Provide test equipment, labor, and personnel as required to perform the tests as specified. Conduct Continuity tests using a dc device with buzzer.

Conduct insulation tests on 380-volt panelboards using a 1,000-volt insulation-resistance test set. Record readings every minute until three equal and consecutive readings have been obtained. Resistance between phase conductors and between phase conductors and ground shall be not less than 50 megohms.

Conduct insulation tests on panelboards rated 300 volts or less using a 500-volt minimum insulation-resistance test set. Record readings after 1 minute and until the reading is constant for 15 seconds. Resistance between phase conductors and between phase conductors and ground shall be not less than 25 megohms.

Record test data and include the location and identification of panelboards and megohm readings versus time.

-- End of Section --

SECTION 26 28 01.00 10

COORDINATED POWER SYSTEM PROTECTION
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE C37.13	(2008) Standard for Low-Voltage AC Power Circuit Breakers Used in Enclosures
IEEE C37.16	(2000) Recommendations for Low-Voltage Power Circuit Breakers and AC Power Circuit Protectors, - Preferred Ratings, Related Requirements, and Application
IEEE Std 242	(2001) Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems - Buff Book
IEEE Std 399	(1997) Recommended Practice for Power Systems Analysis - Brown Book

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA AB 1	(2002) Molded-Case Circuit Breakers, Molded Case Switches, and Circuit-Breaker Enclosures
NEMA FU 1	(2002; R 2007) Low Voltage Cartridge Fuses
NEMA ICS 2	(2000; Errata 2002; R 2005; Errata 2006) Standard for Industrial Control and Systems: Controllers, Contactors, and Overload Relays Rated Not More than 2000 Volts AC or 750 Volts DC: Part 8 - Disconnect Devices for Use in Industrial Control Equipment
NEMA SG 6	(2000) Standard for Power Switching Equipment

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical

Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 198B	(1995) Class H Fuses
UL 198C	(1986; Rev thru Feb 1998) High-Interrupting-Capacity Fuses, Current-Limiting Types
UL 198D	(1995) Class K Fuses
UL 198E	(1988; Rev Jul 1988) Class R Fuses
UL 198H	(1988; Rev thru Nov 1993) Class T Fuses
UL 486E	(1994; Rev thru May 2000) Equipment Wiring Terminals for Use with Aluminum and/or Copper Conductors
UL 489	(2009) Standard for Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 508	(1999; Rev thru Sep 2008) Standard for Industrial Control Equipment
UL 877	(1993; Rev thru Nov 1999) Circuit Breakers and Circuit-Breaker Enclosures for Use in Hazardous (Classified) Locations

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Fault Current Analysis
Protective Device Coordination Study

The study along with protective device equipment submittals. No time extensions or similar contact modifications will be granted for work arising out of the requirements for this study. Approval of protective devices proposed will be based on recommendations of this study. The Government shall not be held responsible for any changes to equipment, device ratings, settings, or additional labor for installation of equipment or devices ordered and/or procured prior to approval of the study.

Equipment

Data consisting of manufacturer's time-current characteristic curves for individual protective devices, recommended settings of adjustable protective devices, and recommended ratings of non-adjustable protective devices.

System Coordinator

Verification of experience and license number, of a registered Professional Engineer with at least 3 years of current experience in the design of coordinated power system protection. Experience data shall include at least five references for work of a magnitude comparable to this contract, including points of contact, addresses and telephone numbers. This engineer must perform items required by this section to be performed by a registered Professional Engineer.

Protective Relays

Data shall including calibration and testing procedures and instructions pertaining to the frequency of calibration, inspection, adjustment, cleaning, and lubrication.

Installation

Procedures including diagrams, instructions, and precautions required to properly install, adjust, calibrate, and test the devices and equipment.

SD-06 Test Reports

Field Testing

The proposed test plan, prior to field tests. Plan shall consist of complete field test procedure including tests to be performed, test equipment required, and tolerance limits, including complete testing and verification of the ground fault protection equipment, where used. Performance test reports in booklet form showing all field tests performed to adjust each component and all field tests performed to prove compliance with the specified performance criteria, upon completion and testing of the installed system. Each test report shall indicate the final position of controls.

SD-07 Certificates

Devices and Equipment

Certificates certifying that all devices or equipment meet the requirements of the contract documents.

1.3 SYSTEM DESCRIPTION

The power system covered by this specification consists of: The installation of the complete electrical interior distribution system.

1.4 QUALIFICATIONS

1.4.1 System Coordinator

System coordination, recommended ratings and settings of protective devices, and design analysis shall be accomplished by a registered professional electrical power engineer with a minimum of 3 years of current experience in the coordination of electrical power systems.

1.4.2 System Installer

Calibration, testing, adjustment, and placing into service of the protective devices shall be accomplished by a manufacturer's product field service engineer or independent testing company with a minimum of two years of current product experience in protective devices.

1.5 DELIVERY, STORAGE, AND HANDLING

Devices and equipment shall be visually inspected when received and prior to acceptance from conveyance. Stored items shall be protected from the environment in accordance with the manufacturer's published instructions. Damaged items shall be replaced.

1.6 PROJECT/SITE CONDITIONS

Devices and equipment furnished under this section shall be suitable for the following site conditions. Seismic details shall conform to Section 26 05 48.00 10 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT.

1.6.1 Altitude

Altitude: As determined by site location.

1.6.2 Ambient Temperature

Ambient Temperature: +50 degrees C -30 degrees C.

1.6.3 Frequency

Frequency: 50 HZ.

1.6.4 Seismic Parameters

Seismic Parameters: As determined by site conditions.

1.7 EXTRA MATERIALS

The following spare fuses or spare fuse elements shall be delivered to the Contracting officer when the electrical system is accepted:

PART 2 PRODUCTS

2.1 STANDARD PRODUCT

Protective devices and equipment shall be the standard product of a manufacturer regularly engaged in the manufacture of the product and shall essentially duplicate items that have been in satisfactory utility type use for at least two years prior to bid opening.

2.2 NAMEPLATES

Nameplates shall be provided to identify all protective devices and equipment. Nameplate information shall be in accordance with NEMA AB 1 or NEMA SG 6 as applicable.

2.3 CORROSION PROTECTION

Metallic materials shall be protected against corrosion. Ferrous metal

hardware shall be zinc or chrome-plated.

2.4 MOTOR CONTROLS AND MOTOR CONTROL CENTERS

2.4.1 Motor Starters

Combination starters shall be provided with circuit breakers or fusible switches.

2.4.2 Thermal-Overload Protection

Each motor of 93 W (1/8 hp) or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller, or shall be mounted in a separate enclosure. Unless otherwise specified, the protective device shall be of the manually reset type. Single or double pole tumbler switches specifically designed for alternating-current operation only may be used as manual controllers for single-phase motors having a current rating not in excess of 80 percent of the switch rating.

2.4.3 Low-Voltage Motor Overload Relays

2.4.3.1 General

Thermal and magnetic current overload relays shall conform to NEMA ICS 2 and UL 508. Overload protection shall be provided either integral with the motor or controller, and shall be rated in accordance with the requirements of NFPA 70. Standard units shall be used for motor starting times up to 7 second. Slow units shall be used for motor starting times from 8 to 12 seconds. Quick trip units shall be used on hermetically sealed, submersible pumps, and similar motors.

2.4.3.2 Construction

Manual reset type thermal relays shall be bimetallic construction. Automatic reset type relays shall be bimetallic construction.

2.4.3.3 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. Trip current ratings shall be established by selection of the replaceable overload device and shall not be adjustable. Where the controller is remotely-located or difficult to reach, an automatic reset, non-compensated overload relay shall be provided. Manual reset overload relays shall be provided otherwise, and at all locations where automatic starting is provided. Where the motor is located in a constant ambient temperature, and the thermal device is located in an ambient temperature that regularly varies by more than minus 10 degrees C, an ambient temperature-compensated overload relay shall be provided.

2.4.4 Automatic Control Devices

2.4.4.1 Direct Control

Automatic control devices (such as thermostats, float or pressure switches) which control the starting and stopping of motors directly shall be designed for that purpose and have an adequate kilowatt rating.

2.4.4.2 Pilot-Relay Control

Where the automatic-control device does not have such a rating, a magnetic starter shall be used, with the automatic-control device actuating the pilot-control circuit.

2.4.4.3 Manual/Automatic Selection

a. Where combination manual and automatic control is specified and the automatic-control device actuates the pilot control circuit of a magnetic starter, the magnetic starter shall be provided with a three-position selector switch marked MANUAL-OFF-AUTOMATIC.

b. Connections to the selector switch shall only allow the normal automatic regulatory control devices to be bypassed when the switch is in the Manual position; all safety control devices, such as low-or high-pressure cutouts, high-temperature cutouts, and motor-overload protective devices, shall be connected in the motor-control circuit in both the Manual and the Automatic positions of the selector switch. Control circuit connections to any MANUAL-OFF-AUTOMATIC switch or to more than one automatic regulatory control device shall be made in accordance with wiring diagram approved by the contracting Officer unless such diagram is included on the drawings. All controls shall be 220 volts or less unless otherwise indicated.

2.5 LOW-VOLTAGE FUSES

2.5.1 General

Low-voltage fuses shall conform to NEMA FU 1. Time delay and nontime delay options shall be as specified. Equipment provided under this contract shall be provided with a complete set of properly rated fuses when the equipment manufacturer utilizes fuses in the manufacture of the equipment, or if current-limiting fuses are required to be installed to limit the ampere-interrupting capacity of circuit breakers or equipment to less than the maximum available fault current at the location of the equipment to be installed. Fuses shall have a voltage rating of not less than the phase-to-phase circuit voltage, and shall have the time-current characteristics requires for effective power system coordination.

2.5.2 Cartridge Fuses; Noncurrent-Limiting Type

Cartridge fuses of the noncurrent-limiting type shall be Class H, nonrenewable, dual element, time lag type and shall have interrupting capacity of 10,000 amperes. Class H Fuses shall conform to UL 198B. At 500 percent current, cartridge fuses shall not blow in less than 10 seconds. Cartridge fuses shall be used for circuits rated in excess of 30 amperes, 220 volts, except where current-limiting fuses are indicated.

2.5.3 Cartridge Fuses; Current-Limiting Type

Cartridge fuses, current-limiting type, Class G, J, K, L, RK1, RK5, RK9, T, CC shall have tested interrupting capacity not less than 200,000 amperes. Fuse holders shall be the type that will reject Class H fuses.

a. Class G, J, L, CC fuses shall conform to UL 198C.

b. Class K fuses shall conform to UL 198D.

c. Class R fuses shall conform to UL 198E.

d. Class T fuses shall conform to UL 198H.

2.5.3.1 Continuous Current Ratings (600 amperes and smaller)

Service entrance and feeder circuit fuses (600 amperes and smaller) shall be Class RK1, RK5, J, current-limiting, time-delay with 200,000 amperes interrupting capacity.

2.5.3.2 Continuous Current Ratings (greater than 600 amperes)

Service entrance and feeder circuit fuses (greater than 600 amperes) shall be Class L, current-limiting, time-delay with 200,000 amperes interrupting capacity.

2.5.3.3 Motor and Transformer Circuit Fuses

Motor, motor controller, transformer, and inductive circuit fuses shall be Class RK1 or RK5, current-limiting, time-delay with 200,000 amperes interrupting capacity.

2.6 MOLDED-CASE CIRCUIT BREAKERS

2.6.1 General

Molded-case circuit breakers shall conform to NEMA AB 1 and UL 489. Circuit breakers may be installed in panelboards, switchboards, enclosures, or combination motor controllers. Circuit breakers and circuit breaker enclosures located in hazardous (classified) areas shall conform to UL 877.

2.6.2 Construction

Molded-case circuit breakers shall be assembled as an integral unit in a supporting and enclosing housing of glass reinforced insulating material providing high dielectric strength. Circuit breakers shall be suitable for mounting and operating in any position. Lugs shall be listed for copper conductors only in accordance with UL 486E. Single-pole circuit breakers shall be full module size with not more than one pole per module. Multi-pole circuit breakers shall be of the common-trip type having a single operating handle such that an overload or short circuit on any one pole will result in all poles opening simultaneously. Sizes of 100 amperes or less may consist of single-pole breakers permanently factory assembled into a multi-pole unit having an internal, mechanical, nontamperable common-trip mechanism and external handle ties. All circuit breakers shall have a quick-make, quick-break overcenter toggle-type mechanism, and the handle mechanism shall be trip-free to prevent holding the contacts closed against a short-circuit or sustained overload. All circuit breaker handles shall assume a position between "ON" and "OFF" when tripped automatically. All ratings shall be clearly visible.

2.6.3 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. The interrupting rating of the circuit breakers shall be at least equal to the available short-circuit current at the line terminals of the circuit breaker and correspond to the UL listed integrated short-circuit current rating specified for the panelboards and switchboards. Molded-case circuit

breakers shall have nominal voltage ratings, maximum continuous-current ratings, and maximum short-circuit interrupting ratings in accordance with NEMA AB 1. Ratings shall be coordinated with system X/R ratio.

2.6.4 Cascade System Ratings

Circuit breakers used in series combinations shall be in accordance with UL 489. Equipment, such as switchboards and panelboards, which house series-connected circuit breakers shall be clearly marked accordingly. Series combinations shall be listed in the UL Recognized Component Directory under "Circuit Breakers-Series Connected."

2.6.5 Thermal-Magnetic Trip Elements

Thermal magnetic circuit breakers shall be provided as shown. Automatic operation shall be obtained by means of thermal-magnetic tripping devices located in each pole providing inverse time delay and instantaneous circuit protection. The instantaneous magnetic trip shall be adjustable and accessible from the front of all circuit breakers on frame sizes above 150 amperes.

2.6.6 SWD Circuit Breakers

Circuit breakers rated 15 amperes or 20 amperes and intended to switch 220 volts or less fluorescent lighting loads shall be marked "SWD."

2.6.7 HACR Circuit Breakers

Circuit breakers 60 amperes or below, 380 volts, 1-pole or 2-pole, intended to protect multi-motor and combination-load installations involved in heating, air conditioning, and refrigerating equipment shall be marked "Listed HACR Type."

2.6.8 Motor Circuit Protectors (MCP)

Motor circuit protectors shall conform to NEMA AB 1 and UL 489 and shall be provided as shown. MCPs shall consist of an adjustable instantaneous trip circuit breaker in conjunction with a combination motor controller which provides coordinated motor circuit overload and short-circuit protection. Motor Circuit Protectors shall be rated in accordance with NFPA 70.

2.7 LOW-VOLTAGE POWER CIRCUIT BREAKERS

2.7.1 Construction

Low-voltage power circuit breakers shall conform to IEEE C37.13, IEEE C37.16, and NEMA SG 6 and shall be three-pole, single-throw, stored energy, manually operated. Circuit breakers shall have an open/close contact position indicator, charged/discharged stored energy indicator, primary disconnect devices, and a mechanical interlock to prevent making or breaking contact of the primary disconnects when the circuit breaker is closed. Control voltage shall be 220 V ac. The circuit breaker enclosure shall be suitable for its intended location.

2.7.2 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. Circuit breakers shall be rated for 100 percent continuous duty and shall have trip current ratings and frame sizes as shown. Nominal voltage

ratings, maximum continuous-current ratings, and maximum short-circuit interrupting ratings shall be in accordance with IEEE C37.16. Tripping features shall be as follows:

a. Long-time current pick-up, adjustable from 50 percent to 100 percent of sensor current rating.

b. Adjustable long-time delay.

c. Short-time current pick-up, adjustable from 1.5 to 9 times long-time current setting.

d. Adjustable short-time delay.

e. Short-time I square times t switch.

f. Instantaneous current pick-up, adjustable from 1.5 to 9 times long-time current setting.

g. Adjustable ground-fault delay.

h. Ground-fault I square times t switch.

i. Ground-fault trip indicators shall be provided.

2.8 COORDINATED POWER SYSTEM PROTECTION

Analyses shall be prepared to demonstrate that the equipment selected and system constructed meet the contract requirements for ratings, coordination, and protection. They shall include a load flow analysis, a fault current analysis, and a protective device coordination study. The studies shall be performed by a registered professional engineer with demonstrated experience in power system coordination in the last 3 years. The Contractor shall provide a list of references complete with points of contact, addresses and telephone numbers. The selection of the engineer is subject to the approval of the Contracting Officer.

2.8.1 Scope of Analyses

The fault current analysis, and protective device coordination study shall begin at: the source bus and extend down to system buses where fault availability is 10,000 amperes (symmetrical) for building/facility 600 volt level distribution buses.

2.8.2 Determination of Facts

The time-current characteristics, features, and nameplate data for each existing protective device shall be determined and documented. The Contractor shall utilize the fault current availability indicated as a basis for fault current studies.

2.8.3 Single Line Diagram

A single line diagram shall be prepared to show the electrical system buses, devices, transformation points, and all sources of fault current (including generator and motor contributions). A fault-impedance diagram or a computer analysis diagram may be provided. Each bus, device or transformation point shall have a unique identifier. If a fault-impedance diagram is provided, impedance data shall be shown. Location of switches,

breakers, and circuit interrupting devices shall be shown on the diagram together with available fault data, and the device interrupting rating.

2.8.4 Fault Current Analysis

2.8.4.1 Method

The fault current analysis shall be performed in accordance with methods described in IEEE Std 242, and IEEE Std 399.

2.8.4.2 Data

Actual data shall be utilized in fault calculations. Bus characteristics and transformer impedance shall be those proposed. Data shall be documented in the report.

2.8.4.3 Fault Current Availability

Balanced three-phase fault, bolted line-to-line fault, and line-to-ground fault current values shall be provided at each voltage transformation point and at each power distribution bus. The maximum and minimum values of fault available at each location shall be shown in tabular form on the diagram or in the report.

2.8.5 Coordination Study

The study shall demonstrate that the maximum possible degree of selectivity has been obtained between devices specified, consistent with protection of equipment and conductors from damage from overloads and fault conditions. The study shall include a description of the coordination of the protective devices in this project. A written narrative shall be provided describing: which devices may operate in the event of a fault at each bus; the logic used to arrive at device ratings and settings; situations where system coordination is not achievable due to device limitations (an analysis of any device curves which overlap); coordination between upstream and downstream devices; and relay settings. Recommendations to improve or enhance system reliability, and detail where such changes would involve additions or modifications to the contract and cost damages (addition or reduction) shall be provided. Composite coordination plots shall be provided on log-log graph paper.

2.8.6 Study report

a. The report shall include a narrative describing: the analyses performed; the bases and methods used; and the desired method of coordinated protection of the power system.

b. The study shall include descriptive and technical data for existing devices and new protective devices proposed. The data shall include manufacturers published data, nameplate data, and definition of the fixed or adjustable features of the existing or new protective devices.

c. The report shall document system voltages, fault MVA, system X/R ratio, time-current characteristic curves, current transformer ratios, and relay device numbers and settings.

d. The report shall contain fully coordinated composite time-current characteristics curves for each bus in the system, as required to

ensure coordinated power system protection between protective devices or equipment. The report shall include recommended ratings and settings of all protective devices in tabulated form.

e. The report shall provide the calculation performed for the analyses, including computer analysis programs utilized. The name of the software package, developer, and version number shall be provided.

PART 3 EXECUTION

3.1 VERIFICATION OF DIMENSIONS

After becoming familiar with details of the work, the Contractor shall verify dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing any work.

3.2 INSTALLATION

Protective devices shall be installed in accordance with the manufacturer's published instructions and in accordance with the requirements of NFPA 70 and IEEE C2.

3.3 FIELD TESTING

3.3.1 General

Field testing shall be performed in the presence of the Contracting Officer. The Contractor shall notify the Contracting Officer 14 days prior to conducting tests. The Contractor shall furnish all materials, labor, and equipment necessary to conduct field tests. The Contractor shall perform all tests and inspections recommended by the manufacturer unless specifically waived by the Contracting Officer. The Contractor shall maintain a written record of all tests which includes date, test performed, personnel involved, devices tested, serial number and name of test equipment, and test results.

3.3.2 Safety

The Contractor shall provide and use safety devices such as rubber gloves, protective barriers, and danger signs to protect and warn personnel in the test vicinity. The Contractor shall replace any devices or equipment which are damaged due to improper test procedures or handling.

3.3.3 Molded-Case Circuit Breakers

Circuit breakers shall be visually inspected, operated manually, and connections checked for tightness. Current ratings shall be verified and adjustable settings incorporated in accordance with the coordination study.

-- End of Section --

SECTION 26 32 15.00 10

DIESEL-GENERATOR SET STATIONARY 100-2500 KW, WITH AUXILIARIES
10/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B16.11	(2009) Forged Fittings, Socket-Welding and Threaded
ASME B16.3	(2006) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.5	(2009) Standard for Pipe Flanges and Flanged Fittings: NPS 1/2 Through NPS 24
ASME BPVC SEC VIII D1	(2007; Addenda 2008) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels Division 1 - Basic Coverage

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

AEIC CS8	(2000) Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV

ASTM INTERNATIONAL (ASTM)

ASTM A 106/A 106M	(2008) Standard Specification for Seamless Carbon Steel Pipe for High-Temperature Service
ASTM A 181/A 181M	(2006) Standard Specification for Carbon Steel Forgings, for General-Purpose Piping
ASTM A 234/A 234M	(2007) Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service
ASTM A 53/A 53M	(2007) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM D 975	(2009b) Standard Specification for Diesel Fuel Oils

ELECTRICAL GENERATING SYSTEMS ASSOCIATION (EGSA)

EGSA 101P	(1995) Engine Driven Generator Sets

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE C57.13.1	(2006) Guide for Field Testing of Relaying Current Transformers
IEEE Std 1	(2000; R 2005) General Principles for Temperature Limits in the Rating of Electric Equipment and for the Evaluation of Electrical Insulation
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms
IEEE Std 115	(1995; R 2002) Test Procedures for Synchronous Machines: Part I: Acceptance and Performance Testing; Part II: Test Procedures and Parameter Determination for Dynamic Analysis
IEEE Std 404	(2006) Extruded and Laminated Dielectric Shielded Cable Joints Rated 2500 V Through 500 000 V
IEEE Std 120	(1989; R 2007) Master Test Guide for Electrical Measurements in Power Circuits
IEEE Std 48	(2009) Test Procedures and Requirements for Alternating-Current Cable Terminations 2.5 kV through 765 kV
IEEE Std 43	(2000; R 2006) Testing Insulation Resistance of Rotating Machinery
IEEE Std 519	(1992; Errata 2004) Recommended Practices and Requirements for Harmonic Control in Electrical Power Systems
IEEE Std 81	(1983) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System (Part 1) Normal Measurements

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2002) Standard for Pipe Hangers and Supports - Materials, Design and Manufacture
MSS SP-69	(2003; R 2004) Standard for Pipe Hangers and Supports - Selection and Application
MSS SP-80	(2008) Bronze Gate, Globe, Angle and Check

Valves

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA C12.11	(2007) Instrument Transformers for Revenue Metering, 10 kV BIL through 350 kV BIL (0.6 kV NSV through 69 kV NSV)
NEMA ICS 6	(1993; R 2006) Standard for Industrial Controls and Systems Enclosures
NEMA MG 1	(2007; Errata 2008) Standard for Motors and Generators
NEMA PB 1	(2006; Errata 2008) Standard for Panelboards
NEMA PB 2	(2006) Deadfront Distribution Switchboards
NEMA SG 6	(2000) Standard for Power Switching Equipment
NEMA WC 74	(2006) Standard for 5-46 kV Shielded Power Cable for use in the Transmission and Distribution of Electric Energy

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 110	(2010) Standard for Emergency and Standby Power Systems
NFPA 30	(2007; Errata 2008) Flammable and Combustible Liquids Code
NFPA 37	(2006) Installation and Use of Stationary Combustion Engines and Gas Turbines
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 99	(2005; Errata 2005) Health Care Facilities

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J537	(2000) Storage Batteries

UNDERWRITERS LABORATORIES (UL)

UL 1236	(2006; Rev thru Feb 2009) Standard for Safety Battery Chargers for Charging Engine-Starter Batteries
UL 891	(2005) Dead-Front Switchboards

1.2 SYSTEM DESCRIPTION

a. Provide and install each engine-generator set complete and totally functional, with all necessary ancillary equipment to include: air filtration; starting system; generator controls, protection, and

isolation; instrumentation; lubrication; fuel system; cooling system; and engine exhaust system. Each engine-generator set shall satisfy the requirements specified in the Engine-Generator Parameter Schedule.

b. Each set shall consist of one engine, one generator, and one exciter mounted, assembled, and aligned on one base; and other necessary ancillary equipment which may be mounted separately. Sets having a capacity of 750 kW or smaller shall be assembled and attached to the base prior to shipping. Sets over 750 kW capacity may be shipped in sections. Each set component shall be environmentally suitable for the location shown and shall be the manufacturer's standard product offered in catalogs for commercial or industrial use. Any nonstandard products or components and the reason for their use shall be specifically identified in paragraph SUBMITTALS.

1.2.1 Engine-Generator Parameter Schedule

ENGINE-GENERATOR PARAMETER SCHEDULE

Power Rating	Prime
Overload Capacity (Prime applications only)	110 percent of Service Load for 1 hour in 12 consecutive hours
Service Load	1,250 kVA (continuous
Power Factor	0.8 lagging
Engine-Generator Applications	parallel with other generators on an isolated bus
Maximum Speed	1800 rpm
Heat Exchanger Type	fin-tube (radiator)
Governor Type	Isochronous
Frequency Bandwidth (steady state)	± 0.4%
Governor Type	Droop
Frequency Regulation (droop) (No Load to Full Load)	3 percent (maximum)
Frequency Bandwidth (steady state)	± 0.4%
Voltage Regulation (No Load to Full Load) (Stand alone applications)	± 2 percent (maximum)
Voltage Bandwidth (steady state)	± 0.5 percent
Frequency	50 Hz
Voltage	380/220 volts

ENGINE-GENERATOR PARAMETER SCHEDULE

Phases	3 Phase, Wye
Minimum Generator Subtransient Reactance	.12 percent
Max Step Load Increase	25% of Service Load at 90 PF
Transient Recovery Time with Step Load Increase (Voltage)	___ seconds
Transient Recovery Time with Step Load Increase (Frequency)	___ seconds
Maximum Voltage Deviation with Step Load Increase	10% of rated voltage
Maximum Frequency Deviation with Step Load Increase	5 percent of rated frequency
Max Step Load Decrease (without shutdown)	100 percent of Service Load at 90 PF
Max Time to Start and be Ready to Assume Load	10 seconds
Max Summer Outdoor Temp (Ambient)	36 degrees C
Min Winter Outdoor Temp (Ambient)	-24 degrees C
Installation Elevation	1,225 M above sea level

1.2.2 Rated Output Capacity

Each engine-generator-set shall provide power equal to the sum of Service Load plus the machine's efficiency loss and associated ancillary equipment loads. Rated output capacity shall also consider engine and/or generator oversizing required to meet requirements in paragraph Engine-Generator Parameter Schedule.

1.2.3 Power Ratings

Power ratings shall be in accordance with EGSA 101P.

1.2.4 Transient Response

The engine-generator set governor and voltage regulator shall cause the engine-generator set to respond to the maximum step load changes such that output voltage and frequency recover to and stabilize within the operational bandwidth within the transient recovery time. The engine-generator set shall respond to maximum step load changes such that the maximum voltage and frequency deviations from bandwidth are not exceeded.

1.2.5 Reliability and Durability

Each prime engine-generator set shall have both an engine and a generator capable of delivering the specified power on a prime basis with an anticipated mean time between overhauls of not less than 10,000 hours operating with a 70 percent load factor. Two like engines and two like generators shall be cited that have performed satisfactorily in a stationary power plant, independent from the physical location of the manufacturer's and assembler's facilities. The engine and generators should have been in operation for a minimum of 8000 actual hours at a minimum load of 70 percent of the rated output capacity. During two consecutive years of service, the units should not have experienced any failure resulting in a downtime in excess of 72 hours. Like engines shall be of the same model, speed, bore, stroke, number and configuration of cylinders and rated output capacity. Like generators shall be of the same model, speed, pitch, cooling, exciter, voltage regulator and rated output capacity. Two like engines and two like generators shall be cited that have performed satisfactorily in a stationary power plant, independent and separate from the physical location of the manufacturer's and assembler's facilities, for standby without any failure to start, including all periodic exercise. Each like engine and generator shall have had no failures resulting in downtime for repairs in excess of 72 hours during two consecutive years of service. Like engines shall be of the same model, speed, bore, stroke, number and configuration of cylinders, and rated output capacity. Like generators shall be of the same model, speed, pitch, cooling, exciter, voltage regulator and rated output capacity.

1.2.6 Parallel Operation

Each engine-generator set specified for parallel operation shall be configured for automatic parallel operation. Each set shall be capable of parallel operation with one or more sets on an isolated bus.

1.2.7 Load Sharing

Each engine-generator set specified for parallel operation shall be configured to automatically load share with other sets by proportional loading. Proportional loading shall load each set to within 5 percent of its fair share. A set's fair share is its nameplate-rated capacity times the total load, divided by the sum of all nameplate-rated capacities of on-line sets. Load sharing shall incorporate both the real and reactive components of the load.

1.2.8 Engine-Generator Set Enclosure

The engine-generator set enclosure shall be corrosion resistant and fully weather resistant. The enclosure shall contain all set components and provide ventilation to permit operation at Service Load under secured conditions. Doors shall be provided for access to controls and equipment requiring periodic maintenance or adjustment. Removable panels shall be provided for access to components requiring periodic replacement. The enclosure shall be capable of being removed without disassembly of the engine-generator set or removal of components other than the exhaust system. The enclosure shall reduce the noise of the generator set to within the limits specified in the paragraph SOUND LIMITATIONS.

Enclosure shall be furnished with a 100 ampere panelboard mounted in side the enclosure. Panel shall be provided with branch circuits for lighting within the enclosure, receptacles, battery charger, jacket water heaters,

generator condensation heater and emergency shutdown switch within the enclosure. The interior exhaust piping shall be extended as noted on plans.

1.2.9 Fuel Consumption

Engine fuel consumption shall not exceed the following maximum limits based on the conditions listed below.

Size Range Net kW	% of Rated Output capacity	Fuel Usage kg/kWH (lbs/kWH)
1000 - 2500	75 and 100	0.243 (0.536)
	50	0.260 (0.573)

Conditions:

a. Net kW of the Set corrected for engine auxiliaries that are electrically driven, where kW is electrical kilowatt hours.

b. 45 MJ/kg high-heat value for fuel used.

c. Sea level operation.

d. Intake-air temperature not over 32 degrees C.

e. Barometric pressure of intake air not less than 95.7 kPa of mercury.

1.2.10 Harmonic Requirements

Non-linear loads to be served by each engine-generator set are as indicated. The maximum linear load demand (kVA @ PF) when non-linear loads will also be in use is as indicated.

1.2.11 Starting Time Requirements

Upon receipt of a signal to start, each engine generator set will start, reach rated frequency and voltage and be ready to assume load within the time specified. For standby sets used in emergency power applications, each engine generator set will start, reach rated frequency and voltage, and power will be supplied to the load terminals of the automatic transfer switch within the starting time specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detailed Drawings; G

Detailed drawings, as specified.

Acceptance; G

Drawings which accurately depict the as-built configuration of the installation, upon acceptance of the diesel-generator set installation. Revise layout drawings to reflect the as-built conditions and submit them with the as-built drawings.

SD-03 Product Data

Harmonic Requirements
Engine-Generator Parameter Schedule

Description of the generator features which mitigate the effects of the non-linear loads listed.

Heat Exchanger

Manufacturers data to quantify heat rejected to the space with the engine generator set at rated capacity.

Generator

Manufacturer's standard data for each generator (prototype data at the specified rating or above is acceptable), listing the following information:

a. Direct-Axis subtransient reactance (per unit).

b. The generator kW rating and short circuit current capacity (both symmetric and asymmetric).

Manufacturer's Catalog

Manufacturer's standard catalog data describing and depicting each engine-generator set and all ancillary equipment in sufficient detail to demonstrate complete specification compliance.

Spare Parts

List of spare parts, as specified.

Onsite Training

A letter giving the date proposed for conducting the onsite training course, the agenda of instruction, a description of the video taping service to be provided, and the kind and quality of the tape to be left with the Contracting Officer at the end of the instructional period.

Vibration-Isolation

Vibration isolation system performance data for the range of frequencies generated by the engine-generator set during operation from no load to full load and the maximum vibration transmitted to the floor. Description of seismic qualification of the engine-generator mounting, base, and vibration isolation.

Posted Data and Instructions

Posted data including wiring and control diagrams showing the

key mechanical and electrical control elements, and a complete layout of the entire system.

Instructions

Instructions including: the manufacturers pre-start checklist and precautions; startup procedures for test-mode, manual-start mode, and automatic-start mode (as applicable); running checks, procedures, and precautions; and shutdown procedures, checks, and precautions. Instructions shall include procedures for interrelated equipment (load-shedding). Instructions shall be weatherproof, laminated in plastic, and posted where directed.

Experience

Statement showing that each component manufacturer has a minimum of 3 years experience in the manufacture, assembly and sale of components used with stationary diesel engine-generator sets for commercial and industrial use. The engine-generator set manufacturer/assembler has a minimum of 3 years experience in the manufacture, assembly and sale of stationary diesel engine-generator sets for commercial and industrial use.

Field Engineer

A letter listing the qualifications, schools, formal training, and experience of the field engineer.

General Installation

A copy of the manufacturer's installation procedures and a detailed description of the manufacturer's recommended break-in procedure.

SD-05 Design Data

Performance Criteria

Calculations of the engine and generator output power capability, including efficiency and parasitic load data.

Sound Limitations

Sound power level data for the packaged unit operating at 100 percent load in a free field environment. The data should demonstrate compliance with the sound limitation requirements of this specification.

Integral Main Fuel Storage Tank

Day Tank

Calculations for the capacity of each day tank, including allowances for recirculated fuel, usable tank capacity, and duration of fuel supply.

Power Factor

The generator capability curve showing generator kVA output

capability (kW vs. kvar) for both leading and lagging power factors ranging from 0 to 1.0.

Time-Delay on Alarms

The magnitude of monitored values which define alarm or action set points, and the tolerance (plus and/or minus) at which the devices activate the alarm or action for items contained within the alarm panels.

Battery Charger

Battery charger sizing calculations.

SD-06 Test Reports

Factory Inspection and Tests

Six complete reproducible copies of the factory inspection result on the checklist format specified in paragraph FACTORY INSPECTION AND TESTS.

Factory Tests

a. A letter giving notice of the proposed dates of factory inspections and tests at least 14 days prior to beginning tests.

b. A detailed description of the manufacturer's procedures for factory tests at least 14 days prior to beginning tests.

c. Six copies of the Factory Test data described below in 215.9 by 279.4 mm binders having a minimum of 3 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs. Data plots shall be full size (215.9 by 279.4 mm minimum), showing grid lines, with full resolution.

(1) A detailed description of the procedures for factory tests.

(2) A list of equipment used, with calibration certifications.

(3) A copy of measurements taken, with required plots and graphs.

(4) The date of testing.

(5) A list of the parameters verified.

(6) The condition specified for the parameter.

(7) The test results, signed and dated.

(8) A description of adjustments made.

Onsite Inspection and Tests; G

a. A letter giving notice of the proposed dates of onsite inspections and tests at least 14 days prior to beginning tests.

b. A detailed description of the Contractor's procedures for onsite

tests including the test plan and a listing of equipment necessary to perform the tests. Submission shall be at least 30 days prior to beginning tests.

c. Six copies of the onsite test data described below in 215.9 by 279.4 mm binders having a minimum of 3 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs. Data plots shall be full size (215.9 by 279.4 mm minimum), showing grid lines, with full resolution.

(1) A detailed description of the procedures for onsite tests.

(2) A list of equipment used, with calibration certifications.

(3) A copy of measurements taken, with required plots and graphs.

(4) The date of testing.

(5) A list of the parameters verified.

(6) The condition specified for the parameter.

(7) The test results, signed and dated.

(8) A description of adjustments made.

SD-07 Certificates

Cooling System

A letter which certifies that the engine-generator set and cooling system function properly in the ambient temperature specified, stating the following values:

a. The maximum allowable inlet temperature of the coolant fluid.

b. The minimum allowable inlet temperature of the coolant fluid.

c. The maximum allowable temperature rise in the coolant fluid through the engine.

Vibration Isolation

Torsional analysis including prototype testing or and calculations which certify and demonstrate that no damaging or dangerous torsional vibrations will occur when the prime mover is connected to the generator, at synchronous speeds, ± 10 percent.

Prototype Test

Manufacturer's standard certification that prototype tests were performed for the generator model proposed.

Reliability and Durability

A reliability and durability certification letter from the manufacturer and assembler to prove that existing facilities are and have been successfully utilizing the same components proposed

to meet this specification, in similar service. Certification may be based on components, i.e. engines used with different models of generators and generators used with different engines, and does not exclude annual technological improvements made by a manufacturer in the basic standard-model component on which experience was obtained, provided parts interchangeability has not been substantially affected and the current standard model meets the performance requirements specified. Provide a list with the name of the installations, completion dates, and name and telephone number of a point of contact.

Emissions

A certification from the engine manufacturer stating that the engine exhaust emissions meet the federal, state, and local regulations and restrictions specified. At a minimum this certification shall include emission factors for criteria pollutants including nitrogen oxides, carbon monoxide, particulate matter, sulfur dioxide, non-methane hydrocarbon, and for hazardous air pollutants (HPAs).

Sound Limitations

A certification from the manufacturer stating that the sound emissions meet the specification.

Site Visit

A letter stating the date the site was visited and listing discrepancies found.

Current Balance

A certification stating that the flywheel has been statically and dynamically balanced and is capable of being rotated at 125 percent of rated speed without vibration or damage.

Materials and Equipment

A certification stating that where materials or equipment are specified to comply with requirements of UL, written proof of such compliance has been obtained. The label or listing of the specified agency, or a written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency are acceptable as proof.

Inspections

A letter certifying that all facilities are complete and functional; that each system is fully functional; and that each item of equipment is complete, free from damage, adjusted, and ready for beneficial use.

Cooling System

Certification that the engine-generator set and cooling system function properly in the ambient temperatures specified.

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals

Six copies of the operation manual (approved prior to commencing onsite tests) in 215.9 by 279.4 mm binders, having a minimum of 3 rings from which material may readily be removed and replaced, including a separate section for each system or subsystem. Sections shall be separated by heavy plastic dividers with tabs which identify the material in the section. Drawings shall be folded blue lines, with the title block visible, and placed in 215.9 by 279.4 mm plastic pockets with reinforced holes. One full size reproducible mylar of each drawing shall accompany the booklets. Mylars shall be rolled and placed in a heavy cardboard tube with threaded caps on each end. The manual shall include: step-by-step procedures for system startup, operation, and shutdown; drawings, diagrams, and single-line schematics to illustrate and define the electrical, mechanical, and hydraulic systems together with their controls, alarms, and safety systems; the manufacturer's name, model number, and a description of equipment in the system. The instructions shall include procedures for interface and interaction with related systems to include load shedding systems. Each booklet shall include a CDROM containing an ASCII file of the procedures.

Maintenance Procedures

Six copies of the maintenance manual containing the information described below in 215.9 by 279.4 mm binders having a minimum of three rings from which material may readily be removed and replaced, including a separate section for each item listed. Each section shall be separated by a heavy plastic divider with tabs. Drawings shall be folded, with the title block visible, and placed in plastic pockets with reinforced holes.

a. Procedures for each routine maintenance item.

b. Procedures for troubleshooting.

c. Factory-service, take-down overhaul, and repair service manuals, with parts lists.

d. A copy of the posted instructions.

e. A component list which includes the manufacturer's name, address, type or style, model or serial number, rating, and catalog number for the major components specified for nameplates.

f. Six complete reproducible copies of the final relay and protective device settings. The settings shall be recorded with the name of the company and individual responsible for their accuracy.

Special Tools

Two complete sets of special tools required for maintenance (except for electronic governor handset). Special tools are those that only the manufacturer provides, for special purposes, or to

reach otherwise inaccessible parts. The tools shall be supplied complete with a suitable tool box. One handset shall be provided for each electronic governor when required to indicate and/or change governor response settings.

Filters

Two complete sets of filters, required for maintenance, shall be supplied in a suitable storage box. These filters shall be in addition to filters replaced after testing.

1.4 QUALITY ASSURANCE

1.4.1 Conformance to Codes and Standards

Where equipment is specified to conform to requirements of any code or standard such as UL, NEMA, etc., the design, fabrication and installation shall also conform to the code.

1.4.2 Vibration Limitation

The maximum engine-generator set vibration in the horizontal, vertical, and axial directions shall be limited to 0.15 mm (peak-peak RMS), with an overall velocity limit of 24 mm/second RMS, for all speeds through 110 percent of rated speed.

1.4.3 Seismic Requirements

Seismic requirements shall be in accordance with UFC 3-310-04 SEISMIC DESIGN FOR BUILDINGS and Sections 13 48 00 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT, 13 48 00 SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT and 26 05 48.00 10 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT .

1.4.4 Experience

Each component manufacturer shall have a minimum of 3 years experience in the manufacture, assembly and sale of components used with stationary diesel engine-generator sets for commercial and industrial use. The engine-generator set manufacturer/assembler shall have a minimum of 3 years experience in the manufacture, assembly and sale of stationary diesel engine-generator sets for commercial and industrial use.

1.4.5 Field Engineer

The engine-generator set manufacturer or assembler shall furnish a qualified field engineer to supervise the complete installation of the engine-generator set, assist in the performance of the onsite tests, and instruct personnel as to the operational and maintenance features of the equipment. The field engineer shall have attended the engine generator manufacturer's training courses on installation and operation and maintenance of engine generator sets.

1.4.6 Detailed Drawings

Submit detailed drawings showing the following:

a. Base-mounted equipment, complete with base and attachments, including anchor bolt template and recommended clearances for maintenance and operation.

b. Complete starting system.

c. Complete fuel system.

d. Complete cooling system.

e. Complete exhaust system.

f. Layout of relays, breakers, programmable controllers,switchgear, and switches including applicable single line and wiring diagrams with written description of sequence of operation and the instrumentation provided.

g. The complete lubrication system, including piping, pumps, strainers, filters, electric heater, controls and wiring.

h. Location, type, and description of vibration isolation devices for all applications.

i. The safety system, together with a detailed description of how it is to work. Wiring schematics, safety devices with a listing of their normal ranges, alarm and shutdown values (to include operation parameters such as pressures, temperatures voltages, currents, and speeds) shall be included.

j. One-line schematic and wiring diagrams of the generator, exciter, regulator, governor, and instrumentation.

k. Layout of each panel.

l. Mounting and support for each panel and major piece of electrical equipment.

m. Engine-generator set lifting points and rigging instructions.

1.5 DELIVERY, STORAGE, AND HANDLING

Properly protect material and equipment, in accordance with the manufacturers recommended storage procedures,before, during, and after installation. Protect stored items from the weather and contamination. During installation, piping and similar openings shall be capped to keep out dirt and other foreign matter.

1.6 EXTRA MATERIALS

Submit a complete list of spare parts for each piece of equipment and a complete list of all material and supplies needed for continued operation. Lists shall include supply source and current prices. Separate each list into two parts, those elements recommended by the manufacturer to be replaced after 3 years of service, and the remaining elements.

PART 2 PRODUCTS

2.1 NAMEPLATES

Each major component of this specification shall have the manufacturer's name, type or style, model or serial number and rating on a plate secured to the equipment. As a minimum, nameplates shall be provided for:

Engines	Relays
Generators	Transformers (CT & PT)
Regulators	Day tanks
Pumps and pump motors	Governors
Generator Breaker	
Economizers	

Where the following equipment is not provided as a standard component by the diesel engine generator set manufacturer, the nameplate information may be provided in the maintenance manual in lieu of nameplates.

Battery charger	Heaters
Exhaust mufflers	Silencers
Switchgear	Exciters
Battery	

2.2 SAFETY DEVICES

Exposed moving parts, parts that produce high operating temperatures, parts which may be electrically energized, and parts that may be a hazard to operating personnel shall be insulated, fully enclosed, guarded, or fitted with other types of safety devices. The safety devices shall be installed so that proper operation of the equipment is not impaired.

2.3 MATERIALS AND EQUIPMENT

2.3.1 Filter Elements

Fuel-oil, lubricating-oil, and combustion-air filter elements shall be manufacturer's standard.

2.3.2 Instrument Transformers

NEMA C12.11.

2.3.3 Pipe (Fuel/Lube-Oil, Compressed Air, Coolant, and Exhaust)

ASTM A 53/A 53M, or ASTM A 106/A 106M steel pipe. Pipe smaller than 50 mm shall be Schedule 80. Pipe 50 mm and larger shall be Schedule 40.

a. Flanges and Flanged Fittings: ASTM A 181/A 181M, Class 60, or ASME B16.5, Grade 1, Class 150.

b. Pipe Welding Fittings: ASTM A 234/A 234M, Grade WPB or WPC, Class 150 or ASME B16.11, 1360.7 kg.

c. Threaded Fittings: ASME B16.3, Class 150.

d. Valves: MSS SP-80, Class 150.

e. Gaskets: Manufacturer's standard.

2.3.4 Pipe Hangers

MSS SP-58 and MSS SP-69.

2.3.5 Electrical Enclosures

NEMA ICS 6.

2.3.5.1 Power Switchgear Assemblies

NEMA SG 6.

552.4 ENGINE

Each engine shall operate on No. 2-D diesel fuel conforming to ASTM D 975, shall be designed for stationary applications and shall be complete with ancillaries. The engine shall be a standard production model described in the manufacturer's catalog. The engine shall be naturally aspirated, supercharged, or turbocharged. The engine shall be 4-stroke-cycle and compression-ignition type. The engine shall be vertical in-line, V- or opposed-piston type, with a solid cast block or individually cast cylinders. The engine shall have a minimum of two cylinders. Opposed-piston type engines shall have not less than four cylinders. Each block shall have a coolant drain port. Each engine shall be equipped with an overspeed sensor.

2.5 FUEL SYSTEM

The entire fuel system for each engine-generator set shall conform to the requirements of NFPA 30 and NFPA 37 and contain the following elements.

2.5.1 Pumps

2.5.1.1 Main Pump

Each engine shall be provided with an engine driven pump. The pump shall supply fuel at a minimum rate sufficient to provide the amount of fuel required to meet the performance indicated within the parameter schedule. The fuel flow rate shall be based on meeting the load requirements and all necessary recirculation.

2.5.1.2 Auxiliary Fuel Pump

Provide auxiliary fuel pumps to maintain the required engine fuel pressure, if either required by the installation or indicated on the drawings. The auxiliary pump shall be driven by a dc electric motor powered by the starting/station batteries. The auxiliary pump shall be automatically actuated by a pressure-detecting device.

2.5.2 Fuel Filter

Provide a minimum of one full-flow fuel filter for each engine. The filter shall be readily accessible and capable of being changed without disconnecting the piping or disturbing other components. The filter shall have inlet and outlet connections plainly marked.

2.5.3 Relief/Bypass Valve

Provide a relief/bypass valve to regulate pressure in the fuel supply line, return excess fuel to a return line and prevent the build-up of excessive pressure in the fuel system.

2.5.4 Day Tank

Each engine shall be provided with a separate self-supporting day tank. Each day tank shall be provided with connections for fuel supply line, fuel return line, fuel overflow line, local fuel fill port, gauge, vent line, drain line, and float switch assembly for control. A fuel return line cooler shall be provided as recommended by the manufacturer and assembler.

2.5.4.1 Capacity, Prime

Each day tank shall have capacity to supply fuel to the engine for an uninterrupted 8-hour period at 100 percent rated load without being refilled, plus any fuel which may be returned to the main fuel storage tank. The calculation of the capacity of each day tank shall incorporate the requirement to stop the supply of fuel into the day tank at a "High" level mark of 90 percent of the ultimate volume of the tank.

2.5.4.2 Local Fuel Fill

Each local fuel fill port on the day tank shall be provided with a screw-on cap.

2.5.4.3 Fuel Level Controls

Each day tank shall have a float-switch assembly to perform the following functions:

a. When the main storage tank is located higher than the day tank, stop the supply of fuel into the day tank and close the solenoid valve located on the fuel supply line entering the day tank. Stop the supply of fuel into the day tank when the fuel level is at 90 percent of the rated tank capacity.

b. Activate the "Overfill Fuel Level" alarm at 95 percent of the rated tank capacity.

c. Activate the "Low Fuel Level" alarm at 70 percent of the rated tank capacity.

d. Activate the automatic fuel supply shut-off valve located on the fill line of the day tank and shut down the fuel pump which supplies fuel to the day tank at 95 percent of the rated tank capacity. The flow of fuel shall be stopped before any fuel can be forced into the fuel overflow line.

2.6 LUBRICATION

Each engine shall have a separate lube-oil system conforming to NFPA 30 and NFPA 37. Each system shall be pressurized by engine-driven pumps. System pressure shall be regulated as recommended by the engine manufacturer. A pressure relief valve shall be provided on the crankcase for closed systems. The crankcase shall be vented in accordance with the manufacturer's recommendation except that it shall not be vented to the engine exhaust system. Crankcase breathers, if provided on engines installed in buildings or enclosures, shall be piped to vent to the outside. The system shall be readily accessible for service such as draining, refilling, etc. Each system shall permit addition of oil and have oil-level indication with the set operating. The system shall utilize an oil cooler as recommended by the engine manufacturer.

2.6.1 Lube-Oil Filter

Provide one full-flow filter for each pump. The filter shall be readily accessible and capable of being changed without disconnecting the piping or disturbing other components. The filter shall have inlet and outlet connections plainly marked.

2.6.2 Lube-Oil Sensors

Equip each engine with lube-oil pressure sensors located downstream of the filters and provide signals for required indication and alarms.

2.6.3 Precirculation Pump

Provide a motor-driven precirculation pump powered by the station battery, complete with motor starter, if recommended by the engine manufacturer.

2.7 COOLING SYSTEM

Provide each engine with its own cooling system to operate automatically while its engine is running. The cooling system coolant shall use a combination of water and ethylene-glycol sufficient for freeze protection at the minimum winter outdoor temperature specified. The maximum temperature rise of the coolant across each engine shall not exceed that recommended and submitted in paragraph SUBMITTALS.

2.7.1 Coolant Pumps

Coolant pumps shall be the centrifugal type. Each engine shall have an engine-driven primary pump. Secondary pumps shall be electric motor driven and have automatic controllers.

2.7.2 Heat Exchanger

2.7.2.1 Fin-Tube-Type Heat Exchanger (Radiator)

Heat exchanger may be factory coated with corrosive resistant film, provided that correction measures are taken to restore the heat rejection capability of the radiator to the initial design requirement via over sizing, or other compensating methods. Internal surfaces shall be compatible with liquid fluid coolant used. Materials and coolant are subject to approval by the Contracting Officer. Heat exchangers shall be pressure type incorporating a pressure valve, vacuum valve and a cap. Caps shall be designed for pressure relief prior to removal. Each heat exchanger and the entire cooling system shall be capable of withstanding a minimum pressure of 48 kPa and shall be protected with a strong grille or screen guard. Each heat exchanger shall have at least two tapped holes; one tapped hole shall be equipped with a drain cock, the rest shall be plugged.

2.7.3 Expansion Tank

The cooling system shall include an air expansion tank which will accommodate the expanded water of the system generated within the normal operating temperature range, limiting the pressure increase at all components in the system to the maximum allowable pressure at those components. The tank shall be suitable for operating temperature of 121 degrees C and a working pressure of 0.86 MPa. The tank shall be

constructed of welded steel, tested and stamped in accordance with ASME BPVC SEC VIII D1 for the stated working pressure. A bladder type tank shall not used. The tank shall be supported by steel legs or bases for vertical or steel saddles for horizontal installation.

2.7.4 Thermostatic Control Valve

A modulating type, thermostatic control valve shall be provided in the coolant system to maintain the coolant temperature range submitted in paragraph SUBMITTALS.

2.7.5 Temperature Sensors

Each engine shall be equipped with coolant temperature sensors. Temperature sensors shall provide signals for pre-high and high indication and alarms.

2.8 SOUND LIMITATIONS

The noise generated by the diesel generator set operating at 100 percent load shall not exceed the following sound pressure levels in any of the indicated frequencies when measured in a free field at a radial distance of 7 meters at 45 degrees apart in all directions. Design, fabricate and install sound attenuation cabinets/enclosures and silencer mufflers (paragraph 3.10.2) at outside generators. Add additional sound deadening devices if/as necessary to meet the specified sound pressure levels.

Frequency Band (Hz)	Maximum Acceptable Pressure Level (Decibels)
31	87
63	87
125	77
250	70
500	64
1,000	61
2,000	60
4,000	60
8,000	62

2.9 AIR INTAKE EQUIPMENT

Filters and silencers shall be provided in locations that are convenient for servicing. The silencer shall be of the high-frequency filter type, located in the air intake system as recommended by the engine manufacturer. Silencer shall be capable of reducing the noise level at the air intake so that the indicated pressure levels specified in paragraph SOUND LIMITATIONS will not be exceeded. A combined filter-silencer unit meeting requirements for the separate filter and silencer items may be provided. Expansion elements in air-intake lines shall be copper.

2.10 EXHAUST SYSTEM

The system shall be separate and complete for each engine. Piping shall be supported to minimize vibration. Where a V-type engine is provided, a V-type connector, with necessary flexible sections and hardware, shall connect the engine exhaust outlets.

2.10.1 Flexible Sections and Expansion Joints

A flexible section shall be provided at each engine and an expansion joint at each muffler. Flexible sections and expansion joints shall have flanged connections. Flexible sections shall be made of convoluted seamless tube without joints or packing. Expansion joints shall be the bellows type. Expansion and flexible elements shall be stainless steel suitable for diesel-engine exhaust gas at the maximum exhaust temperature that is specified by the engine manufacturer. Expansion and flexible elements shall be capable of absorbing vibration from the engine and compensation for thermal expansion and contraction.

2.10.2 Exhaust Muffler

A chamber type exhaust muffler shall be provided. The muffler shall be constructed of welded steel and designed for inside mounting. Eyebolts, lugs, flanges, or other items shall be provided as necessary for support in the location and position indicated. Pressure drop through the muffler shall not exceed the recommendations of the engine manufacturer. Outside mufflers shall be zinc coated or painted with high temperature 900 degrees resisting paint. The muffler and exhaust piping together shall reduce the noise level to less than the maximum acceptable level listed for sound limitations in paragraph SOUND LIMITATIONS. The muffler shall have a drain valve, nipple, and cap at the low-point of the muffler.

2.10.3 Exhaust Piping

Horizontal sections of exhaust piping shall be sloped downward away from the engine to a drip leg for collection of condensate with drain valve and cap. Changes in direction shall be long radius. Vertical exhaust piping shall be provided with a hinged, gravity-operated, self-closing, rain cover.

2.11 PYROMETER

A pyrometer, multi-point selector switch, and individual thermocouples and thermocouple with calibrated leads shall be provided to show the temperature in each engine cylinder and the combined exhaust. For a supercharged engine, additional points, thermocouples and leads shall be provided to show the temperature in the turbocharger exhaust gas outlet and combustion air discharge passages. Graduated scale length shall be not less than 150 mm. The selector switch shall be double pole, with an "off" position, one set of points for each thermocouple, and suitable indicating dial. The pyrometer, thermocouples, leads and compensating devices shall be calibrated to show true exhaust temperature within plus or minus 1 percent above the highest temperature encountered at 110 percent load conditions.

2.12 EMISSIONS

The finished installation shall comply with Federal regulations and restrictions regarding the limits of emissions.

2.13 STARTING SYSTEM

Engine generator sets used in non-emergency applications shall be as follows.

2.13.1 Controls

An engine control switch shall be provided with functions including: run/start(manual), off/reset, and, automatic mode. Start-stop logic shall be provided for adjustable cycle cranking and cooldown operation. The logic shall be arranged for manual starting and fully automatic starting in accordance with paragraph AUTOMATIC ENGINE-GENERATOR-SET SYSTEM OPERATION. Electrical starting systems shall be provided with an adjustable cranking limit device to limit cranking periods from 1 second up to the maximum duration.

2.13.2 Capacity

The starting system shall be of sufficient capacity, at the maximum outdoor summer temperature specified to crank the engine without damage or overheating. The system shall be capable of providing a minimum of three cranking periods with 15 second intervals between cranks. Each cranking period shall have a maximum duration of 15 seconds.

2.13.3 Electrical Starting

Manufacturers recommended dc system, utilizing a negative circuit ground.

2.13.3.1 Battery

A starting battery system shall be provided and shall include the battery, battery rack, intercell connectors, spacers, automatic battery charger with overcurrent protection, metering and relaying. The battery shall be in accordance with SAE J537. Critical system components shall be sized to withstand the seismic acceleration forces specified. The battery shall be lead-acid, with sufficient capacity, at the minimum outdoor and maximum outdoor temperature specified, to provide the specified cranking periods. Valve-regulated lead-acid batteries are not acceptable.

2.13.3.2 Battery Charger

A current-limiting battery charger, conforming to UL 1236, shall be provided and shall automatically recharge the batteries. The charger shall be capable of an equalize-charging rate for recharging fully depleted batteries within 24 hours which is manually adjustable in a continuous range and a floating charge rate for maintaining the batteries at fully charged condition. An ammeter shall be provided to indicate charging rate. A voltmeter shall be provided to indicate charging voltage. A timer shall be provided for the equalize-charging-rate setting. A battery is considered to be fully depleted when the output voltage falls to a value which will not operate the engine generator set and its components.

2.13.4 Starting Aids

The manufacturer shall provide one or more of other following methods to assist engine starting.

2.13.4.1 Glow Plugs

Glow plugs shall be designed to provide sufficient heat for combustion of fuel within the cylinders to guarantee starting at an ambient temperature of -32 degrees C.

2.13.4.2 Jacket-Coolant Heaters

A thermostatically controlled electric heater shall be mounted in the engine coolant jacketing to automatically maintain the coolant within plus or minus 1.7 degrees C of the control temperature. The heater shall operate independently of engine operation so that starting times are minimized. Power for the heaters shall be 380 volts ac.

a. Prime Rated Sets: The control temperature shall be the higher of the manufacturer's recommended temperature or the minimum coolant inlet temperature of the engine recommended in paragraph SUBMITTALS.

2.14 GOVERNOR

Each engine shall be provided with a governor which maintains the frequency within a bandwidth of the rated frequency, over a steady-state load range of zero to 100 percent of rated output capacity. The governor shall be configured for safe manual adjustment of the speed/frequency during operation of the engine-generator set, without special tools, from 90 to 110 percent of the rated speed/frequency, over a steady state load range of 0 to 100 percent or rated capacity. Isochronous governors shall maintain the midpoint of the frequency bandwidth at the same value for steady-state loads over the range of zero to 100 percent of rated output capacity. Droop governors shall maintain the midpoint of the frequency bandwidth linearly for steady-state loads over the range of zero to 100 percent of rated output capacity, with 3 percent droop configured for safe, manual, external adjustment of the droop from zero to 7 percent.

2.15 GENERATOR

Each generator shall be of the synchronous type, one or two bearing, conforming to the performance criteria in NEMA MG 1, equipped with winding terminal housings in accordance with NEMA MG 1, equipped with an amortisseur winding, and directly connected to the engine. Insulation shall be Class F. Generator design shall protect against mechanical, electrical and thermal damage due to vibration, 25 percent overspeeds, or voltages and temperatures at a rated output capacity of 110 percent for prime applications. Generator ancillary equipment shall meet the short circuit requirements of NEMA MG 1. Frames shall be the drip-proof type.

2.15.1 Current Balance

At 100 percent rated output capacity, and load impedance equal for each of the 3 phases, the permissible current difference between any 2 phases shall not exceed 2 percent of the largest current on either of the 2 phases.

2.15.2 Voltage Balance

At any balanced load between 75 and 100 percent of rated output capacity, the difference in line-to-neutral voltage among the 3 phases shall not exceed 1 percent of the average line-to-neutral voltage. For a single-phase load condition, consisting of 25 percent load at unity power factor placed between any phase and neutral with no load on the other 2 phases, the maximum simultaneous difference in line-to-neutral voltage between the phases shall not exceed 3 percent of rated line to neutral voltage. The single-phase load requirement shall be valid utilizing normal exciter and regulator control. The interpretation of the 25 percent load for single phase load conditions means 25 percent of rated current at rated phase voltage and unity power factor.

2.15.3 Waveform

The deviation factor of the line-to-line voltage at zero load and at balanced rated output capacity shall not exceed 10 percent. The RMS of all harmonics shall be less than 5.0 percent and that of any one harmonic less than 3.0 percent of the fundamental at rated output capacity. Each engine-generator shall be designed and configured to meet the total harmonic distortion limits of IEEE Std 519.

2.16 EXCITER

The generator exciter shall be of the brushless type. Semiconductor rectifiers shall have a minimum safety factor of 300 percent for peak inverse voltage and forward current ratings for all operating conditions, including 110 percent generator output at 4O degrees C ambient. The exciter and regulator in combination shall maintain generator-output voltage within the limits specified.

2.17 VOLTAGE REGULATOR

Each generator shall be provided with a solid-state voltage regulator, separate from the exciter. The regulator shall maintain the voltage within a bandwidth of the rated voltage, over a steady-state load range of zero to 100 percent of rated output capacity. Regulator shall be configured for safe manual adjustment of the engine-generator voltage output without special tools, during operation, from 90 to 110 percent of the rated voltage over the steady state load range of 0 to 100 percent of rated output capacity. Regulation drift shall not exceed plus or minus 0.5 percent for an ambient temperature change of 20 degrees C. Reactive droop compensation or reactive differential compensation shall load share the reactive load proportionally between sets during parallel operation. The voltage regulator shall have a maximum droop of 2 percent of rated voltage over a load range from 0 to 100 percent of rated output capacity and automatically maintain the generator output voltage within the specified operational bandwidth.

2.18 GENERATOR ISOLATION AND PROTECTION

Devices necessary for electrical protection and isolation of each engine-generator set and its ancillary equipment shall be provided. The generator circuit breaker (IEEE Device 52) ratings shall be consistent with the generator rated voltage and frequency, with continuous, short circuit withstand, and interrupting current ratings to match the generator capacity. The generator circuit breaker shall be electrically operated. A set of surge capacitors, to be mounted at the generator terminals shall be provided. Monitoring and control devices shall be as specified in paragraph GENERATOR PANEL.

2.18.1 Switchboards

Switchboards shall be free-standing, metal-enclosed, NEMA 3R, 3-phase, 4-wire, 600 volt rated, with neutral bus and continuous ground bus, conforming to NEMA PB 2 and UL 891. Neutral bus and ground bus capacity shall be full capacity. Panelboards shall conform to NEMA PB 1. Enclosure designs, construction, materials and coatings shall be suitable for the application and environment. Bus continuous current rating shall be at least equal to the generator rating and correspond to the UL listed current ratings specified for panelboards and switchboards. Current withstand

(short circuit rating) shall be equal to the breaker interrupting rating. Buses shall be copper.

2.18.2 Devices

Switches, circuit breakers, switchgear, fuses, relays, and other protective devices shall be as specified in Section 26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION.

2.19 SAFETY SYSTEM

Devices, wiring, remote panels, local panels, etc. shall be provided and installed as a complete system to automatically activate the appropriate signals and initiate the appropriate actions. The safety system shall be provided with a self-test method to verify its operability. Alarm signals shall have manual acknowledgment and reset devices. The alarm signal systems shall reactivate for new signals after acknowledgment is given to any signal. The systems shall be configured so that loss of any monitoring device shall be dealt with as an alarm on that system element.

2.19.1 Audible Signal

The audible alarm signal shall sound at a frequency of 70 Hz at a volume of 75 dB at 3.1 m. The sound shall be continuously activated upon alarm and silenced upon acknowledgment. Signal devices shall be located as shown.

2.19.2 Visual Signal

The visual alarm signal shall be a panel light. The light shall be normally off, activated to be blinking upon alarm. The light shall change to continuously lit upon acknowledgement. If automatic shutdown occurs, the display shall maintain activated status to indicate the cause of failure and shall not be reset until cause of alarm has been cleared and/or restored to normal condition. Shutdown alarms shall be red; all other alarms shall be amber.

2.19.3 Alarms and Action Logic

2.19.3.1 Shutdown

Simultaneous activation of the audible signal, activation of the visual signal, stopping the engine, and opening the generator main circuit breakers shall be accomplished.

2.19.3.2 Problem

Activation of the visual signal shall be accomplished.

2.19.4 Local Alarm Panel

A local alarm panel shall be provided with the following shutdown and alarm functions in accordance with NFPA 99 NFPA 110 level 2 and including the listed Corps of Engineer requirements mounted either on or adjacent to the engine generator set.

Device/Condition /Function	What/Where/Size	NFPA 99	NFPA 110 Level 1	NFPA 110 Level 2	Corps of Engrs Required
Shutdowns w/Alarms					
High engine temperature	Automatic/jacket/ water/cylinder	SD/CP VA	SD/CP VA	SD/CP VA	SD VA
Low lube-oil pressure	Automatic/pressure/ level	SD/CP VA	SD/CP VA	SC/CP VA	SD VA
Overspeed Shutdown& Alarm	(110 percent (± 2 percent of rated speed)	SD/CP VA	SD/CP VA	SD/CP VA	SD VA
Overcrank, Failure to start	Automatic/Failure to start when used	SD/CP VA	SD/CP VA SD/CP VA	SD/CP VA SD/CP VA	
Day tank overfill limit indication & transfer pump shutdown (95 percent volume)	Automatic/Day Tank/Level				SD(Pump) CP VA
Red emergency stop switch	Manual Switch		SD/CP VA	SD/CP VA	SD VA
Alarms					
Day Tank integral main fuel storage tank (Low fuel Limit indication) (70 percent volume remaining)	Automatic/Day Tank Level				CP VA
Low fuel level	Main tank, 3 hrs remaining	VA/AA	CP VA	CP VAO	CP VA
Integral Main Fuel Storage Tank High Fuel Level	95 percent volume				CP VA
Low Coolant Temperature	jacket water	CP VA	CP VA	CP VA	
Pre-High Temperature	jacket water/ cylinder	CP VA	CP VA	CP VAO	CP VA
Pre-Low Lube-oil		CP VA			CP VA

Device/Condition /Function	What/Where/Size	NFPA 99	NFPA 110 Level 1	NFPA 110 Level 2	Corps of Engrs Required
Pressure					
High battery Voltage			CP VA	CP VAO	
Low battery Voltage			CP VA	CP VAO	
Battery charger AC Failure	AC supply not available		CP VA	CP VAO	
Control switch not in AUTO			CP VA	CP VAO	

2.19.5 Time-Delay on Alarms

For startup of the engine-generator set, time-delay devices shall be installed bypassing the low lubricating oil pressure alarm during cranking, and the coolant-fluid outlet temperature alarm. The lube-oil time-delay device shall return its alarm to normal status after the engine starts. The coolant time-delay device shall return its alarm to normal status 5 minutes after the engine starts.

2.20 ENGINE GENERATOR SET CONTROLS AND INSTRUMENTATION

Devices, wiring, remote panels, local panels, etc. shall be provided and installed as a complete system to automatically activate the appropriate signals and initiate the appropriate actions.

2.20.1 Controls

Provide a local control panel with controls in accordance with NFPA 110 level 1 and as follows mounted adjacent to the engine generator set. Provide a remote control panel fully redundant to the local control panel.

Device/Condition/ Function	Corps Requirement
Controls	
Switch: run/start - off/reset - auto	CP
Emergency stop switch & alarm	CP
Lamp test/indicator test	CP
Common alarm contacts/ fault relay	
Panel lighting	CP
Audible alarm & silencing/reset switch	CP
Voltage adjust for voltage regulator	CP

Device/Condition/ Function	Corps Requirement
Pyrometer display w/selector switch	CP
Remote emergency stop switch	
Remote fuel shutoff switch	
Remote lube-oil shutoff switch	

2.20.2 Engine Generator Set Metering and Status Indication

Provide a local panel with devices in accordance with NFPA 110 level 1 mounted either on or adjacent to the engine generator set. A remote control panel shall be provided with devices as indicated fully redundant to the local control panel.

Device/Condition/ Function	Corps Requirement
Genset Status & Metering	
Genset supplying load	
System ready	
Engine oil pressure	CP
Engine coolant temperature	CP
Engine RPM (tachometer)	CP
Engine run hours	CP
Pyrometer display w/selector switch	CP
AC volts (generator), 3-phase	CP
AC amps (generator), 3 - phase	CP
Generator Frequency	CP
Phase selector switches (amps & volts)	CP
Watts/kW	
Voltage Regulator Adjustment	CP

X - Required

CP - On Control Panel
VA - Visual Alarm
AA - Audible Alarm
STD- Manufacturers Standard Offering
O - Optional

2.21 SYNCHRONIZING PANEL

The panel shall be as specified in paragraph PANELS and shall provide controls, gauges, meters, and displays to include:

a. Frequency meters, dial type, with a range of 90 to 110 percent of rated frequency. Vibrating-reed type meters shall not be used. One

shall monitor generator output frequency ("Generator Frequency Meter") and the other shall monitor the frequency of the parallel source ("Bus Frequency Meter").

b. Voltmeters, ac, dial type, 3-phase, with 4-position selector switch for the generator output ("Generator Volt Meter") and for the parallel power source ("Bus volt meter").

c. Automatic synchronizer.

d. Manual synchronizing controls.

e. Indicating lights for supplementary indication of synchronization.

f. Synchroscope.

g. Wattmeter, indicating.

2.22 PANELS

Each panel shall be of the type and kind necessary to provide specified functions. Panels shall be mounted on the engine-generator set base by vibration/shock absorbing type mountings. Instruments shall be mounted flush or semiflush. Convenient access to the back of panels shall be provided to facilitate maintenance. Instruments shall be calibrated using recognized industry calibration standards. Each panel shall be provided with a panel identification plate which clearly identifies the panel function. Each instrument and device on the panel shall be provided with a plate which clearly identifies the device and its function as indicated. Switch plates shall clearly identify the switch-position function.

2.22.1 Enclosures

Enclosures shall be designed for the application and environment, conforming to NEMA ICS 6. Locking mechanisms shall be keyed alike.

2.22.2 Electronic

Electronic indicating instruments shall be true RMS indicating instruments, 100 percent solid state, state-of-the-art, microprocessor controlled to provide specified functions. Control, logic, and function devices shall be compatible as a system, sealed, dust and water tight, and shall utilize modular components with metal housings and digital instrumentation. An interface module shall be provided to decode serial link data from the electronic panel and translate alarm, fault and status conditions to set of relay contacts. Instrument accuracy shall be not less than 98 percent for unit mounted devices and 99 percent for control room, panel mounted devices, throughout a temperature range of minus 20 to plus 65 degrees C. Data display shall utilize LED or back lit LCD. Additionally, the display shall provide indication of cycle programming and diagnostic codes for troubleshooting. Numeral height shall be 13 mm.

2.22.3 Parameter Display

Indication or readouts of the tachometer, lubricating-oil pressure, ac voltmeter, ac ammeter, frequency meter, and safety system parameters shall be provided. A momentary switch shall be specified for other panels.

2.23 AUTOMATIC ENGINE-GENERATOR-SET SYSTEM OPERATION

2.23.1 Automatic Paralleling and Loading of Engine-Generator Sets

An automatic loading system shall be provided to load and unload engine-generator sets in the sequence indicated. The loading system shall monitor the system load and cause additional engine-generator sets to start, synchronize, and be connected in parallel with the system bus with increasing load. Actuation of the additional engine-generator set start logic shall occur when the load exceeds a percentage setpoint of the operating set's rating for a period of approximately 10 seconds. The device shall provide an adjustable setpoint range from 50 to 100 percent. When the system load falls below the percentage setpoint of the operating set's rating for a period of approximately 5 minutes, the controller shall unload and disconnect engine-generator sets from the system, stopping each engine-generator set after cool-down.

2.24 MANUAL ENGINE-GENERATOR-SET SYSTEM OPERATION

Complete facilities shall be provided for manual starting and testing of each set without load, loading and unloading of each set, and synchronization of each set with an energized bus.

2.25 STATION BATTERY SYSTEM

2.25.1 Battery Capacity

The battery shall be rated for the ampere hours recommended at the 8-hour rate, and shall have sufficient capacity to serve the following loads without recharging for a period of 8 hours. At the end of the discharge period, the battery shall have the capacity to simultaneously close and trip all the circuit breakers provided.

a. Diesel-generator safety circuits.

b. Switchgear indicating lights, control relays, protective relays, and other switchgear dc components as required for 24 hours.

c. Voltage regulator (dc power supplies).

d. Precirculating lube-oil pumps.

e. Generator circuit breakers.

2.25.2 Battery Charger

A current-limiting, 24-volt battery charger shall be furnished to automatically recharge the batteries. The charger shall be capable of an equalize charging rate for recharging fully depleted batteries within 8 hours which is continuously adjustable and a floating-charge rate for maintaining the batteries in a fully charged condition. The charger shall be equipped with a low-voltage alarm relay, 0- to 24-hour equalizing timer, an ammeter to indicate charging rate, and necessary circuit breakers. The charger shall conform to the requirements of UL 1236. A battery is considered to be fully depleted when the voltage falls to a level incapable of operating the equipment loads served by the battery.

2.26 BASE

The base shall be constructed of steel. The base shall be designed to rigidly support the engine-generator set, ensure permanent alignment of rotating parts, be arranged to provide easy access to allow changing of lube-oil, and ensure that alignment is maintained during shipping and normal operation. The base shall permit skidding in any direction during installation and shall withstand and mitigate the affects of synchronous vibration of the engine and generator. The base shall be provided with suitable holes for anchor bolts and jacking screws for leveling.

2.27 PAINTING AND FINISHING

The engine-generator set shall be cleaned, primed and painted in accordance with the manufacturer's standard color and practice.

2.28 FACTORY INSPECTION AND TESTS

Perform the factory tests on each engine-generator set. The component manufacturer's production line test is acceptable as noted. Each engine-generator set shall be run not less than 1 hour at rated output capacity prior to inspections. Inspections shall be completed and all necessary repairs made, prior to testing. Engine generator controls and protective devices that are provided by the generator set manufacturer as part of the standard package shall be used for factory tests. When controls and switchgear are not provided as part of the generator set manufacturer's standard package, the actual controls and protective devices provided for the project are not required to be used during the factory test. The Contracting Officer may provide one or more representatives to witness inspections and tests.

2.28.1 Factory Inspection

Inspections shall be performed prior to beginning and after completion of testing of the assembled engine-generator set. Inspectors shall look for leaks, looseness, defects in components, proper assembly, etc. and any item found to be in need of correction shall be noted as a necessary repair. The following checklist shall be used for the inspection:

INSPECTION ITEM	GOOD	BAD	NOTES
1. Drive belts			
2. Governor and adjustments			
3. Engine timing mark			
4. Starting motor			
5. Starting aids			
6. Coolant type and concentration			
7. Radiator drains			
8. Block coolant drains			
9. Coolant fill level			
10. All coolant line connections			
11. All coolant hoses			
12. Combustion air filter			
13. Combustion air silencer			
14. Lube oil type			
15. Lube oil sump drain			
16. Lube-oil filter			
17. Lube-oil-level indicator			
18. Lube-oil-fill level			

19. All lube-oil line connections
20. All lube-oil lines
21. Fuel type and amount
22. All fuel-line connections
23. All fuel lines
24. Fuel filter
25. Coupling and shaft alignment
26. Voltage regulators
27. Battery-charger connections
28. All wiring connections
29. Instrumentation
30. Hazards to personnel
31. Base
32. Nameplates
33. Paint
34. Exhaust-heat recovery unit
35. Switchboard
36. Switchgear

2.28.2 Factory Tests

On engine-generator set tests where the engine and generator are required to be connected and operated together, the load power factor shall be the power factor specified in the engine generator set parameter schedule 80% power factor. Electrical measurements shall be performed in accordance with IEEE Std 120. Definitions of terms are in accordance with IEEE Std 100. Temperature limits in the rating of electrical equipment and for the evaluation of electrical insulation shall be in accordance with IEEE Std 1. In the following tests where measurements are to be recorded after stabilization of an engine-generator set parameter (voltage, frequency, current, temperature, etc.), stabilization is considered to have occurred when measurements are maintained within the specified bandwidths or tolerances, for a minimum of four consecutive readings. Tests specifically for the generator may be performed utilizing any prime mover.

a. Insulation Resistance for Stator and Exciter Test, IEEE Std 115 and IEEE Std 43, to the performance criteria in NEMA MG 1, Part 22. Generator manufacturer's production line test is acceptable.

b. High Potential Test, in accordance with IEEE Std 115 and NEMA MG 1, test voltage in accordance with NEMA MG 1. Generator manufacturer's production line test is acceptable.

c. Winding Resistance Test, Stator and Exciter, in accordance with IEEE Std 115. Generator manufacturer's production line test is acceptable.

d. Overspeed Vibration Test, in accordance with IEEE Std 115 to the performance criteria in NEMA MG 1. The test shall be performed at 110 percent of rated speed for 5 minutes. The vibration shall be measured at the end bearings (front and back of engine, outboard end of generator) in the horizontal, vertical, and axial directions. Vibration amplitude and speed shall be recorded at one minute intervals.

e. Phase Balance Voltage Test, to the performance criteria specified in paragraph GENERATOR. This test can be performed with any prime mover. Generator manufacturer's production line test results are acceptable.

(1) Start and operate the generator at no load.

(2) Adjust a regulated phase voltage (line-to-neutral) to rated voltage.

(3) Read and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(4) Apply 75 percent rated load and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(5) Apply rated load and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(6) Calculate average line-neutral voltage and percent deviation of individual line-neutral voltages from average for each load condition.

f. Current Balance on Stator Winding Test, by measuring the current on each phase of the winding with the generator operating at 100 percent of Rated Output Capacity, with the load impedance equal for each of the three phases: to the performance criteria specified in paragraph GENERATOR.

g. Voltage Waveform Deviation and Distortion Test in accordance with IEEE Std 115 to the performance criteria specified in paragraph GENERATOR. High-speed recording instruments capable of recording voltage waveform deviation and all distortion, including harmonic distortion shall be used. Representation of results shall include appropriate scales to provide a means to measure and interpret results.

h. Voltage and Frequency Droop Test. Verify that the output voltage and frequency are within the specified parameters as follows:

(1.) With the generator operating at no load, adjust voltage and frequency to rated voltage and frequency. Record the generator output frequency and line-line and line-neutral voltages.

(2.) Increase load to Rated Output Capacity. Record the generator output frequency and line-line and line-neutral voltages.

3. Calculate the percent droop for voltage and frequency with the following equations:

$$\text{Voltage droop percent} = \frac{\text{(No-Load Volts)} - \text{(Rated Capacity volts)}}{\text{(Service-Load Volts)}} \times 100$$

$$\text{Frequency droop percent} = \frac{\text{(No-Load Hertz)} - \text{(Rated Capacity hertz)}}{\text{(Service-Load hertz)}} \times 100$$

4. Repeat steps 1 through 3 two additional times without making any adjustments.

i. Frequency and Voltage Stability and Transient Response. Verify that the engine-generator set responds to addition and dropping of blocks of load in accordance with the transient response requirements. Document maximum voltage and frequency variation from bandwidth and

verify that voltage and frequency return to and stabilize within the specified bandwidth, within the specified response time period. Document results in tabular form and with high resolution, high speed strip chart recorders or comparable digital recorders, as approved by the Contracting Officer. Tabular data shall include the following:

1. Ambient temperature (at 15 minute intervals).

2. Generator output current (before and after load changes).

3. Generator output voltage (before and after load changes).

4. Frequency (before and after load changes).

5. Generator output power (before and after load changes).

6. Graphic representations shall include the actual instrument trace of voltage and frequency showing: charts marked at start of test; observed steady-state band; mean of observed band; momentary overshoot and undershoot (generator terminal voltage and frequency) and recovery time for each load change together with the voltage and frequency maximum and minimum trace excursions for each steady state load condition prior to and immediately following each load change. Generator terminal voltage and frequency transient recovery time for each step load increase and decrease.

(1.) Perform and record engine manufacturer's recommended prestarting checks and inspections.

(2.) Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period and no load. Verify stabilization of voltage and frequency within specified bandwidths.

(3.) With the unit at no load, apply the Maximum Step Load Increase.

(4.) Apply load in steps equal to the Maximum Step Load Increase until the addition of one more step increase will exceed the Service Load.

(5.) Decrease load to the unit such that addition of the Maximum Step Load Increase will load the unit to 100 percent of Service Load.

(6.) Apply the Maximum Step Load Increase.

(7.) Decrease load to zero percent in steps equal to the Maximum Step Load Decrease.

(8.) Repeat steps 3. through 7.

j. Test Voltage Unbalance with Unbalanced Load (Line-to-Neutral) to the performance criteria specified in paragraph GENERATOR. Prototype test data is acceptable in lieu of the actual test. This test may be performed using any prime mover.

(1.) Start and operate the generator set at rate voltage, no

load, rated frequency, and under control of the voltage regulator. Read and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(2.) Apply the specified load between terminals L_1-L_2, L_2-L_0, and L_3-L_0 in turn. Record all instrument readings at each line-neutral condition.

(3.) Express the greatest difference between any two of the line-to-line voltages and any two of the line-to-neutral voltages as a percent of rated voltage.

(4.) Compare the largest differences expressed in percent with the maximum allowable difference specified.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the job, perform a Site Visit to verify the information shown on the drawings, before performing any work. Notify the Contracting Officer in writing of any discrepancies.

3.2 GENERAL INSTALLATION

Installation shall provide clear space for operation and maintenance in accordance with NFPA 70 and IEEE C2. Installation of pipe, duct, conduit, and ancillary equipment shall be configured to facilitate easy removal and replacement of major components and parts of the engine-generator set.

3.3 PIPING INSTALLATION

Piping shall be welded. Connections at valves shall be flanged. Connections at equipment shall be flanged except that connections to the diesel engine may be threaded if the diesel-engine manufacturers standard connection is threaded. Except where otherwise specified, welded flanged fittings shall be utilized to allow for complete dismantling and removal of each piping system from the facility without disconnecting or removing any portion of any other system's equipment or piping. Connections to equipment shall be made with vibration-isolation-type flexible connectors. Piping and tubing shall be supported and aligned to prevent stressing of flexible hoses and connectors. Pipes extending through the roof shall be properly flashed. Piping shall be installed clear of windows, doors and openings, to permit thermal expansion and contraction without damage to joints or hangers, and shall be installed with a 13 mm drain valve with cap at each low point.

3.3.1 Support

Hangers, inserts, and supports shall be of sufficient size to accommodate any insulation and shall conform to MSS SP-58 and MSS SP-69. Supports shall be spaced not more than 2.1 m on center for pipes 50 mm in diameter or less, not more than 3.6 m on center for pipes larger than 50 mm but smaller than 100 mm in diameter, and not more than 5.2 m on center for pipes larger than 100 mm in diameter. Supports shall be provided at pipe bends or change of direction.

3.3.1.1 Ceiling and Roof

Exhaust piping shall be supported with appropriately sized Type 41 single pipe roll and threaded rods; all other piping shall be supported with appropriately sized Type 1 clevis and threaded rods.

3.3.1.2 Wall

Wall supports for pipe shall be made by suspending the pipe from appropriately sized Type 33 brackets with the appropriate ceiling and roof pipe supports.

3.3.2 Flanged Joints

Flanges shall be Class 125 type, drilled, and of the proper size and configuration to match the equipment and diesel engine connections. Flanged joints shall be gasketed and made up square and tight.

3.3.3 Cleaning

After fabrication and before assembly, piping interiors shall be manually wiped clean of debris.

3.3.4 Pipe Sleeves

Pipes passing through construction such as ceilings, floors, or walls shall be fitted with sleeves. Each sleeve shall extend through and be securely fastened in its respective structure and shall be cut flush with each surface. The structure shall be built tightly to the sleeve. The inside diameter of each sleeve shall be minimum 13 mm, and where pipes pass through combustible materials 25 mm larger than the outside diameter of the passing pipe or pipe insulation/covering.

3.4 ELECTRICAL INSTALLATION

Electrical installation shall comply with NFPA 70, IEEE C2, and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. For vibration isolation, flexible fittings shall be provided for conduit, cable trays, and raceways attached to engine-generator sets; metallic conductor cables installed on the engine generator set and from the engine generator set to equipment not mounted on the engine generator set shall be flexible stranded conductor; and terminations of conductors on the engine generator set shall be crimp-type terminals or lugs.

3.5 FIELD PAINTING

Field painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.6 ONSITE INSPECTION AND TESTS

3.6.1 Test Conditions

3.6.1.1 Data

Measurements shall be made and recorded of all parameters necessary to verify that each set meets specified parameters. If the results of any test step are not satisfactory, adjustments, replacements, or repairs shall be made and the step repeated until satisfactory results are obtained.

Unless otherwise indicated, data shall be recorded in 15 minute intervals during engine-generator set operation and shall include: readings of all engine-generator set meters and gauges for electrical and power parameters; oil pressure; ambient temperature; and engine temperatures available from meters and gauges supplied as permanent equipment on the engine-generator set.Electrical measurements shall be performed in accordance with IEEE Std 120. Definitions of terms are in accordance with IEEE Std 100. Temperature limits in the rating of electrical equipment and for the evaluation of electrical insulations shall be in accordance with IEEE Std 1.

3.6.1.2 Power Factor

For all engine-generator set operating tests the load power factor shall be the power factor specified in the engine-generator set parameter schedule.

3.6.1.3 Contractor Supplied Items

Provide equipment and supplies required for inspections and tests including fuel, test instruments, and loadbanks at the specified power factors.

3.6.1.4 Instruments

Readings of panel gauges, meters, displays, and instruments provided as permanent equipment shall be verified during test runs, using test instruments of greater precision and accuracy. Test instrument accuracy shall be within the following: current plus or minus 1.5 percent, voltage plus or minus 1.5 percent, real power plus or minus 1.5 percent, reactive power plus or minus 1.5 percent, power factor plus or minus 3 percent, frequency plus or minus 0.5 percent. Test instruments shall be calibrated by a recognized standards laboratory within 30 days prior to testing.

3.6.1.5 Sequence

The sequence of testing shall be as specified in the approved testing plan unless variance is authorized by the Contracting Officer. Field testing shall be performed in the presence of the Contracting Officer. Tests may be scheduled and sequenced in order to optimize run-time periods; however, the following general order of testing shall be followed: Construction Tests; Inspections; Pre-operational Tests; Safety Run Tests; Performance Tests; and Final Inspection.

3.6.2 Construction Tests

Individual component and equipment functional tests for fuel piping, coolant piping, and lubricating-oil piping, electrical circuit continuity, insulation resistance, circuit protective devices, and equipment not provided by the engine-generator set manufacturer shall be performed prior to connection to the engine-generator set.

3.6.2.1 Piping Test

a. Lube-oil and fuel-oil piping shall be flushed with the same type of fluid intended to flow through the piping, until the outflowing fluid has no obvious sediment or emulsion.

b. Fuel piping which is external to the engine-generator set shall be tested in accordance with NFPA 30. All remaining piping which is external to the engine-generator set shall be pressure tested with air pressure at 150 percent of the maximum anticipated working pressure,

but not less than 1.03 MPa, for a period of 2 hours to prove the piping has no leaks. If piping is to be insulated, the test shall be performed before the insulation is applied.

3.6.2.2 Electrical Equipment Tests

a. Low-voltage cable insulation integrity tests shall be performed for cables connecting the generator breaker to the distribution bus. Low-voltage cable, complete with splices, shall be tested for insulation resistance after the cables are installed, in their final configuration, ready for connection to the equipment, and prior to energization. The test voltage shall be 500 volts dc, applied for one minute between each conductor and ground and between all possible combinations conductors in the same trench, duct, or cable, with all other conductors in the same trench, duct, or conduit. The minimum value of insulation shall be:

1. R in megohms = (rated voltage in kV + 1) x 304,800/(length of cable in meters)

2. Each cable failing this test shall be repaired or replaced. The repair cable shall be retested until failures have been eliminated.

b. Medium-voltage cable insulation integrity tests shall be performed for cables connecting the generator breaker to the distribution bus. After installation and before the operating test or connection to an existing system, the medium-voltage cable system shall be given a high potential test. Direct-current voltage shall be applied on each phase conductor of the system by connecting conductors as one terminal and connecting grounds of metallic shieldings or sheaths of the cable as the other terminal for each test. Prior to making the test, the cables shall be isolated by opening applicable protective devices and disconnecting equipment. The test shall be conducted with all splices, connectors, and terminations in place. The method, voltage, length of time, and other characteristics of the test for initial installation shall be in accordance with NEMA WC 74 for the particular type of cable installed, except that 28kV and 35kV insulation test voltages shall be in accordance with either AEIC CS8 or AEIC CS8 as applicable, and shall not exceed the recommendations of IEEE Std 404 cable joints and IEEE Std 48 for cable terminations unless the cable and accessory manufacturers indicate higher voltages are acceptable for testing. Should any cable fail due to a weakness of conductor insulation or due to defects or injuries incidental to the installation or because of improper installation of cable, cable joints, terminations, or other connections, make necessary repairs or replace cables as directed. Repaired or replaced cables shall be retested.

c. Ground-Resistance Tests. The resistance of each grounding electrode, each grounding electrode system, the ground mat, and the ground ring shall be measured using the fall-of-potential method defined in IEEE Std 81. Ground resistance measurements shall be made before the electrical distribution system is energized and shall be made in normally dry conditions not less than 48 hours after the last rainfall. Resistance measurements of separate grounding electrode systems shall be made before the systems are bonded together below grade. The combined resistance of separate systems may be used to meet the requirements resistance, but the specified number of electrodes must still be provided as follows:

(1.) Single rod electrode - 25 ohms.

(2.) Multiple rod electrodes - 5 ohms.

(3.) Ground mat - 5 ohms.

d. Circuit breakers and switchgear shall be examined and tested in accordance with the manufacturer's published instructions for functional testing.

3.6.3 Inspections

Perform the following inspections jointly by the Contracting Officer and the Contractor, after complete installation of each engine-generator set and its associated equipment, and prior to startup of the engine-generator set. Checks applicable to the installation shall be performed. The results of those which are physical inspections (I) shall be documented and submitted in accordance with paragraph SUBMITTALS. Present manufacturer's data for the inspections designated (D) at the time of inspection. Inspections shall verify that equipment type, features, accessibility, installation and condition are in accordance with the contract specification. Manufacturer's statements shall certify provision of features which cannot be verified visually.

1.	Drive belts.	(I)
2.	Governor type and features.	(I)
3.	Engine timing mark.	(I)
4.	Starting motor.	(I)
5.	Starting aids.	(I)
6.	Coolant type and concentration.	(D)
7.	Radiator drains.	(I)
8.	Block coolant drains.	(I)
9.	Coolant fill level.	(I)
10.	Coolant line connections.	(I)
11.	Coolant hoses.	(I)
12.	Combustion air filter.	(I)
13.	Intake air silencer.	(I)
14.	Lube oil type.	(D)
15.	Lube oil sump drain.	(I)
16.	Lube-oil filter.	(I)
17.	Lube-oil level indicator.	(I)
18.	Lube-oil fill level.	(I)
19.	Lube-oil line connections.	(I)
20.	Lube-oil lines.	(I)
21.	Fuel type.	(D)
22.	Fuel-level.	(I)
23.	Fuel-line connections.	(I)
24.	Fuel lines.	(I)
25.	Fuel filter.	(I)
26.	Access for maintenance.	(I)
27.	Voltage regulator.	(I)
28.	Battery-charger connections.	(I)
29.	Wiring & terminations.	(I)
30.	Instrumentation.	(I)
31.	Hazards to personnel.	(I)
32.	Base.	(I)
33.	Nameplates.	(I)
34.	Paint.	(I)

35. Exhaust-heat system. (I)
36. Exhaust muffler. (I)
37. Switchboard. (I)
38. Switchgear. (I)
39. Access provided to controls. (I)
40. Enclosure is weather resistant. (I)
41. Engine & generator mounting bolts (application). (I)

3.6.4 Pre-operational Tests

3.6.4.1 Protective Relays

Protective relays shall be visually and mechanically inspected, adjusted, tested, and calibrated in accordance with the manufacturer's published instructions. Tests shall include pick-up, timing, contact action, restraint, and other aspects necessary to ensure proper calibration and operation. Relay settings shall be implemented in accordance with the installation coordination study. Relay contacts shall be manually or electrically operated to verify that the proper breakers and alarms initiate. Relaying current transformers shall be field tested in accordance with IEEE C57.13.1.

3.6.4.2 Insulation Test

Generator and exciter circuits insulation resistance shall be tested in accordance with IEEE Std 43. Stator readings shall be taken at the circuit breaker, to include generator leads to switchgear. Results of insulation resistance tests shall be recorded. Readings shall be within limits specified by the manufacturer. Mechanical operation, insulation resistance, protective relay calibration and operation, and wiring continuity of switchgear assembly shall be verified. Precautions shall be taken to preclude damaging generator components during test.

3.6.4.3 Engine-Generator Connection Coupling Test

When the generator provided is a two-bearing machine, the engine-generator connection coupling shall be inspected and checked by dial indicator to prove that no misalignment has occurred. The dial indicator shall measure variation in radial positioning and axial clearance between the coupling halves. Readings shall be taken at four points, spaced 90 degrees apart. Solid couplings and pin-type flexible couplings shall be aligned within a total indicator reading of 0.012 to 0.025 mm for both parallel and angular misalignment. For gear-type or grid-type couplings, 0.05 mm will be acceptable.

3.6.5 Safety Run Test

For the following tests, if any parts are changed, or adjustments made to the generator set, its controls, or auxiliaries, the associated safety tests shall be repeated.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections.

b. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

c. Activate the manual emergency stop switch and verify that the

engine stops.

d. Remove the high and pre-high lubricating oil temperature sensing elements from the engine and temporarily install a temperature gauge in their normal locations on the engine (required for safety, not for recorded data). Where necessary provide temporary wiring harness to connect the sensing elements to their permanent electrical leads.

e. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period. Operate the engine-generator set at no load until the output voltage and frequency stabilize. Monitor the temporarily installed temperature gauges. If either temperature reading exceeds the value required for an alarm condition, activate the manual emergency stop switch.

f. Immerse the elements in a vessel containing controlled-temperature hot oil and record the temperature at which the pre-high alarm activates and the temperature at which the engine shuts down. Remove the temporary temperature gauges and reinstall the temperature sensors on the engine.

g. Remove the high and pre-high coolant temperature sensing elements from the engine and temporarily install a temperature gauge in their normal locations on the engine (required for safety, not for recorded data). Where necessary provide temporary wiring harness to connect the sensing elements to their permanent electrical leads.

h. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period. Operate the engine generator-set at no load until the output voltage and frequency stabilize.

i. Immerse the elements in a vessel containing controlled-temperature hot oil and record the temperature at which the pre-high alarm activates and the temperature at which the engine shuts down. Remove the temporary temperature gauges and reinstall the temperature sensors on the engine.

j. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

k. Operate the engine generator-set for at least 2 hours at 75 percent of Service Load.

l. Verify proper operation and setpoints of gauges and instruments.

m. Verify proper operation of ancillary equipment.

n. Manually adjust the governor to increase engine speed past the overspeed limit. Record the RPM at which the engine shuts down.

o. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 75 percent of Service Load.

p. Manually adjust the governor to increase engine speed to within 2

percent of the overspeed trip speed previously determined and operate at that point for 5 minutes. Manually adjust the governor to the rated frequency.

q. Manually fill the day tank to a level above the overfill limit. Record the level at which the overfill alarm sounds. Verify shutdown of the fuel transfer pump. Drain the day tank down below the overfill limit.

r. Shut down the engine. Remove the time-delay low lube oil pressure alarm bypass and try to start the engine.

s. Attach a manifold to the engine oil system (at the oil pressure sensor port) that contains a shutoff valve in series with a connection for the engine's oil pressure sensor followed by an oil pressure gauge ending with a bleed valve. The engine's oil pressure sensor shall be moved from the engine to the manifold. The manifold shutoff valve shall be open and bleed valve closed.

t. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 75 percent of Service Load.

u. Close the manifold shutoff valve. Slowly allow the pressure in the manifold to bleed off through the bleed valve while watching the pressure gauge. Record the pressure at which the engine shuts down. Catch oil spillage from the bleed valve in a container. Add the oil from the container back to the engine, remove the manifold, and reinstall the engine's oil pressure sensor on the engine.

v. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 100 percent of Service Load. Record the maximum sound level in each frequency band at a distance of 22.9 m from the end of the exhaust and air intake piping directly along the path of intake and discharge for horizontal piping; or at a radius of 22.9 m from the engine at 45 degrees apart in all directions for vertical piping. If a sound limiting enclosure is provided, the enclosure, the muffler, and intake silencer shall be modified or replaced as required to meet the sound requirements contained within this specification If a sound limiting enclosure is not provided, the muffler and air intake silencer shall be modified or replaced as required to meet the sound limitations of this specification. If the sound limitations can not be obtained by modifying or replacing the muffler and air intake silencer, notify the Contracting Officers Representative and provide a recommendation for meeting the sound limitations.

w. Manually drain off fuel slowly from the day tank to empty it to below the low fuel level limit and record the level at which the audible alarm sounds. Add fuel back to the day tank to fill it above low level alarm limits.

3.6.6 Performance Tests

In the following tests, where measurements are to be recorded after stabilization of an engine-generator set parameter (voltage, frequency, current, temperature, etc.), stabilization is considered to have occurred

when measurements are maintained within the specified bandwidths or tolerances, for a minimum of four consecutive readings. For the following tests, if any parts are changed, or adjustments made to the generator set, its controls, or auxiliaries, the associated tests shall be repeated.

3.6.6.1 Continuous Engine Load Run Test

Test the engine-generator set and ancillary systems at service load to demonstrate durability; verify that heat of extended operation does not adversely affect or cause failure in any part of the system; and check all parts of the system. If the engine load run test is interrupted for any reason, the entire test shall be repeated. The engine load run test shall be accomplished principally during daylight hours, with an average ambient temperature and during the month as directed by the Contracting Officer. After each change in load in the following test, measure the vibration at the end bearings (front and back of engine, outboard end of generator) in the horizontal, vertical, and axial directions. Verify that the vibration is within the allowable range. Data taken at 15 minute intervals shall include the following:

Electrical: Output amperes, voltage, real and reactive power, power factor, frequency.

Pressure: Lube-oil.

Temperature: Coolant, Lube-oil, Exhaust, Ambient.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections. Include as a minimum checking of coolant fluid, fuel, and lube-oil levels.

b. Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warmup period.

c. Operate the engine generator-set for 2 hours at 75 percent of Service Load.

d. Increase load to 100 percent of Service Load and operate the engine generator-set for 4 hours.

e. For prime rated units, increase load to 110 percent of Service Load and operate the engine generator-set for 2 hours.

f. Decrease load to 100 percent of Service Load and operate the engine generator-set for 2 hours or until all temperatures have stabilized.

g. Remove load from the engine-generator set.

3.6.6.2 Voltage and Frequency Droop Test

For the following steps, verify that the output voltage and frequency return to and stabilize within the specified bandwidth values following each load change. Record the generator output frequency and line-line and line-neutral voltages following each load change.

a. With the generator operating at no load, adjust voltage and frequency to rated voltage and frequency.

b. Increase load to 100 percent of Rated Output Capacity. Record the

generator output frequency and line-line and line-neutral voltages.

c. Calculate the percent droop for voltage and frequency with the following equations.

$$\text{Voltage droop percent} = \frac{\text{No-load volts - rated output capacity volts}}{\text{Rated output capacity volts}} \times 100$$

$$\text{Frequency droop percent} = \frac{\text{No load hertz - rated output capacity hertz}}{\text{Rated output capacity volts}} \times 100$$

d. Repeat steps a. through c. two additional times without making any adjustments.

3.6.6.3 Voltage Regulator Range Test

a. While operating at no load, verify that the voltage regulator adjusts from 90 to 110 percent of rated voltage.

b. Increase load to 100 percent of Rated Output Capacity. Verify that the voltage regulator adjusts from 90 to 110 percent of rated voltage.

3.6.6.4 Governor Adjustment Range Test

a. While operating at no load, verify that the governor adjusts from 90 to 110 percent of rated frequency.

b. Increase load to 100 percent of Rated Output Capacity. Verify that the governor adjusts from 90 to 110 percent of rated frequency.

3.6.6.5 Frequency and Voltage Stability and Transient Response

Verify that the engine-generator set responds to addition and dropping of blocks of load in accordance with the transient response requirements. Document maximum voltage and frequency variation from bandwidth and verify that voltage and frequency return to and stabilize within the specified bandwidth, within the specified response time period. Document results in tabular form and with high resolution, high speed strip chart recorders or comparable digital recorders, as approved by the Contracting Officer. Tabular data shall include the following:

(1.) Ambient temperature (at 15 minute intervals).

(2.) Generator output current (before and after load changes).

(3.) Generator output voltage (before and after load changes).

(4.) Frequency (before and after load changes).

(5.) Generator output power (before and after load changes.

(6.) Graphic representations shall include the actual instrument trace of voltage and frequency showing:

Charts marked at start of test; observed steady-state band; mean of observed band; momentary overshoot and undershoot (generator terminal

voltage and frequency) and recovery time for each load change together with the voltage and frequency maximum and minimum trace excursions for each steady state load condition prior to and immediately following each load change. Generator terminal voltage and frequency transient recovery time for each step load increase and decrease.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections.

b. Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period and no load. Verify stabilization of voltage and frequency within specified bandwidths.

c. With the unit at no load, apply the Maximum Step Load Increase.

d. Apply load in steps equal to the Maximum Step Load Increase until the addition of one more step increase will exceed the Service Load.

e. Decrease load to the unit such that addition of the Maximum Step Load Increase will load the unit to 100 percent of Service Load.

f. Apply the Maximum Step Load Increase.

g. Decrease load to zero percent in steps equal to the Maximum Step Load Decrease.

h. Repeat steps c. through g.

3.6.7 Parallel Operation Test

Test the capability of each engine-generator set to parallel and share load with other generator sets, individually and in all combinations. This test must be performed with the voltage regulator and governor adjustment settings used for the Frequency and Voltage Stability and Transient Response test. If settings are changed during the performance of this test, a voltage and frequency stability and transient response test must be performed for each engine generator set using the setting utilized in this test. During operations record load-sharing characteristics of each set in parallel operation. Data taken shall include the following:

(1.) Ambient temperature (at 15 minute intervals).

(2.) Generator output current (before and after load changes).

(3.) Generator output voltage (before and after load changes).

(4.) Power division and exchange between generator sets.

(5.) Real power (watts) and reactive power (vars) on each set.

3.6.7.1 Combinations

Connect each set, while operating at no load, parallel with one other set in the system, operating at service load, until all possible two-unit-in-parallel combinations have been achieved. Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive loads. Document stabilization of voltage and frequency within specified bandwidth, the active power division, active

power exchange, reactive power division, and voltage and frequency stability and transient response in the following steps for each combination.

a. Divide the load proportionally between the sets and operate in parallel for 15 minutes.

b. Increase the load, in steps equal to the Maximum Step Increase, until each set is loaded to its service load.

c. Decrease the load, in steps equal to the Maximum Step Decrease, until each set is loaded to approximately 25 percent of its service load.

d. Increase the load, in steps equal to the Maximum Step Increase, until each set is loaded to approximately 50 percent of its service load Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive load.

e. Reduce the sum of the loads on both sets to the output rating of the smaller set.

f. Transfer a load equal to the output rating of the smaller of the 2 sets to and from each set. Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive load.

g. Document the active power division, active power exchange, reactive power division, and voltage and frequency stability and transient response.

3.6.7.2 Multiple Combinations

Connect each set, while operating at no load, parallel with all multiple combinations of all other set in the system, while operating at service load, until all multiple combinations of parallel operations have been achieved.

3.6.8 Automatic Operation Tests

Test the automatic operating system to demonstrate automatic starting, loading and unloading, the response to loss of operating engine-generator sets, and paralleling of each engine-generator set. The loads for this test shall utilize load banks at the indicated power factor and actual loads to be served, and the loading sequence shall be the indicated sequence. During all operations load-sharing characteristics shall be recorded. Perform this test for a minimum of two successive, successful tests. Data taken shall include the following:

(1.) Ambient temperature (at 15 minute intervals).

(2.) Generator output current (before and after load changes).

(3.) Generator output voltage (before and after load changes).

(4.) Generator output frequency (before and after load changes).

(5.) Power division and exchange between generator sets.

(6.) Real and reactive power on each set.

a. Initiate loss of the preferred power source and verify the specified sequence of operation.

b. Verify resetting of automatic starting and transfer logic.

3.6.9 Fuel Consumption Tests

Perform fuel consumption tests to confirm the manufacturer's certified rates on engine generator set and tabulate and average the results. Fuel consumption tests shall be conducted under the direct supervision of the engine manufacturer's representative. Fuel consumption readings shall be taken at 15 minute intervals, over a minimum period of 1 hour at 50 percent Service Load, 1 hour at 75 percent Service Load, and 4 hours at 100 percent Service Load. Fuel consumption data may be taken during the 75 percent load test and 100 percent load tests. Fuel consumption readings at site conditions shall be correlated to the guarantee-baseline conditions. Test report shall contain: readings of the output frequency, voltage, current, power factor, and power; barometric pressure; ambient temperature; intake-air temperature; fuel temperature; the site fuel consumption readings, adjustment calculations, factors, and source references for correlation of actual consumption rate of the guaranteed rate.

a. Start and operate the generator set and allow it to stabilize at rated load, rated voltage and rated frequency. During this period, readings of all instruments including thermal instrumentation shall be recorded at minimum intervals of 10 minutes. If necessary, adjustments to the load, voltage and frequency may be made to maintain rated load at rated voltage and rated frequency. However, adjustments to the voltage and frequency shall be limited to those adjustments available to the operator, specifically adjustments to the voltage or frequency adjust devices. On generator sets utilizing a droop-type speed control system as the prime speed control, the speed and droop portions of the control may be adjusted. No other adjustments to the voltage and frequency control systems shall be made unless permitted by the procurement document. Adjustments to the load, voltage or frequency controls shall be recorded on the data sheet. Unless otherwise specified in the procurement document, stabilization will be consideration to have occurred when four consecutive voltage and current recorded readings of the generator (or exciter) field either remain unchanged or have only minor variations about an equilibrium condition with no evident continued increase or decrease in value after the last adjustment to the load, voltage or frequency has been made.

b. Perform one of the following procedures:

BALANCE SCALE PROCEDURE.

(1.) Supply fuel from auxiliary container mounted on a balance scale.

(2.) After stabilization has occurred, set the balance weights at any convenient value slightly less than the total weight of the fuel and container.

(3.) Start the stopwatch when the balance weights fall and record the total weight.

(4.) Reduce the balance weight a convenient amount and record the amount of the weights removed.

(5.) Stop the stopwatch when the balance weights fall and record the total weight and the elapsed time.

(6.) Repeat steps (1) thru (2) above until the timed portion of the test exceeds the 2 hours.

(7.) From the total elapsed time and total of the weights removed calculate the fuel consumption in terms of pounds per hour.

(8.) Using the value obtained in step (7) above, compute the rate of fuel consumption per kilowatt hour, as follows:

$$\text{Pounds per kWH} = \frac{\text{Fuel Consumption in Pounds per Hour}}{\text{kW Load}}$$

(9.) Repeat the test for each load condition specified.

(10.) Determine the capacity of the generator set fuel tank in pounds of fuel.

(11.) For each specified load, compute the number of continuous hours the generator set will operate on a full tank of fuel. The following formula shall be used.

$$\text{Operating hours} = \frac{\text{Fuel Tank Capacity (Pounds)}}{\text{Fuel Consumption (Pounds per hour)}}$$

ALTERNATE PROCEDURE FOR WEIGHING FUEL

(1.) Supply fuel from the auxiliary fuel container, mounted on a platform balance, or other weighing device.

(2.) After stabilization has occurred, record weight readings every one-half hour for a period of 2 hours.

(3.) Calculate the average hourly fuel consumption rate in pounds per hour.

(4.) Using the average hourly fuel consumption rate obtained above, compute the rate of fuel consumption per kilowatt hour, as follows:

$$\text{Pounds per kWH} = \frac{\text{Fuel Consumption}}{\text{kW Load}}$$

(5.) Repeat test for each load condition specified.

(6.) Determine the capacity of the generator set fuel tank in pounds of fuel.

(7.) for each specified load test, compute the number of continuous ours the generator set will operate on a full tank of fuel. The following formula shall be used:

$$\text{Operating Hours} = \frac{\text{Fuel Tank Capacity (Pounds)}}{\text{Fuel Consumption (Pounds per Hour)}}$$

ALTERNATE PROCEDURE USING FLOWMETER.

Flowmeters may be used to determine the fuel rate. They usually are calibrated in either gallons per hour, or pounds per hour, for a fuel of a definite specific gravity and temperature.

(1.) After stabilization has occurred record the fuel consumption rate, and continue to record the fuel consumption rate at one-half hour intervals for 2 hours.

(2.) Determine the average of the readings (correct for fuel specific gravity and temperature). This is the fuel consumption rate and should be converted, if necessary, to pounds per hour.

(3.) Using the average value obtained above, calculate the rate of fuel consumption per kilowatt hour.

(4.) Repeat the test for each load condition specified.

(5.) Determine the capacity of the generator set fuel tank in pounds of fuel.

(6.) For each specified load test, compute the number of continuous hours the generator set will operate on a full tank of fuel. The following formula shall be used:

$$\text{Operating Hours} = \frac{\text{Fuel Tank Capacity (Pounds)}}{\text{Fuel Consumption (Pounds per Hour)}}$$

c. Results. Compare the operating hours or the fuel consumption rate per kWH.

3.7 ONSITE TRAINING

Conduct training course for operating staff as designated by the Contracting Officer. The training period shall consist of a total 16 hours of normal working time and shall start after the system is functionally completed but prior to final acceptance. All operation and maintenance manuals shall bee approved and made available for the training course. All posted instructions shall be approved and posted prior to the beginning date of the training course. The training course schedule shall be coordinated with the Using Service's work schedule, and submitted for approval 14 days prior to beginning date of proposed beginning date of training. The course instructions shall cover pertinent points involved in operating, starting, stopping, servicing the equipment, as well as major elements of the operation and maintenance manuals. Additionally, the course instructions shall demonstrate routine maintenance procedures as described in the operation and maintenance manuals.

3.8 FINAL TESTING AND INSPECTION

a. Start the engine, record the starting time, make and record all engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

b. Increase the load in steps no greater than the Maximum Step Load Increase to 100 percent of Service Load, and operate the engine-generator set for at least 30 minutes. Measure the vibration at

the end bearings (front and back of engine, outboard end of generator) in the horizontal, vertical, and axial directions. Verify that the vibration is within the same range as previous measurements and is within the required range.

c. Remove load and shut down the engine-generator set after the recommended cool down period.

d. Remove the lube oil filter and have the oil and filter examined by the engine manufacturer for excessive metal, abrasive foreign particles, etc. Any corrective action shall be verified for effectiveness by running the engine for 8 hours at Service Load, then re-examining the oil and filter.

e. Remove the fuel filter and examine the filter for trash, abrasive foreign particles, etc.

f. Visually inspect and check engine and generator mounting bolts for tightness and visible damage.

g. Replace air, oil, and fuel filters with new filters.

3.9 POSTED DATA AND INSTRUCTIONS

Posted Data and Instructions shall be posted prior to field acceptance testing of the engine generator set. Two sets of instructions/data shall be typed and framed under weatherproof laminated plastic, and posted side-by-side where directed. First set shall include a one-line diagram, wiring and control diagrams and a complete layout of the system. Second set of shall include the condensed operating instructions describing manufacturer's pre-start checklist and precautions; startup procedures for test-mode, manual-start mode, and automatic-start mode (as applicable); running checks, procedures, and precautions; and shutdown procedures, checks, and precautions. Instructions shall include procedures for interrelated equipment. Two sets of instructions/data shall be typed in 216 X 279 mm format, laminated in weatherproof plastic, and placed in three-ring vinyl binders. The binders shall be placed as directed by the Contracting Officer. The instructions shall be in place prior to acceptance of the engine generator set installation. First set shall include a one-line diagram, wiring and control diagrams and a complete layout of the system. Second set shall include the condensed operating instructions describing manufacturer's pre-start checklist and precautions; startup procedures for test-mode, manual-start mode, and automatic-start mode (as applicable); running checks, procedures, and precautions; and shutdown procedures, checks, and precautions. Instructions shall include procedures for interrelated equipment.

3.10 ACCEPTANCE

Final acceptance of the engine-generator set will not be given until the Contractor has successfully completed all tests and all defects in installation material or operation have been corrected.

-- End of Section --

SECTION 26 32 33.00 10

UNINTERRUPTIBLE POWER SUPPLY (UPS) SYSTEM ABOVE 15 KVA CAPACITY
10/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C57.110	(1998; Errata 2002; R 2004) Recommended Practice for Establishing Transformer Capability When Supplying Nonsinusoidal Load Currents
IEEE C62.41.1	(2002; R 2008) IEEE Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.41.2	(2002) IEEE Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE Std 450	(2002; Errata 2004; INT 2005) Recommended Practice for Maintenance, Testing, and Replacement of Vented Lead-Acid Batteries for Stationary Applications
IEEE Std 485	(1997; R 2003; INT 2008) Recommended Practice for Sizing Lead-Acid Batteries for Stationary Applications

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA PE 1	(2003; R 2003) Uninterruptible Power Systems -- Specification and Performance Verification

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

1.2 SYSTEM DESCRIPTION

Provide a UPS system consisting of UPS module, battery system, battery protective device, static bypass transfer switch, controls and monitoring. Connect input ac power to the normal source ac input of the UPS module. The battery shall be connected to the dc input of the UPS module through the battery protective device. The ac output of the UPS system shall be connected to the critical loads. Active electronic devices shall be solid state. Semiconductor devices shall be sealed. Relays shall be dust-tight.

1.2.1 UPS Module and Battery System

UPS module shall contain required input isolation transformer, rectifier/charger unit, inverter unit and controls, battery protective device, and any other specified equipment/devices. Battery system shall contain the battery cells, racks, battery disconnect, battery monitor and cabinet, if required.

1.2.2 UPS System Devices

The UPS system shall include the static bypass transfer switch, system protective devices, monitoring and controls, means of isolating the system from the critical load, and remote monitoring interfaces.

1.2.3 Design Requirements

1.2.3.1 Semiconductor Fusing

Power semiconductors shall be fused to prevent cascaded or sequential semiconductor failures. Indicator lamp denoting blown fuse conditions shall be readily observable by the operator without removing panels or opening cabinet doors.

1.2.3.2 Interchangeability

The subassemblies in one UPS module shall be interchangeable with the corresponding modules within the same UPS, and from one UPS system to another of identical systems.

1.2.3.3 Control Power

Control power shall be derived from two sources, input and output, with automatic selective control. The control power circuit shall have suitable protection, appropriately marked and located in the immediate vicinity of the input protective device.

1.2.3.4 EMI/RFI Protection

The components and the system shall be designed to minimize the emission of electromagnetic waves that may cause interference with other equipment.

1.2.3.5 Wiring

Wiring practices, materials, and coding shall be in accordance with the requirements of NFPA 70 and other applicable standards. Wire runs shall be protected in a manner which separates power and control wiring. Control wiring shall be minimum No. 16 AWG extra-flexible stranded copper. Logic-circuit wiring may be smaller. Ribbon cables shall be minimum No. 22 AWG. Control wiring shall have permanently attached wire numbers.

1.2.3.6 Terminations

Terminals shall be supplied for making power and control connections. Terminal blocks shall be provided for field wiring terminals. Terminal blocks shall be heavy-duty, strap-screw type. Terminal blocks for field wiring shall be located in one place in each module and in the system cabinet. Control wiring shall be extended to the terminal block location. No more than two wires shall land on any terminal point. Where control

wiring is attached to the same point as power wiring, a separate terminal shall be provided. If bus duct is used, bus stubs shall be provided where bus duct enters cabinets.

1.2.3.7 Internal Assembly

The subassemblies shall be mounted in pull-out and/or swing-out trays where feasible. Cable connections to the trays shall be sufficiently long to allow easy access to all components. Where not feasible to mount subassemblies in pull-out or swing-out trays, they shall be firmly mounted inside the enclosure. Test points or logic indicators shall be labeled and located on the front edge of the control logic cards, if used.

1.2.3.8 Cabinet Structure

UPS system shall be installed in cabinets of heavy-duty structure meeting the NEMA PE 1 standards for floor mounting. UPS module cabinet shall be structurally adequate for forklift handling or lifting. Removable lifting eyes shall be provided on top of each cabinet. UPS module cabinet shall have hinged and lockable doors on the front only, with assemblies and components accessible from the front. Doors shall be key lockable. Operating controls shall be located outside the locked doors. Input, output, and battery cables shall be installed through the top or bottom of the cabinet.

1.2.3.9 Cabinet Finish

Equipment cabinet shall be cleaned, primed and painted in the manufacturer's standard colors, in accordance with accepted industry standards.

1.2.3.10 Mimic Bus

If painted, mimic bus and other front-panel markings (such as those showing circuit breakers or switches and fuses) shall be painted with durable acrylic-based paint.

1.2.3.11 Live Parts (300 Volts and Above)

Live parts (300 volts and above) that are exposed when front access doors are open shall be adequately protected or covered to minimize the chance of accidental contact.

1.2.3.12 Drawout Assemblies

Drawout assemblies weighing 23 kg or more shall be provided with a means of lifting, either an overhead device or a hoisting device.

1.2.3.13 Safety

UPS shall be equipped with instruction plates including warnings and cautions, suitably located, describing any special or important procedures to be followed in operating and servicing the equipment.

1.2.4 Performance Requirements

1.2.4.1 Normal Operation

The UPS module rectifier/charger shall convert the incoming ac input power

to dc power for the inverter and for float charging the battery. The inverter shall supply ac power continuously. Inverter output shall be synchronized with the bypass ac power source, provided that the bypass ac power source is within the specified frequency range. The UPS system shall supply ac power to the critical loads.

1.2.4.2 Loss of ac Input Power

The battery shall supply dc power to the inverter so that there is no interruption of ac power to the critical load whenever the ac input power source deviates from the specified tolerances or fails completely. The battery shall continue to supply power to the inverter for the specified protection time. At the same time, an alarm shall sound to alert operating personnel, allowing startup of a secondary power source or orderly shutdown of the critical load.

1.2.4.3 Return of ac Input Power Source

The rectifier/charger shall start and assume the dc load from the battery when the ac input power source returns. The rectifier/charger shall then simultaneously supply the inverter with dc power and recharge the battery. This shall be an automatic function and shall cause no disturbance to the critical load.

1.2.4.4 Failure of ac Input Power to Return

Should the ac input power fail to return before the battery voltage reaches the discharge limit, the UPS system shall disconnect from the critical load to safeguard the battery.

1.2.4.5 Transfer to Bypass ac Power Source

When the static bypass switch senses an overload, two or more inverter shutdown signals, or degradation of the inverter output, the bypass switch shall automatically transfer the critical load from the inverter output to the bypass ac power source without an interruption of power only if the connected load exceeds the capacity of the remaining on-line modules. If the bypass ac power source is out of normal tolerance limits, the UPS and the critical load shall shut down.

1.2.4.6 Retransfer to Inverter

The static bypass switch shall be capable of automatically retransferring the load back to the inverter output after the inverter output has returned to normal conditions. Retransfer shall not occur if the two sources are not synchronized.

1.2.4.7 UPS System Servicing

Manual closure of the maintenance bypass switch shall transfer the critical load from the inverter output to the bypass ac power source without disturbing the critical load bus. UPS module shall be capable of manual return to normal operation after completion of maintenance.

1.2.4.8 Battery Servicing

The battery protective device shall provide the means of disconnecting the battery from the rectifier/charger and inverter for maintenance. The UPS module shall continue to function and meet the performance criteria

specified except for the battery function.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

UPS System Installation

Detail drawings consisting of a complete list of equipment and materials, manufacturer's descriptive and technical literature, battery sizing calculations according to IEEE Std 485, installation instructions, single-line diagrams, ladder-type schematic diagrams, elevations, layout drawings, and details required to demonstrate that the system has been coordinated and will function properly as a unit.

SD-03 Product Data

Performance Requirements

Pertinent performance data for the UPS system, using a copy of the data sheets supplied with this specification. Data sheets shall be certified by a responsible officer of the UPS manufacturer.

Spare Parts

Spare parts data, as specified.

Field Training

Lesson plans and training manuals for the training phases, including type of training to be provided and proposed dates, with a list of reference materials.

SD-06 Test Reports

Factory Testing
Field Supervision, Startup and Testing

A detailed description of proposed factory test and field test procedures, including proposed dates and steps outlining each test, how it is to be performed, what it accomplishes, and its duration, not later than 1 month prior to the date of each test.

Factory and field test reports in booklet form tabulating factory and field tests and measurements performed, upon completion and testing of the installed system. Factory and field test reports shall be signed by an official authorized to certify on behalf of the manufacturer of the UPS system that the system meets specified requirements. The reports shall be dated after

the award of this contract, shall state the Contractor's name and address, shall name the project and location, and shall list the specific requirements which are being certified.

SD-10 Operation and Maintenance Data

Operating and Maintenance Manuals

Six complete copies of operation manuals for the UPS System outlining the step-by-step procedures required for system startup, operation and shutdown shall be provided. The instructions shall include the manufacturer's name, equipment model number, service manual, parts list, and brief description of equipment and its basic operational features. Six complete copies of maintenance manuals listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guides shall be provided. Corrective maintenance procedures shall identify the most probable failures and the appropriate repairs. Test measurement levels shall be referenced to specific test points on the installed equipment. Operation and maintenance manuals may be either combined or separate.

1.4 QUALITY ASSURANCE

1.4.1 Reliability

UPS shall have a minimum acceptable system Mean Time Between Failures (MTBF) of 100,000 hours. A failure is defined as any interruption to or degradation of the UPS output. Automatic switching to bypass due to a problem with the UPS system does not constitute a failure, provided that the critical load is not disturbed.

1.4.2 Maintainability

UPS shall have a maximum acceptable system Mean Time To Repair (MTTR) of 30 minutes. Repair time is defined as the clock time from the arrival of the service technician to the time when the UPS is restored to service either by repair or substitution of the failed component.

1.5 DELIVERY, STORAGE, AND HANDLING

Equipment placed in storage shall be protected from humidity and temperature variations, dirt, dust, or other contaminants.

1.6 PROJECT/SITE CONDITIONS

1.6.1 Environmental Requirements

The UPS and battery system shall be capable of withstanding any combination of the following external environmental conditions without mechanical or electrical damage or degradation of operating characteristics.

a. Operating altitude: Sea level to 1,200 m. (Systems applied at higher altitudes shall be derated in accordance with the manufacturer's instructions).

b. Non-operating altitude: Sea level to 12,000 m.

c. Operating ambient temperature range: 0 to 40 degrees C.

d. Non-operating and storage ambient temperature range: Minus 20 to plus 60 degrees C.

e. Operating relative humidity: 0 to 95 percent, without condensation.

1.6.2 Sound Pressure Levels

Sound pressure levels produced by the UPS, when operating under full rated load, at a distance of 1.5 m in any direction from the perimeter of the unit, shall not exceed 75 dB as measured on the A scale of a standard sound level meter at slow response.

1.7 EXTRA MATERIALS

Provide one set of special tools, calibration devices, and instruments required for operation, calibration, and maintenance of the equipment. Submit spare parts data for each different item of material and equipment specified, not later than the date of beneficial occupancy, including a complete list of parts and supplies with current unit prices and source of supply and an itemized price breakdown of spare parts recommended for stocking. The recommended spare parts selected shall be those which, in the manufacturer's judgment, will be involved in the majority of maintenance difficulties encountered.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

a. Provide materials and equipment which are the standard products of a manufacturer regularly engaged in the manufacture of such products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Equipment shall be supported by a service organization that is, in the opinion of the Contracting Officer, reasonably convenient to the site.

b. Parts and materials comprising the UPS system shall be new, of current manufacture, of a high grade and free of defects and imperfections, and shall not have been in prior service except as required during aging and factory testing.

2.2 NAMEPLATES

Each major item of equipment shall have the manufacturer's name, address, type or style, model or serial number, and catalog number on a plate secured to the item of equipment.

2.3 LOAD PROFILE

The UPS system shall be compatible with the load characteristics defined in the LOAD PROFILE TABLE below and load configuration shown. Provide compensation for UPS/load interaction problems resulting from nonlinear loads or transformer and motor inrush.

LOAD PROFILE TABLE

a. Type of load: Nonlinearity.

b. Size of load: 140 kVA.

c. Switching pattern:

d. Transient characteristics:

e. Steady-state characteristics:

f. Special factors:

2.4 UPS SYSTEM RATINGS

Unless stated otherwise, the parameters listed are under full output load at 0.8 power factor, with batteries fully charged and floating on the dc bus and with nominal input voltage.

2.4.1 System Capacity

Overall 225 kVA, 180 kW, non redundant, at 40 degrees C.

2.4.2 Module Capacity

225 kVA, 180 kW.

2.4.3 Battery Capacity

Discharge time to end voltage: 15 minutes, at 25 degrees C. Battery shall be capable of delivering 125 percent of full rated UPS load at initial start-up.

2.4.4 Static Switch

18 K amperes symmetrical interrupting capacity.

2.4.5 System Bus Bracing

Braced for 18 k amperes symmetrical interrupting capacity.

2.4.6 ac Input

a. Voltage 380 volts line-to-line.

b. Number of phases: 3-phase, 3-wire, plus ground.

c. Voltage Range: Plus 10 percent, minus 15 percent, without affecting battery float voltage or output voltage.

d. Frequency: 50 Hz, plus or minus 5 percent.

e. Power walk-in: 20 percent to 100 percent over 15 to 24 seconds.

f. Total harmonic current distortion (THD) reflected into the primary line: 5 percent maximum.

g. Transformer sub-cycle inrush: 4 to 8 times full load rating.

2.4.7 ac Output

a. Voltage 380 volts line-to-line, 220 volts line-to-neutral.

b. Number of phases: 3-phase, 4-wire, plus ground.

c. Voltage regulation:

(1) Balanced load: Plus or minus 1.0 percent.

(2) 50 percent load imbalance, phase-to-phase: Plus or minus 2 percent.

(3) No-load voltage modulation: Plus or minus 1 percent.

(4) Voltage drift: Plus or minus 1 percent over any 30 day interval (or length of test) at stated ambient conditions.

d. Voltage adjustment: Plus or minus 5 percent manually.

e. Frequency: 50 Hz.

f. Frequency regulation: Plus or minus 0.1 percent.

g. Frequency drift: Plus or minus 0.1 percent over any 24 hour interval (or length of test) at stated ambient conditions when on internal oscillator.

h. Harmonic content (RMS voltage): 3 percent single harmonic, maximum; 5 percent total maximum with linear load. Voltage THD shall be less than 7 percent with up to 50 percent nonlinear load and a crest factor of less than 3 to 1.

i. Load power factor operating range: 1.0 to 0.8 lagging.

j. Phase displacement:

(1) Balanced load: Plus or minus 1 degree of bypass input.

(2) 50 percent load imbalance phase-to-phase: Plus or minus 3 degrees of bypass input.

k. Wave-form deviation factor: 5 percent at no load.

l. Overload capability (at full voltage) (excluding battery):

(1) 125 percent load for 10 minutes.

(2) 150 percent load for 30 seconds.

(3) 300 percent load for one cycle after which it shall be current limited to 150 percent until fault is cleared or UPS goes to bypass.

m. Load sharing of parallel modules: Plus or minus 5 percent of average load per module.

2.4.8 Transient Response

2.4.8.1 Voltage Transients

a. 50 percent load step/0 percent to 50 percent load: Plus or minus 8 percent.

b. 50 percent load step/50 percent to 100 percent load: Plus or minus 8 percent.

c. Loss or return of ac input: Plus or minus 1 percent.

d. Loss or return of redundant module:

(1) Manually: Plus or minus 8 percent.

(2) Automatically: Plus or minus 8 percent.

e. Automatic transfer of load from UPS to bypass: Plus or minus 4 percent.

f. Manual retransfer of load from bypass to UPS: Plus or minus 4 percent.

g. Response time: Recovery to 99 percent steady-state condition within 50 milliseconds after any of the above transients.

2.4.8.2 Frequency

a. Transients: Plus or minus 0.5 Hz maximum.

b. Slew Rate: 1.0 Hz maximum per second.

2.4.9 Efficiency

a. Minimum Single-Module Efficiency: 90 percent at full load kW.

2.5 UPS MODULE

2.5.1 General Description

UPS module shall consist of a rectifier/charger unit and a 3-phase inverter unit with their associated transformers, synchronizing equipment, protective devices and accessories as required for operation.

2.5.2 Rectifier/Charger Unit

Rectifier/charger unit shall be solid state and shall provide direct current to the dc bus.

2.5.2.1 Input Protective Device

Rectifier/charger unit shall be provided with an input protective device. The protective device shall be sized to accept simultaneously the full-rated load and the battery recharge current. The protective device shall be capable of shunt tripping and shall have 18,000 amperes symmetrical interrupting capacity. The protective device shall have provision for locking in the "off" position. A surge suppression device shall be installed at the UPS input to protect against lightning and switching surges.

2.5.2.2 Power Transformer

A dry-type, isolated-winding power transformer shall be used for the rectifier unit. The transformer's hottest spot winding temperature shall

not exceed the temperature limit of the transformer insulation material when operating at full load. The transformer insulation shall be Class H, 150 degrees C rise. Transformer connections shall be accessible from the front.

2.5.2.3 Power Walk-In

Rectifier/charger unit shall be protected by a power walk-in feature such that when ac power is returned to the ac input bus, the total initial power requirement will not exceed 20 percent of the rated full load current. This demand shall increase gradually to 100 percent of the rated full load current plus the battery charging current over the specified time interval.

2.5.2.4 Sizing

Rectifier/charger unit shall be sized for the following two simultaneous operating conditions:

a. Supplying the full rated load current to the inverter.

b. Recharging a fully-discharged battery to 95 percent of rated ampere-hour capacity within ten times the discharge time after normal ac power is restored, with the input protective device closed.

2.5.2.5 Battery Charging Current

a. Primary current limiting: Battery-charging current shall be voltage regulated and current limited. The battery-charging current limit shall be separately adjustable from 2 percent to 25 percent of the maximum discharge current. After the battery is recharged, the rectifier/charger unit shall maintain the battery at full float charge until the next operation under input power failure. Battery charger shall be capable of providing equalizing charge to the battery.

b. Second step current limiting: The rectifier/charger unit shall also have a second-step battery current limit. This second-step current limit shall sense actual battery current and reduce the input power demand for battery recharging to 50 percent (adjustable from 30 percent to 70 percent) of the normal rate without affecting the system's ability to supply full-rated power to the connected load. The second-step current-limit circuit shall be activated by a dry contact signal from the generator set controls and shall prevent normal rate battery recharging until utility power is restored.

2.5.2.6 Output Filter

Rectifier/charger unit shall have an output filter to minimize ripple current supplied to the battery; the ripple current into the battery shall not exceed 3 percent RMS.

2.5.2.7 dc Voltage Adjustment

Rectifier/charger unit shall have manual means for adjusting dc voltage for battery equalization, to provide voltage within plus 10 percent of nominal float voltage.

2.5.2.8 Battery Isolation Protective Device

Module shall have a dc protective device to isolate the module from the

battery system. The protective device size and interrupting rating shall be as required by system capacity and shall incorporate a shunt trip as required by circuit design. The protective device shall have provision for locking in the "off" position.

2.5.3 Inverter Unit

Inverter unit shall be a solid-state device capable of accepting power from the dc bus and providing ac power within specified limits.

2.5.3.1 Output Overload

The inverter shall be able to sustain an overload as specified across its output terminals. The inverter shall not shut off, but shall continue to operate within rated parameters, with inverse-time overload shutdown protection.

2.5.3.2 Synchronism

The inverter shall normally operate in phase-lock and synchronism with the bypass source. Should the bypass source frequency deviate beyond 60 Hz by more than 0.5 Hz, the internal frequency oscillators contained in the power module shall be used to derive the new frequency reference. Upon restoration of the bypass source within the required tolerance, the inverter shall resynchronize with that source at a slew rate not exceeding the specified rate. The oscillator shall be temperature compensated and shall be manually adjustable. The design of the oscillator and synchronizing circuits shall be such that failure of any associated component, connector pin, terminal lead wire or dc power source in either the open or shorted mode shall affect only one inverter leg. Such failure shall not cause transient disturbance of the critical load in excess of the stated limits.

2.5.3.3 Phase Balance

Electronic controls shall be incorporated to provide individual phase voltage compensation to obtain phase balance.

2.5.3.4 Modular Construction

Each control logic printed circuit board shall be electrically and physically packaged on an individual plug-in module with separate indication and adjustments.

2.5.3.5 Output Protective Device

The output protective device shall be capable of shunt tripping and shall have interrupting capacity as specified. Protective device shall have provision for locking in the "off" position.

2.5.3.6 Output Transformer

The inverter output transformer shall be similar to the input transformer and shall be capable of handling up to K-13 nonlinear loads as described in IEEE C57.110.

2.5.4 External Protection

UPS module shall have built-in self-protection against undervoltage,

overvoltage, overcurrent and surges introduced on the ac input source and/or the bypass source. The UPS system shall sustain input surges without damage in accordance with IEEE C62.41.1 and IEEE C62.41.2. The UPS shall also have built-in self-protection against overvoltage and voltage surges introduced at the output terminals by paralleled sources, load switching, or circuit breaker operation in the critical load distribution system.

2.5.5 Internal Protection

UPS module shall be self-protected against overcurrent, sudden changes in output load and short circuits at the output terminals. UPS module shall be provided with output reverse power detection which shall cause that module to be disconnected from the critical load bus when output reverse power is present. UPS module shall have built-in protection against permanent damage to itself and the connected load for predictable types of failure within itself and the connected load. At the end of battery discharge limit, the module shall shut down without damage to internal components.

2.6 STATIC BYPASS TRANSFER SWITCH

Provide a static bypass transfer switch as an integral part of the UPS consisting of a static switch and a bypass protective device or bypass switch. The control logic shall contain an automatic transfer circuit that senses the status of the inverter logic signals and alarm conditions and provides an uninterrupted transfer of the load to the bypass ac power source, without exceeding the transient limits specified herein, when a malfunction occurs in the UPS or when an external overload condition occurs. The power section of the static bypass transfer switch shall be provided as a plug-in type assembly to facilitate maintenance. The static bypass transfer switch shall be used to connect the bypass ac power source or the UPS inverter output to the critical load when required, and shall have the following features:

2.6.1 Uninterrupted Transfer

The static bypass transfer switch shall automatically cause the bypass ac power source to assume the critical load without interruption when the bypass control logic senses one of the following conditions and the UPS inverter output is synchronized to the bypass ac power source:

a. Inverter overload exceeds unit's rating.

b. Battery protection period is expired and bypass is available.

c. Inverter failure.

2.6.2 Interrupted Transfer

If an overload occurs and the UPS inverter output is not synchronized to the bypass ac power source, the UPS inverter output shall current-limit for 200 milliseconds minimum. The inverter shall then turn off and an interrupted transfer to the bypass ac power source shall be made. If the bypass ac power source is beyond the conditions stated below, an interrupted transfer shall be made upon detection of a fault condition:

a. Bypass voltage greater than plus or minus 10 percent from the UPS rated output voltage.

b. Bypass frequency greater than plus or minus 0.5 Hz from the UPS rated output frequency.

c. Phase differential of ac bypass voltage to UPS output voltage greater than plus or minus 3 degrees.

2.6.3 Manual Transfer

It shall be possible to make a manually-initiated static transfer from the system status and control panel by turning the UPS inverter off.

2.6.4 Automatic Uninterrupted Forward Transfer

The static bypass transfer switch shall automatically forward transfer, without interruption after the UPS inverter is turned "on", or after an instantaneous overload-induced reverse transfer has occurred and the load current has returned to less than the unit's 100 percent rating.

2.6.5 Forced Transfer

The control logic circuitry shall provide the means of making a forced or reverse transfer of the static bypass transfer switch on an interrupted basis. Minimum interruption shall be 200 milliseconds when the UPS inverter is not synchronized to the bypass ac power source.

2.6.6 Overload Ratings

The static bypass transfer switch shall withstand the following overload conditions:

a. 2000 percent of UPS output rating for two cycles.

b. 200 percent of UPS output rating for 5 minutes.

c. 125 percent of UPS output rating for 10 minutes.

2.7 MAINTENANCE BYPASS SWITCH

2.7.1 General

Provide a maintenance bypass switch as an integral part of the UPS located within the UPS module. The maintenance bypass switch shall provide the capability to continuously support the critical load from the bypass ac power source while the UPS is isolated for maintenance. The maintenance bypass switch shall be housed in an isolated compartment inside the UPS cabinet in such a way that service personnel will not be exposed to electrically live parts while maintaining the unit. Switch shall contain a maintenance bypass protective device and a module isolation protective device.

2.7.2 Load Transfer

The maintenance bypass switch shall provide the capability of transferring the critical load from the UPS static bypass transfer switch to maintenance bypass and then back to the UPS static bypass transfer switch with no interruption to the critical load.

2.8 MODULE CONTROL PANEL

The UPS module shall be provided with a control/indicator panel. The panel shall be on the front of the UPS module. Controls, meters, alarms and indicators for operation of the UPS module shall be on this panel.

2.8.1 Module Meters

2.8.1.1 Monitored Functions

The following functions shall be monitored and displayed:

a. Input voltage, phase-to-phase (all three phases).

b. Input current, all three phases.

c. Input frequency.

d. Battery voltage.

e. Battery current (charge/discharge).

f. Output voltage, phase-to-phase and phase-to-neutral (all three phases).

g. Output current, all three phases.

h. Output frequency.

i. Output kilowatts.

j. Elapsed time meter to indicate hours of operation, 6 digits.

k. Bypass voltage, phase-to-phase and phase-to-neutral (all three phases).

l. Output kilovars.

m. Output kilowatt hours, with 15-minute demand attachment.

2.8.1.2 Meter Construction

Meters shall have 1 percent accuracy and shall be digital type (minimum 4 significant digits).

2.8.2 Module Controls

Module shall have the following controls:

a. Lamp test/reset pushbutton.

b. Alarm test/reset pushbutton.

c. Module input protective device trip pushbutton, with guard.

d. Module output protective device trip pushbutton, with guard.

e. Battery protective device trip pushbutton, with guard.

f. Emergency off pushbutton, with guard.

g. dc voltage adjustment potentiometer, with locking guard.

h. Control power off switch.

i. UPS/bypass transfer selector switch.

j. Static bypass transfer switch enable/disable selector switch.

2.8.3 Module Alarm Indicators

Module shall have indicators for the following alarm items. Any one of these conditions shall turn on an audible alarm and the appropriate summary indicator. Each new alarm shall register without affecting any previous alarm.

a. Input ac power source failure.

b. Input protective device open.

c. Output protective device open.

d. Overload.

e. Overload shutdown.

f. dc overvoltage.

g. dc ground fault.

h. Low battery.

i. Battery discharged.

j. Battery protective device open.

k. Blower failure.

l. Input transformer overtemperature.

m. Inverter transformer overtemperature.

n. Equipment overtemperature.

o. Operating on internal oscillator.

p. Fuse blown.

q. Control power failure.

r. Charger off.

s. Inverter off.

t. Emergency off.

u. UPS on battery.

v. Critical load on static bypass.

w. Static bypass transfer switch disabled.

x. Inverter output overvoltage.

y. Inverter output undervoltage.

z. Inverter output overfrequency.

aa. Inverter output underfrequency.

bb. Bypass source overvoltage.

cc. Bypass source undervoltage.

dd. Bypass source overfrequency.

ee. Bypass source underfrequency.

ff. Bypass source to inverter out of synchronization.

2.8.4 Module Mimic Panel

UPS module shall have a mimic panel in the format of a module single-line diagram, with status indicators for input, output, battery protective devices, and battery disconnect switch. Each protective device shall have indicators for open (green) and closed (red), to give positive indication. The mimic panel shall provide indication of the following additional functions:

a. Charger on (functional).

b. UPS on-line (inverter furnishing load power).

c. UPS on-bypass (static switch operating).

d. System alarm (flashes for abnormalities, minor or major faults).

2.8.5 Module Emergency Off Button

Pressing the emergency off button shall cause the affected module to be disconnected from the system, via its input protective device, output protective device, and battery protective device. Activation of this button shall not affect the operation of the remainder of the system.

2.9 SYSTEM CONTROL CABINET

2.9.1 UPS Output Switchgear

The UPS output switchgear shall consist of a main protective device feeding the UPS output switchgear critical load bus, a load bank protective device (connected on the line side of the main protective device), a maintenance bypass protective device and associated feeder protective devices for the critical loads.

2.9.1.1 Switchgear

UPS output switchgear shall be provided in accordance with Section

26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION.

2.9.2 System Control Panel

A separate control panel shall be provided for the overall UPS system. The panel shall be on the front surface of the system cabinet. The controls, meters, alarms and indicators for operation of the UPS system shall be on this panel.

2.9.2.1 System Meters

Meters shall have 1 percent accuracy and shall be digital type (minimum 4 significant digits). ac voltages shall be measured as true RMS voltages.

The following functions shall be monitored:

a. Output voltage, phase-to-phase and phase-to-ground (all three phases).

b. Output current, all three phases.

c. Output frequency.

d. Bypass voltage, phase-to-phase and phase-to-ground (all three phases).

e. Output kilowatts.

f. Output kilovars.

g. Output kVA.

h. Output kilowatt-hours, with demand attachment.

i. Maintenance bypass voltage, phase-to-phase and phase-to-ground (all three phases).

2.9.2.2 System Controls

The system cabinet shall include the following controls:

a. Lamp test/reset.

b. Alarm test/reset.

c. Voltage adjustment potentiometer.

d. Emergency off pushbutton with protective cover.

e. UPS/bypass transfer selector switch.

f. Static switch enable/disable selector switch.

g. Control power off switch.

2.9.2.3 System Alarm Indicators

The system control panel shall contain indicators for the following additional alarm items. Any one of these alarm conditions shall also

activate the audible alarm. Each new alarm shall register without affecting previous alarms.

a. Module summary alarm, one for each UPS module.

b. UPS on battery.

c. Low battery voltage.

d. Critical load on bypass.

e. Static switch disable.

f. Output overvoltage.

g. Output undervoltage.

h. Output overfrequency.

i. Output underfrequency.

j. Overload.

k. Bypass source overvoltage.

l. Bypass source undervoltage.

m. Bypass source overfrequency.

n. Bypass source underfrequency.

o. Bypass source to inverter out of synchronization.

p. Equipment overtemperature.

q. Control power failure.

2.9.2.4 System Mimic Panel

The system control panel shall contain a mimic panel in the format of a single-line diagram, with status indicators for the following items:

a. Module on-line, one per UPS module.

b. UPS output protective device status, one for closed (red), one for open (green), and one for withdrawn (amber).

c. Static bypass protective device status, one for closed (red), one for open (green), and one for withdrawn (amber).

d. Static switch status, one for connected (red), and one for disconnected (green).

2.9.2.5 Emergency Off

Pressing the emergency off button shall cause the module input, output, and battery circuit breakers to open, completely isolating the UPS system from sources of power. The critical load shall be transferred to the bypass source when this occurs.

2.10 SELF-DIAGNOSTIC CIRCUITS

The control logic shall include status indicators for trouble-shooting the control circuits. These indicators shall be mounted on the circuit card edge or face such that they will be visible without repositioning the card, and shall be labeled with the function name.

2.11 REMOTE MONITORING PANEL

A remote monitoring panel shall be provided to monitor system status. The panel shall be designed for wall mounting near the critical load.

2.11.1 Indicators

Minimum display shall include the following indicators:

a. Load on UPS.

b. Load on battery.

c. Load on bypass.

d. Low battery.

e. Summary alarm.

f. New alarm (to alert the operator that a second summary alarm condition has occurred).

2.12 COMMUNICATIONS AND DATA ACQUISITION PORT

An RS 232C communications and data acquisition port shall be provided. This port shall allow the system parameters, status, alarm indication and control panel functions specified to be remotely monitored and controlled.

2.13 TEMPERATURE CONTROL

2.13.1 General

Cabinet and enclosure ventilation shall be adequate to ensure that components are operated within their ratings. Forced-air cooled rectifier, inverter, and control unit will be acceptable. The cooling fans shall continue operation if UPS input power is lost. Redundancy shall be provided so that failure of one fan or associated circuit breaker will not cause an overheat condition. Cooling air shall enter the lower front of the cabinets and exhaust at the top. Blower power failure shall be indicated as a visual and audible alarm on the control panel. Air inlets shall have filters that can be replaced without opening the cabinet doors.

2.13.2 Blower Power Source

Blower power source shall be internally derived from the input and output sides of UPS module, with automatic transfer arrangement.

2.13.3 Temperature Sensors

Temperature sensors shall be provided to monitor the air temperature. Separate sensors shall monitor the temperature of rectifier and inverter

heat sinks. Separate sensors shall also monitor the transformer temperature. Critical equipment overtemperature indication shall start a timer that shall shut down the UPS system if the temperature does not return below the setpoint level in 3 minutes.

2.14 BATTERY SYSTEM

2.14.1 General

A storage battery with sufficient ampere-hour rating to maintain UPS output at full capacity for the specified duration shall be provided for each UPS module. The battery shall be of heavy-duty, industrial design suitable for UPS service. The cells shall be provided with flame arrestor vents, intercell connectors and cables, cell-lifting straps, cell-numbering sets, and terminal grease. Intercell connectors shall be sized to maintain terminal voltage within voltage window limits when supplying full load under power failure conditions. Cell and connector hardware shall be stainless steel of a type capable of resisting corrosion from the electrolyte used.

2.14.2 Battery Ratings

a. Type: lead calcium .

b. Specific gravity when fully charged: 1.215 .

c. End voltage 1.67 volts per cell.

d. Float voltage: 2.17 to 2.26 volts per cell.

e. Equalizing voltage: 2.33 to 2.38 volts per cell.

2.14.3 Battery Construction

The battery shall be of the valve-regulated, sealed, non-gassing, recombinant type and shall be supplied complete with thermometer and hydrometer holder.

2.14.4 Battery Cabinet

The battery pack assembly shall be furnished in a battery cabinet matching the UPS cabinet. The battery cabinet shall be designed to allow for checking the torque on the connections in the battery system and to provide adequate access for annual housekeeping chores. External wiring interface shall be through the bottom or top of the assembly. A smoke and high temperature alarm shall annunciate detection of either smoke or high temperature within the battery cabinet.

2.15 FACTORY TESTING

The UPS system shall be factory tested to meet the requirements specified using a test battery (not the battery to be supplied with the system). UPS module shall be factory load tested as an independent assembly with 3-phase ac input power and with battery power for a minimum of 8 hours, with meter readings taken every 30 minutes. Load shall be balanced at rated kVA and rated power factor. Factory tests for the UPS module shall be run under full load, and will be witnessed by the Government. Should a malfunction occur, the problem shall be corrected and the test shall be repeated. As a minimum, the factory tests shall include the parameters described in

paragraphs ac Input, ac Output, Transient Response and Efficiency. The tests shall encompass all aspects of operation, such as module failure, static bypass operation, battery failure, input power failure and overload ratings. Notify the Government in writing at least 2 weeks before testing. Factory-test time shall not be used for system debugging and/or checkout. Such work shall be done prior to notifying the Government that the system is ready for testing. Factory tests shall be performed during normal business hours. The system shall be interconnected and tested for an additional 8 hours to ensure proper wiring and performance.

2.15.1 Transient Tests

Transient tests shall be conducted using high-speed oscillograph type recorders to demonstrate the operation of the components to the satisfaction of the Government. These tests shall include 50 percent to 100 percent load changes, manual transfer, manual retransfer, low dc bus initiated transfer and low ac output bus transfer. A recording instrument equipped with an event marker shall be used.

2.15.2 Efficiency Tests

Testing for efficiency shall be performed at zero output up to 100 percent of stated kVA output in 25 percent steps, 0.8 power factor, with battery fully charged and floating on the dc bus, with nominal input voltage, and with modules connected to the system to represent actual operating conditions.

2.16 INSPECTION

Inspection before shipment is required. The manufacturer shall notify the Government at least 2 weeks before shipping date so that an inspection can be made.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

The UPS system shall be set in place, wired and connected in accordance with the approved shop drawings and manufacturer's instructions. The UPS battery shall be shipped to the site dry.

3.3 FIELD SUPERVISION, STARTUP AND TESTING

The services of a manufacturer's representative who is experienced in the installation, adjustment, and operation of the equipment specified shall be provided. The representative shall supervise the installation, adjustment and testing of the equipment. The representative shall check the wiring between equipment, start up the system, and field test the functions, interlocks and protective devices to ensure that the total system is functioning according to the intent of the design. The field tests shall be performed under the supervision of a factory-trained representative of the equipment manufacturer and witnessed by the Government. The Government shall be given 2 weeks written advance notice of the date and time when

testing will be conducted.

3.3.1 Field Tests

As a minimum, the startup and field test procedures shall include the following:

a. Ensure that shipping members have been removed.

b. Check for damage (dents, scratches, frame misalignment, damage to panel devices, etc).

c. Ensure that interiors are free of foreign materials, tools and dirt.

d. Attach a phase rotation meter to the UPS input, output and bypass buses, and observe proper phase sequences.

e. Torque test bus connections at shipping splits. Also torque test battery connections.

f. Check each electrical bus for proper phasing and identification.

g. Check and test selector switches and meters for proper operation.

h. Check doors for proper alignment and operation.

i. Check and test each protective device for proper mechanical and electrical operation.

j. Check protective device overcurrent trip settings.

k. Check and test indicating lights for proper operation and color.

l. Perform onsite field test procedures.

m. Demonstrate to the Government that the specified functions and interlocks have been implemented.

n. Provide IEEE Std 450 battery installation certification.

o. Check key interlock key numbers, if used, to ensure agreement with interlocking scheme.

3.3.2 Load Test

The installed system shall be load tested for a continuous 24 hour period by means of resistive load banks. The system shall be continuously tested at 1/2 load for 8 hours, 3/4 load for 8 hours and full load for 8 hours. Load banks will be available onsite and shall be connected to UPS equipment by the Contractor or, the equipment manufacturer shall provide resistive load banks of total kW load of equipment to facilitate startup under load conditions, and to conduct load tests described above. Instrument readings shall be recorded every half hour for the following:

a. Input voltage (all three phases, for each module).

b. Input current (all three phases, for each module).

c. Input frequency.

d. Battery voltage for each module.

e. Output voltage (all three phases, for each module).

f. Output current (all three phases, for each module).

g. Output kilowatts for each module.

h. Output frequency.

i. Output voltage (all three phases - system output).

j. Output current (all three phases - system output).

k. Output kilowatts (system output).

3.4 FIELD TRAINING

Provide a field training course, for designated operating and maintenance staff members, for a total period of 12 hours of normal working time starting after the system is functionally complete but prior to final acceptance test. Field training shall cover the items contained in the operating and maintenance manuals. Divide the 12 hours into two sessions of 6 hours each. Each session shall be conducted on a different day.

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 1 OF 6

	ITEM	SPECIFIED	SUBMITTED
GENERAL	SYSTEM OPERATION	SINGLE MODULE PARALLEL REDUNDANT PARALLEL NON REDUNDANT	
	NUMBER OF SYSTEMS	_____	
	NUMBER OF MODULES IN EACH SYSTEM	PRESENT _____ FUTURE _____	
	SYSTEM CAPACITY: PRESENT FUTURE	 _____ kW/_____ kVA _____ kW/_____ kVA	
	BATTERY	ONE PER MODULE	
	MTBF (SYSTEM)		
	MTTR		
	MODULE RATING	_____ kW/_____ kVA	
MODULE	DC VOLTAGE WINDOW	_____ Vdc	
	INPUT/OUTPUT PROTECTIVE DEVICE INTERRUPT. RATING	_____ A SYM.	
BATTERY	MANUFACTURER	_____	
	TYPE	LEAD-CALCIUM LEAD-ANTIMONY NICKEL-CADMIUM	
	DISCHARGE TIME TO END VOLTAGE AT FULL LOAD	_____ MINUTES	
	END VOLTAGE	_____ V/CELL	
	SPECIFIC GRAVITY	_____	
	FLOAT VOLTAGE	_____ V/CELL	
	NUMBER OF CELLS	_____ CELLS	

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 2 OF 6

	ITEM	SPECIFIED	SUBMITTED
BATT	HYDROGEN GENERATION	_____	
	RECHARGE TIME TO 95 percent CAPACITY	10 X DISCHARGE	
SYSTEM CABINET	PROTECTIVE DEVICE	AIR POWER, DRAW-OUT	
	MANUFACTURER	_____	
	INTERRUPTING RATE	_____ A SYM.	
	STATIC SWITCH	_____ A	
AC INPUT	VOLTS, LINE/LINE	_____ V	
	PHASES	3-PHASE, 3-WIRE	
	VOLTAGE RANGE	+ 10 percent, - 15 percent	
	FREQUENCY	[50] [60] Hz	
	FREQUENCY RANGE	+/- 5 percent	
	POWER WALK-IN 20 TO 100 percent LOAD	15 - 24 SECONDS	
	TOTAL HARMONIC DISTORTION REFLECTED-PRIMARY	5 percent MAX (CURRENT)	
	ORDER OF HARMONIC	_____	PERCENTAGE OF TOTAL
	2nd		
	3rd		
	4th		
	5th		
	6th		
	7th		
	8th		
	9th		
	(FILL IN AS REQUIRED)		
	TRANSFORMER SUB-CYCLE INRUSH	_____ x FULL LOAD	
	POWER FACTOR	[0.8] [0.9]	

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 3 OF 6

	ITEM	SPECIFIED	SUBMITTED
	VOLTAGE, LINE-LINE	_____ V	
	PHASES	3-PHASE, 4-WIRE	
	POWER FACTOR	0.8 LAGGING, 1.0	
	VOLTAGE REGULATION		
	BALANCED LOAD	+/- 1.0 percent	
	50 percent IMBALANCE BETWEEN PHASES	+/- 2.0 percent	
	NO-LOAD MODULATION	+/- 1.0 percent	
	DRIFT (30 DAYS)	+/- 1.0 percent	
	VOLTAGE ADJUST.	+/- 5.0 percent MANUALLY	
A	FREQUENCY	60 Hz	
C			
	REGULATION	+/- 0.1 percent	
O			
U	DRIFT (24 HRS.)	+/- 0.1 percent	
T			
P	HARMONIC CONTENT		
U	TOTAL (50% NON-LINEAR LOAD	7.0 percent MAX.	
T	TOTAL (LINEAR LOAD)	5.0 percent MAX.	
	SINGLE HARMONIC (LINEAR LOAD)	3.0 percent MAX.	
	PHASE DISPLACEMENT		
	BALANCED LOAD	+/- 1.0 DEG. OF BYPASS	
	50 percent IMBALANCE	+/- 3.0 DEG. OF BYPASS	
	WAVE FORM DEVIATION FACTOR	5.0 perent (NO LOAD)	
	OVERLOAD CAPACITY		
	125 percent	10 MINUTES	
	150 percent	30 SECONDS	
	300 percent	MOMENTARY	

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 4 OF 6

	ITEM	SPECIFIED	SUBMITTED
	LOAD SHARING AMONG MODULES	+/- 5.0 percent OF AVERAGE LOAD	
	VOLT. TRANSIENT RESPONSE		
	50% STEP LOAD 0 to 50 percent	+/- 8.0 percent	
	50% STEP LOAD 50 to 100%	+/- 8.0 percent	
	LOSS OR RETURN OF INPUT	+/- 1.0 percent	
	LOSS OR RETURN OF A REDUNDANT MODULE AUTOMATICALLY	+/- 8.0 percent	
	MANUALLY	+/- 8.0 percent	
A C O U T P U T	AUTO TRANSFER, AT FULL LOAD, FROM UPS TO BYPASS	+/- 4.0 percent	
	MANUAL TRANSFER, AT FULL LOAD, FROM BYPASS TO UPS	+/- 4.0 percent	
	RECOVERY TIME TO 99% STEADY-STATE COND.	50 MILLISECONDS	
	FREQUENCY TRANSIENT RESPONSE	+/- 0.5 Hz	
	SLEW RATE	1.0 Hz/SECOND	

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 5 OF 6

	ITEM	SPECIFIED	SUBMITTED
AC OUTPUT	EFFICIENCY @ FULL LOAD MODULE	_____percent	
	SYSTEM	_____percent	
	SYSTEM NOISE GEN. LEVEL @ 1.8 M FROM EQUIPMENT	_____ DBA	
	OPERATING AMBIENT TEMPERATURE	0 to [40] [50] DEG. C	
	STORAGE AMBIENT TEMPERATURE	-20 to +60 DEG. C	
ENVIRONMENTAL	BATTERY ROOM AMBIENT TEMP.	25 DEG. C NOMINAL	
	RELATIVE HUMIDITY (NON-CONDENSING)	0 - 95 percent	
	BAROMETRIC PRESSURE (ALTITUDE) OPERATING		
	NON-OPERATING	12,200 M	
	HEAT REJECTION	_____	
	MODULE		
	SYSTEM		
PHYSICAL DATA	MODULE	_____	
	SIZE		
	WEIGHT		
	SYSTEM CABINET	_____	
	SIZE		
	WEIGHT		

UPS SYSTEM PERFORMANCE DATA SHEET SHEET 6 OF 6

	ITEM	SPECIFIED	SUBMITTED
PHYSICAL DATA	BATTERY	_____	
	SEISMIC PARAMETERS		
	RACKS SIZE		
	WEIGHT		
	CELLS SIZE		
	WEIGHT		
	DISCON- SIZE		
	NECT WEIGHT		

-- End of Section --

SECTION 26 41 00.00 20

LIGHTNING PROTECTION SYSTEM
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE Std 81	(1983) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System (Part 1) Normal Measurements

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 780	(2007) Standard for the Installation of Lightning Protection Systems

UNDERWRITERS LABORATORIES (UL)

UL 467	(2007) Standard for Grounding and Bonding Equipment
UL 96	(2005) Standard for Lightning Protection Components
UL 96A	(2007) Standard for Installation Requirements for Lightning Protection Systems
UL Electrical Constructn	(2009) Electrical Construction Equipment Directory

1.2 RELATED REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to this section with additions and modifications specified herein.

1.2.1 Verification of Dimensions

Contractor shall become familiar with all details of work, verify all dimensions in field, and shall advise Contracting Officer of any discrepancy before performing work. No departures shall be made without prior approval of Contracting Officer.

1.2.2 System Requirements

Materials shall consist of standard products of a manufacturer regularly

engaged in production of lightning protection systems and shall be manufacturer's latest UL approved design. Lightning protection system shall conform to NFPA 70, NFPA 780, UL 96 and UL 96A.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Overall lightning protection system; G

Each major component; G

SD-06 Test Reports

Grounding system test; G

Lightning protection system inspection; G

SD-07 Certificates

UL listing or label

1.4 QUALITY ASSURANCE

In each standard referred to herein, consider the advisory provisions to be mandatory, as though the word "shall" has been substituted for "should" wherever it appears. Interpret references in these standards to "authority having jurisdiction," or words of similar meaning, to mean Contracting Officer.

1.4.1 Installation Drawings

a. Submit installation shop drawing for the overall lightning protection system. Drawings shall include physical layout of the equipment, mounting details, relationship to other parts of the work, and wiring diagram.

b. Submit detail drawings for each major component to include manufacturer's descriptive and technical literature, catalog cuts, and installation instructions.

1.4.2 UL Listing or Label

Submit proof of compliance. Label of or listing in UL Electrical Constructn is acceptable evidence. In lieu of label or listing, submit written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that items have been tested and conform to requirements and testing methods of Underwriters Laboratories.

1.5 SITE CONDITIONS

Contractor will become familiar with details of the work, verify dimensions in the field, and advise Contracting Officer of discrepancies before

performing work. Deviations from contract drawings will not be made without prior approval of Contracting Officer.

PART 2 PRODUCTS

2.1 MATERIALS

Do not use a combination of materials that forms an electrolytic couple of such nature that corrosion is accelerated in presence of moisture unless moisture is permanently excluded from the junction of such metals. Where unusual conditions exist which would cause corrosion of conductors, provide conductors with protective coatings or oversize conductors. Where mechanical hazard is involved, increase conductor size to compensate for hazard or protect conductors by covering them with molding or tubing made of wood or nonmagnetic material. When metallic conduit or tubing is provided, electrically bond conductor to conduit or tubing at the upper and lower ends by clamp type connectors or welds (including exothermic).

2.1.1 Main and Bonding Conductors

NFPA 780 and UL 96 Class I, Class II, or Class II modified materials as applicable.

2.1.2 Copper

Provide copper conductors on nonmetallic stacks that do not weigh less than 144.83 kg per 305 meters, and provide cable such that the size of any strand in the cable is not less than No. 15 AWG. Provide thickness of web or ribbon on stacks that is not less than No. 12 AWG. Provide loop conductors that are comprised of copper conductors not smaller than No. 1/0 AWG.

2.1.3 Aluminum

Do not allow aluminum to contact the earth and do not use in any other manner that will contribute to rapid deterioration of the metal. Observe appropriate precautions at connections with dissimilar metals in accordance with NFPA 70 Article 110-14. Provide aluminum cable conductors for bonding and interconnecting metallic bodies to main cable that are at least equivalent to strength cross-sectional area of a No. 4 AWG aluminum wire. When perforated strips are provided, use strips that are much wider than solid strips. Use a strip width that is at least twice that of the diameter of the perforations. Use an aluminum strip which has a thickness of not less than the diameter of No. 12 AWG and at least 40 mm wide for connecting exposed water pipes.

2.2 COMPONENTS

2.2.1 Air Terminals

Provide terminals in accordance with UL 96, except provide Class II for Class I and Class II applications. Support air terminals more than 610 mm in length by suitable brace, with guides, not less than one-half the height of the terminal.

2.2.2 Ground Rods

Provide ground rods made of copper-clad steel conforming to conform to UL 467. Provide ground rods that are not less than 20 mm in diameter and

3050 mm in length. Do not mix ground rods of copper-clad steel, stainless steel, galvanized ferrous, or solid copper on the job.

2.2.3 Grounding Plates

Provide grounding plates made of copper-clad steel conforming to UL 96.

2.2.4 Connections and Terminations

Provide connectors for splicing conductors that conform to UL 96, class as applicable. Conductor connections can be made by clamps or welds (including exothermic). Provide style and size connectors required for the installation.

2.2.5 Connector Fittings

Provide connector fittings for "end-to-end", "Tee", or "Y" splices that conform to NFPA 780.

2.2.6 Lightning Protection Components

Provide bonding plates, air terminal supports, chimney bands, clips, and fasteners that conform to UL 96 classes as applicable.

PART 3 EXECUTION

3.1 INTEGRAL SYSTEM

Lightning protection system consists of air terminals, roof conductors, down conductors, ground connections, grounding electrodes and ground loop conductor. Electrically interconnect lightning protection system to form the shortest distance to ground. Do not use nonconducting parts of the structure as part of the building's lightning protection system. Expose conductors on the structures except where conductors are required to be in protective sleeves. Interconnect secondary conductors with grounded metallic parts within the building. Make interconnections within side-flash distances at or above the level of the grounded metallic parts.

3.1.1 Air Terminals

Air terminal design and support conforming to NFPA 780. Rigidly connect terminals to, and make electrically continuous with, roof conductors by means of pressure connectors or crimped joints of T-shaped malleable metal. Provide pressure connector or crimped joint with a dowel or threaded fitting to connect ground rod conductor with air terminal. Set air terminals at ends of structures not more than 610 mmfrom ends of ridges and corners of roofs. Do not exceed 7620 mm in spacing of 610 mm high air terminals on ridges, parapets, and around perimeter of building with flat roofs. When necessary to exceed this spacing, increase specified height of air terminals not less than 50 mm for each 305 mm of increase over 7620 mm. On large flat, or gently sloping roofs, as defined in NFPA 780, place air terminals at points of the intersection of imaginary lines dividing the surface into rectangles having sides not exceeding 15 m in length. Secure air terminals against overturning either by attachment to the object to be protected or by means of a substantial tripod or other braces which are permanently and rigidly attached to the building or structure. Metal projections and metal parts of buildings such as smokestacks and other metal objects that are at least 4.763 mm thick and that do not contain hazardous materials, need not be provided with air terminals. However,

bond these metal objects to a lightning conductor through a metal conductor of the same unit weight per length as the main conductor. Where metal ventilators are installed, mount air terminals thereon, where practical. Bond air terminals, erected by necessity adjacent to a metal ventilator, to the ventilator near the top and bottom. Where nonmetallic spires, steeples, or ventilators are present, mount air terminals to the side. In addition, where spires or steeples project more than 3050 mm above the building, continue conductor from air terminal to nearest down conductor securely connect thereto.

3.1.2 Roof Conductors

Connect roof conductors directly to the roof or ridge roll. Avoid sharp bends or turns in conductors. Do not make turns of less than 205 mm. Preserve horizontal or downward course on conductors. Rigidly fasten conductors every 915 mm along the roof and down the building to the ground. Rigidly connect metal ventilators to the roof conductor at three places. Make connections electrically continuous. Course roof conductors along contours of flat roofs, ridges, parapets, and edges; and where necessary, over flat surfaces, in such a way as to join each air terminal to all the rest. Connect roof conductors surrounding tank tops, decks, flat surfaces, and flat roofs to form a closed loop.

3.1.3 Down Conductors

Make down conductors electrically continuous from air terminals and roof conductors to grounding electrodes. Course down conductors over outer extreme portions of the building, such as corners, with consideration given to location of ground connections and air terminals. Provide each building or structure not less than two down conductors located as widely separated as practicable, such as at diagonally opposite corners. Rectangular structures having gable, hip, or gambrel roofs more than 33 m long, provide at least one additional down conductor for each additional 15 m of length or fraction thereof. Irregularly shaped structures, provide enough conductors so that the average distance between them along the perimeter is not greater than 30 m. Install additional down conductors when necessary to avoid "dead ends" or branch conductors exceeding 5 m in length, ending at air terminals. Equally and symmetrically spaced down conductors about the perimeter of the structure. Protect conductors where necessary, to prevent physical damage or displacement to the conductor.

3.1.4 Interconnection of Metallic Parts

Connect metal doors, windows, and gutters directly to ground or down conductors using not smaller than No. 6 copper conductor, or equivalent. Where there is probability of unusual wear, mechanical injury, or corrosion, provide conductors with greater electrical capacity than normal or protect the conductor. Provide mechanical ties or pressure connectors between grounds and metal doors and windows.

3.1.5 Ground Connections

Securely connect conductor forming continuations of down conductors from structure to grounding electrode in a manner to ensure electrical continuity between the two. Provide clamp type connections or welds (including exothermic) for continuation. Provide a ground connection for each down conductor. Attach down conductors to ground rods by welding (including exothermic), brazing, or clamping. Provide clamps suitable for direct burial. Protect ground connection from mechanical injury. Bond

metal water pipes and other large underground metallic objects together with all grounding mediums. In making ground connections, take advantage of all permanently moist places where practicable, although avoid such places when area is wet with waste water that contains chemical substances, especially those corrosive to metal.

3.1.6 Grounding Electrodes

Provide grounding electrode for each down conductor. Extend driven ground rods into the existing undisturbed earth for a distance of not less 3050 mm. Set ground rods not less than 610 mm nor more than 3050 mm, from the structure. After the completed installation, measure the total resistance to ground using the fall-of-potential method described in IEEE Std 81. Maximum resistance of a driven ground rod shall be 10 ohms, under normally dry conditions. Use a ground loop when two of any three ground rods, driven not less than 3050 mm into the ground, a minimum of 3050 mm apart, and equally spaced around the perimeter, give a combined value exceeding 50 ohms immediately after having driven. For ground loop, provide continuous No. 1/0 bare stranded copper cable or equivalent material having suitable resistance to corrosion. Lay ground loop around the perimeter of the structure in a trench not less than 765 mm below grade, at a distance not less than 610 mm nor more than 3050 mm from the nearest point of the structure. Install a ground loop in earth undisturbed by excavation, not earth fill, and do not locate beneath roof overhang, or wholly under paved areas or roadways where rainfall cannot penetrate to keep soil moist in the vicinity of the cable. Make connections between ground conductors and grounds or ground loop, and between ground loop and grounds electrically continuous.

3.1.7 Grounding Plates

Provide a grounding plate for down conductor. Set grounding plates not less than 610 mm nor more than 3050 mm, from the structure. Grounding plate is to be buried as deeply in the existing dirt as local conditions allow, without exceeding 3050 mmin depth.

3.2 APPLICATIONS

3.2.1 Nonmetallic Exterior Walls with Metallic Roof

Bond metal roof sections together which are insulated from each other so that they are electrically continuous. Connect air terminals so that they are electrically continuous with the metal roof as well as the roof conductors and down conductors. Bond ridge cables and roof conductors to the roof at upper and lower edges of roof and at intervals not to exceed 30 m. Bond down conductors to roof conductors and to lower edge of metal roof. Where metal of roof is in small sections, make connections between air terminals and down conductors to at least four sections of the metal roof. Make connections electrically continuous and have a surface contact of at least 1935 square mm.

3.2.2 Metal Roofs with Metal Walls

Bond metal roof and metal walls so that they are electrically continuous and considered as one unit. Connect air terminals to and make them electrically continuous with the metal roof as well as the roof down conductors. Bond all roof conductors and down conductors to metal roof or metal walls at upper and lower edges at intervals not to exceed 30 m. Make all connections electrically continuous and have surface contact of at least

1935 square mm.

3.2.3 Steel Frame Building

Make the steel framework of the building electrically continuous. Electrical continuity may be provided by bolting, riveting, or welding unless another specific method is indicated. Connect air terminals to the structural steel framework at the ridge. Provide short runs of conductors to join air terminals to the metal framework so that proper placing of air terminals is maintained. Separate down conductors from air terminals to ground connections are not required. Where water system enters the building, securely connect structural steel framework and water system at point of entrance by a ground connector. Make connections to pipes by means of ground clamps with lugs. Make connections to structural framework by means of nut and bolt or welding. Make connections between columns and ground connections at bottom of steel columns. Make ground connections to grounds or ground loop runs from not less than one-half of the columns distributed equally around perimeter of structure. When no water system enter the structure, run ground connections from steel columns distributed equally around the perimeter of the structure. Bond metal doors, windows, gutters, and similar metal installation to steel work of the building. Provide a grounding electrode for each ground connection.

3.2.4 Ramps and Covered Passageways

Ramps and covered passageways which are in the zone of protection of a lightning protection system, as defined by NFPA 780, need no additional lightning protection. However, ramps and covered passageways which are outside the zone of protection of a lightning protection system shall be provided with a lightning protection conforming to the requirements for lightning protection systems for buildings of similar construction. Place a down conductor and a driven ground at one of the corners where the ramp connects to each building or structure. Connect down conductor and driven ground to the ground loop or nearest ground connection of the building or structure. Where buildings or structures and connecting ramps are clad with metal, connect metal of the buildings or structures and metal of the ramp in a manner to ensure electrical continuity, in order to avoid the possibility of a flash-over or spark due to a difference in potential. Make connections electrically continuous and have a surface contact area of at least 1935 square mm.

3.2.5 Tanks and Towers

3.2.5.1 Wooden Tanks and Towers

Electrically interconnect lightning protection system components (such as: air terminals, ridge cables, down conductors, ground connections, and grounds) to form the shortest distance to ground without passing through any nonconducting parts of the structure. Where the roof of the structure ends in a peak, a single air terminal not less than 610 mm high will be regarded as sufficient. When structure does not end in a peak, provide air terminals not less than 610 mm high at intervals not exceeding 7620 m along the perimeter of the structure. When the tank or tower is an adjunct of a building, near or touching the perimeter, extend one of the down conductors directly to a ground connection and connect the other to lightning protection of the building. When tank or tower is set well within the perimeter of the building, connect both down conductors to lightning protection system of the building. When height of the structure exceeds 30 m, cross-connect down conductors midway between the top and bottom. Where

buried metal pipes enter tank or tower, connect one down conductor to pipes, approximately 305 mm below grade. Ground metal guy wires or cables set in concrete or attached to buildings or nonconducting supports to a ground rod driven full length into the ground.

3.2.5.2 Metal or Reinforced-Concrete Tanks and Towers

Make metal or reinforcing steel electrically continuous. Electrical continuity may be provided by bolting, riveting, or welding metal and tying or clipping reinforcing bars, unless a specific method is noted on the drawings. Air terminals and down conductors are required except on bolted, riveted, or welded 4.75 mm minimum steel plate tanks. Ground connections and grounding electrodes are not required on metal tanks that are electrically continuous with a metallic underground pipe system. On other structures, provide two ground connections approximately 3.14 rad apart at the base of the structure. Connect each buried metal pipe entering the tank or tower to one ground connection approximately 305 mm below finished grade. Ground metal guy wires on tanks and towers. Metal guy wires or cables attached to steel anchor rods set in earth will be considered as grounded. Ground metal guy wires or cables set in concrete or attached to buildings or nonconducting supports to a ground rod driven full length into the ground.

3.2.6 Stacks

Ground metal guy wires for stacks. Metal guy wires or cables attached to steel anchor rods set in earth will be considered as sufficiently well grounded. However, ground metal guy wires or cables attached to anchor rods set in concrete or attached to buildings or nonconducting supports to a ground rod driven full length into the ground.

3.2.6.1 Metal Stacks

Make metal smokestacks electrically continuous and to ground. Heavy-duty metal stacks having a metal thickness of 4.75 mm or greater do not require air terminals or down conductors. Otherwise, provide two ground rods driven full length into the earth. Locate ground rods approximately 3.14 rad apart and set ground rods not less than 915 mm nor more than 2440 mm from the nearest point of the stack foundation.

3.2.6.2 Nonmetallic Stacks

On nonmetallic smokestacks constructed of brick, hollow tile, or concrete, make the air terminals solid copper, copper alloy, stainless steel or Monel metal. Distribute uniformly about the rim of the stack at intervals not exceeding 2440 mm and extending at least 765 mm above the rim of stack. Electrically connect air terminal together by means of a metal band or ring to form a closed loop about 610 mm below the top of the stack. Where the stack has a metal crown, connect air terminals to the metal crown. Where stacks have metal lining extending part way up, connect lining to air terminal at its upper end and ground at the bottom. Provide at least two down conductors on opposite sides of the stack leading from the ring or crown at the top to the ground. When the stack is an adjunct of building near or touching the building perimeter, extend one of the conductors directly to a ground connection while the other may be connected to lightning protection system on the building. On stacks exceeding 48 m in height, cross-connect down conductors approximately midway between the top and bottom. Reduce joints in conductors to a minimum and make joints to have the same tension strength as the conductors that are joining. Space

fasteners of copper or copper-bronze alloy not over 915 mmapart for vertical conductors and not over 610 mm apart for horizontal conductors. To prevent gases from corroding copper air terminals, provide conductors and fasteners within 7620 mmof the top of stack with continuous coating of hot dipped lead or an equivalent coating. Provide conductors conforming to the requirements for nonmetallic stacks for stacks partly or wholly of reinforced concrete. For nonmetallic stacks, electrically connect reinforcing steel to down conductors at top and bottom of concrete.

3.3 INTERFACE WITH OTHER STRUCTURES

3.3.1 Interconnection of Metal Bodies

Protect metal bodies when not within the zone of protection of air terminal. Bond metal bodies having an area of 0.258 square m or greater or a volume of 0.016387 cubic m or greater to lightning protection system using main size conductors and a bonding plate having a surface contact area of not less than 1935 square mm. Make provisions to guard against the corrosive effect of bonding dissimilar metals. Bond metal bodies at their closest point to the lightning protection system using bonding conductors and fittings. Independently ground any metal body that exceeds 1525 mm in any dimension, that is situated wholly within a building, and that does not at any point come within 1830 mm of a lightning conductor or metal connected to a lightning protection system.

3.3.2 Fences

Except as specified below, metal fences that are electrically continuous with metal posts extending at least 610 mm into the ground require no additional grounding. Ground other fences on each side of every gate at gate posts, at corner posts, and at end posts. Bond gate to adjacent fence post utilizing flexible copper grounding braid with sufficient slack to permit 3.14 rad opening of the gate. Provide flexible copper ground braid which has an ampacity equivalent to that of the fence ground wire specified herein. Provide ground rods every 305 to 457 m for grounding fences when fences are located in isolated places, and every 152 to 228 m when in proximity (30 m or less) to public roads, highways, and buildings. Provide connection to ground from the post where it is metal and is electrically continuous with the fencing using removable ground clamps on the fence posts and split-bolt connectors suitable for dissimilar metals on the fence fabric and barbed wire. Make connections to ground from the horizontal metal strand using split-bolt connectors suitable for dissimilar metals on the fence fabric and barbed wire. Ground metal fences at or near points 45 m on each side of medium and high voltage, (meaning in excess of 600 volts,) overhead line crossings. Ground metal fences at 45 m intervals where high and medium voltage lines are directly overhead and run parallel to the fence.

3.3.3 Exterior Overhead Pipe Lines

Properly ground overhead pipes, conduits, and cable trays on the exterior of the building that enter a building, preferably to building grounds at points where pipes enter the building. Where a separate ground is provided, bond the pipes to the building ground at points where the pipes are closest to the ground connections. In addition, bond pipes to any metallic masses that are within 1830 mm of the pipe.

3.4 RESTORATION

Where sod has been removed, place sod as soon as possible after completing the backfilling. Restore to original condition the areas disturbed by trenching, storing of dirt, cable laying, and other work. Include necessary topsoiling, fertilizing, liming, seeding, sodding, sprigging or mulching in any restoration. Maintain disturbed surfaces and replacements until final acceptance.

3.5 FIELD QUALITY CONTROL

3.5.1 Grounding System Test

Test the grounding system to ensure continuity and that resistance to ground is not in excess of 10 ohms. Test the ground rod for resistance to ground before making connections to the rod. Tie the grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not earlier than 48 hours after rainfall. Include in the written report: locations of ground rods, resistance, and soil conditions at the time that measurements were made. Submit results of each test to the Contracting Officer.

3.5.2 Lightning Protection System Inspection

Make visual inspections to verify that there are no loose connections which may result in high resistance joints, and that conductors and system components are securely fastened to their mounting surfaces and are protected against accidental mechanical displacement.

-- End of Section --

SECTION 26 51 00

INTERIOR LIGHTING
07/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 580/A 580M	(2008) Standard Specification for Stainless Steel Wire
ASTM A 641/A 641M	(2009a) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM B 164	(2003; R 2008) Standard Specification for Nickel-Copper Alloy Rod, Bar, and Wire

CALIFORNIA ENERGY COMMISSION (CEC)

CEC Title 24	(1978; R 2005) California's Energy Efficiency Standards for Residential and Nonresidential Buildings

ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA)

IESNA HB-9	(2000; Errata 2004; Errata 2005) IES Lighting Handbook

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE C62.41	(1991; R 1995) Recommended Practice for Surge Voltages in Low-Voltage AC Power Circuits
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA C78.901	(2005) Electric Lamps - Single Base Fluorescent Lamps Dimensional and Electrical Characteristics

NEMA C78.81	(2005) Electric Lamps - Double-capped Fluorescent Lamps Dimensional and Electrical Characteristics
NEMA C82.1	(2004) Electric Lamp Ballasts - Line Frequency Fluorescent Lamp Ballasts
NEMA C82.11	(2002) High-Frequency Fluorescent Lamp Ballasts
NEMA C82.2	(2002) Methods of Measurement of Fluorescent Lamp Ballasts
NEMA LL 1	(1997; R 2002) Procedures for Linear Fluorescent Lamp Sample Preparation and the TCLP Extraction

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2008; Amendment 2009) Life Safety Code
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

Energy Star	(1992; R 2006) Energy Star Energy Efficiency Labeling System

UNDERWRITERS LABORATORIES (UL)

UL 1598	(2004; Rev thru May 2006) Luminaires
UL 924	(2006; Rev thru Sep 2009) Standard for Emergency Lighting and Power Equipment
UL 935	(2001; Rev thru Feb 2006) Standard for Fluorescent-Lamp Ballasts

1.2 RELATED REQUIREMENTS

Materials not considered to be lighting equipment or lighting fixture accessories are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Lighting fixtures and accessories mounted on exterior surfaces of buildings are specified in this section.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. Average life is the time after which 50 percent will have failed and 50 percent will have survived under normal conditions.

c. Total harmonic distortion (THD) is the root mean square (RMS) of all the harmonic components divided by the total fundamental current.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Data, drawings, and reports shall employ the terminology, classifications, and methods prescribed by the IESNA HB-9, as applicable, for the lighting system specified.

SD-03 Product Data

Fluorescent lighting fixtures; G,

Fluorescent electronic ballasts; G,

Fluorescent electromagnetic ballasts; G,

Fluorescent lamps; G,

Incandescent lighting fixtures; G,

Incandescent lamps; G,

Exit signs; G,

Emergency lighting equipment; G,

Environmental Data

Energy Efficiency

SD-04 Samples

Lighting fixtures, complete with lamps and ballasts; G,

SD-06 Test Reports

Operating test

Submit test results as stated in paragraph entitled "Field Quality Control."

SD-10 Operation and Maintenance Data

Lighting Control System, Data Package 5; G,

Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein, showing all light fixtures, schematic diagrams and all interconnecting control wire, conduit, and associated hardware.

Operational Service

Submit documentation that includes contact information, summary of procedures, and the limitations and conditions applicable to the

project. Indicate manufacturer's commitment to reclaim materials for recycling and/or reuse.

1.5 QUALITY ASSURANCE

1.5.1 Fluorescent Electronic Ballasts

Submit ballast catalog data as required in the paragraph entitled "Fluorescent Lamp Electronic Ballasts" contained herein. As an option, submit the fluorescent fixture manufacturer's electronic ballast specification information in lieu of the actual ballast manufacturer's catalog data. This information shall include published specifications and sketches, which covers the information required by the paragraph entitled "Fluorescent Lamp Electronic Ballasts" herein. This information may be supplemented by catalog data if required, and shall contain a list of vendors with vendor part numbers.

1.5.2 Lighting Fixtures, Complete With Lamps and Ballasts

Submit one sample of each fixture type for inspection, review, and approval. The sample shall be retained for comparison against the remainder of the fixtures. The sample may be used in the final fixture installation.

1.5.3 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.5.4 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.4.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.4.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site

shall not be used, unless specified otherwise.

1.5.4.3 Energy Efficiency

Comply with National Energy Policy Act and Energy Star requirements for lighting products. Submit data indicating lumens per watt efficiency and color rendition index of light source.

1.6 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.6.1 Electronic Ballast Warranty

Furnish the electronic ballast manufacturer's warranty. The warranty period shall not be less than 5 years from the date of manufacture of the electronic ballast. Ballast assembly in the lighting fixture, transportation, and on-site storage shall not exceed 12 months, thereby permitting 4 years of the ballast 5 year warranty to be in service and energized. The warranty shall state that the malfunctioning ballast shall be exchanged by the manufacturer and promptly shipped to the using Government facility. The replacement ballast shall be identical to, or an improvement upon, the original design of the malfunctioning ballast.

1.7 OPERATIONAL SERVICE

Coordinate with manufacturer for maintenance agreement. Collect information from the manufacturer about maintenance agreement options, and submit to Contracting Officer. Services shall reclaim materials for recycling and/or reuse. Services shall not landfill or burn reclaimed materials. Indicate procedures for compliance with regulations governing disposal of mercury. When such a service is not available, local recyclers shall be sought after to reclaim the materials.

PART 2 PRODUCTS

2.1 FLUORESCENT LIGHTING FIXTURES

UL 1598. Fluorescent fixtures shall have electronic ballasts.

2.1.1 Fluorescent Lamp Electronic Ballasts

The electronic ballast shall as a minimum meet the following characteristics:

a. Ballast shall comply with UL 935, NEMA C82.11, NFPA 70, and CEC Title 24 unless specified otherwise. Ballast shall be 100% electronic high frequency type with no magnetic core and coil components. Ballast shall provide transient immunity as recommended by IEEE C62.41. Ballast shall be designed for the wattage of the lamps used in the indicated application. Ballasts shall be designed to operate on the voltage system to which they are connected.

b. Power factor shall be 0.95 (minimum).

c. Ballast shall operate at a frequency of 20,000 Hertz (minimum).

Ballast shall be compatible with and not cause interference with the operation of occupancy sensors or other infrared control systems. Provide ballasts operating at or above 40,000 Hertz where available.

d. Ballast shall have light regulation of plus or minus 10 percent lumen output with a plus or minus 10 percent input voltage regulation. Ballast shall have 10 percent flicker (maximum) using any compatible lamp.

e. Ballast factor shall be between 0.85 (minimum) and 1.00 (maximum). Current crest factor shall be 1.7 (maximum).

f. Ballast shall be UL listed Class P with a sound rating of "A."

g. Ballast shall have circuit diagrams and lamp connections displayed on the ballast.

h. Ballasts shall be instant start unless otherwise indicated. Instant start ballasts shall operate lamps in a parallel circuit configuration that permits the operation of remaining lamps if one or more lamps fail or are removed.

i. Ballasts for compact fluorescent fixtures shall be programmed start.

j. Ballasts for T-5 and smaller lamps shall have end-of-life protection circuits as required by NEMA C78.81 and NEMA C78.901 as applicable.

k. Ballast shall be capable of starting and maintaining operation at a minimum of -17 degrees C unless otherwise indicated.

l. Electronic ballast shall have a full replacement warranty of 5 years from date of manufacture as specified in paragraph entitled "Electronic Ballast Warranty" herein.

2.1.1.1 T-8 Lamp Ballast

a. Total harmonic distortion (THD): Shall be 20 percent (maximum).

b. Input wattage.

1. 32 watts (maximum) when operating one F32T8 lamp

2. 62 watts (maximum) when operating two F32T8 lamps

c. Ballast efficacy factor.

1. 2.54 (minimum) when operating one F32T8 lamp

2. 1.44 (minimum) when operating two F32T8 lamps

d. A single ballast may be used to serve multiple fixtures if they are continuously mounted and factory manufactured for that installation with an integral wireway.

2.1.2 Fluorescent Lamp Electronic Dimming Ballast

2.1.2.1 T-8 Lamp Ballast

Input wattage, for indicated lamp quantity shall be:

a. 35 watts (maximum) when operating one F32T8 lamp.

b. 70 watts (maximum) when operating two F32T8 lamps.

c. 104 watts (maximum) when operating three F32T8 lamps.

2.1.3 Fluorescent Electromagnetic Ballasts

2.1.3.1 Electromagnetic Energy-Saving Ballasts

NEMA C82.1. Provide energy-saving fluorescent ballasts of the CBM certified full light output type except where fixtures are provided with low temperature ballasts. Ballasts shall have an average input wattage of 40 or less when operating one 32-watt F32T8 lamp or 72 or less when operating two 32 watt F32T8 lamps tested in accordance with NEMA C82.2 methods.

2.1.3.2 Electromagnetic Low Temperature Ballasts

Provide fluorescent ballasts having a minimum starting temperature of minus 28 degrees C in rooms, outdoors, in unheated buildings, and as indicated.

2.1.4 Fluorescent Lamps

a. T-8 rapid start low mercury lamps shall be rated 32 watts (maximum), 2800 initial lumens (minimum), CRI of 75 (minimum), color temperature of 3500 K, and an average rated life of 20,000 hours. Low mercury lamps shall have passed the EPA Toxicity Characteristic Leachate Procedure (TCLP) for mercury by using the lamp sample preparation procedure described in NEMA LL 1.

Average rated life is based on 3 hours operating per start.

2.2 INCANDESCENT LIGHTING FIXTURES

Use of incandescent lamps and fixtures is prohibited, unless specifically indicated otherwise. UL 1598.

2.2.1 Incandescent Lamps

Provide the number, type, and wattage indicated.

2.3 SWITCHES

2.3.1 Toggle Switches

Provide toggle switches as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.4 EXIT SIGNS

UL 924, NFPA 70, and NFPA 101. Exit signs shall be self-powered type. Exit signs shall use no more than 5 watts.

2.4.1 Self-Powered LED Type Exit Signs (Battery Backup)

Provide with automatic power failure device, integral self-testing module and fully automatic high/low trickle charger in a self-contained power

pack. Battery shall be sealed electrolyte type, shall operate unattended, and require no maintenance, including no additional water, for a period of not less than 5 years. LED exit sign shall have emergency run time of 1 1/2 hours (minimum). The light emitting diodes shall have rated lamp life of 70,000 hours (minimum).

2.5 EMERGENCY LIGHTING EQUIPMENT

UL 924, NFPA 70, and NFPA 101. Provide lamps in wattage indicated. Provide accessories required for remote-mounted lamps where indicated. Remote-mounted lamps shall be as indicated.

2.5.1 Fluorescent Emergency System

Each system shall consist of an automatic power failure device, test switch operable from outside of the fixture, pilot light visible from outside the fixture, and fully automatic solid-state charger in a self-contained power pack. Provide self-testing module integral to the fixture. Charger shall be either trickle, float, constant current or constant potential type, or a combination of these. Battery shall be sealed electrolyte type with capacity as required to supply power to the number of lamps shown for each system for 90 minutes at a minimum of 1100 lumens per lamp output. Battery shall operate unattended and require no maintenance, including no additional water, for a period of not less than 5 years. Emergency ballasts provided with fixtures containing solid-state ballasts shall be fully compatible with the solid-state ballasts. Furnish spare emergency ballast based on 10 percent of the number of emergency ballast provided for the project.

2.6 SELF-TESTING MODULE

Self-testing module for exit signs and emergency lighting equipment shall perform the following functions:

a. Continuous monitoring of charger operation and battery voltage with visual indication of normal operation and of malfunction.

b. Monthly discharge cycling of battery with monitoring of transfer circuit function, battery capacity and emergency lamp operation with visual indication of malfunction. The battery capacity test may be conducted by using a synthetic load.

c. Manual test switch to simulate a discharge test cycle.

d. Module shall have low voltage battery disconnect (LVD) and brown-out protection circuit.

2.7 SUPPORT HANGERS FOR LIGHTING FIXTURES IN SUSPENDED CEILINGS

2.7.1 Wires

ASTM A 641/A 641M, galvanized regular coating, soft temper, 2.68 mm in diameter.

2.7.2 Wires, for Humid Spaces

ASTM A 580/A 580M, composition 302 or 304, annealed stainless steel 2.68 mm in diameter.

ASTM B 164, UNS NO4400, annealed nickel-copper alloy 2.68 mm in diameter.

2.8 EQUIPMENT IDENTIFICATION

2.8.1 Manufacturer's Nameplate

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.8.2 Labels

Provide labeled luminaires in accordance with UL 1598 requirements. All luminaires shall be clearly marked for operation of specific lamps and ballasts according to proper lamp type. The following lamp characteristics shall be noted in the format "Use Only _____":

a. Lamp diameter code (T-8), tube configuration, base type, and nominal wattage for fluorescent and compact fluorescent luminaires.

b. Lamp type, wattage, bulb type (ED17, BD56, etc.) and coating (clear or coated) for HID luminaires.

c. Start type (rapid start) for fluorescent and compact fluorescent luminaires.

d. ANSI ballast type (M98, M57, etc.) for HID luminaires.

e. Correlated color temperature (CCT) and color rendering index (CRI) for all luminaires.

All markings related to lamp type shall be clear and located to be readily visible to service personnel, but unseen from normal viewing angles when lamps are in place. Ballasts shall have clear markings indicating multi-level outputs and indicate proper terminals for the various outputs.

2.9 FACTORY APPLIED FINISH

Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA 250 corrosion-resistance test.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations shall conform to IEEE C2, NFPA 70, and to the requirements specified herein.

3.1.1 Lamps

Lamps of the type, wattage, and voltage rating indicated shall be delivered to the project in the original cartons and installed just prior to project completion. Lamps installed and used for working light during construction shall be replaced prior to turnover to the Government if more than 15 percent of their rated life has been used. Lamps shall be tested for proper operation prior to turn-over and shall be replaced if necessary with new lamps from the original manufacturer. Provide 10 percent spare lamps

of each type from the original manufacturer.

3.1.2 Lighting Fixtures

Set lighting fixtures plumb, square, and level with ceiling and walls, in alignment with adjacent lighting fixtures, and secure in accordance with manufacturers' directions and approved drawings. Installation shall meet requirements of NFPA 70. Mounting heights specified or indicated shall be to the bottom of fixture for ceiling-mounted fixtures and to center of fixture for wall-mounted fixtures. Obtain approval of the exact mounting for lighting fixtures on the job before commencing installation and, where applicable, after coordinating with the type, style, and pattern of the ceiling being installed. Recessed and semi-recessed fixtures shall be independently supported from the building structure by a minimum of four wires per fixture and located near each corner of each fixture. Ceiling grid clips are not allowed as an alternative to independently supported light fixtures. Round fixtures or fixtures smaller in size than the ceiling grid shall be independently supported from the building structure by a minimum of four wires per fixture spaced approximately equidistant around the fixture. Do not support fixtures by ceiling acoustical panels. Where fixtures of sizes less than the ceiling grid are indicated to be centered in the acoustical panel, support such fixtures independently and provide at least two 19 mm metal channels spanning, and secured to, the ceiling tees for centering and aligning the fixture. Provide wires for lighting fixture support in this section.

3.1.3 Suspended Fixtures

Suspended fixtures shall be provided with 0.79 rad swivel hangers so that they hang plumb and shall be located with no obstructions within the 0.79 rad range in all directions. The stem, canopy and fixture shall be capable of 0.79 rad swing. Pendants, rods, or chains 1.2 meters or longer excluding fixture shall be braced to prevent swaying using three cables at 2.09 rad separation. Suspended fixtures in continuous rows shall have internal wireway systems for end to end wiring and shall be properly aligned to provide a straight and continuous row without bends, gaps, light leaks or filler pieces. Aligning splines shall be used on extruded aluminum fixtures to assure hairline joints. Steel fixtures shall be supported to prevent "oil-canning" effects. Fixture finishes shall be free of scratches, nicks, dents, and warps, and shall match the color and gloss specified. Pendants shall be finished to match fixtures. Aircraft cable shall be stainless steel. Canopies shall be finished to match the ceiling and shall be low profile unless otherwise shown. Maximum distance between suspension points shall be 3.1 meters or as recommended by the manufacturer, whichever is less.

3.1.4 Exit Signs and Emergency Lighting Units

Wire exit signs and emergency lighting units ahead of the switch to the normal lighting circuit located in the same room or area.

3.2 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

-- End of Section --

SECTION 26 52 00.00 40

EMERGENCY LIGHTING
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2008; Amendment 2009) Life Safety Code
NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 924	(2006; Rev thru Sep 2009) Standard for Emergency Lighting and Power Equipment

1.2 GENERAL REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to work specified in this section.

Submit Material, Equipment, and Fixture Lists showing manufacturer's style or catalog numbers, specification and drawing reference numbers, warranty information, and fabrication site.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submit Material, Equipment, and Fixture Lists in accordance with paragraph entitled, "General Requirements," of this section.

SD-02 Shop Drawings

Submit installation drawings for the Central Emergency Lighting Systems indicating location of installed fixture.

SD-03 Product Data

Submit the manufacturer's catalog data for the following items:

Emergency Lighting Egress Units

Emergency Fluorescent Lighting
Accessories

SD-06 Test Reports

Submit test reports showing results of System Operational Tests for emergency lighting systems.

SD-07 Certificates

Submit certificates for the following showing conformance with the referenced standards contained in this section.

Emergency Lighting Egress Units
Emergency Fluorescent Lighting
Accessories

PART 2 PRODUCTS

2.1 PRODUCT STANDARDS

Provide emergency lighting units conforming to UL 924 and NFPA 101.

Furnish emergency lighting units completely assembled with wiring and mounting devices, ready for installation at the locations indicated. Equip fixtures with lamps.

2.2 EMERGENCY LIGHTING EGRESS UNITS

Provide complete self-contained emergency lighting units with batteries, battery charger, one or more local or remote lamp heads with lamps, under-voltage relay, indicator lights, on/off switch, and test switch, in accordance with UL 924 for Type I (emergency light set), Class I (rechargeable storage-battery-powered unit), Style D (nonrefillable nickel-cadmium battery), as indicated.

Provide batteries rated not less than 6-12 volts.

Include in battery charger a dry-type full-wave rectifier with two charging rates, one to automatically maintain the battery in a fully charged state under normal conditions and the other to automatically recharge the battery to a fully charged state within 12 hours after continuous discharge of 1-1/2 hours through the connected lampload.

Provide batteries with the capacity and rating to supply the lamp load with maintained 87.5 -percent power, minimum, for 1.5 hours, or the battery-lamp combination maintaining 60 -percent, minimum, illumination. Provide maintenance-free lead acid type batteries, with a minimum normal life of 10 years.

Fabricate the unit enclosure from sheet steel not less than 1.3 mm. Design of cover is to provide access to the battery and battery-charger compartments and have a full-length piano hinge and a latching device. Protect component parts within the enclosure from dust, moisture, and oxidizing fumes from the battery. Coat interior and exterior surfaces of enclosure with a corrosion-resistant gray baked-enamel finish.

Mount the lampheads on the top of the unit enclosure, or wall mount, except where otherwise indicated and fully adjustable in the horizontal and

vertical planes. Provide steel lamp head assembly with chromium plating. Form the exterior housing of the lamp from cadmium-plated sheet steel.

Provide sealed-beam type lamps, PAR-36, rated not less than 12 watts at the specified dc voltage.

Mount an amber "ready-for-use on alternating current" indicating light, a red "recharging on alternating current" indicating light, and a momentary-contact pushbutton test switch on the cover of the unit enclosure. The amber light indicates, when illuminated, that the unit is electrically connected to the normal ac supply source and that the battery is fully charged. The red light indicates, when illuminated, that the battery is being recharged. The momentary-contact pushbutton test switch transfers the unit from normal supply to battery supply and tests operation of equipment under simulated ac source power failure.

Provide an under-voltage relay of the self-clearing type which automatically connects the lampload to the battery supply upon failure of the alternating current supply. Mount an on-off toggle switch inside the unit enclosure to disconnect the battery from the lampload when the unit is taken out of service for maintenance purposes. The relay energizes when the ac supply falls to 70 percent of normal voltage.

Provide emergency lighting units with angle iron mounting shelves and with a protective screen designed by the equipment manufacturer for this purpose. Coat the mounting shelf and screen with a corrosion-resistant finish in accordance with manufacturer's standard practice.

Provide emergency lighting units suitable for operation on the ac supply circuit to which they are to be electrically connected.

2.3 SELF-TESTING MODULE

Provide self-testing module for exit signs and emergency lighting equipment which performs the following functions:

a. Continuous monitoring of charger operation and battery voltage with visual indication of normal operation and of malfunction.

b. Monthly discharge cycling of battery with monitoring of transfer circuit function, battery capacity and emergency lamp operation with visual indication of malfunction. Conduct the battery capacity test using a synthetic load.

c. Manual test switch to simulate a discharge test cycle.

d. Provide module with low voltage battery disconnect (LVD) and brown-out protection circuit.

PART 3 EXECUTION

3.1 INSTALLATION

Permanently fix in place the emergency lighting unit and install wiring for each unit in accordance with NFPA 70. Use the same panel bus or branch circuit as that serving the normal lighting in the area for the branch circuit feeding the unit equipment, and connect ahead of area switches. Keep remotely connected emergency lighting circuit wiring independent of all other wiring and equipment and do not enter the same conduit, cable,

box, or cabinet with other wiring unless the fixture is supplied from two sources.

Mount emergency lighting units and remote lamps at a minimum of 2100 millimeter above the finished floor.

3.2 FIELD TESTING

Demonstrate emergency lighting units to operate satisfactorily in the presence of the Contracting Officer.

Perform System Operational Tests in accordance with referenced standards in this section.

-- End of Section --

SECTION 26 53 00.00 40

EXIT SIGNS
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101 (2008; Amendment 2009) Life Safety Code

U.S. DEPARTMENT OF ENERGY (DOE)

DOE LT-4 (2000) How to Buy Energy-Efficient Exit Signs

UNDERWRITERS LABORATORIES (UL)

UL 924 (2006; Rev thru Sep 2009) Standard for Emergency Lighting and Power Equipment

1.2 GENERAL REQUIREMENTS

Section 26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS applies to work specified in this section.

Material, Equipment, and Fixture Lists shall be submitted for the following showing manufacturer's style or catalog numbers, specification and drawing reference numbers, warranty information, and fabrication site.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Material, Equipment, and Fixture Lists shall be submitted for the following in accordance with paragraph entitled, "General Requirements," of this section.

Exit Lighting Units
Accessories

SD-02 Shop Drawings

Installation drawings shall be submitted for Exit Lighting Units in accordance with the paragraph entitled, "Installation," of this

section.

Outline drawings shall be submitted for Exit Lighting Units indicating overall physical features, dimensions, ratings, service requirements, and weights of equipment.

SD-03 Product Data

Manufacturer's catalog data shall be submitted for the following items:

Exit Lighting Units
Accessories

SD-06 Test Reports

Test reports shall be submitted showing results of Operational Tests of exit lighting systems.

SD-07 Certificates

Certificates shall be submitted showing compliance with the following requirements.

Efficiencies

PART 2 PRODUCTS

2.1 PRODUCT STANDARDS

Emergency exit lighting fixtures shall conform to UL 924, NFPA 101, and as specified.

Exit lighting fixtures shall be furnished completely assembled with wiring and mounting devices and ready for installation at the locations indicated. Ceiling-mounted fixtures shall be designed to be supported independent of the ceiling. Fixtures shall be equipped with lamps.

2.1.1 Efficiencies

Exit lighting fixtures shall have efficiencies in accordance with the recommended levels specified in DOE LT-4.

2.2 CONTEMPORARY FIXTURES

Contemporary exit lighting fixture shall have a fixture body with edge-lighted plastic exit-sign panels, face trims, lamps, lampholders, and mounting brackets for top, back, and end mounting to walls and ceilings in accordance with NFPA 101, as indicated.

Fixtures shall be single face with thin wedge-shaped vertical cross sections. Top edge of double-face fixtures shall be not more than 70 millimeter thick. Top edge of single-face fixtures shall be not more than 50 millimeter thick. Bottom edge of double-face fixtures shall be not more than 45 millimeter thick. Bottom edge of single-face fixtures shall be not more than 32 millimeter thick.

Plastic sign panels shall be acrylic with green translucent letters and directional arrows, as required. Letters shall be 150 millimeter high with

stroke not less than 30 millimeter wide.

Wireway cover and plastic sign backup plate shall be anodized sheet aluminum with a matte finish. Face trims shall be formed from sheet aluminum and shall have a brushed-satin finish. Fixture bodies formed from sheet steel shall be not less than 1 millimeter and painted.

Plastic sign panels shall be edge-lighted from the top with at least two low-voltage miniature incandescent lamps that will illuminate the plastic sign panels and floor. Exit signs shall be wired for two-circuit service at 220-volts and shall include a diode circuit that will provide a minimum of 50,000 hours of lamp life.

Mounting plates and brackets formed from sheet aluminum or plate shall have a brushed-satin finish. Mounting plates shall be not less than 115 millimeter square and designed to secure the fixture to a 100 millimeter square outlet box.

2.3 EMERGENCY POWER LOSS EXIT LIGHTING UNITS

Each self-contained unit shall have an automatic power failure device, test switch, pilot light, and fully automatic high/low solid-state trickle charger in a self-contained power pack. Battery shall be the gelled-electrolyte type and shall be maintenance-free for a period of not less than 10 -years under normal operating conditions. Normal operation shall be with 220-volts.

2.4 LIGHT EMITTING DIODES (LEDs) EXIT LIGHTING FIXTURES

Exit lighting fixtures shall include sheetmetal enclosures with frames, battery charger, batteries, red light emitting diodes (LEDs) and mounting brackets. Fixtures shall be single faced. Mounting plates shall be suitable for securing the fixture to a 100 millimeter outlet box. Fixture features shall include continuous charging, automatic switching to standby batteries upon loss of power, overload protection, short circuit protection, test switch, low voltage disconnect, switch controlled left and right LED directional arrows, and shall be field connectable to operate from 220 volts. Minimum operating time of the battery system shall be three (3) hours for double faced fixtures and seven (7) hours for single faced fixtures. Brightness shall not be less than ten (10) candela. All components shall have a five year warranty.

2.5 SELF LUMINOUS EXIT SIGNS

2.5.1 Enclosure

The assembled tamperproof enclosure shall be of 3 millimeter high impact ABS plastic, framed with 1.3 millimeter thick extruded aluminum.

Each sign shall bear a permanently attached plastic nameplate bearing the Manufacturer's Name and Address and Date of Manufacture (in addition to information required by listed authorities.

2.5.2 Face

Each face of the sign shall be a non-colored translucent panel covered by an opaque 3 millimeter red ABS plastic stencil bearing the word "EXIT" in 150 by 20 millimeter letters and including a universal directional arrow which indicates the direction of the exit (left, right or both ways).

2.5.3 Mounting Accessories

Each sign shall be supplied with tamperproof hardware for wall mounting. Edge on for double face, flat for single face or double face for ceiling mount.

PART 3 EXECUTION

3.1 INSTALLATION

Fixtures shall be connected to the main panel bus through overcurrent protection. Emergency lighting panel shall be used where available.

3.2 FIELD TESTING

Exit lighting shall be demonstrated to operate satisfactorily in the presence of the Contracting Officer.

Operational Tests shall be performed in accordance with referenced standards in this section.

-- End of Section --

SECTION 26 56 00

EXTERIOR LIGHTING
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO LTS-4	(2006) Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C136.21	(2004) Roadway Lighting Equipment - Vertical Tenons Used with Post-Top-Mounted Luminaires

ASTM INTERNATIONAL (ASTM)

ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA)

IESNA HB-9	(2000; Errata 2004; Errata 2005) IES Lighting Handbook

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C136.10	(1996) American National Standard for Roadway Lighting Equipment-Locking-Type Photocontrol Devices and Mating Receptacles - Physical and Electrical Interchangeability and Testing
IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA C136.13	(2004; R 2009) Roadway Lighting Equipment, Metal Brackets for Wood Poles

NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA C78.1381	(1998) Electric Lamps - 250-Watt, 70 Watt, M85 Metal-Halide Lamps
NEMA C136.3	(2005) Roadway and Area Lighting Equipment Luminaire Attachments
NEMA C78.43	(2005) Standard for Electric Lamps - Single-Ended Metal-Halide Lamps
NEMA C82.4	(2002) Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 1029	(1994; Rev thru Feb 2006) Standard for Safety High-Intensity-Discharge Lamp Ballasts
UL 1598	(2004; Rev thru May 2006) Luminaires
UL 773	(1995; Rev thru Mar 2002) Standard for Plug-In Locking Type Photocontrols for Use with Area Lighting
UL 773A	(2006) Nonindustrial Photoelectric Switches for Lighting Control

1.2 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. Average life is the time after which 50 percent will have failed and 50 percent will have survived under normal conditions.

c. Groundline section is that portion between 305 mm above and 610 mm below the groundline.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Luminaire drawings

Poles

SD-03 Product Data

Environmental Data

Energy Efficiency

Luminaires; G,

Lamps; G,

Ballasts; G,

Lighting contactor; G,

Time switch; G,

Photocell switch; G,

Wooden poles; G,

Brackets

SD-04 Samples

Luminaires; G,

Submit one sample of each luminaire type, complete with lamp and ballast. Sample will be returned to the Contractor for installation in the project work.

SD-05 Design Data

Design Data for luminaires; G,

1.4 QUALITY ASSURANCE

1.4.1 Drawing Requirements

1.4.1.1 Luminaire Drawings

Include dimensions, effective projected area (EPA), accessories, and installation and construction details. Photometric data, including zonal lumen data, average and minimum ratio, aiming diagram, and computerized candlepower distribution data shall accompany shop drawings.

1.4.1.2 Poles

Include dimensions, wind load determined in accordance with AASHTO LTS-4, pole deflection, pole class, and other applicable information.

1.4.2 Design Data for Luminaires

a. Distribution data according to IESNA classification type as defined in IESNA HB-9.

b. Computerized horizontal illumination levels in lux at ground level, taken every 3050 mm. Include average maintained lux level and maximum and minimum ratio.

c. Amount of shielding on luminaires.

1.4.3 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.4.4 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.4.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.4.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site shall not be used, unless specified otherwise.

1.5 DELIVERY, STORAGE, AND HANDLING

1.6 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.7 OPERATIONAL SERVICE

Coordinate with manufacturer for maintenance agreement. Collect information from the manufacturer about maintenance agreement options, and submit to Contracting Officer. Services shall reclaim materials for recycling and/or reuse. Services shall not landfill or burn reclaimed materials. Indicate procedures for compliance with regulations governing

disposal of mercury. When such a service is not available, local recyclers shall be sought after to reclaim the materials.

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

Products and materials not considered to be lighting equipment or lighting fixture accessories are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Lighting fixtures and accessories mounted on exterior surfaces of buildings are specified in Section 26 51 00 INTERIOR LIGHTING.

2.2 LUMINAIRES

UL 1598. Provide luminaires as indicated. Provide luminaires complete with lamps of number, type, and wattage indicated. Details, shapes, and dimensions are indicative of the general type desired, but are not intended to restrict selection to luminaires of a particular manufacturer. Luminaires of similar designs, light distribution and brightness characteristics, and of equal finish and quality will be acceptable as approved.

2.2.1 Lamps

2.2.1.1 Metal-Halide Lamps

Provide luminaires with tempered glass lens.

a. Double-ended, 70 watt, conforming to NEMA C78.1381

b. Single-ended, wattage as indicated, conforming to NEMA C78.43

Lamps shall have Luminaire Efficiency Ratings (LER) as follows:

a. Upward efficiency of 0%

    1. 150-399 watts: minimum 41 LER for closed fixture

b. Upward efficiency of 1%-10%

    1. 150-399 watts: minimum 56 LER for closed fixture

c. Upward efficiency greater than 20%

    1. 150-399 watts: minimum 62 LER for closed fixture; minimum 77 for open fixture

2.2.2 Ballasts for High-Intensity-Discharge (HID) Luminaires

UL 1029 and NEMA C82.4, and shall be constant wattage autotransformer (CWA) or regulator, high power-factor type (minimum 90%). Provide single-lamp ballasts which shall have a minimum starting temperature of minus 30 degrees C. Ballasts shall be:

a. Designed to operate on voltage system to which they are connected.

b. Constructed so that open circuit operation will not reduce the average life.

HID ballasts shall have a solid-state igniter/starter with an average life in the pulsing mode of 10,000 hours at the intended ambient temperature. Igniter case temperature shall not exceed 90 degrees C.

2.3 PHOTOCELL SWITCH

UL 773 or UL 773A, hermetically sealed cadmium-sulfide or silicon diode type cell rated 220 volts ac, 50 Hz with single-throw contacts designed to fail to the ON position. Switch shall turn on at or below 32 lux and off at 43 to 107 lux. A time delay shall prevent accidental switching from transient light sources.

a. In a high-impact-resistant, noncorroding and nonconductive molded plastic housing with a fixture mounted, locking-type receptacle conforming to IEEE C136.10 and rated 1800 VA, minimum.

b. In a cast weatherproof aluminum housing with adjustable window slide, rated 1800 VA, minimum.

c. In a U.V. stabilized polycarbonate housing with swivel arm and adjustable window slide, rated 1800 VA, minimum.

d. Integral to the luminaire, rated 1000 VA, minimum.

2.4 POLES

Provide poles designed for wind loading of 161 km/hr determined in accordance with AASHTO LTS-4 while supporting luminaires and all other appurtenances indicated. The effective projected areas of luminaires and appurtenances used in calculations shall be specific for the actual products provided on each pole. Poles shall be anchor-base type designed for use with underground supply conductors.Poles shall have oval-shaped handhole having a minimum clear opening of 65 by 130 mm. Handhole cover shall be secured by stainless steel captive screws. Metal poles shall have an internal grounding connection accessible from the handhole near the bottom of each pole. Scratched, stained, chipped, or dented poles shall not be installed.

2.5 BRACKETS AND SUPPORTS

NEMA C136.3, NEMA C136.13, and ANSI C136.21, as applicable. Pole brackets shall be not less than 31.75 mm aluminum secured to pole. Slip-fitter or pipe-threaded brackets may be used, but brackets shall be coordinated to luminaires provided, and brackets for use with one type of luminaire shall be identical. Brackets for pole-mounted street lights shall correctly position luminaire no lower than mounting height indicated. Mount brackets not less than 7320 mm above street. Special mountings or brackets shall be as indicated and shall be of metal which will not promote galvanic reaction with luminaire head.

2.6 POLE FOUNDATIONS

Anchor bolts shall be steel rod having a minimum yield strength of 344.5 MPa (50,000 psi); the top 305 mm of the rod shall be galvanized in accordance with ASTM A 153/A 153M. Concrete shall be as specified in Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

2.7 EQUIPMENT IDENTIFICATION

2.7.1 Manufacturer's Nameplate

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.7.2 Labels

Provide labeled luminaires in accordance with UL 1598 requirements. Luminaires shall be clearly marked for operation of specific lamps and ballasts according to proper lamp type. The following lamp characteristics shall be noted in the format "Use Only _____":

a. Lamp diameter code (T-8), tube configuration, base type, and nominal wattage for fluorescent and compact fluorescent luminaires.

b. Lamp type, wattage, bulb type (ED17, BD56, etc.) and coating (clear or coated) for HID luminaires.

c. Start type (rapid start) for fluorescent and luminaires.

d. ANSI ballast type (M98, M57, etc.) for HID luminaires.

e. Correlated color temperature (CCT) and color rendering index (CRI) for all luminaires.

Markings related to lamp type shall be clear and located to be readily visible to service personnel, but unseen from normal viewing angles when lamps are in place. Ballasts shall have clear markings indicating multi-level outputs and indicate proper terminals for the various outputs.

2.8 FACTORY APPLIED FINISH

Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA 250 corrosion-resistance test.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations shall conform to IEEE C2, NFPA 70, and to the requirements specified herein.

3.1.1 Photocell Switch Aiming

Aim switch according to manufacturer's recommendations. Mount switch on or beside each luminaire when switch is provided in cast weatherproof aluminum housing with swivel arm.

3.1.2 Grounding

Ground noncurrent-carrying parts of equipment including metal poles, luminaires, mounting arms, brackets, and metallic enclosures as specified in Section 33 71 02.00 20 UNDERGROUND ELECTRICAL DISTRIBUTION. Where copper grounding conductor is connected to a metal other than copper,

provide specially treated or lined connectors suitable for this purpose.

3.1.3 Field Applied Painting

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

-- End of Section --

SECTION 27 51 16

PUBLIC ADDRESS SYSTEM
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

Detail drawings as specified.

SD-03 Product Data

Spare Parts

Spare parts data for each different item of material and equipment specified.

SD-06 Test Reports

Approved Test Procedures

Test plan and test procedures for the acceptance tests. The test plan and test procedures shall explain in detail, step-by-step actions and expected results to demonstrate compliance with the requirements specified. The procedure shall also explain methods for simulating the necessary conditions of operation to demonstrate system performance.

Acceptance Tests

Test reports in booklet form showing all field tests performed to adjust each component and to prove compliance with the specified performance criteria, upon completion and testing of the installed system. The reports shall include the manufacturer, model number, and serial number of test equipment used in each test. Each

report shall indicate the final position of controls and operating mode of the system.

SD-07 Certificates

Components

Copies of current approvals or listings issued by UL, or other nationally recognized testing laboratory for all components.

1.3 SYSTEM DESCRIPTION

The public address system shall consist of an exterior cluster mounted speakers, amplifiers, mixers, microphones, speakers, cabling, and ancillary components required to meet the required system configuration and operation.

1.3.1 Detail Drawings

The Contractor shall submit detail drawings consisting of a complete list of equipment and material, including manufacturer's descriptive and technical literature, performance charts and curves, catalog cuts, and installation instructions. Note that the contract drawings show layouts based on typical speakers. The Contractor shall check the layout based on the actual speakers to be installed and make necessary revisions in the detail drawings. Detail drawings shall also contain complete point to point wiring, schematic diagrams and other details required to demonstrate that the system has been coordinated and will properly function as a unit. Drawings shall show proposed layout of equipment and appurtenances, and equipment relationship to other parts of the work including clearances for maintenance and operation.

1.3.2 Spare Parts

The Contractor shall submit spare parts data for each different item of material and equipment specified, after approval of the detail drawings and not later than 2 months prior to the date of beneficial occupancy. The data shall include a complete list of parts and supplies, with current unit prices and source of supply.

1.4 DELIVERY AND STORAGE

Equipment placed in storage until installation shall be stored with protection from the weather, humidity and temperature variations, dirt and dust, and other contaminants.

1.5 VERIFICATION OF DIMENSIONS

The Contractor shall become familiar with the details of the work and working conditions, shall verify dimensions in the field, and shall advise the Contracting Officer of any discrepancies before performing the work.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Material and equipment to be provided shall be the standard products of a manufacturer regularly engaged in the manufacture of such products, and shall essentially duplicate material and equipment that have been in satisfactory use at least 2 years. All components used in the system shall

be commercial designs that comply with the requirements specified.

2.1.1 Identical Items

Items of the same classification shall be identical. This requirement includes equipment, modules, assemblies, parts, and components.

2.1.2 Nameplates

Each major component of equipment shall have the manufacturer's name, address, model and catalog number, and serial number on a plate secured to the equipment.

2.2 MIXER-PREAMPLIFIER

Mixer-preamplifier shall as a minimum conform to the following specifications:

Rated Output:	18 dB
Frequency Response:	Plus or Minus 1 dB, 20 - 20,000 Hz
Distortion:	Less than 0.5 percent, 20 - 20,000 Hz
Signal to noise:	Output Volumn Min 90 dB Output Volumn Max 61 dB
Inputs:	5 independent balanced low- impedance transformer-isolated
Input Sensitivity:	Microphone - 58 dB
Input Channel Isolation:	1,2:0 BV, 600 ohm
Tone Controls:	Plus or Minus 12 dB range at 50 and 15,000 Hz
Power Requirement:	220 Vac 50 Hz

2.3 POWER AMPLIFIERS

Power amplifiers as a minimum conform to the following specifications:

Rated power output:	250 watts RMS
Frequency Response:	Plus or Minus 3 dB, 20-20,000 Hz
Distortion:	Less than 1 percent at RPO, 600-13,000 Hz
Input Impedance:	50 k ohm unbalanced
Output Impedance:	Balanced 8 ohms
Output voltage:	25 and 70.7 volts
Power Requirement:	220 Vac 50 Hz

2.4 MICROPHONE INPUT MODULES

Microphone input modules shall as a minimum conform to the following specifications:

Rated Outputs:	0.25 volts into 10,000 ohms 1.0 volts into 10,000 ohms
Frequency Response:	Plus or Minus 2 dB, 20 - 20,000 Hz
Distortion:	Less than 0.5 percent 20 - 20,000 Hz
Inputs:	4 transformer - coupled balanced 150 ohm
Input Sensitivity:	0.003 volts
Input Channel Isolation:	70 dB minimum

2.5 MICROPHONES

2.5.1 Desk Microphone

Microphones shall as a minimum conform to the following specifications:

Element:	Dynamic
Pattern:	Cardioid
Frequency Response:	50 - 12,000 Hz
Impedance:	Low impedance mic (150-400 ohms)
Front-to-back Ratio:	20 dB
Selector switches:	Push to talk bar in base with locking lever

2.5.2 Microphone Jack

Each outlet for microphones shall consist of a standard outlet box, flush-mounted, and fitted with a three-pole, polarized, locking-type, female microphone jack and a corrosion resistant-steel device plate.

2.6 LOUDSPEAKERS

2.6.1 Voice Range Horn System

The horns shall as a minimum conform to the following specifications:

Application:	Outdoor Weatherproof
Frequency Response:	400 - 4700 Hz
Power Taps:	70 volt line - .9, 1.8, 3.8, 7.5, and 15 watts
Impedance:	5000, 2500, 1300, 670, 330, 90, and 45 ohms

Power Rating:	Normal - 75 watts Peak - 120 watts
Dispersion:	50 degrees Horz 40 degrees Vert
Signal Processing	400 Hz high pass filter
Drivers	Ferro fluid-cooled
Input Connection	2.5 MM^2, 2/C, 13M, sjow cable thru gland nut
Enclosure	Fiberglass

2.6.2 Cluster Mounted Speakers

Furnish eight (8) cluster mounted speakers mounted on a pole with stainless steel speaker mounting brackets. See plans for general arrangement of installation. Aim speakers to cover all areas within the compound.

2.7 CABLES

2.7.1 Speaker Cable

Cables shall be of the gauge required depending upon the cable run length. In no case shall cable be used which is smaller than $2.5MM^2$. Insulation on the conductors shall be polyvinyl chloride (PVC) or an equivalent synthetic thermoplastic not less than 0.2 mm. The jacket thickness shall be 0.5 mm minimum.

2.7.2 Microphone Cable

Cable conductor shall be stranded copper $6MM^2$. Insulation on the conductors shall be polyvinyl chloride (PVC) or an equivalent synthetic thermoplastic not less than 0.2 mm. Cable shall be shielded 100% of aluminum polyester foil with a bare $.5MM^2$ stranded soft copper drain conductor. The jacket thickness shall be 0.5 mm minimum.

2.8 TERMINALS

Terminals shall be solderless, tool-crimped pressure type.

2.9 SURGE PROTECTION

2.9.1 SIGNAL SURGE PROTECTION

Major components of the system shall have internal protection circuits which protects the component from mismatched loads, direct current, and shorted output lines. Communication cables/conductors shall have surge protection installed at each point where it exits or enters a building.

2.10 WALL CABINET

Furnish a series 27M wall cabinet for the equipment specified. Cabinet shall be vented and provided with hinged locking door.

PART 3 EXECUTION

3.1 INSTALLATION

Equipment shall be installed as indicated and specified, and in accordance with the manufacturer's recommendations except where otherwise indicated. Equipment mounted out-of-doors or subject to inclement conditions shall be weatherproofed.

3.1.1 Wiring

Wiring shall be installed in rigid steel conduit, intermediate metal conduit, cable trays, or electric metallic tubing as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Wiring for microphone, grounding, line level, speaker and power cables shall be isolated from each other by physical isolation and metallic shielding. Shielding shall be terminated at only one end.

3.2 GROUNDING

All grounding practices shall comply with NFPA 70. Equipment shall be grounded to the serving panelboard ground bus through a green grounding conductor. Metallic conduits serving the equipment shall be isolated on the equipment end with an insulating bushing to prevent noise from being transferred to the circuit. Equipment racks shall be grounded to the panelboard ground bus utilizing a $10MM^2$ conductor. Grounding conductor shall be terminated to the rack using connector suitable for that purpose.

3.3 ACCEPTANCE TESTS

After installation has been completed, the Contractor shall conduct acceptance tests, utilizing the approved test procedures, to demonstrate that equipment operates in accordance with specification requirements. The Contractor shall notify the Contracting Officer 14 days prior to the performance of tests. In no case shall notice be given until after the Contractor has received written Contracting Officer approval of the test plans as specified. The acceptance tests shall include originating and receiving messages at specified stations, at proper volume levels, without cross talk or noise from other links or nondesignated units.

3.4 TRAINING

The Contractor shall conduct a training course for 6 members of the operating and maintenance staff as designated by the Contracting Officer. The training course will be given at the installation during normal working hours for a total of 3 hours and shall start after the system is functionally complete but prior to final acceptance tests. The field instructions shall cover all of the items contained in the approved operating and maintenance manuals, as well as demonstrations of routine maintenance operations. The Contracting Officer shall be notified at least 14 days prior to the start of the training course.

-- End of Section --

SECTION 28 31 64.00 10

FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE
08/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S3.41	(1990; R 2008) Audible Emergency Evacuation Signal (ASA 96)

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41.1	(2002; R 2008) IEEE Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.41.2	(2002) IEEE Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 72	(2010) National Fire Alarm Code
NFPA 90A	(2008; Errata 2009) Standard for the Installation of Air Conditioning and Ventilating Systems

UNDERWRITERS LABORATORIES (UL)

UL 1971	(2002; Rev thru Oct 2008) Signaling Devices for the Hearing Impaired
UL 1242	(2006; Rev thru Jul 2007) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 268	(2009) Standard for Smoke Detectors for Fire Alarm Signaling Systems
UL 268A	(2008; Rev thru Sep 2009) Smoke Detectors for Duct Application
UL 38	(2008; Rev thru Dec 2008) Standard for Signaling Boxes for Fire Alarm Systems

UL 464	(2009) Standard for Audible Signal Appliances
UL 521	(1999; Rev thru Jul 2005) Heat Detectors for Fire Protective Signaling Systems
UL 6	(2007) Standard for Electrical Rigid Metal Conduit-Steel
UL 797	(2007) Standard for Electrical Metallic Tubing -- Steel
UL 864	(2003; Rev thru May 2007) Control Units and Accessories for Fire Alarm Systems

1.2 SYSTEM DESCRIPTION

The fire detection and alarm system and the central reporting system shall be a complete, supervised fire alarm reporting system configured in accordance with NFPA 72; exceptions are acceptable as directed by the Contracting Officer. Furnish equipment compatible and UL listed, FM approved, or approved or listed by a nationally recognized testing laboratory in accordance with the applicable NFPA standards. Locks shall be keyed alike. Provide four keys for the system. Furnish tags with stamped identification number for keys and locks.

1.2.1 Operation

Activate the system into the alarm mode by actuation of any alarm initiating device. The system will remain in the alarm mode until the initiating device is reset and the fire alarm control panel is reset and restored to normal. Alarm and supervisory initiating devices shall be individually addressable. Alarm initiating devices shall be connected to initiating device circuits (IDC), Style D, to signal line circuits (SLC), Style 6, in accordance with NFPA 72. Connect alarm notification appliances to notification appliance circuits (NAC), Style Z in accordance with NFPA 72. Provide a looped conduit system so that if the conduit and all conductors within are severed at any point, all IDC, NAC and SLC will remain functional. Textual, audible, and visual appliances and systems shall comply with NFPA 72. Fire alarm system components requiring power, except for the control panel power supply, shall operate on 24 Volts dc. Addressable system shall be microcomputer (microprocessor or microcontroller) based with a minimum word size of eight bits and shall provide the following features:

a. Sufficient memory to perform as specified and as shown for addressable system.

b. Individual identity of each addressable device for the following conditions: alarm; trouble; open; short; and appliances missing/failed remote detector - sensitivity adjustment from the panel for smoke detectors.

c. Capability of each addressable device being individually disabled or enabled from the panel.

d. Size each SLC to provide 40 percent addressable expansion without hardware modifications to the panel.

1.2.2 Operational Features

The system shall have the following operating features:

a. Monitor electrical supervision of IDC, SLC, and NAC.

b. Monitor electrical supervision of the primary power (ac) supply, battery voltage, placement of alarm zone module (card, PC board) within the control panel, and transmitter tripping circuit integrity.

c. A trouble buzzer and trouble LED/LCD (light emitting diode/liquid crystal diode) to activate upon a single break, open, or ground fault condition which prevents the required normal operation of the system. The trouble signal shall also operate upon loss of primary power (ac) supply, low battery voltage, removal of alarm zone module (card, PC board), and disconnection of the circuit used for transmitting alarm signals off-premises. A trouble alarm silence switch shall be provided which will silence the trouble buzzer, but will not extinguish the trouble indicator LED/LCD. Subsequent trouble and supervisory alarms shall sound the trouble signal until silenced. After the system returns to normal operating conditions, the trouble buzzer shall again sound until the silencing switch returns to normal position, unless automatic trouble reset is provided.

d. A one person test mode. Activating an initiating device in this mode will activate an alarm for a short period of time, then automatically reset the alarm, without activating the transmitter during the entire process.

e. A transmitter disconnect switch to allow testing and maintenance of the system without activating the transmitter but providing a trouble signal when disconnected and a restoration signal when reconnected.

f. Evacuation alarm silencing switch which, when activated, will silence alarm devices, but will not affect the zone indicating LED/LCD displays on the control panel nor the operation of the transmitter. This switch shall be over-ridden upon activation of a subsequent alarm from an unalarmed device and the NAC devices will be activated.

g. Electrical supervision for circuits used for supervisory signal services. Supervision shall detect any open, short, or ground.

h. Confirmation or verification of all smoke detectors. The control panel shall interrupt the transmission of an alarm signal to the system control panel for a factory preset period. This interruption period shall be adjustable from 1 to 60 seconds and be factory set at 20 seconds. Immediately following the interruption period, a confirmation period shall be in effect during which time an alarm signal, if present, will be sent immediately to the control panel. Fire alarm devices other than smoke detectors shall be programmed without confirmation or verification.

i. The control panel and field panels shall be software reprogrammable to enable expansion or modification of the system without replacement of hardware or firmware. Examples of required changes are: adding or deleting devices or zones; changing system responses to particular input signals; programming certain input signals to activate auxiliary devices.

j. Zones for IDC and NAC shall be arranged as indicated on the contract drawings.

1.2.3 Alarm Functions

An alarm condition on a circuit shall automatically initiate the following functions:

a. Transmission of a signal over the station telephonic fire reporting system. The signal shall be common for any device.

b. Visual indications of the alarmed devices on the fire alarm control panel display.

c. Continuous sounding or operation of alarm notification appliances throughout the building as required by ASA S3.41.

1.2.4 Primary Power

Operating power shall be provided as required by paragraph Power Supply for the System. Transfer from normal to emergency power or restoration from emergency to normal power shall be fully automatic and not cause transmission of a false alarm. Loss of ac power shall not prevent transmission of a signal via the fire reporting system upon operation of any initiating circuit.

1.2.5 Battery Backup Power

Battery backup power shall be through use of rechargeable, sealed-type storage batteries and battery charger.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings

Detail drawings, prepared and signed by a Registered Professional Engineer or a NICET Level 3 Fire Alarm Technician, as specified.

SD-03 Product Data

Storage Batteries

Substantiating battery calculations for supervisory and alarm power requirements. Ampere-hour requirements for each system component and each panel component, and the battery recharging period shall be included.

Low Battery Voltage

Voltage drop calculations for notification appliance circuits to indicate that sufficient voltage is available for proper appliance operation.

Special Tools and Spare Parts

Spare parts data for each different item of material and equipment specified, not later than 3 months prior to the date of beneficial occupancy. Data shall include a complete list of parts and supplies with the current unit prices and source of supply and a list of the parts recommended by the manufacturer to be replaced after 1 year of service.

Technical Data and Computer Software; G

Technical data which relates to computer software.

Training

Lesson plans, operating instructions, maintenance procedures, and training data, furnished in manual format, for the training courses. The operations training shall familiarize designated government personnel with proper operation of the fire alarm system. The maintenance training course shall provide the designated government personnel adequate knowledge required to diagnose, repair, maintain, and expand functions inherent to the system.

Testing

Detailed test procedures, prepared and signed by a Registered Professional Engineer or a NICET Level 3 Fire Alarm Technician, for the fire detection and alarm system 60 days prior to performing system tests.

SD-06 Test Reports

Testing

Test reports, in booklet form, showing field tests performed to prove compliance with the specified performance criteria, upon completion and testing of the installed system. Each test report shall document readings, test results and indicate the final position of controls. Include the NFPA 72 Certificate of Completion and NFPA 72 Inspection and Testing Form, with the appropriate test reports.

SD-07 Certificates

Equipment

Certified copies of current approvals or listings issued by an independent test lab if not listed by UL, FM or other nationally recognized testing laboratory, showing compliance with specified NFPA standards.

Qualifications

Proof of qualifications for required personnel. The installer

shall submit proof of experience for the Professional Engineer, fire alarm technician, and the installing company.

SD-10 Operation and Maintenance Data

Operating and Maintenance Instructions; G

Six copies of operating manual outlining step-by-step procedures required for system startup, operation, and shutdown. The manual shall include the manufacturer's name, model number, service manual, parts list, and complete description of equipment and their basic operating features. Six copies of maintenance manual listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guide. The manuals shall include conduit layout, equipment layout and simplified wiring, and control diagrams of the system as installed. The manuals shall include complete procedures for system revision and expansion, detailing both equipment and software requirements. Original and backup copies of all software delivered for this project shall be provided, on each type of media utilized. Manuals shall be approved prior to training.

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

1.4.1.1 Engineer and Technician

a. Registered Professional Engineer with verification of experience and at least 4 years of current experience in the design of the fire protection and detection systems.

b. National Institute for Certification in Engineering Technologies (NICET) qualifications as an engineering technician in fire alarm systems program with verification of experience and current NICET certificate.

c. The Registered Professional Engineer may perform all required items under this specification. The NICET Fire Alarm Technician shall perform only the items allowed by the specific category of certification held.

1.4.1.2 Installer

The installing Contractor shall provide the following: NICET Fire Alarm Technicians to perform the installation of the system. A NICET Level 3 Fire Alarm Technician shall supervise the installation of the fire alarm system. NICET Level 2 or higher Fire Alarm Technician shall install and terminate fire alarm devices, cabinets and panels. An electrician or NICET Level 1 Fire Alarm Technician shall install conduit for the fire alarm system. The Fire Alarm technicians installing the equipment shall be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.4.1.3 Fire Protection Engineer

Installations needing designs or modifications of fire detection, fire alarm, or fire suppression systems require the services and review of a qualified fire protection engineer. For the purposes of meeting this

requirement, a qualified fire protection engineer is defined as an individual meeting one of the following conditions:

a. An engineer having a Bachelor of Science or Masters of Science Degree in Fire Protection Engineering from an accredited university engineering program, plus a minimum of 2 years' work experience in fire protection engineering.

b. A registered professional engineer (P.E.) in fire protection engineering.

c. A registered PE in a related engineering discipline and member grade status in the National Society of Fire Protection Engineers.

d. An engineer with a minimum of 10 years' experience in fire protection engineering and member grade status in the National Society of Fire Protection Engineers.

1.4.2 Detail Drawings

Submit detail drawings consisting of a complete list of equipment and material, including manufacturer's descriptive and technical literature, catalog cuts, and installation instructions. Note that the contract drawings show layouts based on typical audible appliances. Check the layout based on the actual audible devices to be installed and make any necessary revisions in the detail drawings. The detail drawings shall also contain complete wiring and schematic diagrams for the equipment furnished, equipment layout, and any other details required to demonstrate that the system has been coordinated and will properly function as a unit. Detailed point-to-point wiring diagram shall be prepared and signed by a Registered Professional Engineer or a NICET Level 3 Fire Alarm Technician showing points of connection. Diagram shall include connections between system devices, appliances, control panels, supervised devices, and equipment that is activated or controlled by the panel.

1.5 TECHNICAL DATA AND COMPUTER SOFTWARE

Technical data and computer software (meaning technical data which relates to computer software) which is specifically identified in this project, and which may be defined/required in other specifications, shall be delivered, strictly in accordance with the CONTRACT CLAUSES, and in accordance with the Contract Data Requirements List, DD Form 1423. Data delivered shall be identified by reference to the particular specification paragraph against which it is furnished. Data to be submitted shall include complete system, equipment, and software descriptions. Descriptions shall show how the equipment will operate as a system to meet the performance requirements of this contract. The data package shall also include the following:

a. Identification of programmable portions of system equipment and capabilities.

b. Description of system revision and expansion capabilities and methods of implementation detailing both equipment and software requirements.

c. Provision of operational software data on all modes of programmable portions of the fire alarm and detection system.

d. Description of Fire Alarm Control Panel equipment operation.

e. Description of auxiliary and remote equipment operations.

f. Library of application software.

g. Operation and maintenance manuals as specified in SD-19 of the Submittals paragraph.

1.6 DELIVERY, STORAGE, AND HANDLING

Protect equipment delivered and placed in storage from the weather, humidity and temperature variation, dirt, dust, and any other contaminants.

1.7 SPECIAL TOOLS AND SPARE PARTS

Furnish to the Contracting Officer software, connecting cables, proprietary equipment and two spare fuses of each type and size required, necessary for the maintenance, testing, and reprogramming of the equipment. Two percent of the total number of each different type of detector, but no less than two each, shall be furnished. Mount spare fuses in the fire alarm panel.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide material and equipment which are the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid opening. Equipment shall be supported by a service organization that can provide service within 24 hours of notification.

2.2 NAMEPLATES

Major components of equipment shall have the manufacturer's name, address, type or style, voltage and current rating, and catalog number on a noncorrosive and nonheat-sensitive plate which is securely attached to the equipment.

2.3 CONTROL PANEL

Control Panel shall comply with the applicable requirements of UL 864. Panel shall be modular, installed in a surface mounted steel cabinet with hinged door and cylinder lock. Control panel shall be a clean, uncluttered, and orderly assembled panel containing components and equipment required to provide the specified operating and supervisory functions of the system. The panel shall have prominent rigid plastic, phenolic or metal identification plates for LED/LCDs, zones, SLC, controls, meters, fuses, and switches.

a. Nameplates for fuses shall also include ampere rating. The LED/LCD displays shall be located on the exterior of the cabinet door or be visible through the cabinet door. Control panel switches shall be within the locked cabinet. A suitable means (single operation) shall be provided for testing the control panel visual indicating devices (meters or LEDs/LCDs). Meters and LEDs shall be plainly visible when the cabinet door is closed. Signals and LEDs/LCDs shall be provided to indicate by zone any alarm, supervisory or trouble condition on the system.

b. Loss of power, including batteries, shall not require the manual

reloading of a program. Upon restoration of power, startup shall be automatic, and shall not require any manual operation. The loss of primary power or the sequence of applying primary or emergency power shall not affect the transmission of alarm, supervisory or trouble signals.

c. Visual annunciation shall be provided for LED/LCD visual display as an integral part of the control panel and shall identify with a word description and id number each device. Cabinets shall be provided with ample gutter space to allow proper clearance between the cabinet and live parts of the panel equipment. If more than one modular unit is required to form a control panel, the units shall be installed in a single cabinet large enough to accommodate units. Cabinets shall be painted red.

2.3.1 Remote System Audible/Visual Display

Audible appliance shall have a minimum sound level output rating of 85 dBA at 3.05 m and operate in conjunction with the panel integral display. The audible device shall be silenced by a system silence switch on the remote system. The audible device shall be silenced by the system silence switch located at the remote location, but shall not extinguish the visual indication. The remote LED/LCD visual display shall provide identification, consisting of the word description and id number for each device as displayed on the control panel. A rigid plastic, phenolic or metal identification sign which reads "Fire Alarm System Remote Display" shall be provided at the remote audible/visual display. The remote visual appliance located with the audible appliance shall not be extinguished until the trouble or alarm has been cleared.

2.3.2 Circuit Connections

Connect circuit conductors entering or leaving the panel to screw-type terminals with each conductor and terminal marked for identification.

2.3.3 System Expansion and Modification Capabilities

Provide, as part of this contract, any equipment and software needed by qualified technicians to implement future changes to the fire alarm system.

2.3.4 Addressable Control Module

The control module shall be capable of operating as a relay (dry contact form C) for interfacing the control panel with other systems, and to control door holders or initiate elevator fire service. The module shall be UL listed as compatible with the control panel. The indicating device or the external load being controlled shall be configured as a Style Y notification appliance circuits. The system shall be capable of supervising, audible, visual and dry contact circuits. The control module shall have both an input and output address. The supervision shall detect a short on the supervised circuit and shall prevent power from being applied to the circuit. The control model shall provide address setting means compatible with the control panel's SLC supervision and store an internal identifying code. The control module shall contain an integral LED that flashes each time the control module is polled.

2.4 STORAGE BATTERIES

Provide storage batteries which are 24 Vdc sealed, lead-calcium type

requiring no additional water with ample capacity, with primary power disconnected, to operate the fire alarm system for a period of 72 hours. Following this period of battery operation, the batteries shall have ample capacity to operate all components of the system, including all alarm signaling devices in the total alarm mode for a minimum period of 15 minutes. Locate batteries at the bottom of the panel . Provide batteries with overcurrent protection in accordance with NFPA 72.

2.5 BATTERY CHARGER

Battery charger shall be completely automatic, 24 Vdc with high/low charging rate, capable of restoring the batteries from full discharge (18 Volts dc) to full charge within 48 hours. A pilot light indicating when batteries are manually placed on a high rate of charge shall be provided as part of the unit assembly, if a high rate switch is provided. Locate charger in control panel cabinet or in a separate battery cabinet.

2.6 ADDRESSABLE MANUAL FIRE ALARM STATIONS

Addressable manual fire alarm stations shall conform to the applicable requirements of UL 38. Manual stations shall be connected into signal line circuits. Stations shall be installed on flush mounted outlet boxes. Manual stations shall be mounted at 1220 mm. Stations shall be single action type. Stations shall be finished in red, with raised letter operating instructions of contrasting color. Stations requiring the breaking of glass or plastic panels for operation are not acceptable. Stations employing glass rods are not acceptable. The use of a key or wrench shall be required to reset the station. Gravity or mercury switches are not acceptable. Switches and contacts shall be rated for the voltage and current upon which they operate. Addressable pull stations shall be capable of being field programmed, shall latch upon operation and remain latched until manually reset. Stations shall have a separate screw terminal for each conductor. Surface mounted boxes shall be matched and painted the same color as the fire alarm manual stations.

2.7 FIRE DETECTING DEVICES

Fire detecting devices shall comply with the applicable requirements of NFPA 72, NFPA 90A, UL 268, UL 268A, and UL 521. The detectors shall be provided as indicated. Detector base shall have screw terminals for making connections. No solder connections will be allowed. Detectors located in concealed locations (above ceiling, raised floors, etc.) shall have a remote visible indicator LED/LCD. Addressable fire detecting devices shall be dynamically supervised and uniquely identified in the control panel. All fire alarm initiating devices shall be individually addressable.

2.7.1 Heat Detectors

Design heat detectors for detection of fire by combination fixed temperature and rate-of-rise principle. Heat detector spacing shall be rated in accordance with UL 521. Detectors located in areas subject to moisture, exterior atmospheric conditions, or hazardous locations as defined by NFPA 70 and shall be types approved for such locations. Heat detectors located in attic spaces or similar concealed spaces below the roof shall be intermediate temperature rated.

2.7.1.1 Combination Fixed-Temperature and Rate-of-Rise Detectors

Detectors shall be designed for surface outlet box mounting and supported

independently of wiring connections. Contacts shall be self-resetting after response to rate-of-rise principle. Under fixed temperature actuation, the detector shall have a permanent external indication which is readily visible. Detector units located in boiler rooms, showers, or other areas subject to abnormal temperature changes shall operate on fixed temperature principle only. The UL 521 test rating for the fixed temperature portion shall be 57.2 degrees C. The UL 521 test rating for the Rate-of-Rise detectors shall be rated for 15 by 15 m.

2.7.1.2 Rate Compensating Detectors

Detectors shall be surface mounted horizontal type, with outlet box supported independently of wiring connections. Detectors shall be hermetically sealed and automatically resetting. Rate Compensated detectors shall be rated for 15 by 15 m.

2.7.2 Smoke Detectors

Design smoke detectors for detection of abnormal smoke densities. Smoke detectors shall be photoelectric type. Detectors shall contain a visible indicator LED/LCD that shows when the unit is in alarm condition. Detectors shall not be adversely affected by vibration or pressure. Detectors shall be the plug-in type in which the detector base contains terminals for making wiring connections. Detectors that are to be installed in concealed (above false ceilings, etc.) locations shall be provided with a remote indicator LED/LCD suitable for mounting in a finished, visible location.

2.7.2.1 Photoelectric Detectors

Detectors shall operate on a light scattering concept using an LED light source. Failure of the LED shall not cause an alarm condition. Detectors shall be factory set for sensitivity and shall require no field adjustments of any kind. Detectors shall have an obscuration rating in accordance with UL 268. Addressable smoke detectors shall be capable of having the sensitivity being remotely adjusted by the control panel.

2.7.2.2 Duct Detectors

Duct-mounted photoelectric smoke detectors shall be furnished and installed where indicated and in accordance with NFPA 90A. Units shall consist of a smoke detector as specified in paragraph Photoelectric Detectors, mounted in a special housing fitted with duct sampling tubes. Detector circuitry shall be mounted in a metallic enclosure exterior to the duct. Detectors shall have a manual reset. Detectors shall be rated for air velocities that include air flows between 2.5 and 20 m/s. Detectors shall be powered from the fire alarm panel. Sampling tubes shall run the full width of the duct. The duct detector package shall conform to the requirements of NFPA 90A, UL 268A, and shall be UL listed for use in air-handling systems. The control functions, operation, reset, and bypass shall be controlled from the fire alarm control panel. Lights to indicate the operation and alarm condition; and the test and reset buttons shall be visible and accessible with the unit installed and the cover in place. Detectors mounted above 1.83 m and those mounted below 1.83 m that cannot be easily accessed while standing on the floor, shall be provided with a remote detector indicator panel containing test and reset switches. Remote lamps and switches as well as the affected fan units shall be properly identified in etched plastic placards. Detectors shall have auxiliary contacts to provide control, interlock, and shutdown functions. The detectors shall be

supplied by the fire alarm system manufacturer to ensure complete system compatibility.

2.8 NOTIFICATION APPLIANCES

Audible appliances shall conform to the applicable requirements of UL 464. Devices shall be connected into notification appliance circuits. Devices shall have a separate screw terminal for each conductor. Audible appliances shall generate a unique audible sound from other devices provided in the building and surrounding area. Surface mounted audible appliances shall be painted red. Recessed audible appliances shall be installed with a grill that is painted red.

2.8.1 Alarm Bells

Bells shall be surface mounted with the matching mounting back box recessed. Bells shall be suitable for use in an electrically supervised circuit. Bells shall be the underdome type producing a minimum output rating of 85 dBA at 3.1 m. Bells used in exterior locations shall be specifically listed or approved for outdoor use and be provided with metal housing and protective grilles. Single stroke, electrically operated, supervised, solenoid bells shall be used for coded applications.

2.8.2 Alarm Horns

Horns shall be surface mounted, with the matching mounting back box single projector, vibrating type suitable for use in an electrically supervised circuit. Horns shall produce a sound rating of at least 85 dBA at 3.05 m. Horns used in exterior locations shall be specifically listed or approved for outdoor use and be provided with metal housing and protective grilles.

2.8.3 Visual Notification Appliances

Visual notification appliances shall conform to the applicable requirements of UL 1971 and the contract drawings. Appliances shall have clear high intensity optic lens, xenon flash tubes, and output white light. Strobe flash rate shall be between 1 to 3 flashes per second and a minimum of 75 candela. Strobe shall be surface mounted.

2.8.4 Combination Audible/Visual Notification Appliances

Combination audible/visual notification appliances shall provide the same requirements as individual units except they shall mount as a unit in standard backboxes. Units shall be factory assembled. Any other audible notification appliance employed in the fire alarm systems shall be approved by the Contracting Officer.

2.8.5 Voice Evacuation System

The voice evacuation system shall provide for one-way voice communications, routing and pre-amplification of digital alarm tones and voice (digital and analog) messages. The system shall be zoned for messages (Custom and prerecorded) and tones as indicated on the drawings. The following electronic tones shall be available from the amplifier: Slow Whoop, High/Low, Horn, Chime, Beep, Stutter, Wail and Bell. The system shall have a microphone and allow for general paging within the space. Operation shall be either manually from a control switch or automatically from the fire alarm control panel. Reset shall be accomplished by the fire alarm control panel during panel reset.

2.9 FIRE DETECTION AND ALARM SYSTEM PERIPHERAL EQUIPMENT

2.9.1 Conduit

Conduit and fittings shall comply with NFPA 70, UL 6, UL 1242, and UL 797.

2.9.2 Wiring

Wiring shall conform to NFPA 70. Wiring for 120 Vac power shall be No. 12 AWG minimum. The SLC wiring shall be copper cable in accordance with the manufacturers requirements. Wiring for fire alarm dc circuits shall be No. 14 AWG minimum. Voltages shall not be mixed in any junction box, housing, or device, except those containing power supplies and control relays. Wiring shall conform to NFPA 70. System field wiring shall be solid copper and installed in metallic conduit or electrical metallic tubing, except that rigid plastic conduit may be used under slab-on-grade. Conductors shall be color coded. Conductors used for the same functions shall be similarly color coded. Wiring code color shall remain uniform throughout the circuit. Pigtail or T-tap connections to initiating device circuits, supervisory alarm circuits, and notification appliance circuits are prohibited. T-tapping using screw terminal blocks is allowed for style 5 addressable systems.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with details of the work, verify dimensions in the field and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

Instal all work as shown, in accordance with NFPA 70 and NFPA 72, and in accordance with the manufacturer's diagrams and recommendations, unless otherwise specified. Smoke detectors shall not be installed until construction is essentially complete and the building has been thoroughly cleaned.

3.2.1 Power Supply for the System

Provide a single dedicated circuit connection for supplying power from a branch circuit to each building fire alarm system. The power shall be supplied as shown on the drawings. The power supply shall be equipped with a locking mechanism and marked in red with the words "FIRE ALARM CIRCUIT CONTROL".

3.2.2 Wiring

Conduit size for wiring shall be in accordance with NFPA 70. Wiring for the fire alarm system shall not be installed in conduits, junction boxes, or outlet boxes with conductors of lighting and power systems. Not more than two conductors shall be installed under any device screw terminal. The wires under the screw terminal shall be straight when placed under the terminal then clamped in place under the screw terminal. The wires shall be broken and not twisted around the terminal. Circuit conductors entering or leaving any mounting box, outlet box enclosure, or cabinet shall be connected to screw terminals with each terminal and conductor marked in

accordance with the wiring diagram. Connections and splices shall be made using screw terminal blocks. The use of wire nut type connectors in the system is prohibited. Wiring within any control equipment shall be readily accessible without removing any component parts. The fire alarm equipment manufacturer's representative shall be present for the connection of wiring to the control panel.

3.2.3 Control Panel

The control panel and its assorted components shall be mounted so that no part of the enclosing cabinet is less than 300 mm nor more than 2000 mm above the finished floor. Manually operable controls shall be between 900 and 1100 mm above the finished floor. Panel shall be installed to comply with the requirements of UL 864.

3.2.4 Detectors

Detectors shall be located and installed in accordance with NFPA 72. Detectors shall be connected into signal line circuits or initiating device circuits as indicated on the drawings. Detectors shall be at least 300 mm from any part of any lighting fixture. Detectors shall be located at least 900 mm from diffusers of air handling systems. Each detector shall be provided with appropriate mounting hardware as required by its mounting location. Detectors which mount in open space shall be mounted directly to the end of the stubbed down rigid conduit drop. Conduit drops shall be firmly secured to minimize detector sway. Where length of conduit drop from ceiling or wall surface exceeds 900 mm, sway bracing shall be provided. Detectors installed in concealed locations (above ceiling, raised floors, etc.) shall have a remote visible indicator LED/LCD in a finished, visible location.

3.2.5 Notification Appliances

Notification appliances shall be mounted 2003 mm above the finished floor or 150 mm below the ceiling, whichever is lower.

3.2.6 Annunciator Equipment

Annunciator equipment shall be mounted where indicated on the drawings.

3.3 OVERVOLTAGE AND SURGE PROTECTION

3.3.1 Power Line Surge Protection

All equipment connected to alternating current circuits shall be protected from surges in accordance with IEEE C62.41.1/IEEE C62.41.2 B3 combination waveform and NFPA 70. Fuses shall not be used for surge protection. The surge protector shall be rated for a maximum let thru voltage of 350 Volts ac (line-to-neutral) and 350 Volt ac (neutral-to-ground).

3.3.2 Low Voltage DC Circuits Surge Protection

All IDC, NAC, and communication cables/conductors, except fiber optics, shall have surge protection installed at each point where it exits or enters a building. Equipment shall be protected from surges in accordance with IEEE C62.41.1/IEEE C62.41.2 B3 combination waveform and NFPA 70. The surge protector shall be rated to protect the 24 Volt dc equipment. The maximum dc clamping voltages shall be 36 V (line-to-ground) and 72 Volt dc (line-to-line).

3.4 GROUNDING

Grounding shall be provided by connecting to building ground system.

3.5 TRAINING

Provide training course for the operations and maintenance staff. Conduct the course in the building where the system is installed or as designated by the Contracting Officer. The training period for systems operation shall consist of 1 training days (8 hours per day) and shall start after the system is functionally completed but prior to final acceptance tests. The training period for systems maintenance shall consist of 2 training days (8 hours per day) and shall start after the system is functionally completed but prior to final acceptance tests. The instructions shall cover items contained in the operating and maintenance instructions. In addition, training shall be provided on performance of expansions or modifications to the fire detection and alarm system. The training period for system expansions and modifications shall consist of at least 1 training days (8 hours per day) and shall start after the system is functionally completed but prior to final acceptance tests.

3.6 TESTING

Notify the Contracting Officer at least 10 days before the preliminary and acceptance tests are to be conducted. Perform the tests in accordance with the approved test procedures in the presence of the Contracting Officer. The control panel manufacturer's representative shall be present to supervise tests. Furnish instruments and personnel required for the tests.

3.6.1 Preliminary Tests

Upon completion of the installation, subject the system to functional and operational performance tests including tests of each installed initiating and notification appliance, when required. Tests shall include the meggering of system conductors to determine that the system is free from grounded, shorted, or open circuits. Conduct the megger test prior to the installation of fire alarm equipment. If deficiencies are found, corrections shall be made and the system shall be retested to assure that it is functional. After completing the preliminary testing complete and submit the NFPA 72, Certificate of Completion and Testing Form.

3.6.2 Acceptance Test

Acceptance testing shall not be performed until the Contractor has completed and submitted the Certificate of Completion. Conduct testing in accordance with NFPA 72. The recommended tests in NFPA 72 are considered mandatory and shall verify that previous deficiencies have been corrected. The Fire alarm Technician supervising the installation of the fire alarm system shall attend the testing of the system. The test shall include all requirements of NFPA 72 and the following:

a. Test of each function of the control panel.

b. Test of each circuit in both trouble and normal modes.

c. Tests of each alarm initiating devices in both normal and trouble conditions.

d. Tests of each control circuit and device.

e. Tests of each alarm notification appliance.

f. Tests of the battery charger and batteries.

g. Complete operational tests under emergency power supply.

h. Visual inspection of wiring connections.

i. Opening the circuit at each alarm initiating device and notification appliance to test the wiring supervisory feature.

j. Ground fault.

k. Short circuit faults.

l. Stray voltage.

m. Loop resistance.

-- End of Section --

SECTION 31 00 00

EARTHWORK
07/06

PART 1 GENERAL

The contractor will provide all necessary site grading to establish the approximate grades indicated on the conteptual site plans unless otherwise approved by the Contracting Officer. Work will include providing adequate drainage so that no areas will be flooded due to a rainfall of a 10-year frequency. Grading and drainage of the area should be compatable with the existing terrain. Building floor elevations shall be a minimum of 150 mm above grade and slope away from the building on all sides at a minimum of 5 percent for 3 meters.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(2001; R 2004) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457-mm (18-in) Drop
AASHTO T 224	(2001; R 2004) Correction for Coarse Particles in the Soil Compaction Test

ASTM INTERNATIONAL (ASTM)

ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D 1140	(2000) Amount of Material in Soils Finer than the No. 200 (75-micrometer) Sieve
ASTM D 1556	(2000) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(2002e1) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D 2167	(1994; R 2001) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2434	(1968; R 2006) Permeability of Granular Soils (Constant Head)
ASTM D 2487	(2006) Soils for Engineering Purposes (Unified Soil Classification System)

ASTM D 2922	(2005) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 2937	(2004) Density of Soil in Place by the Drive-Cylinder Method
ASTM D 3017	(2005) Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
ASTM D 422	(1963; R 2002e1) Particle-Size Analysis of Soils
ASTM D 4318	(2005) Liquid Limit, Plastic Limit, and Plasticity Index of Soils

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008) Safety and Health Requirements Manual

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 600/4-79/020	(1983) Methods for Chemical Analysis of Water and Wastes
EPA SW-846.3-3	(1999, Third Edition, Update III-A) Test Methods for Evaluating Solid Waste: Physical/Chemical Methods

1.2 DEFINITIONS

1.2.1 Satisfactory Materials

Satisfactory materials comprise any materials classified by ASTM D 2487 as GW, GP, GM, SW, SP, SM, SW-SM, SC, SW-SC, SP-SM, SP-SC, CL-ML. Satisfactory materials for grading comprise stones less than 200 mm, except for fill material for pavement and building areas which comprise stones less than 75 mm in any dimension.

1.2.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include trash; refuse; man-made fills and backfills containing debris from previous construction; and material classified as satisfactory which contains root and other organic matter or frozen material. Notify the Contracting Officer when encountering any contaminated materials.

1.2.3 Cohesionless and Cohesive Materials

Cohesionless materials include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM will be identified as cohesionless only when the fines are nonplastic. Perform testing, required for classifying materials, in accordance with ASTM D 4318, ASTM C 136, ASTM D 422, and ASTM D 1140.

1.2.4 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum dry density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum dry density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 19.0 mm sieve, express the degree of compaction for material having more than 30 percent by weight of their particles retained on the 19.0 mm sieve as a percentage of the maximum density in accordance with AASHTO T 180 and corrected with AASHTO T 224. To maintain the same percentage of coarse material, use the "remove and replace" procedure as described in NOTE 8 of Paragraph 7.2 in AASHTO T 180.

For soils that are too coarse for testing by any of the methods listed above, compaction will be based on nonmovement of the material under the compaction equipment and a specified number of passes of the compaction equipment.

1.2.5 Topsoil

Material suitable for topsoils obtained from onsite and offsite areas is defined as: Natural, friable soil representative of productive, well-drained soils in the area, free of subsoil, stumps, rocks larger than 25 mm diameter, brush, weeds, toxic substances, and other material detrimental to plant growth. Amend topsoil pH range to obtain a pH of 5.5 to 7. Topsoil shall contain 5 to 10 percent organic matter as defined in Section 32 92 19.

1.2.6 Hard/Unyielding Materials

Hard/Unyielding materials comprise weathered rock, dense consolidated deposits, or conglomerate materials which are not included in the definition of "rock". These materials usually require the use of heavy excavation equipment, ripper teeth, or jack hammers for removal.

1.2.7 Rock

Solid homogeneous interlocking crystalline material with firmly cemented, laminated, or foliated masses or conglomerate deposits, neither of which can be removed without systematic drilling and blasting, drilling and the use of expansion jacks or feather wedges, or the use of backhoe-mounted pneumatic hole punchers or rock breakers; also large boulders, buried masonry, or concrete other than pavement. Removal of hard material will not be considered rock excavation because of intermittent drilling and blasting that is performed merely to increase production.

1.2.8 Unstable Material

Unstable material are too wet for compaction and are too wet to properly support the utility pipe, conduit, or appurtenant structure.

1.2.9 Select Granular Material

Select granular material consisting of free draining materials classified as GW, GP, SW, SP, by ASTM D 2487 where indicated. Material gradation and minimum coefficient of permeability determined in accordance with ASTM D 2434 shall correspond with design requirements for the application specified.

1.2.10 Expansive Soils

Expansive soils are defined as soils that have a plasticity index equal to or greater than 30 and liquid limit exceeding 50 percent when tested in accordance with ASTM D 4318.

1.2.11 Nonfrost Susceptible (NFS) Material

Nonfrost susceptible materials are clean coarse aggregates having less than 5 percent passing the 0.075 mm size sieve, and with not more than 3 percent by weight finer than 0.02 mm grain size.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Shoring and Sheeting Plan; G
Dewatering Work Plan; G
Blasting; G

Submit 15 days prior to starting work.

SD-03 Product Data

Utilization of Excavated Materials; G
Rock Excavation
Opening of any Excavation or Borrow Pit

Procedure and location for disposal of unused satisfactory material. Proposed source of borrow material.

Notification of encountering rock in the project.
Advance notice on the opening of excavation or borrow areas.

SD-06 Test Reports

Testing
Borrow Site Testing; G

Within 24 hours of conclusion of physical tests, 2 copies of test results, including calibration curves and results of calibration tests. Results of testing at the borrow site.

SD-07 Certificates

Testing

Qualifications of the Corps validated commercial testing laboratory or the Contractor's validated testing facilities.

1.4 SUBSURFACE DATA

The contractor shall confirm subsurface conditions and parameters necessary for the work by geotechnical investigation.

1.5 CLASSIFICATION OF EXCAVATION

No consideration will be given to the nature of the materials, and all excavation will be designated as unclassified excavation.

1.6 BLASTING

Perform blasting in accordance with EM 385-1-1 and in conformance with Federal, State, and local safety regulations. The Contractor shall submit a Blasting Plan, prepared and sealed by a registered professional engineer that includes calculations for overpressure and debris hazard. Provide blasting mats and use the non-electric blasting caps. Obtain written approval prior to performing any blasting and notify the Contracting Officer 24 hours prior to blasting. Include provisions for storing, handling and transporting explosives as well as for the blasting operations in the plan. The Contractor is responsible for damage caused by blasting operations.

1.7 DEWATERING WORK PLAN

Submit procedures for accomplishing dewatering work.

PART 2 PRODUCTS

2.1 REQUIREMENTS FOR OFFSITE SOILS

Test offsite soils brought in for use as backfill for Total Petroleum Hydrocarbons (TPH), Benzene, Toluene, Ethyl Benzene, and Xylene (BTEX) and full Toxicity Characteristic Leaching Procedure (TCLP) including ignitability, corrosivity and reactivity. Backfill shall contain a maximum of 100 parts per million (ppm) of total petroleum hydrocarbons (TPH) and a maximum of 10 ppm of the sum of Benzene, Toluene, Ethyl Benzene, and Xylene (BTEX) and shall pass the TCPL test. Determine TPH concentrations by using EPA 600/4-79/020 Method 418.1. Determine BTEX concentrations by using EPA SW-846.3-3 Method 5030/8020. Perform TCLP in accordance with EPA SW-846.3-3 Method 1311. Provide Borrow Site Testing for TPH, BTEX and TCLP from a composite sample of material from the borrow site, with at least one test from each borrow site. Do not bring material onsite until tests have been approved by the Contracting Officer.

PART 3 EXECUTION

3.1 STRIPPING OF TOPSOIL

Where indicated or directed, strip topsoil to a depth of 100 mm. Spread topsoil on areas already graded and prepared for topsoil, or transported and deposited in stockpiles convenient to areas that are to receive application of the topsoil later, or at locations indicated or specified. Keep topsoil separate from other excavated materials, brush, litter, objectionable weeds, roots, stones larger than 50 mm in diameter, and other materials that would interfere with planting and maintenance operations.

3.2 GENERAL EXCAVATION

Perform excavation of every type of material encountered within the limits of the project to the lines, grades, and elevations needed to construct the site as indicated. Perform the grading in accordance with the typical sections shown and the tolerances specified in paragraph FINISHING. Transport satisfactory excavated materials and place in fill or embankment within the limits of the work. Excavate unsatisfactory materials encountered within the limits of the work below grade and replace with satisfactory materials as directed. Include such excavated material and the satisfactory material ordered as replacement in excavation. Dispose surplus satisfactory excavated material not required for fill or embankment in areas approved for surplus material storage or designated waste areas. Dispose unsatisfactory excavated material in designated waste or spoil areas. During construction, perform excavation and fill in a manner and sequence that will provide proper drainage at all times. Excavate material required for fill or embankment in excess of that produced by excavation within the grading limits from approved areas selected by the Contractor as specified.

3.2.1 Ditches, Gutters, and Channel Changes

Finish excavation of ditches, gutters, and channel changes by cutting accurately to the cross sections, grades, and elevations required. Backfill the excessive open ditch or gutter excavation with satisfactory, thoroughly compacted, material or with suitable stone or cobble to grades shown. Maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work.

3.2.2 Drainage

Provide for the collection and disposal of surface and subsurface water encountered during construction. Completely drain construction site during periods of construction to keep soil materials sufficiently dry. Construct storm drainage features (ponds/basins) at the earliest stages of site development, and throughout construction grade the construction area to provide positive surface water runoff away from the construction activity. Provide temporary ditches, swales, and other drainage features and equipment as required to maintain dry soils. When unsuitable working platforms for equipment operation and unsuitable soil support for subsequent construction features develop, remove unsuitable material and provide new soil material as specified herein. It is the responsibility of the Contractor to assess the soil and ground water conditions presented by the plans and specifications and to employ necessary measures to permit construction to proceed.

3.2.3 Dewatering

Control groundwater flowing toward or into excavations to prevent sloughing of excavation slopes and walls, boils, uplift and heave in the excavation and to eliminate interference with orderly progress of construction. Do not permit French drains, sumps, ditches or trenches within 0.9 m of the foundation of any structure, except with specific written approval, and after specific contractual provisions for restoration of the foundation area have been made. Take control measures by the time the excavation reaches the water level in order to maintain the integrity of the in situ material. While the excavation is open, maintain the water level continuously, below the working level. Operate dewatering system continuously until construction work below existing water levels is

complete. Submit performance records weekly. Measure and record performance of dewatering system at same time each day by use of observation wells or piezometers installed in conjunction with the dewatering system.

3.2.4 Underground Utilities

The Contractor is responsible for movement of construction machinery and equipment over pipes and utilities during construction. Perform work adjacent to utilities in accordance with procedures outlined by utility company. Excavation made with power-driven equipment is not permitted within 600 mm of utilities or subsurface construction. For work immediately adjacent to or for excavations exposing a utility or other buried obstruction, excavate by hand. Start hand excavation on each side of the indicated obstruction and continue until the obstruction is uncovered or until clearance for the new grade is assured. Support uncovered lines or other existing work affected by the contract excavation until approval for backfill is granted by the Contracting Officer. Report damage to utility lines or subsurface construction immediately to the Contracting Officer.

3.3 SELECTION OF BORROW MATERIAL

Select borrow material to meet the requirements and conditions of the particular fill or embankment for which it is to be used. Obtain borrow material from approved sources. Unless otherwise provided in the contract, the Contractor is responsible for obtaining the right to procure material, pay royalties and other charges involved, and bear the expense of developing the sources, including rights-of-way for hauling from the owners. Unless specifically provided, do not obtain borrow within the limits of the project site without prior written approval. Consider necessary clearing, grubbing, and satisfactory drainage of borrow pits and the disposal of debris thereon related operations to the borrow excavation.

3.4 OPENING AND DRAINAGE OF EXCAVATION AND BORROW PITS

The Contractor is responsible for notifying the Contracting Officer sufficiently in advance of the opening of any excavation or borrow pit to permit elevations and measurements of the undisturbed ground surface to be taken. Except as otherwise permitted, excavate borrow pits and other excavation areas providing adequate drainage. Transport overburden and other spoil material to designated spoil areas or otherwise dispose of as directed. Provide neatly trimmed and drained borrow pits after the excavation is completed. Ensure that excavation of any area, operation of borrow pits, or dumping of spoil material results in minimum detrimental effects on natural environmental conditions.

3.5 GRADING AREAS

Where indicated, divide work into grading areas within which satisfactory excavated material will be placed in embankments, fills, and required backfills. Do not haul satisfactory material excavated in one grading area to another grading area except when so directed in writing. Place and grade stockpiles of satisfactory, unsatisfactory and wasted materials as specified. Keep stockpiles in a neat and well drained condition, giving due consideration to drainage at all times. Clear, grub, and seal by rubber-tired equipment, the ground surface at stockpile locations; separately stockpile excavated satisfactory and unsatisfactory materials. Protect stockpiles of satisfactory materials from contamination which may

destroy the quality and fitness of the stockpiled material. If the Contractor fails to protect the stockpiles, and any material becomes unsatisfactory, remove and replace such material with satisfactory material from approved sources.

3.6 FINAL GRADE OF SURFACES TO SUPPORT CONCRETE

Do not excavate to final grade until just before concrete is to be placed. Only use excavation methods that will leave the foundation rock in a solid and unshattered condition. Roughen the level surfaces, and cut the sloped surfaces, as indicated, into rough steps or benches to provide a satisfactory bond. Protect shales from slaking and all surfaces from erosion resulting from ponding or water flow.

3.7 GROUND SURFACE PREPARATION

3.7.1 General Requirements

Remove and replace unsatisfactory material with satisfactory materials, as directed by the Contracting Officer, in surfaces to receive fill or in excavated areas. Scarify the surface to a depth of 150 mm before the fill is started. Plow, step, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so that the fill material will bond with the existing material. When subgrades are less than the specified density, break up the ground surface to a minimum depth of 150 mm, pulverizing, and compacting to the specified density. When the subgrade is part fill and part excavation or natural ground, scarify the excavated or natural ground portion to a depth of 300 mm and compact it as specified for the adjacent fill.

3.7.2 Frozen Material

Do not place material on surfaces that are muddy, frozen, or contain frost. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, or other approved equipment well suited to the soil being compacted. Moisten material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used.

3.8 UTILIZATION OF EXCAVATED MATERIALS

Dispose unsatisfactory materials removed from excavations into designated waste disposal or spoil areas. Use satisfactory material removed from excavations, insofar as practicable, in the construction of fills, embankments, subgrades, shoulders, bedding (as backfill), and for similar purposes. Do not waste any satisfactory excavated material without specific written authorization. Dispose of satisfactory material, authorized to be wasted, in designated areas approved for surplus material storage or designated waste areas as directed. Clear and grub newly designated waste areas on Government-controlled land before disposal of waste material thereon. Stockpile and use durable coarse rock from excavations for constructing slopes or embankments adjacent to streams, or sides and bottoms of channels and for protecting against erosion. Do not dispose excavated material to obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way.

3.9 EMBANKMENTS

3.9.1 Earth Embankments

Construct earth embankments from satisfactory materials free of organic or frozen material and rocks with any dimension greater than 75 mm. Place the material in successive horizontal layers of loose material not more than 300 mm in depth. Spread each layer uniformly on a soil surface that has been moistened or aerated as necessary, and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, plow, disk, or otherwise brake up each layer; moisten or aerate as necessary; thoroughly mix; and compact to at least 90 percent laboratory maximum density for cohesive materials or 95 percent laboratory maximum dry density for cohesionless materials. Compaction requirements for the upper portion of earth embankments forming subgrade for pavements are identical with those requirements specified in paragraph SUBGRADE PREPARATION. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.9.2 Rock Embankments

Construct rock embankments from material classified as rock excavation, as defined above, placed in successive horizontal layers of loose material not more than 900 mm in depth. Do not use pieces of rock larger than 900 mm in the greatest dimension. Spread each layer of material uniformly, completely saturate, and compact. Place rock so larger pieces are evenly distributed and voids are filled as completely as possible. Adequately bond each successive layer of material to the material on which it is placed. Finish compaction with vibratory compactors, heavy rubber-tired rollers or steel-wheeled rollers weighing at least 9 metric tons. In embankments on which pavements are to be constructed, do not use rock above a point 900 mm below the surface of the pavement.

3.10 SUBGRADE PREPARATION

3.10.1 Proof Rolling

Finish proof rolling on an exposed subgrade free of surface water (wet conditions resulting from rainfall) which would promote degradation of an otherwise acceptable subgrade. Proof roll the subgrade with six passes of a dump truck loaded with 6 cubic meters of soil or a 13.6 metric ton pneumatic-tired roller. Operate the roller or truck in a systematic manner to ensure the number of passes over all areas, and at speeds between 4 to 5.5 km/hour. When proof rolling, provide one-half of the passes made with the roller in a direction perpendicular to the other passes. Notify the Contracting Officer a minimum of 3 days prior to proof rolling. Perform proof rolling in the presence of the Contracting Officer. Undercut rutting or pumping of material as directed by the Contracting Officer and replace with properly compacted satisfactory material.

3.10.2 Construction

Shape subgrade to line, grade, and cross section, and compact as specified. Include plowing, disking, and any moistening or aerating required to obtain specified compaction for this operation. Remove soft or otherwise unsatisfactory material and replace with satisfactory excavated material or other approved material as directed. Excavate rock encountered in the cut section to a depth of 150 mm below finished grade for the

subgrade. Bring up low areas resulting from removal of unsatisfactory material or excavation of rock to required grade with satisfactory materials, and shape the entire subgrade to line, grade, and cross section and compact as specified. After rolling, do not show deviations for the surface of the subgrade for roadways greater than 13 mm when tested with a 4 m straightedge applied both parallel and at right angles to the centerline of the area. Do not vary the elevation of the finish subgrade more than 13 mm from the established grade and cross section.

3.10.3 Compaction

Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Except for paved areas and railroads, compact each layer of the embankment to at least 95 percent of laboratory maximum dry density.

3.10.3.1 Subgrade for Pavements

Compact subgrade for pavements to at least 95 percent of the laboratory maximum dry density for the depth below the surface of the pavement shown. When more than one soil classification is present in the subgrade, thoroughly blend, reshape, and compact the top 203 mm of subgrade.

3.10.3.2 Subgrade for Shoulders

Compact subgrade for shoulders to at least 95 percent of the laboratory maximum dry density for the full depth of the shoulder.

3.11 SHOULDER CONSTRUCTION

Construct shoulders of satisfactory excavated or borrow material or as otherwise shown or specified. Construct shoulders immediately after adjacent paving is complete. In the case of rigid pavements, do not construct shoulders until permission of the Contracting Officer has been obtained. Compact the entire shoulder area to at least the percentage of maximum density as specified in paragraph SUBGRADE PREPARATION above, for specific ranges of depth below the surface of the shoulder. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Finish shoulder construction in proper sequence in such a manner that adjacent ditches will be drained effectively and that no damage of any kind is done to the adjacent completed pavement. Align the completed shoulders true to grade and shaped to drain.

3.12 FINISHING

Finish the surface of excavations, embankments, and subgrades to a smooth and compact surface in accordance with the required lines, grades, and cross sections or elevations. Provide the degree of finish for graded areas within 30 mm of the required grades and elevations except that the degree of finish for subgrades specified in paragraph SUBGRADE PREPARATION. Finish gutters and ditches in a manner that will result in effective drainage. Finish the surface of areas to be turfed from settlement or washing to a smoothness suitable for the application of turfing materials. Repair graded, topsoiled, or backfilled areas prior to acceptance of the work, and re-established grades to the required elevations and slopes.

3.12.1 Subgrade and Embankments

During construction, keep embankments and excavations shaped and drained. Maintain ditches and drains along subgrade to drain effectively at all times. Do no disturb the finished subgrade by traffic or other operation. The Contractor is responsible for protecting and maintaining the finsihed subgrade in a satisfactory condition until ballast, subbase, base, or pavement is placed. Do not permit the storage or stockpiling of materials on the finished subgrade. Do not lay subbase, base course, ballast, or pavement until the subgrade has been checked and approved, and in no case place subbase, base, surfacing, pavement, or ballast on a muddy, spongy, or frozen subgrade.

3.12.2 Capillary Water Barrier

Place a capillary water barrier under concrete floor and area-way slabs grade directly on the subgrade and compact with a minimum of two passes of a hand-operated plate-type vibratory compactor.

3.12.3 Grading In and Around Structures

Construct areas within 3 m of each building and structure line true-to-grade, shape to drain and in accordance with these specifications. Maintain free of trash and debris until final inspection has been completed and the work has been accepted.

3.13 PLACING TOPSOIL

On areas to receive topsoil, prepare the compacted subgrade soil to a 50 mm depth for bonding of topsoil with subsoil. Spread topsoil evenly to a thickness of 102 mm and grade to the required elevations and slopes. Do not spread topsoil when frozen or excessively wet or dry. Obtain material required for topsoil in excess of that produced by excavation within the grading limits from approved offsite areas.

3.14 TESTING

Perform testing by a Corps validated commercial testing laboratory or the Contractor's validated testing facility. If the Contractor elects to establish testing facilities, do not permit work requiring testing until the Contractor's facilities have been inspected, Corps validated and approved by the Contracting Officer. Determine field in-place density in accordance with ASTM D 1556, ASTM D 2167, or ASTM D 2922. When ASTM D 2922 is used, check the calibration curves and adjust using only the sand cone method as described in ASTM D 1556. ASTM D 2922 results in a wet unit weight of soil to determine the moisture content of the soil when using this method ASTM D 3017. Check the calibration curves furnished with the moisture gauges along with density calibration checks as described in ASTM D 3017; check the calibration of both the density and moisture gauges at the beginning of a job on each different type of material encountered and at intervals as directed by the Contracting Officer. ASTM D 2937, use the Drive Cylinder Method only for soft, fine-grained, cohesive soils. When test results indicate, as determined by the Contracting Officer, that compaction is not as specified, remove the material, replace and recompact to meet specification requirements. Perform tests on recompacted areas to determine conformance with specification requirements. Appoint a registered professional civil engineer to certify inspections and test results. These certifications shall state that the tests and observations were performed by or under the direct supervision of the engineer and that

the results are representative of the materials or conditions being certified by the tests. The following number of tests, if performed at the appropriate time, will be the minimum acceptable for each type operation.

3.14.1 In-Place Densities

a. One test per 465 square meters, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines.

b. One test per 95 square meters, or fraction thereof, of each lift of fill or backfill areas compacted by hand-operated machines.

3.14.2 Check Tests on In-Place Densities

If ASTM D 2922 is used, check in-place densities by ASTM D 1556 as directed by the Contracting Officer.

3.14.3 Moisture Contents

In the stockpile, excavation, or borrow areas, perform a minimum of two tests per day per type of material or source of material being placed during stable weather conditions. During unstable weather, perform tests as dictated by local conditions and approved by the Contracting Officer.

3.14.4 Optimum Moisture and Laboratory Maximum Density

Perform tests for each type material or source of material including borrow material to determine the optimum moisture and laboratory maximum density values. One representative test per 1910 cubic meters of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density.

3.14.5 Tolerance Tests for Subgrades

Perform continuous checks on the degree of finish specified in paragraph SUBGRADE PREPARATION during construction of the subgrades.

3.15 DISPOSITION OF SURPLUS MATERIAL

Remove from Government property as directed by the Contracting Officer.

-- End of Section --

SECTION 31 05 19

GEOTEXTILE
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 4354	(1999; R 2004) Sampling of Geosynthetics for Testing
ASTM D 4355	(2005) Deterioration of Geotextiles from Exposure to Light, Moisture and Heat in a Xenon-Arc Type Apparatus
ASTM D 4759	(2002) Determining the Specification Conformance of Geosynthetics
ASTM D 4873	(2002) Identification, Storage, and Handling of Geosynthetic Rolls and Samples

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Thread

A minimum of 7 days prior to scheduled use, proposed thread type for sewn seams along with data sheets showing the physical properties of the thread.

Manufacturing Quality Control Sampling and Testing

A minimum of 7 days prior to scheduled use, manufacturer's quality control manual.

SD-04 Samples

Quality Assurance Samples and Tests

Samples for quality assurance testing; 7 days shall be allotted in the schedule to allow for testing.

SD-07 Certificates

Geotextile

A minimum of 7 days prior to scheduled use, manufacturer's certificate of compliance stating that the geotextile meets the requirements of this section. For needle punched geotextiles, the manufacturer shall also certify that the geotextile has been continuously inspected using permanent on-line full-width metal detectors and does not contain any needles which could damage other geosynthetic layers. The certificate of compliance shall be attested to by a person having legal authority to bind the geotextile manufacturer.

1.3 DELIVERY, STORAGE AND HANDLING

Delivery, storage, and handling of geotextile shall be in accordance with ASTM D 4873.

1.3.1 Delivery

The Contracting Officer shall be notified a minimum of 24 hours prior to delivery and unloading of geotextile rolls. Rolls shall be packaged in an opaque, waterproof, protective plastic wrapping. The plastic wrapping shall not be removed until deployment. If quality assurance samples are collected, rolls shall be immediately rewrapped with the plastic wrapping. Geotextile or plastic wrapping damaged during storage or handling shall be repaired or replaced, as directed. Each roll shall be labeled with the manufacturer's name, geotextile type, roll number, roll dimensions (length, width, gross weight), and date manufactured.

1.3.2 Storage

Rolls of geotextile shall be protected from construction equipment, chemicals, sparks and flames, temperatures in excess of 71 degrees C, or any other environmental condition that may damage the physical properties of the geotextile. To protect geotextile from becoming saturated, rolls shall either be elevated off the ground or placed on a sacrificial sheet of plastic in an area where water will not accumulate.

1.3.3 Handling

Geotextile rolls shall be handled and unloaded with load carrying straps, a fork lift with a stinger bar, or an axial bar assembly. Rolls shall not be dragged along the ground, lifted by one end, or dropped to the ground.

PART 2 PRODUCTS

2.1 RAW MATERIALS

2.1.1 Geotextile

Geotextile shall be the type and class required for the intended application and shall exhibit properties conforming to design requirements. Geotextile shall be a pervious sheet of polymeric material and shall consist of long-chain synthetic polymers composed of at least 95 percent by weight polyolefins, polyesters, or polyamides. The use of woven slit film geotextiles (i.e. geotextiles made from yarns of a flat, tape-like character) will not be allowed. Stabilizers and/or inhibitors shall be added to the base polymer, as needed, to make the filaments

resistant to deterioration by ultraviolet light, oxidation, and heat exposure. Regrind material, which consists of edge trimmings and other scraps that have never reached the consumer, may be used to produce the geotextile. Post-consumer recycled material shall not be used. Geotextile shall be formed into a network such that the filaments or yarns retain dimensional stability relative to each other, including the edges. Minimum average roll properties shall be specified in accordance with ASTM D 4759 and shall include the properties listed below. Where applicable, property values represent minimum average roll values (MARV) in the weakest principal direction. Values for AOS represent maximum average roll values.

2.1.2 Thread

Sewn seams shall be constructed with high-strength polyester, nylon, or other approved thread type. Thread shall have ultraviolet light stability equivalent to the geotextile and the color shall contrast with the geotextile.

2.2 MANUFACTURING QUALITY CONTROL SAMPLING AND TESTING

The Manufacturer shall be responsible for establishing and maintaining a quality control program to assure compliance with the requirements of the specification. Documentation describing the quality control program shall be made available upon request. Manufacturing quality control sampling and testing shall be performed in accordance with the manufacturer's approved quality control manual. As a minimum, geotextiles shall be randomly sampled for testing in accordance with ASTM D 4354, Procedure A. Acceptance of geotextile shall be in accordance with ASTM D 4759. Tests not meeting the design requirements shall result in the rejection of applicable rolls.

PART 3 EXECUTION

3.1 QUALITY ASSURANCE SAMPLES AND TESTS

3.1.1 Quality Assurance Samples

The Contractor shall provide assistance to the Contracting Officer in the collection of quality assurance samples. Samples shall be collected upon delivery to the site for quality assurance testing at the request of the Contracting Officer and in accordance with ASTM D 4354, Procedure B. Lot size for quality assurance sampling shall be considered to be the shipment quantity of the product or a truckload of the product, whichever is smaller. The unit size shall be considered one roll of geotextile at a frequency of one per 10,000 square meters. Samples shall be identified with a waterproof marker by manufacturer's name, product identification, lot number, roll number, and machine direction. The date and a unique sample number shall also be noted on the sample. The outer layer of the geotextile roll shall be discarded prior to sampling a roll. Samples shall then be collected by cutting the full-width of the geotextile sheet a minimum of 1 meter long in the machine direction. Rolls which are sampled shall be immediately resealed in their protective covering.

3.1.2 Quality Assurance Tests

The Contractor shall provide quality assurance samples to an Independent Laboratory. Samples will be tested to verify that geotextile meets the requirements. Test method ASTM D 4355 shall not be performed on the collected samples. Geotextile product acceptance shall be based on

ASTM D 4759. Tests not meeting the specified requirements shall result in the rejection of applicable rolls.

3.2 INSTALLATION

3.2.1 Subgrade Preparation

The surface underlying the geotextile shall be smooth and free of ruts or protrusions which could damage the geotextile. Subgrade materials and compaction requirements shall be in accordance with Section 31 00 00.

3.2.2 Placement

The Contractor shall notify the Contracting Officer a minimum of 24 hours prior to installation of geotextile. Geotextile rolls which are damaged or contain imperfections shall be repaired or replaced as directed. The geotextile shall be laid flat and smooth so that it is in direct contact with the subgrade. The geotextile shall also be free of tensile stresses, folds, and wrinkles. On slopes steeper than 10 horizontal on 1 vertical, the geotextile shall be laid with the machine direction of the fabric parallel to the slope direction.

3.3 SEAMS

3.3.1 Overlap Seams

Geotextile panels shall be continuously overlapped a minimum of 300 mm at all longitudinal and transverse joints. Where seams must be oriented across the slope, the upper panel shall be lapped over the lower panel. If approved, sewn seams may be used instead of overlapped seams.

3.3.2 Sewn Seams

Factory and field seams shall be continuously sewn on all slopes steeper than 1 vertical on 4 horizontal. The stitch type used shall be a 401 locking chain stitch or as recommended by the manufacturer. For factory seams which are sewn, the Contractor shall provide at least a 2-meter sample of sewn seam before the geotextile is installed. For seams that are field sewn, the seams shall be sewn using the same equipment and procedures as will be used for the production seams. If seams are sewn in both the machine and cross machine direction, samples of seams from both directions shall be provided. Quality Assurance seam samples shall be provided to the Government at the request of the Contracting Officer. Seam strength shall meet the minimum requirements. The thread at the end of each seam run shall be tied off to prevent unraveling. Skipped stitches or discontinuities shall be sewn with an extra line of stitching with a minimum of 450 mm of overlap.

3.4 PROTECTION

The geotextile shall be protected during installation from clogging, tears, and other damage. Damaged geotextile shall be repaired or replaced as directed. Adequate ballast (e.g. sand bags) shall be used to prevent uplift by wind. The geotextile shall not be left uncovered for more than 14 days after installation.

3.5 REPAIRS

Torn or damaged geotextile shall be repaired. Clogged areas of geotextile

shall be removed. Repairs shall be performed by placing a patch of the same type of geotextile over the damaged area. The patch shall extend a minimum of 300 mm beyond the edge of the damaged area. Patches shall be continuously fastened using approved methods. The machine direction of the patch shall be aligned with the machine direction of the geotextile being repaired. Geotextile rolls which cannot be repaired shall be removed and replaced. Repairs shall be performed at no additional cost to the Government

3.6 PENETRATIONS

Engineered penetrations of the geotextile shall be constructed by methods recommended by the geotextile manufacturer.

3.7 COVERING

Geotextile shall not be covered prior to inspection and approval by the Contracting Officer. Cover material shall be placed in a manner that prevents soil from entering the geotextile overlap zone, prevents tensile stress from being mobilized in the geotextile, and prevents wrinkles from folding over onto themselves. On side slopes, cover material shall be placed from the bottom of the slope upward. Cover material shall not be dropped onto the geotextile from a height greater than 1 m. No equipment shall be operated directly on top of the geotextile without approval of the Contracting Officer. Equipment with ground pressures less than 50 kPa shall be used to place the first lift over the geotextile. A minimum of 300 mm of cover material shall be maintained between full-scale construction equipment and the geotextile. Equipment placing cover material shall not stop abruptly, make sharp turns, spin their wheels, or travel at speeds exceeding 2.2 m/s.

-- End of Section --

SECTION 31 11 00

CLEARING AND GRUBBING
04/06

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Nonsaleable Materials; G

Written permission to dispose of such products on private property shall be filed with the Contracting Officer.

SD-04 Samples

Tree wound paint

Herbicide

Submit samples in cans with manufacturer's label.

1.2 DELIVERY, STORAGE, AND HANDLING

Deliver materials to, store at the site, and handle in a manner which will maintain the materials in their original manufactured or fabricated condition until ready for use.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 PROTECTION

3.1.1 Roads and Walks

Keep roads and walks free of dirt and debris at all times.

3.1.2 Trees, Shrubs, and Existing Facilities

Trees and vegetation to be left standing shall be protected from damage incident to clearing, grubbing, and construction operations by the erection of barriers or by such other means as the circumstances require.

3.1.3 Utility Lines

Protect existing utility lines from damage. Notify the Contracting Officer immediately of damage to or an encounter with an unknown existing utility line. The Contractor shall be responsible for the repairs of damage to existing utility lines that are indicated or made known to the Contractor prior to start of clearing and grubbing operations. When utility lines

which are to be removed are encountered within the area of operations, the Contractor shall notify the Contracting Officer in ample time to minimize interruption of the service.

3.2 CLEARING

Clearing shall consist of the felling, trimming, and cutting of trees into sections and the satisfactory disposal of the trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within the areas to be cleared. Clearing shall also include the removal and disposal of structures that obtrude, encroach upon, or otherwise obstruct the work. Trees, stumps, roots, brush, and other vegetation in areas to be cleared shall be cut off flush with or below the original ground surface, except such trees and vegetation as may be indicated or directed to be left standing. Trees designated to be left standing within the cleared areas shall be trimmed of dead branches 40 mm or more in diameter and shall be trimmed of all branches the heights indicated or directed. Limbs and branches to be trimmed shall be neatly cut close to the bole of the tree or main branches. Cuts more than 40 mm in diameter shall be painted with an approved tree-wound paint.

3.3 TREE REMOVAL

Where indicated or directed, trees and stumps that are designated as trees shall be removed from areas outside those areas designated for clearing and grubbing. This work shall include the felling of such trees and the removal of their stumps and roots as specified in paragraph GRUBBING. Trees shall be disposed of as specified in paragraph DISPOSAL OF MATERIALS.

3.4 PRUNING

Prune trees designated to be left standing within the cleared areas of dead branches 38 mm or more in diameter; and trim branches to heights and in a manner as indicated. Neatly cut limbs and branches to be trimmed close to the bole of the tree or main branches. Paint cuts more than 32 mm in diameter with an approved tree wound paint.

3.5 GRUBBING

Grubbing shall consist of the removal and disposal of stumps, roots larger than 75 mm in diameter, and matted roots from the designated grubbing areas. Material to be grubbed, together with logs and other organic or metallic debris not suitable for foundation purposes, shall be removed to a depth of not less than 455 mm below the original surface level of the ground in areas indicated to be grubbed and in areas indicated as construction areas under this contract, such as areas for buildings, and areas to be paved. Depressions made by grubbing shall be filled with suitable material and compacted to make the surface conform with the original adjacent surface of the ground.

3.6 DISPOSAL OF MATERIALS

3.6.1 Saleable Timber

All timber, limbs, tops, stumps, and debris shall be cleared and disposed of by the Contractor as specified.

3.6.2 Nonsaleable Materials

Logs, stumps, roots, brush, rotten wood, and other refuse from the clearing and grubbing operations, except for salable timber, shall be disposed of in the designated waste disposal area outside the limits of Government-controlled land at the Contractor's responsibility, or by burning, except when otherwise directed in writing. Such directive will state the conditions covering the disposal of such products and will also state the areas in which they may be placed. Refuse to be burned shall be burned at specified locations and in a manner to prevent damage to existing structures and appurtenances, construction in progress, trees, and other vegetation. The Contractor shall be responsible for compliance with all Federal and State laws and regulations and with reasonable practice relative to the building of fires. Burning or other disposal of refuse and debris and any accidental loss or damage attendant thereto shall be the Contractor's responsibility.

-- End of Section --

SECTION 31 23 00.00 20

EXCAVATION AND BACKFILLING FOR UTILITIES AND STRUCTURES
04/06

PART 1 GENERAL

This work shall consist of excavation/trenching, and furnishing and placement of bedding and backfilling material associated with the installation of drainage pipes and structure foundations. The work also shall include furnishing, placing and removal of sheeting and shoring (if required), pumping and bailing, and all incidentals necessary to complete the work required by this section. This section shall be coordinated with requirements of Secrtion 31 00 00, EARTHWORK.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C600	(2005) Installation of Ductile-Iron Water Mains and Their Appurtenances

ASTM INTERNATIONAL (ASTM)

ASTM C 117	(2004) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C 33	(2003) Standard Specification for Concrete Aggregates
ASTM D 1557	(2002e1) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D 2216	(2005) Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D 2321	(2005) Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications
ASTM D 2487	(2006) Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 422	(1963; R 2002e1) Particle-Size Analysis of Soils

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008) Safety and Health Requirements Manual

1.2 DEFINITIONS

1.2.1 Degree of Compaction

As defined in Specification Section 31 00 00.

1.2.2 Hard Materials

As defined in Specification Section 31 00 00.

1.2.3 Rock

As defined in Specification Section 31 00 00.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Shoring and Sheeting Plan

Dewatering work plan

Submit 15 days prior to starting work.

SD-06 Test Reports

Borrow Site Testing; G

Fill and backfill test

Select material test

Density tests

Moisture Content Tests

Copies of all laboratory and field test reports within 24 hours of the completion of the test.

1.4 DELIVERY, STORAGE, AND HANDLING

Perform in a manner to prevent contamination or segregation of materials.

1.5 QUALITY ASSURANCE

1.5.1 Shoring and Sheeting Plan

Submit drawings and calculations, certified by a registered professional

engineer, describing the methods for shoring and sheeting of excavations. Drawings shall include material sizes and types, arrangement of members, and the sequence and method of installation and removal. Calculations shall include data and references used.

1.5.2 Dewatering Work Plan

Submit procedures for accomplishing dewatering work.

1.5.3 Utilities

Movement of construction machinery and equipment over pipes and utilities during construction shall be at the Contractor's risk. Perform work adjacent to utilities in accordance with procedures outlined by the utility company. Excavation made with power-driven equipment is not permitted within 600 mm of known utilities or subsurface construction. For work immediately adjacent to or for excavations exposing a utility or other buried obstruction, excavate by hand. Start hand excavation on each side of the indicated obstruction and continue until the obstruction is uncovered or until clearance for the new grade is assured. Support uncovered lines or other existing work affected by the contract excavation until approval for backfill is granted by the Contracting Officer. Report damage to utility lines or subsurface construction immediately to the Contracting Officer.

PART 2 PRODUCTS

2.1 SOIL MATERIALS

2.1.1 Satisfactory Materials for Use as Pipe Bedding and Backfill

Any materials classified by ASTM D 2487 as GW, GP, GM, GP-GM, GW-GM, GC, GP-GC, GM-GC, SW, SP, free of debris, roots, wood, scrap material, vegetation, refuse, soft unsound particles, and frozen, deleterious, or objectionable materials. Unless specified otherwise, the maximum particle diameter shall be one-half the lift thickness at the intended location. Grain size determination shall be made by the contractor in conformance with ASTM C 117, ASTM C 136, and ASTM D 422

2.1.2 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials. Unsatisfactory materials also include man-made fills, trash, refuse, or backfills from previous construction. Unsatisfactory material also includes material classified as satisfactory which contains root and other organic matter, frozen material, and stones larger than 75 mm. The Contracting Officer shall be notified of any contaminated materials.

2.1.3 Cohesionless and Cohesive Materials

Cohesionless materials include materials classified in ASTM D 2487 as GW, GP, SW, and SP. Cohesive materials include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM, GP-GM, GW-GM, SW-SM, SP-SM, and SM shall be identified as cohesionless only when the fines are nonplastic (plasticity index equals zero). Materials classified as GM and SM will be identified as cohesive only when the fines have a plasticity index greater than zero.

2.1.4 Expansive Soils

As defined in Specification Section 31 00 00.

2.1.5 Backfill and Fill Material

As defined in Specification Section 31 00 00.

2.1.6 Select granular Material

As defined in Specification Section 31 00 00.

2.1.7 Topsoil

Topsoil shall be as defined in Specification Section 31 00 00.

2.2 PIPE BEDDING MATERIAL

Except as specified otherwise in the individual piping section, provide bedding for buried piping in accordance with AWWA C600, Type 4, except as specified herein. Backfill to top of pipe shall be compacted to 95 percent of ASTM D 1557 maximum dry density. Plastic piping shall have bedding to spring line of pipe. Provide ASTM D 2321 materials as follows:

a. Class I: Angular, 6 to 40 mm, graded stone, including a number of fill materials that have regional significance such as coral, slag, cinders, crushed stone, and crushed shells.

b. Class II: Coarse sands and gravels with maximum particle size of 40 mm, including various graded sands and gravels containing small percentages of fines, generally granular and noncohesive, either wet or dry. Soil Types GW, GP, SW, and SP are included in this class as specified in ASTM D 2487.

2.3 RIP-RAP MATERIALS

Provide bedding material or geotextile and rock conforming to these requirements.

2.3.1 Bedding Material

Provide bedding material consisting of sand, gravel, or crushed rock, well graded, with a maximum particle size of 50 mm. Compose material of tough, durable particles. Allow fines passing the 75 micrometers standard sieve with a plasticity index less than six.

2.3.2 Rock

Provide rock fragments sufficiently durable to ensure permanence in the structure and the environment in which it is to be used. Use rock fragments free from cracks, seams, and other defects that would increase the risk of deterioration from natural causes. Provide fragments that are well graded and sized to prevent movement during the design storm event.

2.4 SEWAGE ABSORPTION TRENCHES

2.4.1 Porous Fill

Backfill material consisting of clean crushed rock or gravel having a

gradation such that 100 percent passes the 65 mm sieve and zero percent passes the 12.5 mm sieve and conforming to the gradation requirements for coarse aggregate in ASTM C 33.

2.4.2 Cover

Geotextile conforming to Specification Section 31 05 19 or a layer of straw at least 50 mm thick as indicated.

2.5 BORROW

Obtain borrow materials required in excess of those furnished from excavations from sources outside of Government property.

2.6 BURIED WARNING AND IDENTIFICATION TAPE

Polyethylene plastic and metallic core or metallic-faced, acid- and alkali-resistant, polyethylene plastic warning tape manufactured specifically for warning and identification of buried utility lines. Provide tape on rolls, 75 mm minimum width, color coded as specified below for the intended utility with warning and identification imprinted in bold black letters continuously over the entire tape length. Warning and identification to read, "CAUTION, BURIED (intended service) LINE BELOW" or similar wording. Color and printing shall be permanent, unaffected by moisture or soil.

Warning Tape Color Codes

Yellow:	Electric
Orange:	Telephone and Other Communications
Blue:	Water Systems
Green:	Sewer Systems

2.6.1 Detectable Warning Tape for Non-Metallic Piping

Polyethylene plastic tape conforming to the width, color, and printing requirements specified above. Minimum thickness of the tape shall be 0.10 mm. Tape shall have a minimum strength of 10.3 MPa lengthwise and 8.6 MPa crosswise. Tape shall be manufactured with integral wires, foil backing, or other means of enabling detection by a metal detector when tape is buried up to 920 mm deep. Encase metallic element of the tape in a protective jacket or provide with other means of corrosion protection.

PART 3 EXECUTION

3.1 PROTECTION

3.1.1 Shoring and Sheeting

Provide shoring, bracing, cribbing, trench boxes, underpinning, and sheeting where indicated. In addition to Section 25 A and B of EM 385-1-1 and other requirements set forth in this contract, include provisions in the shoring and sheeting plan that will accomplish the following:

a. Prevent undermining of pavements, foundations and slabs.

b. Prevent slippage or movement in banks or slopes adjacent to the excavation.

3.1.2 Drainage and Dewatering

Drainage and dewatering shall be in accordance with Specification Section 31 00 00.

3.1.3 Underground Utilities

The Contractor shall physically verify the location and elevation of the existing utilities prior to starting construction.

3.1.4 Machinery and Equipment

Movement of construction machinery and equipment over pipes during construction shall be at the Contractor's risk. Repair, or remove and provide new pipe for existing or newly installed pipe that has been displaced or damaged.

3.2 SURFACE PREPARATION

3.2.1 Clearing and Grubbing

Clearing and gubbing shall be in accordance with Specification Section 31 00 00.

3.2.2 Stripping

Strip suitable topsoil from the site where excavation or grading is indicated and stockpile separately from other excavated material. Material unsuitable for use as topsoil shall be wasted or shall be stockpiled and used for backfilling. Locate topsoil so that the material can be used readily for the finished grading. Where sufficient existing topsoil conforming to the material requirements is not available on site, provide borrow materials suitable for use as topsoil. Protect topsoil and keep in segregated piles until needed.

3.2.3 Unsuitable Material

Remove vegetation, debris, decayed vegetable matter, sod, mulch, and rubbish underneath paved areas or concrete slabs.

3.3 EXCAVATION

Excavate to contours, elevation, and dimensions required. Reuse excavated materials that meet the specified requirements for the material type required at the intended location. Keep excavations free from water. Excavate soil disturbed or weakened by Contractor's operations, soils softened or made unsuitable for subsequent construction due to exposure to weather. Excavations below indicated depths will not be permitted except to remove unsatisfactory material. Unsatisfactory material encountered below the grades shown shall be removed as directed. Refill with satisfactory material and compact to 95 percent of ASTM D 1557 maximum dry density. Unless specified otherwise, refill excavations cut below indicated depth with satisfactory material and compact to 95 percent of ASTM D 1557 maximum dry density. Satisfactory material removed below the depths indicated, without specific direction of the Contracting Officer, shall be replaced with satisfactory materials to the indicated excavation grade; except as specified for spread footings. Determination of elevations and measurements of approved overdepth excavation of

unsatisfactory material below grades indicated shall be done under the direction of the Contracting Officer.

3.3.1 Pipe Trenches

Excavate to the dimension indicated. Grade bottom of trenches to provide uniform support for each section of pipe after pipe bedding placement. Tamp if necessary to provide a firm pipe bed. Recesses shall be excavated to accommodate bells and joints so that pipe will be uniformly supported for the entire length. Rock, where encountered, shall be excavated to a depth of at least 150 mm below the bottom of the pipe.

3.3.2 Structures

Make excavations to the lines, grades, and elevations shown, or as directed. Provide trenches and foundation pits of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations. Clean rock or other hard foundation material of loose debris and cut to a firm, level, stepped, or serrated surface. Remove loose disintegrated rock and thin strata. Do not disturb the bottom of the excavation when concrete or masonry is to be placed in an excavated area. Do not excavate to the final grade level until just before the concrete or masonry is to be placed.

Inspections to determine adequacy of the foundations will be performed by a licensed Geotechnical Engineer in the presence of the Contracting Officer in all foundation areas between completion of excavation and placement of concrete. The Contractor will cooperate to the extent necessary to assist in inspection. Coordinate the schedule for foundation excavation and preliminary cleanup with the Contracting Officer to ensure that the cleanup, inspection and proceed in an orderly manner.

3.3.3 Hard Material and Rock Excavation

Remove hard material and rock to elevations indicated in a manner that will leave foundation material in an unshattered and solid condition. Roughen level surfaces and cut sloped surfaces into benches for bond with concrete. Protect shale from conditions causing decomposition along joints or cleavage planes and other types of erosion. Removal of hard material and rock beyond lines and grades indicated will not be grounds for a claim for additional payment unless previously authorized by the Contracting Officer. Excavation of the material claimed as rock shall not be performed until the material has been cross sectioned by the Contractor and approved by the Contracting Officer. Common excavation shall consist of all excavation not classified as rock excavation.

3.3.4 Excavated Materials

Satisfactory excavated material required for fill or backfill shall be placed in the proper section of the permanent work required or shall be separately stockpiled if it cannot be readily placed. Satisfactory material in excess of that required for the permanent work and all unsatisfactory material shall be disposed of as specified in Section 31 00 00.

3.3.5 Final Grade of Surfaces to Support Concrete

Excavation to final grade shall not be made until just before concrete is to be placed. Only excavation methods that will leave the foundation rock

in a solid and unshattered condition shall be used. Approximately level surfaces shall be roughened, and sloped surfaces shall be cut as indicated into rough steps or benches to provide a satisfactory bond. All surfaces shall be protected from erosion resulting from ponding or flow of water.

3.4 FILLING AND BACKFILLING

Fill and backfill to contours, elevations, and dimensions indicated. Compact each lift before placing overlaying lift.

3.4.1 Backfill and Fill Material Placement

Place in 150 mm lifts. Do not place over wet or frozen areas. Place backfill material adjacent to structures as the structural elements are completed and accepted. Backfill against concrete only when approved. Place and compact material to avoid loading upon or against the structure.

3.4.2 Select Granular Material Placement

Place in 150 mm lifts. Do not place over wet or frozen areas. Backfill adjacent to structures shall be placed as structural elements are completed and accepted. Backfill against concrete only when approved. Place and compact material to avoid loading upon or against structure.

3.4.3 Backfill and Fill Material Placement Over Pipes and at Walls

Backfilling shall not begin until construction below finish grade has been approved, underground utilities systems have been inspected, tested and approved, forms removed, and the excavation cleaned of trash and debris. Backfill shall be brought to indicated finish grade and shall include backfill for outside grease interceptors. Where pipe is coated or wrapped for protection against corrosion, the backfill material up to an elevation 600 mm above sewer lines and 300 mm above other utility lines shall be free from stones larger than 25 mm in any dimension. Heavy equipment for spreading and compacting backfill shall not be operated closer to foundation or retaining walls than a distance equal to the height of backfill above the top of footing; the area remaining shall be compacted in layers not more than 100 mm in compacted thickness with power-driven hand tampers suitable for the material being compacted. Backfill shall be placed carefully around pipes or tanks to avoid damage to coatings, wrappings, or tanks. Backfill shall not be placed against foundation walls prior to 7 days after completion of the walls. As far as practicable, backfill shall be brought up evenly on each side of the wall and sloped to drain away from the wall.

3.4.4 Porous Fill Placement

Place in 100 mm lifts with a minimum of two passes of a hand-operated plate-type vibratory compactor.

3.4.5 Trench Backfilling

Backfill as rapidly as construction, testing, and acceptance of work permits. Place and compact backfill under structures and paved areas in 150 mm lifts to top of trench and in 150 mm lifts to 300 mm over pipe outside structures and paved areas.

3.5 BORROW

Where satisfactory materials are not available in sufficient quantity from required excavations, approved borrow materials shall be obtained as specified herein.

3.6 BURIED WARNING AND IDENTIFICATION TAPE

Provide buried utility lines with utility identification tape. Bury tape 300 mm below finished grade; under pavements and slabs, bury tape 150 mm below top of subgrade.

3.7 BURIED DETECTION WIRE

Bury detection wire directly above non-metallic piping at a distance not to exceed 300 mm above the top of pipe. The wire shall extend continuously and unbroken, from manhole to manhole. The ends of the wire shall terminate inside the manholes at each end of the pipe, with a minimum of 0.9 m of wire, coiled, remaining accessible in each manhole. The wire shall remain insulated over it's entire length. The wire shall enter manholes between the top of the corbel and the frame, and extend up through the chimney seal between the frame and the chimney seal. For force mains, the wire shall terminate in the valve pit at the pump station end of the pipe.

3.8 COMPACTION

Material placement and compaction shall be in accordance with Specification Section 31 00 00.

3.9 SPECIAL EARTHWORK REQUIREMENTS FOR SUBSURFACE DRAINS

Excavate to dimensions indicated. Place select granular material in 150 mm lifts and compact with mechanical, vibrating plate tampers or rammers until no further consolidation can be achieved. Compact backfill overlying the select granular material as specified for adjacent or overlying work.

3.9.1 Granular Backfill Using Geotextile

Where goetextile is needed to prevent piping of soil into the drain, install geotextile in trenches with smoothly graded sides and bottom, free of cavities or projecting rocks. Lay the fabric flat but not stretched and secure with anchor pins. Place geotextile so that drain water must pass through the cloth into the specified granular filter material. Overlap ends at least of 300 mm. Place backfill on geotextile in the direction of overlaps. Where fabric is damaged, place a new piece of geotextile over damaged area and overlap at least of 300 mm in every direction.

3.10 EARTHWORK REQUIREMENTS FOR SEWAGE ABSORPTION TRENCHES

Provide sewage absorption trench as indicated. Grade trenches uniformly downward to ends of laterals. Place porous fill around and over pipe as indicated. Take special care to prevent displacement of or damage to pipe or pit walls. Cover porous fill with geotextile as indicated before continuing with backfill for adjacent or overlying work.

3.11 RIP-RAP CONSTRUCTION

Construct rip-rap on bedding material or geotextile filter.

3.11.1 Preparation

Trim and dress indicated areas to conform to cross sections, lines and grades shown within a tolerance of 30 mm.

3.11.2 Filter Placement

If bedding material is used as the filter, spread the material uniformly to a thickness of at least 75 mm on prepared subgrade as indicated. Compaction of bedding is not required. Finish bedding to present even surface free from mounds and windrows. Place geotextile filter in accordance with Specification Section 31 00 00.

3.11.3 Stone Placement

Place rock for rip-rap on prepared filter material to produce a well graded mass with the minimum practicable percentage of voids in conformance with lines and grades indicated. Distribute larger rock fragments, with dimensions extending the full depth of the rip-rap throughout the entire mass and eliminate "pockets" of small rock fragments. Rearrange individual pieces by mechanical equipment or by hand as necessary to obtain the distribution of fragment sizes specified above.

3.12 FINISH OPERATIONS

3.12.1 Grading

Finish grades as indicated within 30 mm. Grade areas to drain water away from structures. Maintain areas free of trash and debris. For existing grades that will remain but which were disturbed by Contractor's operations, grade as directed.

3.12.2 Topsoil and Seed

Provide as specified in Section 32 92 19 SEEDING.

3.12.3 Protection of Surfaces

Protect newly backfilled, graded, and topsoiled areas from traffic, erosion, and settlements that may occur. Repair or reestablish damaged grades, elevations, or slopes.

3.13 FIELD QUALITY CONTROL

3.13.1 Sampling

Take the number and size of samples required to perform the following tests.

3.13.2 Testing

Material testing shall be in accordance with Specification Section 31 00 00 except that in-place density testing shall be performed at a rate of one test per 15 m of trench per lift.

3.13.2.1 Porous Fill Testing

Test porous fill in accordance with ASTM C 136 for conformance to gradation specified in ASTM C 33.

3.13.2.2 Moisture Content Tests

In the stockpile, excavation or borrow areas, a minimum of two tests per day per type of material or source of materials being placed is required during stable weather conditions. During unstable weather, tests shall be made as dictated by local conditions and approved moisture content shall be tested in accordance with ASTM D 2216. Include moisture content test results in daily report.

-- End of Section --

SECTION 31 32 11

SOIL SURFACE EROSION CONTROL

10/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 1560	(2005e1) Resistance to Deformation and Cohesion of Bituminous Mixtures by Means of Hveem Apparatus
ASTM D 2028	(1997; R 2004) Cutback Asphalt (Rapid-Curing Type)
ASTM D 1777	(1996; R 2002) Thickness of Textile Materials
ASTM D 2844	(2001e1) Resistance R-Value and Expansion Pressure of Compacted Soils
ASTM D 3776	(1996; R 2002) Mass Per Unit Area (Weight) of Fabric
ASTM D 3787	(2001) Bursting Strength of Textiles - Constant-Rate-of-Traverse (CRT), Ball Burst Test
ASTM D 3884	(2001e1) Abrasion Resistance of Textile Fabrics (Rotary Platform, Double-Head Method)
ASTM D 4355	(2005) Deterioration of Geotextiles from Exposure to Light, Moisture and Heat in a Xenon-Arc Type Apparatus
ASTM D 4491	(1999; R 2004e1) Water Permeability of Geotextiles by Permittivity
ASTM D 4533	(2004) Trapezoid Tearing Strength of Geotextiles
ASTM D 4632	(1991; R 2003) Standard Test Method for Grab Breaking Load and Elongation of Geotextiles
ASTM D 4751	(2004) Determining Apparent Opening Size of a Geotextile

ASTM D 4833	(2000e1) Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products
ASTM D 4972	(2001) pH of Soils
ASTM D 5268	(2002) Topsoil Used for Landscaping Purposes
ASTM D 977	(2005) Emulsified Asphalt

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Work sequence schedule; G
Erosion control plan; G

SD-02 Shop Drawings

Erosion Control;G

Scale drawings defining areas to receive recommended materials as required by federal, state or local regulations.

Seed Establishment Period

Calendar time period for the seed establishment period. When there is more than one seed establishment period, the boundaries of the seeded area covered for each period shall be described.

Maintenance Record

Record of maintenance work performed, of measurements and findings for product failure, recommendations for repair, and products replaced.

SD-03 Product Data

Manufacturer's literature including physical characteristics, application and installation instructions.

SD-07 Certificates

Fill Material
Mulch
Hydraulic Mulch
Geotextile Fabrics

Prior to delivery of materials, certificates of compliance attesting that materials meet the specified requirements. Certified copies of the material certificates shall include the following.

For items listed in this section:

a. Certification of recycled content or,

b. Statement of recycled content.

c. Certification of origin including the name, address and telephone number of manufacturer.

Geosynthetic Binders
Synthetic Soil Binders

Certification for binders showing EPA registered uses, toxicity levels, and application hazards.

Installer's Qualification

The installer's company name and address; training and experience and or certification.

Recycled Plastic

Individual component and assembled unit structural integrity test; creep tolerance; deflection tolerance; and vertical load test results. Life-cycle durability.

Seed

Classification, botanical name, common name, percent pure live seed, minimum percent germination and hard seed, maximum percent weed seed content, and date tested.

Asphalt Adhesive
Tackifier

Composition.

Wood By-Products

Composition, source, and particle size. Products shall be free from toxic chemicals or hazardous material.

Wood Cellulose Fiber

Certification stating that wood components were obtained from managed forests.

SD-10 Operation and Maintenance Data

Maintenance Instructions

Instruction for year-round care of installed material. The Contractor shall include manufacturer supplied spare parts.

1.3 MEASUREMENT AND PAYMENT

No separate measurement and payment shall be made for Soil Surface Erosion Control measures.

1.4 DESCRIPTION OF WORK

The work consists of furnishing and installing temporary and permanent soil surface erosion control materials, including fine grading, blanketing, stapling, mulching and miscellaneous related work, within project limits and in areas outside the project limits where the soil surface is disturbed from work under this contract at the designated locations. This work includes all necessary materials, labor, supervision and equipment for installation of a complete system.

1.5 DELIVERY, INSPECTION, STORAGE, AND HANDLING

Store materials in designated areas and as recommended by the manufacturer protected from the elements, direct exposure, and damage. Do not drop containers from trucks. Material shall be free of defects that would void required performance or warranty. Deliver geosynthetic binders and synthetic soil binders in the manufacturer's original sealed containers and stored in a secure area.

a. Furnish erosion control blankets and geotextile fabric in rolls with suitable wrapping to protect against moisture and extended ultraviolet exposure prior to placement. Label erosion control blanket and geotextile fabric rolls to provide identification sufficient for inventory and quality control purposes.

b. Seed shall be appropriate for the region and inspected upon arrival at the jobsite for quality. Seed that is wet, moldy, or bears a test date five months or older, shall be rejected.

1.6 QUALITY ASSURANCE

1.6.1 Installer's Qualification

The installer shall be certified by the manufacturer for training and experience installing the material.

1.7 TIME LIMITATIONS

Complete backfilling the openings in synthetic grid systems a maximum 7 days after placement to protect the material from ultraviolet radiation.

1.8 WARRANTY

Erosion control material shall have a warranty for use and durable condition for project specific installations. Temporary erosion control materials shall carry a minimum eighteen month warranty. Permanent erosion control materials shall carry a minimum three year warranty.

PART 2 PRODUCTS

2.1 BINDERS

2.1.1 Synthetic Soil Binders

Calcium chloride, or other standard manufacturer's spray on adhesives designed for dust suppression.

2.1.2 Geosynthetic Binders

Geosynthetic binders shall be manufactured in accordance with ASTM D 1560, ASTM D 2844; and shall be referred to as products manufactured for use as modified emulsions for the purpose of erosion control and soil stabilization. Emulsions shall be manufactured from all natural materials and provide a hard durable finish.

2.2 MULCH

Mulch shall be free from weeds, mold, and other deleterious materials. Mulch materials shall be native to the region.

2.2.1 Straw

Straw shall be stalks from oats, wheat, rye, barley, or rice, furnished in air-dry condition and with a consistency for placing with commercial mulch-blowing equipment.

2.2.2 Hay

Hay shall be native hay, sudan-grass hay, broomsedge hay, or other herbaceous mowings, furnished in an air-dry condition suitable for placing with commercial mulch-blowing equipment.

2.2.3 Wood Cellulose Fiber

Wood cellulose fiber shall be 100 percent recycled material and shall not contain any growth or germination-inhibiting factors and shall be dyed with non-toxic, biodegradable dye an appropriate color to facilitate placement during application. Composition on air-dry weight basis: a minimum 9 to a maximum 15 percent moisture, and between a minimum 4.5 to a maximum 6.0 pH.

2.2.4 Paper Fiber

Paper fiber mulch shall be 100 percent post-consumer recycled news print that is shredded for the purpose of mulching seed.

2.2.5 Shredded Bark

Locally shredded material shall be treated to retard the growth of mold and fungi.

2.2.6 Wood By-Products

Wood locally chipped or ground bark shall be treated to retard the growth of mold and fungi. Gradation: A maximum 50 mm wide by 100 mm long.

2.2.7 Coir

Coir shall be manufactured from 100 percent coconut fiber cured in fresh water for a minimum of 6 months.

2.2.8 Asphalt Adhesive

Asphalt adhesive shall conform to the following: Emulsified asphalt, conforming to ASTM D 977, Grade SS-1; and cutback asphalt, conforming to ASTM D 2028, Designation RC-70.

2.2.9 Mulch Control Netting and Filter Fabric

Mulch control netting and filter fabric may be constructed of lightweight recycled plastic, cotton, or paper or organic fiber. The recycled plastic shall be a woven or nonwoven polypropylene, nylon, or polyester containing stabilizers and/or inhibitors to make the fabric resistant to deterioration from UV, and with the following properties:

a. Minimum grab tensile strength (TF 25 #1/ASTM D 4632), 0.8 kN.

b. Minimum Puncture (TF 25 #4/ASTM D 3787), 0.52 MPa in the weakest direction.

c. Apparent opening sieve size of a minimum 40 and maximum 80 (U.S. Sieve Size).

d. Minimum Trapezoidal tear strength (TF 25 #2/ASTM D 4533), 0.22 kN.

2.2.10 Hydraulic Mulch

Hydraulic mulch shall be made of 100 percent recycled material or virgin aspen wood fibers. Wood shall be naturally air-dried to a moisture content of 10.0 percent, plus or minus 3.0 percent. A minimum of 50 percent of the fibers shall be equal to or greater than 5 mm in length and a minimum of 75 percent of the fibers shall be retained on a 28 mesh screen. No reprocessed paper fibers shall be included in the hydraulic mulch. Hydraulic mulch shall have the following mixture characteristics:

CHARACTERISTIC (typical)	VALUE
pH	5.4 ± 0.1
Organic Matter (oven dried basis),	percent 99.3 within ± 0.2
Inorganic Ash (oven dried basis),	percent 0.7 within ± 0.2
Water Holding Capacity,	percent 1,401

2.2.11 Tackifier

Tackifier shall be a blended polyacrylimide material with non-ionic galactomannan of Gramineae endosperm in powder and crystalline form with molecular weights over 250,000.

2.2.12 Dye

Dye shall be a water-activated, green color. Pre-package dye in water dissolvable packets in the hydraulic mulch.

2.3 GEOTEXTILE FABRICS

Geotextile fabrics shall be woven of polyester or polypropylene filaments formed into a stable network so that the filaments retain their relative position to each other. Sewn seams shall have strength equal to or greater than the geotextile itself. Install fabric to withstand maximum velocity flows as recommended by the manufacturer. The geotextile shall conform to the following minimum average roll values:

Property	Performance	Test Method
Weight	264 g/m^2	ASTM D 3776
Thickness	0.635 mm	ASTM D 1777

Property	Performance	Test Method
Permeability	0.12 cm/sec	ASTM D 4491
Abrasion Resistance, Type (percent strength retained)	58 percent X 81 percent	ASTM D 3884
Tensile Grab Strength	1,467 N X 1, 933 N	ASTM D 4632
Grab Elongation	15percent X 20percent	ASTM D 4632
Burst Strength	5,510 kN/m^2	ASTM D 3787
Puncture Strength	733 N	ASTM D 4833
Trapezoid Tear	533 N X 533 N	ASTM D 4533
Apparent Opening Size	40 US Std Sieve	ASTM D 4751
UV Resistance @ 500 hrs	90 percent	ASTM D 4355

2.4 EROSION CONTROL BLANKETS

2.4.1 Erosion Control Blankets Type I

Use Type I blankets for erosion control and vegetation establishment on roadside embankments, abutments, berms, shoulders, and median swales where natural vegetation will provide long term stabilization. Erosion control blankets shall be a machine-produced mat of 100% straw. The blanket shall be of consistent thickness with the straw evenly distributed over the entire area of the mat. cover the blanket on the top side with a photodegradable polypropylene netting having an approximate 13 by 13 mm mesh and be sewn together on a maximum 40 mm centers with degradable thread. The erosion control blanket shall have the following properties:

Material Content

Straw	100 percent with approximately 0.27 kg/m^2 weight
Netting	One side only, lightweight photodegradable with approximately 8.0 kg/100 m^2 weight.
Thread	Degradable

Note 1: Photodegradable life a minimum of 2 months with a minimum 90 percent light penetration. Apply to slopes up to a maximum 3:1 gradient.

2.5 WATER

Unless otherwise directed, water is the responsibility of the Contractor.

PART 3 EXECUTION

3.1 CONDITIONS

Perform erosion control operations under favorable weather conditions; when excessive moisture, frozen ground or other unsatisfactory conditions prevail, the work shall be stopped as directed. When special conditions warrant a variance to earthwork operations, submit a revised construction schedule for approval. Do not apply erosion control materials in adverse weather conditions which could affect their performance.

3.1.1 Placement of Erosion Control Blankets

Before placing the erosion control blankets, ensure the subgrade has been graded smooth; has no depressed, void areas; is free from obstructions, such as tree roots, projecting stones or other foreign matter. Vehicles shall not be permitted directly on the blankets.

3.2 SITE PREPARATION

3.2.1 Soil Test

Test soil in accordance with ASTM D 5268 and ASTM D 4972 for determining the particle size and mechanical analysis. Sample collection onsite shall be random over the entire site. The test shall determine the soil particle size as compatible for the specified material.

3.2.2 Layout

Erosion control material locations may be adjusted to meet field conditions. When soil tests result in unacceptable particle sizes, a shop drawing shall be submitted indicating the corrective measures.

3.2.3 Protecting Existing Vegetation

When there are established lawns in the work area, the turf shall be covered and/or protected or replaced after construction operations. Identify existing trees, shrubs, plant beds, and landscape features that are to be preserved on site by appropriate tags and barricade with reusable, high-visibility fencing along the dripline. Mitigate damage to existing trees at no additional cost to the Government. Damage shall be assessed by a state certified arborist or other approved professional using the National Arborist Association's tree valuation guideline.

3.2.4 Obstructions Below Ground

When obstructions below ground affect the work, submit shop drawings showing proposed adjustments to placement of erosion control material for approval.

3.3 INSTALLATION

3.3.1 Synthetic Binders

Apply synthetic binders heaviest at edges of areas and at crests of ridges and banks to prevent displacement. Apply binders to the remainder of the area evenly at the rate recommended by the manufacturer.

3.3.2 Mulch Control Netting

Netting may be stapled over mulch according to manufacturer's recommendations.

3.3.3 Mechanical Anchor

Mechanical anchor shall be a V-type-wheel land packer; a scalloped-disk land packer designed to force mulch into the soil surface; or other suitable equipment.

3.3.4 Asphalt Adhesive Tackifier

Asphalt adhesive tackifier shall be sprayed at a rate between 666 to 866 L/hectare. Do no completely exclude sunlight from penetrating to the ground surface.

3.3.5 Non-Asphaltic Tackifier

Apply hydrophilic colloid at the rate recommended by the manufacturer, using hydraulic equipment suitable for thoroughly mixing with water. Apply a uniform mixture over the area.

3.3.6 Asphalt Adhesive Coated Mulch

Hay or straw mulch may be spread simultaneously with asphalt adhesive applied at a rate between 666 to 866 L/hectare, using power mulch equipment equipped with suitable asphalt pump and nozzle. Apply the adhesive-coated mulch evenly over the surface. Do not completely exclude sunlight from penetrating to the ground surface.

3.3.7 Wood Cellulose Fiber, Paper Fiber, and Recycled Paper

Apply wood cellulose fiber, paper fiber, or recycled paper as part of the hydraulic mulch operation.

3.3.8 Hydraulic Mulch Application

3.3.8.1 Unseeded Area

Install hydraulic mulch as indicated and in accordance with manufacturer's recommendations. Mix hydraulic mulch with water at the rate recommended by the manufacturer for the area to be covered. Mixing shall be done in equipment manufactured specifically for hydraulic mulching work, including an agitator in the mixing tank to keep the mulch evenly disbursed.

3.3.8.2 Seeded Area

For drill or broadcast seeded areas, apply hydraulic mulch evenly at an approved rate.

3.3.9 Erosion Control Blankets

a. Install erosion control blankets as indicated and in accordance with manufacturer's recommendations. The extent of erosion control blankets shall be as shown on drawings.

b. Orient erosion control blankets in vertical strips and anchored with staples, as indicated. Abut adjacent strips to allow for installation of a common row of staples. Overlap horizontal joints between erosion control blankets sufficiently to accommodate a common row of staples with the uphill end on top.

c. Where exposed to overland sheet flow, locate a trench at the uphill termination. Staple the erosion control blanket to the bottom of the trench. Backfill and compact the trench as required.

d. Where terminating in a channel containing an installed blanket, the erosion control blanket shall overlap installed blanket sufficiently to accommodate a common row of staples.

3.4 CLEAN-UP

Dispose of excess material, debris, and waste materials offsite at an approved landfill or recycling center. Clear adjacent paved areas. Immediately upon completion of the installation in an area, protect the area against traffic or other use by erecting barricades and providing signage as required, or as directed.

3.5 WATERING SEED

Apply water to supplement rainfall at a sufficient rate to ensure moist soil conditions to a minimum 25 mm depth. Prevent run-off and puddling. Do no drive watering trucks over turf areas, unless otherwise directed. Prevent watering of other adjacent areas or plant material.

3.6 MAINTENANCE RECORD

Furnish a record describing the maintenance work performed, record of measurements and findings for product failure, recommendations for repair, and products replaced.

3.6.1 Maintenance

Maintenance shall include eradicating weeds; protecting embankments and ditches from surface erosion; maintaining the performance of the erosion control materials and mulch; protecting installed areas from traffic.

3.6.2 Maintenance Instructions

Furnish written instructions containing drawings and other necessary information, describing the care of the installed material; including, when and where maintenance should occur, and the procedures for material replacement.

3.6.3 Patching and Replacement

Unless otherwise directed, material shall be placed, seamed or patched as recommended by the manufacturer. Remove material not meeting the required performance as a result of placement, seaming or patching from the site. Replace the unacceptable material at no additional cost to the Government.

-- End of Section --

SECTION 32 11 23

GRANULAR FILL AND STONE WATER CAPILLARY BARRIER
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(2009) Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and an 457-mm (18-in) Drop
AASHTO T 224	(2001; R 2004) Correction for Coarse Particles in the Soil Compaction Test

ASTM INTERNATIONAL (ASTM)

ASTM C 117	(2004) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 127	(2007) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate
ASTM C 128	(2007a) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate
ASTM C 131	(2006)Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C 29/C 29M	(2007) Standard Test Method for Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C 88	(2005) Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM D 1556	(2007) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(2007) Standard Test Methods for

	Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D 2167	(2008) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(2006e1) Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 4318	(2005) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D 5821	(2001: R 2006) Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D 6938	(2007a) Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)
ASTM D 75/D 75M	(2009) Standard Practice for Sampling Aggregates
ASTM E 11	(2009) Wire Cloth and Sieves for Testing Purposes

1.2 DEFINITIONS

For the purposes of this specification, the following definitions apply.

1.2.1 Graded-Crushed Aggregate Base Course

Graded-crushed aggregate (GCA) base course is well graded, crushed, durable aggregate uniformly moistened and mechanically stabilized by compaction. Indicated granular fill beneath pavement and stone water capillary barrier beneath interior slabs on grade shall be GCA.

1.2.2 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum laboratory dry density obtained by the test procedure presented in ASTM D 1557 abbreviated as a percent of laboratory maximum dry density. Since ASTM D 1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 19.0 mm sieve, the degree of compaction for material having more than 30 percent by weight of their particles retained on the 19.0 mm sieve are expressed as a percentage of the laboratory maximum dry density in accordance with AASHTO T 180 Method D and corrected with AASHTO T 224.

1.3 SYSTEM DESCRIPTION

All plant, equipment, and tools used in the performance of the work will be subject to approval before the work is started and shall be maintained in satisfactory working condition at all times. Provide adequate equipment having the capability of producing the required compaction, meeting grade controls, thickness control, and smoothness requirements as set forth herein.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Plant, Equipment, and Tools

List of proposed equipment to be used in performance of construction work, including descriptive data.

Waybills and Delivery Tickets

Copies of waybills and delivery tickets during the progress of the work.

SD-06 Test Reports

Sampling and Testing
Field Density Tests

Certified copies of test results for approval not less than 30 days before material is required for the work.

Calibration curves and related test results prior to using the device or equipment being calibrated.

Copies of field test results within 24 hours after the tests are performed.

1.5 QUALITY ASSURANCE

Sampling and testing are the responsibility of the Contractor and performed by an approved testing laboratory. Work requiring testing will not be permitted until the testing laboratory has been inspected and approved. Test the materials to establish compliance with the specified requirements; perform testing at the specified frequency. The Contracting Officer may specify the time and location of the tests. Furnish copies of test results to the Contracting Officer within 24 hours of completion of the tests.

1.5.1 Sampling

Take samples for laboratory testing in conformance with ASTM D 75/D 75M. When deemed necessary, the sampling will be observed by the Contracting Officer.

1.5.2 Tests

Perform the following tests in conformance with the applicable standards listed.

1.5.2.1 Sieve Analysis

Make sieve analysis in conformance with ASTM C 117 and ASTM C 136. Sieves

shall conform to ASTM E 11. .

1.5.2.2 Liquid Limit and Plasticity Index

Determine liquid limit and plasticity index in accordance with ASTM D 4318.

1.5.2.3 Moisture-Density Determinations

Determine the laboratory maximum dry density and optimum moisture content in accordance with ASTM D 1557 .

1.5.2.4 Field Density Tests

Measure field density in accordance with ASTM D 1556, ASTM D 2167 or ASTM D 6938.

1.5.2.5 Wear Test

Perform wear tests on GCA course material in conformance with ASTM C 131.

1.5.2.6 Soundness

Perform soundness tests on GCA in accordance with ASTM C 88.

1.5.2.7 Weight of Slag

Determine weight per cubic meter of slag in accordance with ASTM C 29/C 29M on the GCA course material.

1.5.3 Testing Frequency

1.5.3.1 Initial Tests

Perform one of each of the following tests, on the proposed material prior to commencing construction, to demonstrate that the proposed material meets all specified requirements when furnished. If materials from more than one source are going to be utilized, this testing shall be completed for each source.

a. Sieve Analysis

b. Liquid limit and plasticity index

c. Moisture-density relationship

d. Wear

e. Soundness

f. Weight per cubic meter of Slag

1.5.3.2 In Place Tests

Perform each of the following tests on samples taken from the placed and compacted GCA. Samples shall be taken and tested at the rates indicated. Perform sampling and testing of recycled concrete aggregate at twice the specified frequency until the material uniformity is established.

a. Perform density tests on every lift of material placed and at a

frequency of one set of tests for every 250 square meters , or portion thereof, of completed area.

b. Perform sieve analysis on every lift of material placed and at a frequency of one sieve analysis for every 500 square meters , or portion thereof, of material placed.

c. Perform liquid limit and plasticity index tests at the same frequency as the sieve analysis.

d. Measure the total thickness of the base course at intervals, in such a manner as to ensure one measurement for each 500 square meters of base course. Measurements shall be made in 75 mm diameter test holes penetrating the base course.

1.5.4 Approval of Material

Select the source of the material 30 days prior to the time the material will be required in the work. Tentative approval of material will be based on initial test results. Final approval of the materials will be based on sieve analysis, liquid limit, and plasticity index tests performed on samples taken from the completed and fully compacted course(s).

1.6 ENVIROMENTAL REQUIREMENTS

Perform construction when the atmospheric temperature is above 2 degrees C. When the temperature falls below 2 degrees C, protect all completed areas by approved methods against detrimental effects of freezing. Correct completed areas damaged by freezing, rainfall, or other weather conditions to meet specified requirements.

PART 2 PRODUCTS

2.1 AGGREGATES

Provide GCA consisting of clean, sound, durable particles of crushed stone, crushed slag, crushed gravel, crushed recycled concrete, angular sand, or other approved material. GCA shall be free of silt and clay as defined by ASTM D 2487, organic matter, and other objectionable materials or coatings. The portion retained on the 4.75 mm sieve is known as coarse aggregate; that portion passing the 4.75 mm sieve is known as fine aggregate.

2.1.1 Coarse Aggregate

Provide coarse aggregates with angular particles of uniform density. When the coarse aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements and shall be stockpiled separately.

a. Crushed Gravel: Crushed gravel shall be manufactured by crushing gravels, and shall meet all the requirements specified below.

b. Crushed Stone: Provide crushed stone consisting of freshly mined quarry rock, meeting all the requirements specified below.

c. Crushed Recycled Concrete: Provide crushed recycled concrete consisting of previously hardened portland cement concrete or other concrete containing pozzolanic binder material. The recycled material shall be free of all reinforcing steel, bituminous concrete surfacing,

and any other foreign material and shall be crushed and processed to meet the required gradations for coarse aggregate. Reject recycled concrete aggregate exceeding this value. Crushed recycled concrete shall meet all other applicable requirements specified below.

d. Crushed Slag: Crushed slag shall be an air-cooled blast-furnace product having an air dry unit weight of not less than 1120 kg/cubic meter as determined by ASTM C 29/C 29M, and shall meet all the requirements specified below.

2.1.1.1 Graded-Crushed Aggregate Fill (#2A) and Stone Water Capillary Barrier (#57)

GCA coarse aggregate shall not show more than 40 percent loss when subjected to the Los Angeles abrasion test in accordance with ASTM C 131. GCA coarse aggregate shall not exhibit a loss greater than 18 percent weighted average, at five cycles, when tested for soundness in magnesium sulfate, or 12 percent weighted average, at five cycles, when tested in sodium sulfate in accordance with ASTM C 88. The amount of flat and elongated particles shall not exceed 20 percent for the fraction retained on the 12.5 mm sieve nor 20 percent for the fraction passing the 12.5 mm sieve. A flat particle is one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3. In the portion retained on each sieve specified, the crushed aggregate shall contain at least 90 percent by weight of crushed pieces having two or more freshly fractured faces determined in accordance with ASTM D 5821. When two fractures are contiguous, the angle between planes of the fractures must be at least 30 degrees in order to count as two fractured faces. Crushed gravel shall be manufactured from gravel particles 90 percent of which by weight are retained on the maximum size sieve listed in TABLE 1.

2.1.2 Fine Aggregate

Fine aggregates shall be angular particles of uniform density. When the fine aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements.

2.1.2.1 Graded-Crushed Aggregate Fill and Stone Water Capillary Barrier

Provide GCA fine aggregate consisting of angular particles produced by crushing stone, slag, recycled concrete, or gravel that meets the requirements for wear and soundness specified for GCA coarse aggregate.

2.1.3 Gradation Requirements

Apply the specified gradation requirements to the completed GCA course. The aggregates shall be continuously well graded within the limits specified in TABLE 1. Sieves shall conform to ASTM E 11.

TABLE 1. GRADATION OF AGGREGATES

Percentage by Weight Passing Square-Mesh Sieve

Sieve Designation	No. 2A	No. 57
50.0 mm	100	----
37.5 mm	----	100
25.0 mm	----	95-100
19.0 mm	52-100	----
12.5 mm	----	25-60
9.5 mm	37-60	----
4.75 mm	24-50	0-10
2.36 mm	16-38	0-5
1.18 mm	10-30	----

NOTE 1: Particles having diameters less than 0.02 mm shall not be in excess of 3 percent by weight of the total sample tested.

NOTE 2: The values are based on aggregates of uniform specific gravity. If materials from different sources are used for the coarse and fine aggregates, they shall be tested in accordance with ASTM C 127 and ASTM C 128 to determine their specific gravities. If the specific gravities vary by more than 10 percent, the percentages passing the various sieves shall be corrected as directed by the Contracting Officer.

2.2 LIQUID LIMIT AND PLASTICITY INDEX

Apply liquid limit and plasticity index requirements to the completed course and to any component that is blended to meet the required gradation. The portion of any component or of the completed course passing the 0.425 mm sieve shall be either nonplastic or have a liquid limit not greater than 25 and a plasticity index not greater than 5.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

When the GCA is constructed in more than one layer, clean the previously constructed layer of loose and foreign matter by sweeping with power sweepers or power brooms, except that hand brooms may be used in areas where power cleaning is not practicable. Provide adequate drainage during the entire period of construction to prevent water from collecting or standing on the working area. Provide line and grade stakes as necessary for control. Grade stakes shall be in lines parallel to the centerline of the area under construction and suitably spaced for string lining.

3.2 OPERATION OF AGGREGATE SOURCES

Clearing, stripping, and excavating are the responsibility of the Contractor. Operate the aggregate sources to produce the quantity and quality of materials meeting the specified requirements in the specified time limit. Aggregate sources on private lands shall be conditioned in agreement with local laws or authorities.

3.3 STOCKPILING MATERIAL

Clear and level storage sites prior to stockpiling of material. Stockpile all materials, including approved material available from excavation and grading, in the manner and at the locations designated. Aggregates shall be stockpiled on the cleared and leveled areas designated by the Contracting Officer to prevent segregation. Materials obtained from different sources shall be stockpiled separately.

3.4 PREPARATION OF UNDERLYING COURSE

Prior to constructing the base course(s), the underlying course or subgrade shall be cleaned of all foreign substances. At the time of construction of the base course(s), the underlying course shall contain no frozen material. The surface of the underlying course or subgrade shall meet specified compaction and surface tolerances. The underlying course shall conform to Section 31 00 00 EARTHWORK. Ruts or soft yielding spots in the underlying courses, areas having inadequate compaction, and deviations of the surface from the requirements set forth herein shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line and grade, and recompacting to specified density requirements. For cohesionless underlying courses containing sands or gravels, as defined in ASTM D 2487, the surface shall be stabilized prior to placement of the base course(s). Stabilization shall be accomplished by mixing GCA into the underlying course and compacting by approved methods. The stabilized material shall be considered as part of the underlying course and shall meet all requirements of the underlying course. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained in a satisfactory condition until the base course is placed.

3.5 INSTALLATION

3.5.1 Mixing the Materials

Mix the coarse and fine aggregates in a stationary plant, or in a traveling plant or bucket loader on an approved paved working area. Make adjustments in mixing procedures or in equipment, as directed, to obtain true grades, to minimize segregation or degradation, to obtain the required water content, and to insure a satisfactory base course meeting all requirements of this specification.

3.5.2 Placing

Place the mixed material on the prepared subgrade in layers of uniform thickness with an approved spreader. When a compacted layer 150 mm or less in thickness is required, place the material in a single layer. When a compacted layer in excess of 150 mm is required, place the material in layers of equal thickness. No layer shall be thicker than 150 mm or thinner than 75 mm when compacted. The layers shall be so placed that when compacted they will be true to the grades or levels required with the least possible surface disturbance. Where the base course is placed in more than one layer, the previously constructed layers shall be cleaned of loose and foreign matter by sweeping with power sweepers, power brooms, or hand brooms, as directed. Such adjustments in placing procedures or equipment shall be made as may be directed to obtain true grades, to minimize segregation and degradation, to adjust the water content, and to insure an acceptable base course.

3.5.3 Grade Control

The finished and completed base course shall conform to the lines, grades, and cross sections shown. Underlying material(s) shall be excavated and prepared at sufficient depth for the required base course thickness so that the finished base course and the subsequent surface course will meet the designated grades.

3.5.4 Edges of GCA

A applicable, The GCA shall be placed so that the completed section will be a minimum of 600 mm wider, on all sides, than the next layer that will be placed above it. Additionally, place approved fill material along the outer edges of the GCA in sufficient quantities to compact to the thickness of the course being constructed, or to the thickness of each layer in a multiple layer course, allowing in each operation at least a600 mm width of this material to be rolled and compacted simultaneously with rolling and compacting of each layer of GCA. If this GCA material is to be placed adjacent to another pavement section, then the layers for both of these sections shall be placed and compacted along this edge at the same time.

3.5.5 Compaction

Compact each layer of the GCA, as specified, with approved compaction equipment. Maintain water content during the compaction procedure to within plus or minus 2 percent of the optimum water content determined from laboratory tests as specified in paragraph SAMPLING AND TESTING. Begin rolling at the outside edge of the surface and proceed to the center, overlapping on successive trips at least one-half the width of the roller. Alternate trips of the roller shall be slightly different lengths. Speed of the roller shall be such that displacement of the aggregate does not occur. In all places not accessible to the rollers, the mixture shall be compacted with hand-operated power tampers. Continue compaction until each layer has a degree of compaction that is at least 100 percent of laboratory maximum density through the full depth of the layer. Make such adjustments in compacting or finishing procedures as may be directed to obtain true grades, to minimize segregation and degradation, to reduce or increase water content, and to ensure a satisfactory base course. Any materials that are found to be unsatisfactory shall be removed and replaced with satisfactory material or reworked, as directed, to meet the requirements of this specification.

3.5.6 Thickness

Construct the compacted thickness of the GCA as indicated. No individual layer shall be thicker than 150 mm nor be thinner than 75 mm in compacted thickness. The total compacted thickness of the base course(s) shall be within 13 mm of the thickness indicated. Where the measured thickness is more than 13 mm deficient, correct such areas by scarifying, adding new material of proper gradation, reblading, and recompacting as directed. Where the measured thickness is more than 13 mm thicker than indicated, the course shall be considered as conforming to the specified thickness requirements. Average job thickness shall be the average of all thickness measurements taken for the job, but shall be within 6 mm of the thickness indicated. The total thickness of the base course shall be measured at intervals in such a manner as to ensure one measurement for each 500 square meters of GCA. Measurements shall be made in 75 mm diameter test holes penetrating the base course.

3.5.7 Finishing

The surface of the top layer of GCA shall be finished after final compaction by cutting any overbuild to grade and rolling with a steel-wheeled roller. Thin layers of material shall not be added to the top layer of base course to meet grade. If the elevation of the top layer of GCA is 13 mm or more below grade, then the top layer should be scarified to a depth of at least 75 mm and new material shall be blended in and compacted to bring to grade. Adjustments to rolling and finishing procedures shall be made as directed to minimize segregation and degradation, obtain grades, maintain moisture content, and insure an acceptable base course. Should the surface become rough, corrugated, uneven in texture, or traffic marked prior to completion, the unsatisfactory portion shall be scarified, reworked and recompacted or it shall be replaced as directed.

3.5.8 Smoothness

The surface of the top layer shall show no deviations in excess of 10 mm when tested with a 3.66 meter straightedge. Take measurements in successive positions parallel to the centerline of the area to be paved. Measurements shall also be taken perpendicular to the centerline at 15 meter intervals. Deviations exceeding this amount shall be corrected by removing material and replacing with new material, or by reworking existing material and compacting it to meet these specifications.

3.6 TRAFFIC

Do not allow traffic on the completed GCA.

3.7 MAINTENANCE

Maintain the GCA in a satisfactory condition until the full pavement section is completed and accepted. Maintenance shall include immediate repairs to any defects and shall be repeated as often as necessary to keep the area intact. Any GCA that is not paved over prior to the onset of winter, shall be retested to verify that it still complies with the requirements of this specification. Any area of base course that is damaged shall be reworked or replaced as necessary to comply with this specification.

3.8 DISPOSAL OF UNSATISFACTORY MATERIALS

Any unsuitable materials that must be removed shall be disposed of outside the limits of Government-controlled landas directed in waste disposal areas indicated. No additional payments will be made for materials that must be replaced.

-- End of Section --

SECTION 32 15 00

AGGREGATE SURFACE COURSE
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 117	(2004) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 131	(2006) Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(2006) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D 1556	(2000) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(2002e1) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D 3740	(2004a) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM D 422	(1963; R 2002e1) Particle-Size Analysis of Soils
ASTM D 4318	(2005) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D 75	(2003) Standard Practice for Sampling Aggregates
ASTM E 11	(2004) Wire Cloth and Sieves for Testing Purposes

1.2 UNIT PRICES

1.2.1 Measurement

The quantity of aggregate surface course used for construction of parking

areas and aggrgegate sidewalks completed and accepted as determined by the Contracting Officer shall be measured in cubic meters.

1.2.2 Payment

Quantities of aggregate surface course for parking areas and sidewalks, as measured above, will be paid for at the respective contract unit prices. Payment will constitute full compensation for the construction and completion of the aggregate surface course, including furnishing all labor and incidentals necessary to complete the work required by this section.

1.3 DEGREE OF COMPACTION

Degree of compaction is a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated herein as present laboratory maximum density.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Equipment

List of proposed equipment to be used in performance of construction work including descriptive data.

SD-06 Test Reports

Sampling and Testing

1.5 EQUIPMENT

All plant, equipment, and tools used in the performance of the work covered by this section will be subject to approval by the Contracting Officer before the work is started and shall be maintained in satisfactory working condition at all times. The equipment shall be adequate and shall have the capability of producing the required compaction, and meeting the grade controls, thickness controls, and smoothness requirements set forth herein.

1.6 SAMPLING AND TESTING

Sampling and testing shall be the responsibility of the Contractor. Sampling and testing shall be performed by an approved commercial testing laboratory or by the Contractor, subject to approval. If the Contractor elects to establish its own testing facilities, approval of such facilities will be based on compliance with ASTM D 3740. No work requiring testing will be permitted until the Contractor's facilities have been inspected and approved.

1.6.1 Sampling

Sampling for material gradation, liquid limit, and plastic limit tests shall be taken in conformance with ASTM D 75. When deemed necessary, the

sampling will be observed by the Contracting Officer.

1.6.2 Testing

1.6.2.1 Gradation

Aggregate gradation shall be made in conformance with ASTM C 117, ASTM C 136, and ASTM D 422. Sieves shall conform to ASTM E 11.

1.6.2.2 Liquid Limit and Plasticity Index

Liquid limit and plasticity index shall be determined in accordance with ASTM D 4318.

1.6.3 Approval of Materials

The source of the material to be used for producing aggregates shall be selected 14 days prior to the time the material will be required in the work. Approval of sources not already approved by the Corps of Engineers will be based on an inspection by the Contracting Officer. Tentative approval of materials will be based on appropriate test results on the aggregate source. Final approval of the materials will be based on tests for gradation, liquid limit, and plasticity index performed on samples taken from the completed and compacted surface course.

1.7 WEATHER LIMITATIONS

Aggregate surface courses shall not be constructed when the ambient temperatures is below 2 degrees C and on subgrades that are frozen or contain frost. It shall be the responsibility of the Contractor to protect, by approved method or methods, all areas of surfacing that have not been accepted by the Contracting Officer. Surfaces damaged by freeze, rainfall, or other weather conditions shall be brought to a satisfactory condition by the Contractor.

PART 2 PRODUCTS

2.1 AGGREGATES

Aggregates shall consist of clean, sound, durable particles of natural gravel, crushed gravel, crushed stone, sand, slag, soil, or other approved materials processed and blended or naturally combined. Aggregates shall be free from lumps and balls of clay, organic matter, objectionable coatings, and other foreign materials. The Contractor shall be responsible for obtaining materials that meet the specification and can be used to meet the grade and smoothness requirements specified herein after all compaction and proof rolling operations have been completed.

2.1.1 Coarse Aggregates

The material retained on the 4.75 mm sieve shall be known as coarse aggregate. Coarse aggregates shall be reasonably uniform in density and quality. The coarse aggregate shall have a percentage of wear not to exceed 50 percent after 500 revolutions as determined by ASTM C 131. The amount of flat and/or elongated particles shall not exceed 20 percent. A flat particle is one having a ratio of width to thickness greater than three; an elongated particle is one having a ratio of length to width greater than three. When the coarse aggregate is supplied from more than one source, aggregate from each source shall meet the requirements set

forth herein.

2.1.2 Fine Aggregates

The material passing the 4.75 mm sieve shall be known as fine aggregate. Fine aggregate shall consist of screenings, sand, soil, or other finely divided mineral matter that is processed or naturally combined with the coarse aggregate.

2.1.3 Gradation Requirements for Surface Courses

Gradation requirements specified in TABLE I shall apply to the completed aggregate surface. It shall be the responsibility of the Contractor to obtain materials that will meet the gradation requirements after mixing, placing, compacting, and other operations. TABLE I shows permissible gradings for granular material used in aggregate surface roads and airfields. Sieves shall conform to ASTM E 11.

TABLE I. GRADATION FOR AGGREGATE SURFACE COURSES

Sieve Designation	Parking or Road No. 1 or	No. 2	Sidewalk No. 3 or	No. 4
25.0 mm	100	100	100	100
9.5 mm	50-85	60-100	--	--
4.75 mm	35-65	50-85	55-100	70-100
2.00 mm	25-50	40-70	40-100	55-100
0.425 mm	15-30	24-45	20-50	30-70
0.075 mm	8-15	8-15	8-15	8-15

2.1.4 Gradation Requirements for Base Courses

The previous base course shall be of such nature that it can be compacted readiliy to a firm, stable base and shall conform to one of the following sizes:

TABLE II. GRADATION FOR AGGREGATE BASE COURSES

Sieves	Size Numbers No. 1	No. 2	No. 3
50.0 mm	100	--	--
37.5 mm	70-100	100	--
25.0 mm	45-80	60-100	100
12.5 mm	30-60	30-65	40-70
4.75 mm	20-50	20-50	20-50
2.0 mm	15-40	15-40	15-40
425 micrometers	0-25	0-25	0-25

2.2 LIQUID LIMIT AND PLASTICITY INDEX REQUIREMENTS

The portion of the completed aggregate surface course passing the 0.425 mm sieve shall have a maximum liquid limit of 35 and a plasticity index of 4 to 9.

PART 3 EXECUTION

3.1 OPERATION OF AGGREGATE SOURCES

Clearing, stripping, and excavating shall be the responsibility of the Contractor. The aggregate sources shall be operated to produce the quantity and quality of materials meeting these specification requirements in the specified time limit. Upon completion of the work, the aggregate sources on Government property shall be conditioned to drain readily and be left in a satisfactory condition. Aggregate sources on private lands shall be conditioned in agreement with local laws or authorities.

3.2 STOCKPILING MATERIALS

Prior to stockpiling the material, the storage sites shall be cleared and leveled by the Contractor. All materials, including approved material available from excavation and grading, shall be stockpiled in the manner and at the locations designated. Aggregates shall be stockpiled in such a manner that will prevent segregation. Aggregates and binders obtained from different sources shall be stockpiled separately.

3.3 PREPARATION OF UNDERLYING COURSE SUBGRADE

The subgrade shall be cleaned of all foreign substances. At the time of surface course construction, the subgrade shall contain no frozen material. Ruts or soft yielding spots in the subgrade areas having inadequate compaction and deviations of the surface from the requirements set forth herein shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line and grade and recompacting. The completed subgrade shall not be disturbed by traffic or other operations and shall be maintained by the Contractor in a satisfactory condition until the surface course is placed.

3.4 GRADE CONTROL

During construction, the lines and grades including crown and cross slope indicated for the aggregate surface course shall be maintained by means of line and grade stakes placed by the Contractor.

3.5 MIXING AND PLACING MATERIALS

The materials shall be mixed and placed to obtain uniformity of the material and a uniform optimum water content for compaction. The Contractor shall make adjustments in mixing, placing procedures, or in equipment to obtain the true grades, to minimize segregation and degradation, to obtain the desired water content, and to ensure a satisfactory surface course.

3.6 LAYER THICKNESS

The aggregate material shall be placed in layers of uniform thickness. When a compacted layer of 150 mm or less is specified, the material may be placed in a single layer; when a compacted thickness of more than 150 mm is required, no layer shall exceed 150 mm nor be less than 75 mm when compacted.

3.7 COMPACTION

Each layer of the aggregate surface course shall be compacted with approval

compaction equipment. The water content during the compaction procedure shall be maintained at optimum or at the percentage specified by the Contracting Officer. In locations not accessible to the rollers, the mixture shall be compacted with mechanical tampers. Compaction shall continue until each layer through the full depth is compacted to at least 100 percent of laboratory maximum density. Any materials that are found to be unsatisfactory shall be removed and replaced with satisfactory material or reworked to produce a satisfactory material.

3.8 PROOF ROLLING

Proof rolling of the areas designated shall be in addition to compaction specified above and shall consist of application of 30 coverages with a heavy rubber-tired roller having four tires abreast with each tire loaded to 13,600 kg and tires inflated to 1000 kPa. In the areas designated, proof rolling shall be applied to the top lift of layer on which surface course is laid and to each layer of the base course. Water content of the lift of the layer on which the surface course is placed and each layer of the aggregate surface course shall be maintained at optimum or at the percentage directed from the start of compaction to the completion of a proof rolling. Materials in the aggregate surface course or underlying materials indicated unacceptable by the proof rolling shall be removed and replaced, as directed, with acceptable materials.

3.9 SMOOTHNESS TEST

The surface of each layer shall not show any deviations in excess of 10 mm when tested with a 3 m straightedge applied both parallel with and at right angles to the centerline of the area to be paved. Deviations exceeding this amount shall be corrected by the Contractor by removing material, replacing with new material, or reworking existing material and compacting, as directed.

3.10 THICKNESS CONTROL

The completed thickness of the aggregate surface course shall be within 13 mm, plus or minus, of the thickness indicated on plans. The thickness of the aggregate surface course shall be measured at intervals in such manner that there will be a thickness measurement for at least each 500 square meters of the aggregate surface course. The thickness measurement shall be made by test holes at least 75 mm in diameter through the aggregate surface course. When the measured thickness of the aggregate surface course is more than 13 mm deficient in thickness, the Contractor, at no additional expense to the Government, shall correct such areas by scarifying, adding mixture of proper gradation, reblading, and recompacting, as directed. Where the measured thickness of the aggregate surface course is more than 13 mm thicker than that indicated, it shall be considered as conforming with the specified thickness requirements plus 13 mm. The average job thickness shall be the average of the job measurements determined as specified above, but shall be within 6 mm of the thickness indicated. When the average job thickness fails to meet this criterion, the Contractor shall, at no additional expense to the Government, make corrections by scarifying, adding or removing mixture of proper gradation, and reblading and recompacting, as directed.

3.11 DENSITY TESTS

Density shall be measured in the field in accordance with ASTM D 1556.

3.12 WEAR TEST

Wear tests shall be made in conformance with ASTM C 131.

3.13 MAINTENANCE

The aggregate surface course shall be maintained in a condition that will meet all specification requirements until accepted.

-- End of Section --

SECTION 32 31 13.00 20

CHAIN LINK FENCES AND GATES
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A 153/A 153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 392	(2003) Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric
ASTM A 780	(2001; R 2006) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A 824	(2001) Standard Specification for Metallic-Coated Steel Marcelled Tension Wire for Use With Chain Link Fence
ASTM C 94/C 94M	(2009) Standard Specification for Ready-Mixed Concrete
ASTM F 1043	(2004) Strength and Protective Coatings on Metal Industrial Chain-Link Fence Framework
ASTM F 1083	(2004) Standard Specification for Pipe, Steel, Hot-Dipped Zinc Coated (Galvanized) Welded, for Fence Structures
ASTM F 1184	(2003) Industrial and Commercial Horizontal Slide Gates
ASTM F 626	(1996a; R 2003) Standard Specification for Fence Fittings
ASTM F 883	(2004) Padlocks
ASTM F 900	(2003) Industrial and Commercial Swing Gates

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be

submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-07 Certificates

Chain Link Fence

Statement, signed by an official authorized to certify on behalf of the manufacturer, attesting that the chain link fence and component materials meet the specified requirements.

PART 2 PRODUCTS

2.1 FENCE FABRIC

Fence fabric shall conform to the following:

2.1.1 Chain Link Fence Fabric

ASTM A 392, Class 1, zinc-coated galvanized steel wire with minimum coating weight of 370 grams of zinc per square meter of coated surface. Fabric shall be fabricated of 9 gauge wire woven in 50 mm mesh. Fabric height shall be as shown. Fabric shall be twisted and barbed on the top selvage and knuckled on the bottom selvage.

2.2 GATES

As applicable and except as specified elsewhere, gates shall be in accordance with the following requirements, ASTM F 900 and/or ASTM F 1184. Gate shall be the type and configuration shown. Gate frames shall conform to strength and coating requirements of ASTM F 1083 for Group IA, steel pipe, with external coating Type A, nominal pipe size (NPS) 1-1/2. Gate frames shall conform to strength and coating requirements of ASTM F 1043, for Group IC, steel pipe with external coating Type A or Type B, nominal pipe size (NPS) 1-1/2. Gate fabric shall be as specified for chain link fabric. Gate leaves more than 2.44 m wide shall have either intermediate members and diagonal truss rods or shall have tubular members as necessary to provide rigid construction, free from sag or twist. Gate leaves less than 2.44 m wide shall have truss rods or intermediate braces. Gate fabric shall be attached to the gate frame by method standard with the manufacturer except that welding will not be permitted. Except as specified otherwise, latches, hinges, stops, keepers, rollers, and other hardware items shall be furnished as required for the operation of the gate. Latches shall be arranged for padlocking so that the padlock will be accessible from both sides of the gate. Stops shall be provided for holding the gates in the open position.

2.3 POSTS

2.3.1 Metal Posts for Chain Link Fence

ASTM F 1083, zinc-coated. Group IA, with external coating Type A steel hot dipped zinc coated galvanized welded pipe. Sizes shall be as shown on the drawings. Line posts and terminal (corner, gate, and pull) posts selected shall be of the same designation throughout the fence. Gate post shall be for the gate type specified subject to the limitation specified in ASTM F 900 and/or ASTM F 1184.

2.4 BRACES AND RAILS

ASTM F 1083, zinc-coated, Group IA, steel pipe, size NPS 1-1/4. Group IC steel pipe, zinc-coated, shall meet the strength and coating requirements of ASTM F 1043. Group II, formed steel sections, size 42 mm, conforming to ASTM F 1043, may be used as braces and rails if Group II line posts are furnished. Use rails only if/as shown.

2.5 WIRE

2.5.1 Tension Wire

Tension wire shall be Type I or Type II, Class 4 coating, in accordance with ASTM A 824.

2.6 ACCESSORIES

ASTM F 626. Ferrous accessories shall be zinc or aluminum coated. Truss rods shall be furnished for each terminal post. Truss rods shall be provided with turnbuckles or other equivalent provisions for adjustment. Barbed wire support arms shall be the V arm type and of the design required for the post furnished. Tie wire for attaching fabric to rails, braces, and posts shall be 9 gauge steel wire and match the coating of the fence fabric. Tie wires for attaching fabric to tension wire on high security fences shall be 1.6 mm stainless steel. The tie wires shall be a double loop and 165 mm in length. Miscellaneous hardware coatings shall conform to ASTM A 153/A 153M unless modified.

2.7 CONCRETE

ASTM C 94/C 94M, using 19 mm maximum size aggregate, and having minimum compressive strength of 21 MPa at 28 days. Grout shall consist of one part portland cement to three parts clean, well-graded sand and the minimum amount of water to produce a workable mix.

2.8 PADLOCKS

Padlocks shall conform to ASTM F 883, Type PO1, Options A, B, and G, Grade 6. EPB, Size 44 mm. All padlocks shall be keyed alike.

2.9 BARBED TAPE

Provide reinforced barbed tape, double coil, for fence toppings fabricated from 430 series stainless steel with a hardness range of Rockwell (30N) 37-45 conforming to the requirements of ASTM A 176. Provide stainless steel strip 0.6 mm thick by 25 mm wide before fabrication. Each barb shall be a minimum of 30.5 mm in length, in groups of 4, spaced on 102 mm centers. The
stainless steel core wire shall have a 2.5 mm diameter with a minimum tensile strength of 9.68 MPa 140 psi and be in accordance with ASTM A 478. Use sixteen gauge stainless steel twistable wire ties for attaching the barbed tape to the barbed wire.

PART 3 EXECUTION

3.1 INSTALLATION

Fence and gates shall be installed as indicated and otherwise to the lines and grades indicated. Wall posts and line posts shall be spaced

equidistant at intervals not exceeding 3 m. Terminal (corner, gate, and pull) posts shall be set at abrupt changes in vertical and horizontal alignment. Fabric shall be continuous between terminal posts; however, runs between terminal posts shall not exceed 152.4 m. Any damage to galvanized surfaces, including welding, shall be repaired with paint containing zinc dust in accordance with ASTM A 780.

3.2 EXCAVATION

As applicable, post holes shall be cleared of loose material. Waste material shall be spread where directed. The ground surface irregularities shall be eliminated to the extent necessary to maintain a 50 mm clearance between the bottom of the fabric and finish grade.

3.3 POST INSTALLATION

3.3.1 Posts for Chain Link Fence

Post sizes shall be as shown on drawings. Post footings, where applicable, shall be no less that 250 mm in diameter and below the area's frost depth level usually not less that 800 mm. Posts shall be set plumb and in alignment. For posts set in ground, except where solid rock is encountered, posts shall be set in concrete to the depth indicated on the drawings. Where solid rock is encountered with no overburden, posts shall be set to a minimum depth of 457 mm in rock. Where solid rock is covered with an overburden of soil or loose rock, posts shall be set to the minimum depth indicated on the drawing unless a penetration of 457 mm in solid rock is achieved before reaching the indicated depth, in which case depth of penetration shall terminate. All portions of posts set in rock shall be grouted. Portions of posts not set in rock shall be set in concrete from the rock to ground level. Posts set in concrete shall be set in holes not less than the diameter shown on the drawings. Diameters of holes in solid rock shall be at least 25 mm greater than the largest cross section of the post. Concrete and grout shall be thoroughly consolidated around each post, shall be free of voids and finished to form a dome. Concrete and grout shall be allowed to cure for 72 hours prior to attachment of any item to the posts. Group II line posts may be mechanically driven, for temporary fence construction only, if rock is not encountered. Driven posts shall be set to a minimum depth of 914 mm and shall be protected with drive caps when being set. Fence post rigidity shall be tested by applying a 222.4 newtons force on the post, perpendicular to the fabric, at 1.52 m above ground; post movement measured at the point where the force is applied shall be less than or equal to 19 mm from the relaxed position; every tenth post shall be tested for rigidity; when a post fails this test, further tests on the next four posts on either side of the failed post shall be made; all failed posts shall be removed, replaced, and retested at the Contractor's expense.

3.4 RAILS

3.4.1 Top Rail

Top rail (if/as shown) shall be supported at each post to form a continuous brace between terminal posts. Where required, sections of top rail shall be joined using sleeves or couplings that will allow expansion or contraction of the rail. Top rail, if required for high security fence, shall be installed as indicated on the drawings.

3.4.2 Bottom Rail

The bottom rail (if/as shown) shall be bolted to double rail ends and double rail ends shall be securely fastened to the posts. Bolts shall be peened to prevent easy removal. Bottom rail shall be installed before chain link fabric.

3.5 BRACES AND TRUSS RODS

Braces and truss rods shall be installed as indicated and in conformance with the standard practice for the fence furnished. Horizontal (compression) braces and diagonal truss (tension) rods shall be installed on fences over 1.83 m in height. A center brace or 2 diagonal truss rods shall be installed on 3.66 m fences. Braces and truss rods shall extend from terminal posts to line posts. Diagonal braces shall form an angle of approximately 40 to 50 degrees with the horizontal. No bracing is required on fences 1.83 m high or less if a top rail is installed.

3.6 TENSION WIRES

Tension wires shall be installed along the top and bottom of the fence line and attached to the terminal posts of each stretch of the fence. Top tension wires shall be installed within the top 305 mm of the installed fabric. Bottom tension wire shall be installed within the bottom 152 mm of the installed fabric. Tension wire shall be pulled taut and shall be free of sag.

3.7 CHAIN LINK FABRIC

Chain link fabric shall be installed on the side of the post indicated. Fabric shall be attached to terminal posts with stretcher bars and tension bands. Bands shall be spaced at approximately 381 mm intervals. The fabric shall be installed and pulled taut to provide a smooth and uniform appearance free from sag, without permanently distorting the fabric diamond or reducing the fabric height. Fabric shall be fastened to line posts at approximately 381 mm intervals and fastened to all rails and tension wires at approximately 305 mm intervals. Fabric shall be cut by untwisting and removing pickets. Splicing shall be accomplished by weaving a single picket into the ends of the rolls to be joined. The bottom of the installed fabric shall be 50 mm plus or minus 13 mm above the wall or ground or as shown. After the fabric installation is complete, the fabric shall be exercised by applying a 222 newtons push-pull force at the center of the fabric between posts; the use of a 133 newtons pull at the center of the panel shall cause fabric deflection of not more than 63.5 mm when pulling fabric from the post side of the fence; every second fence panel shall meet this requirement; all failed panels shall be resecured and retested at the Contractor's expense.

3.8 GATE INSTALLATION

Gates shall be installed at the locations shown. Hinged gates shall be mounted to swing as indicated. Latches, stops, and keepers shall be installed as required. Slide or Lift gates shall be installed as recommended by the manufacturer. Padlocks shall be attached to gates or gate posts with chains. Hinge pins, and hardware shall be welded or otherwise secured to prevent removal.

3.9 TOLERANCES

Posts shall be straight and plumb within a vertical tolerance of 6 millimeter after the fabric has been stretched. Fencing and gates shall be true to line with no more than 15 millimeter deviation from the established centerline between line posts. Defects shall be repaired as directed.

3.10 BARBED TAPE INSTALLATION

Install stainless steel reinforced barbed tape as detailed on the drawings. Stretch out barbed tape to its manufacturer's recommended length, set on top of the barbed wire and "V" shaped support arms, then secure it to the barbed wire. Secure the barbed tape to the barbed wire at the two points and at every spiral turn of both coils as shown on the drawings.

-- End of Section --

SECTION 32 92 19

SEEDING
10/06

PART 1 GENERAL

Areas not paved or surface with aggregate, including the soccer field (if provided), shall be seeded in accordance with this specification.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 602	(2006) Agricultural Liming Materials
ASTM D 4427	(1992; R 2002e1) Peat Samples by Laboratory Testing

U.S. DEPARTMENT OF AGRICULTURE (USDA)

DOA SSIR 42	(1996) Soil Survey Investigation Report No. 42, Soil Survey Laboratory Methods Manual, Version 3.0

1.2 DEFINITIONS

1.2.1 Stand of Turf

95 percent ground cover of the established species.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Proposed seed mixture and planting plan; G

Wood cellulose fiber mulch

Fertilizer

Include physical characteristics, and recommendations.

SD-06 Test Reports

Topsoil composition tests (reports and recommendations).

SD-07 Certificates

State certification and approval for seed

SD-08 Manufacturer's Instructions

Erosion Control Materials

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery

1.4.1.1 Seed Protection

Protect from drying out and from contamination during delivery, on-site storage, and handling.

1.4.1.2 Fertilizer and Lime Delivery

Deliver to the site in original, unopened containers bearing manufacturer's chemical analysis, name, trade name, trademark, and indication of conformance to state and federal laws. Instead of containers, fertilizer and lime may be furnished in bulk with certificate indicating the above information.

1.4.2 Storage

1.4.2.1 Seed, Fertilizer and Lime Storage

Store in cool, dry locations away from contaminants.

1.4.2.2 Topsoil

Prior to stockpiling topsoil, treat growing vegetation with application of appropriate specified non-selective herbicide. Clear and grub existing vegetation three to four weeks prior to stockpiling topsoil.

1.4.2.3 Handling

Do not drop or dump materials from vehicles.

1.5 TIME RESTRICTIONS AND PLANTING CONDITIONS

1.5.1 Restrictions

Do not plant when the ground is frozen, snow covered, muddy, or when air temperature exceeds 32 degrees Celsius.

1.6 TIME LIMITATIONS

1.6.1 Seed

Apply seed within twenty four hours after seed bed preparation.

PART 2 PRODUCTS

2.1 SEED

Provide a seed mixture that is typical to the region. Planting dates also shall be typical to the region.

2.2 TOPSOIL

2.2.1 On-Site Topsoil

Surface soil stripped and stockpiled on site and modified as necessary to meet the requirements specified for topsoil in paragraph entitled "Composition." When available topsoil shall be existing surface soil stripped and stockpiled on-site in accordance with Section 31 00 00 EARTHWORK and 31 23 00.00 20 EXCAVATION AND BACKFILLING FOR UTILITIES AND STRUCTURES.

2.2.2 Off-Site Topsoil

Conform to requirements specified in paragraph entitled "Composition." Additional topsoil shall be furnished by the Contractor.

2.2.3 Composition

As specified in Section 31 00 00. Also, topsoil shall contain from 5 to 10 percent organic matter as determined by the topsoil composition tests of the Organic Carbon, 6A, Chemical Analysis Method described in DOA SSIR 42.

2.3 SOIL CONDITIONERS

Add conditioners to topsoil as required to bring into compliance with "composition" standard for topsoil as specified herein.

2.3.1 Lime

Commercial grade hydrate or burnt limestone, hydated lime containing a calcium carbonate equivalent (C.C.E.) as specified in ASTM C 602 of not less than 95,100 and percent, respectively.

2.3.2 Aluminum Sulfate

Commercial grade.

2.3.3 Sulfur

100 percent elemental

2.3.4 Iron

100 percent elemental

2.3.5 Peat

Natural product of peat moss derived from a freshwater site and conforming to ASTM D 4427. Shred and granulate peat to pass a 12.5 mm mesh screen and condition in storage pile for minimum 6 months after excavation.

2.3.6 Sand

Clean and free of materials harmful to plants.

2.3.7 Perlite

Horticultural grade.

2.3.8 Composted Derivatives

Ground bark, nitrolized sawdust, humus or other green wood waste material free of stones, sticks, and soil stabilized with nitrogen and having the following properties:

2.3.8.1 Particle Size

Minimum percent by weight passing:

4.75 mm screen	95
2.36 mm screen	80

2.3.8.2 Nitrogen Content

Minimum percent based on dry weight:

Fir Sawdust	0.7
Fir or Pine Bark	1.0

2.3.9 Gypsum

Coarsely ground gypsum comprised of calcium sulfate dihydrate 61 percent, calcium 22 percent, sulfur 17 percent; minimum 96 percent passing through 850 micrometers, 100 percent passing thru 970 micrometers screen.

2.3.10 Calcined Clay

Calcined clay shall be granular particles produced from montmorillonite clay calcined to a minimum temperature of 650 degrees C. Gradation: A minimum 90 percent shall pass a 2.36 mm sieve; a minimum 99 percent shall be retained on a 0.250 mm sieve; and a maximum 2 percent shall pass a 0.150 mm sieve. Bulk density: A maximum 640 kilogram per cubic meter.

2.4 FERTILIZER

2.4.1 Granular Fertilizer

Granular controlled release fertilizer containing the following minimum percentages, by weight, of plant food nutrients:

10 percent available nitrogen
20 percent available phosphorus
10 percent available potassium

2.4.2 Hydroseeding Fertilizer

Controlled release fertilizer, to use with hydroseeding and composed of pills coated with plastic resin to provide a continuous release of nutrients for at least 6 months and containing the minimum percentages, by weight, of plant food nutrients specified above.

2.5 MULCH

Mulch shall be free from noxious weeds, mold, and other deleterious materials.

2.5.1 Straw

Stalks from oats, wheat, rye, barley, or rice. Furnish in air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Straw shall contrain no fertile seed.

2.5.2 Hay

Air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Hay shall be sterile, containing no fertile seed.

2.5.3 Wood Cellulose Fiber Mulch

Use recovered materials of either paper-based or wood-based hydraulic mulch. Processed to contain no growth or germination-inhibiting factors and dyed an appropriate color to facilitate visual metering of materials application. Composition on air-dry weight basis: 9 to 15 percent moisture, pH range from 5.5 to 8.2. Use with hydraulic application of grass seed and fertilizer.

2.6 WATER

Source of water shall be approved by Contracting Officer and of suitable quality for irrigation, containing no elements toxic to plant life.

2.7 EROSION CONTROL MATERIALS

Erosion control material shall conform to Specification Section 31 32 11.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 EXTENT OF WORK

Provide soil preparation (including soil conditioners as required), fertilizing, seeding, and surface topdressing of all newly graded finished earth surfaces, unless indicated otherwise, and at all areas inside or outside the limits of construction that are disturbed by the Contractor's operations.

3.1.1.1 Topsoil

Provide 102 mm of topsoil to meet indicated finish grade. After areas have been brought to indicated finish grade, incorporate fertilizer pH adjusters and soil conditioners into soil as needed by disking, harrowing, tilling or other method approved by the Contracting Officer. Remove debris and stones larger than 19 mm in any dimension remaining on the surface after finish grading. Correct irregularities in finish surfaces to eliminate depressions. Protect finished topsoil areas from damage by vehicular or pedestrian traffic.

3.1.1.2 Soil Conditioner Application Rates

Apply soil conditioners at rates as determined by laboratory soil analysis of the soils at the job site.

3.1.1.3 Fertilizer Application Rates

Apply fertilizer at rates as determined by laboratory soil analysis of the soils at the job site.

3.2 SEEDING

3.2.1 Seed Application Seasons and Conditions

Immediately before seeding, restore soil to proper grade. Do not seed when ground is muddy, frozen, snow covered or in an unsatisfactory condition for seeding. If special conditions exist that may warrant a variance in the above seeding dates or conditions, submit a written request to the Contracting Officer stating the special conditions and proposed variance. Apply seed within twenty four hours after seedbed preparation. Sow seed by approved sowing equipment. Sow one-half the seed in one direction, and sow remainder at right angles to the first sowing.

3.2.2 Seed Application Method

Seeding method is unspecified but shall be typical to region.

3.2.3 Mulching

3.2.3.1 Hay or Straw Mulch

Hay or straw mulch shall be spread uniformly at the rate of 0.75 metric tons per hectare. Mulch shall be spread by hand, blower-type mulch spreader, or other approved method. Mulching shall be started on the windward side of relatively flat areas or on the upper part of steep slopes, and continued uniformly until the area is covered. The mulch shall not be bunched or clumped. Sunlight shall not be completely excluded from penetrating to the ground surface. All areas installed with seed shall be mulched on the same day as the seeding. Mulch shall be anchored immediately following spreading.

3.2.3.2 Mechanical Anchor

Mechanical anchor shall be a V-type-wheel land packer; a scalloped-disk land packer designed to force mulch into the soil surface; or other suitable equipment.

3.2.3.3 Asphalt Adhesive Tackifier

Asphalt adhesive tackifier shall be sprayed at a rate between 666 to 866 liters per hectare. Sunlight shall not be completely excluded from penetrating to the ground surface.

3.2.3.4 Non-Asphaltic Tackifier

Hydrophilic colloid shall be applied at the rate recommended by the manufacturer, using hydraulic equipment suitable for thoroughly mixing with water. A uniform mixture shall be applied over the area.

3.2.3.5 Asphalt Adhesive Coated Mulch

Hay or straw mulch may be spread simultaneously with asphalt adhesive applied at a rate between 666 to 866 liters per hectare, using power mulch equipment which shall be equipped with suitable asphalt pump and nozzle.

The adhesive-coated mulch shall be applied evenly over the surface. Sunlight shall not be completely excluded from penetrating to the ground surface.

3.2.4 Rolling

Immediately after seeding, firm entire area except for slopes in excess of 3 to 1 with a roller not exceeding 134 kg per m for each foot of roller width. If seeding is performed with cultipacker-type seeder or by hydroseeding, rolling may be eliminated.

3.2.5 Erosion Control Material

Install in accordance with manufacturer's instructions, where indicated or as directed by the Contracting Officer.

3.2.6 Watering

Start watering areas seeded as required by temperature and wind conditions. Apply water at a rate sufficient to insure thorough wetting of soil to a depth of 50 mm without run off. During the germination process, seed is to be kept actively growing and not allowed to dry out.

3.3 PROTECTION OF TURF AREAS

Immediately after turfing, protect area against traffic and other use.

3.4 RESTORATION

Restore to original condition existing turf areas which have been damaged during turf installation operations at the Contractor's expense. Keep clean at all times at least one paved pedestrian access route and one paved vehicular access route to each building. Clean other paving when work in adjacent areas is complete.

-- End of Section --

SECTION 33 56 13

ABOVEGROUND FUEL STORAGE TANKS
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

UNDERWRITERS LABORATORIES (UL)

UL 674	(2003; Rev thru Apr 2006) Standard for Electric Motors and Generators for Use in Division 1 Hazardous (Classified) Locations
UL 698	(2006) Industrial Control Equipment for Hazardous (Classified) Locations
UL 886	(1994; Rev thru Nov 2005) Outlet Boxes and Fittings for Use in Hazardous (Classified) Locations

1.2 SYSTEM DESCRIPTION

Provide aboveground gasoline and diesel storage tank systems (ASTs), mechanical, electrical, control and fuel piping systems complete and ready for operation. Fuel piping systems shall include aboveground piping and connections to piping systems.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Aboveground Storage Tanks (AST); G

Submit shop drawings for each size of AST for approval. Indicate types, sizes, locations, system layout, pipe sizes, location of supports, elevations, equipment mounting, installation details, and other construction details.

Provide drawings and specifications that include the proposed conduit layout and wiring diagrams for equipment covered in this section that requires electrical connections. Indicate conduit

size and material, number and size of wires, location of wiring in classified areas and location of intrinsically safe circuits and conduits.

Provide diagram for the system including a complete bill of material/equipment list.

As applicable, provide control system designs including electrical schematics, panel physical, and field wiring diagrams. Control panels shall include power conditioners.

Provide drawings of reinforced concrete tank foundation slabs. Include conduit stub up locations, and bollard spacing. Provide drawings of structural steel for walkways or pipe trestles where required.

SD-03 Equipment Submissions, and Catalog and Product Data; GA

Aboveground Fuel Storage Tanks (AST)G

Fuel Dispensing Systems

Remote Fill Station

Fuel Pumps

Fuel Piping

Instrumentation

SD-05 Calculations

Provide calculations for pump selection, pipe sizes, pipe support requirements, atmospheric vent sizing, and emergency vent sizing.

SD-06 Testing of Fuel Tanks and Fuel Pumps including instrumentation and Fuel Oil Piping; GA

The contractor shall provide the following: Six copies of each test containing the information described below (items 1-7) in bound letter-size booklets; individual reports shall be provided for the storage tank tests, the piping tests, the system performance tests, the high level alarm test, and the system leak tests. Drawings shall be folded blue lines, with the title block visible. 1) The date the tests were performed. 2) A list of equipment used, with calibration certifications. 3) A copy of measurements taken. 4) The parameters to be verified. 5) The condition specified for the parameter. 6) The inspection results, signed, dated, and certified by the installer. The certification shall state that required procedures were accomplished, that the procedures were conducted in compliance the plans and specifications. 7) A description of adjustments performed.

SD-10 Installation, Operation and Maintenance Manual; GA

Installation instructions: Include Manufacturer's Instructions

Operation Data: Include installation instructions and exploded assembly views.

Maintenance Data: Include maintenance and inspection data, and replacement part numbers and availability.

Provide (4) copies of Operations and Maintenance manual. One copy shall be attached to tank in a clear PVC weather resistant document tube.

Submit Data Package 3 in accordance with Section 01 78 23 "OPERATION AND MAINTENANCE DATA".

1.4 QUALITY ASSURANCE

1.4.1 Installation

Installation shall be in compliance with the latest version of the Petroleum Equipment Institute Publications RP100, RP 200, and RP300, NFPA-30, 30A, and 31 and all manufacturers' current installation instructions.

1.4.2 Design and Construction

Comply with NFPA 30 "Flammable and Combustible Liquids Code" and NFPA 30A "Automotive and Marine Service Station Code" for design and construction, installation, inspection, and testing of fuel dispensing system components and accessories.

1.4.3 Electrical

Comply with NFPA 70 "National Electric Code" for equipment, wiring, and conduit installed under this section.

1.4.4 Label

Provide listing/approval stamp, label, or other marking on equipment made to specified standards.

1.4.5 Welding Materials and Procedures

Conform to ASME Code and applicable regulations.

1.5 QUALIFICATIONS

1.5.1 Manufacturer

Company specializing in manufacturing the products specified in this section with minimum five years documented experience and International Fire Code Institute certified in the installation of underground/aboveground storage tank equipment.

1.5.2 Installer

Company specializing in performing the work of this section with minimum five years documented experience.

1.5.3 Workmen

Workmen who have a minimum of two years continuous experience installing this type equipment and who have attended a training seminar put on by the

tank manufacturer in the past two years shall perform installation of equipment and International Fire Code Institute certified in the installation of underground/aboveground storage tank equipment.

1.6 DELIVERY AND STORAGE

Handle and store aboveground storage tanks and containment piping systems, to prevent distortions and other damage that could affect their structural, mechanical, or electrical integrity. Replace damaged items that cannot be restored to original condition. Store items subject to deterioration by exposure to elements, in a well-drained location, protected from weather, and accessible for inspection and handling. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

PART 2 PRODUCTS

2.1 TANKS

2.1.1 Aboveground Fuel Tanks, Diesel and MOGAS Fuel for Vehicles and Generator Diesel Fuel

a. General: Provide and install aboveground tank and fuel dispensing system complete with tank, piping, gauges, fuel dispenser and other accessories specified herein. The tank shall have a total volume as noted on drawings.

b. Design Criteria: The tank system shall be designed and tested in strict accordance with UL subject 142. The UL 142 listing is for above ground tanks for flammable liquids. Numbered brass plaques issued by Underwriters Laboratories, Inc. confirming UL subject 142 approval shall be installed on the tank and be clearly visible to inspectors.

c. Tank Construction: - Internal Steel Tank

(1) Furnish and install a 6,000 gallon aboveground, horizontal, single-wall, steel storage tank 8'0" inches in diameter by 16'0" long. Tank shall be fabricated from mild carbon steel with flat-flanged heads. Tank gauges: head gauge 1/4", shell gauge 1/4". All items included with the tank shall be coated with red primer and white urethane paint. The tank shall be manufactured in conformance with Underwriters Laboratories' UL-142 specifications and so labeled.

The tank shall be fabricated with the threaded connections as indicated and as located on attached drawing. Thread protectors shall be inserted in all threaded openings prior to shipment.

Tanks shall be air tested at the factory but MUST be retested at the jobsite by the installer prior to installation.

Tank shall be fitted with the following options & accessories:

Loose-bolt Manway ___ inches in diameter with bolted and gasketed lid (emergency vent)
Support Saddles
External Ladder
Pump Platform
Level Sensing System(s)

Warranty:

Tanks shall be warranted by manufacturer to be free from defects in manufacturing, workmanship and materials. Manufacturer shall repair or replace, at its sole discretion F.O.B. factory, within a period of one year after date of shipment, any item of its manufacture. All other items shall be warranted by their respective manufacturers. Liability hereunder is limited, as stated above, and does not include labor, installation costs, indirect or consequential damages of any kind. Tanks must be returned to the factory and if found to be defective upon examination, will be repaired, replaced or credit will be issued at our option.

(2) Tank shall comply with the normal and emergency venting requirements of NFPA 30.

(3) Tank shall carry a thirty-year written warranty including materials and workmanship.

d. Tank Appurtenances: The tank manufacturer shall provide the following integral components.

(1) Saddles: Tank shall have integral seam welded tank saddles in accordance U.L. Standard 142 designed to support the full load of tank and contents. Saddles shall provide for a minimum 152 mm (6")clearance between tank and pad for complete visual inspection. The tank support system shall be anchored to concrete pad to protect from floatation. Saddle anchors shall be as provided by tank manufacturer.

e. Access Ladders: Tanks shall be equipped with ladders as indicated on the drawings. Ladders shall be of welded steel construction with prime and finish paint of industrial enamel. Ladders shall be designed to conform to OSHA requirements. Steps shall include non-skid tread surfaces, handrails, platforms, and kick plates as required for OSHA compliance.

f. Venting: Provide properly sized U.L. listed and C.A.R.B. approved emergency and standard vents to satisfy code requirements. Standard vent shall terminate a minimum of 3.66 m above the adjacent ground level.

g. Grounding: A grounding cable, clamp, and ground rod shall be provided by tank manufacturer and installed by contractor. System shall be electrically grounded in full compliance with N.F.P.A. 78 standards for static electricity build up. Clamp shall be attached to base of vent riser prior to finish painting.

h. Exterior Finish: The complete tank system shall include a urethane based high gloss white exterior finish. The final coat shall be a clear fuel resistant coating. Color of finish to be selected by Government.

i. Environmental Protection: All service fittings shall have 305 mm x 305 mm gauge/deflector plates under them on bottom of tank.

2.2 TANK ACCESSORIES

2.2.1 Accessory Equipment For ASTs - Generator Diesel Fuel

The following accessory equipment shall be provided as part of the pre-engineered tank and coordinated with each tank design: Direct read tank level gage, direct read leak gage, inspection port adapter cap, and tank fill system.

Anti-spill Valves: Where product piping extends below the top of the primary tank, piping shall include shutoff valve and a normally closed safety valve; safety valve shall be an approved anti-siphon valve or an electric solenoid valve.

2.2.1.1 Direct Read Leak Gauge

Tank shall be equipped with a direct reading leak gauge with aluminum housing, calibration assembly, red HDPE plastic indicator tube, float arm assembly. Krueger Sentry Gauge At-A-Glance leak gauge or engineer approved equivalent.

2.2.1.2 Direct Read Level Gauge - High Level Alarm

Tank shall be equipped with a direct reading level gauge with aluminum housing. The level gauge shall have metric face and be readable from ground level. Provide gauge with re-settable built-in high level warning alarm(at 95% capacity). Alarm shall be battery powered, intrinsically safe, and mounted remote from gauge. Morrison Model #918 or engineer approved equivalent.

2.2.1.3 Direct Read Level Gauge - Low Level Alarm

Provide an audibel alarm for low level warning. System shall incorporate an alarm box and single-point level sensor. Alarm box shall be weatherproof, intrinsically safe with a 90 decibel alarm (at 10% capacity). Alarm shall operate on two 9-volt batteries and feature a membrane-type test/cancel button. Morrison Model #918TCP or engineer approved equivalent.

2.2.1.4 Overfill Protection Valve

Provide valve to terminate flow of product when liquid level reaches preset warning level. Morrison Model 9095A or engineer approved equavilent.

2.2.1.5 Remote Fill System

Each tank shall be provided with a fill container designed to minimize and contain fuel spilled when disconnecting the delivery fitting during normal tank filling operations. The interior shall be prime coated and painted with durable white urethane to aid in visual product leak inspection. Total leak containment shall be 57 litre and shall be provided with drain connection and lockable valve. Provide for capability for fuel delivery from outside the wall around the compound. The remote fill station shall be lockable and securable from tampering and sabotage.

2.2.1.6 Product Label Marker

Stainless Steel band clamp with API color-coded plaque for product being stored.

2.2.1.7 Decal/Placard

Provide decal or placard affixed to the tank fill box that gives a detailed, step-by-step tank filling procedure as well as the tank calibration chart. The decal or placard must be readily visible during tank filling operations and must be of a material that does not deteriorate when exposed to weather.

2.2.2 Accessory Equipment For ASTs - Vehicle Diesel Fuel and MOGAS

The following accessory equipment shall be provided as part of the pre-engineered tank and coordinated with each tank design: Direct read tank level gage, direct read leak gage, inspection port adapter cap, and tank fill system

2.2.2.1 Inspection Port Adapter Cap

Tank shall be equipped with a 100 mm adapter and lockable cap for inspection and manual gauging of fuel level. Gauge port shall be accessible from steps or ladder.

2.2.2.2 Line Purging Valve

Carbon steel, stainless ball, with Viton seals.

2.2.2.3 Spill Sump Drain Valve

Tied into suction side of pump. Carbon steel, stainless ball, with Viton seals.

2.2.2.4 Ground Stud

Provide labeled ground stud for connection of static bonding cable

2.2.2.5 Operating Valve

75 mm Stainless steel ball valve.

2.2.2.6 Check Valve

Iron body, Viton seals.

2.2.2.7 Overfill Prevention Valve

Installed in the fill pipe. The valve shall close automatically at 90% of tank capacity. The valve shall incorporate a drop tube extending to within 152 mm of the tank bottom. Valve shall be rated for pressurized fuel delivery. Valve shall include integral vacuum breaker for siphon prevention. Size as shown on drawings.

2.2.2.8 Fuel/Vapor Recovery Piping

Pre-piped tank piping shall be 304L Stainless Steel Schedule 10 belled fitted fittings and pipe connections are ANSI 150# RF Flanged W/ #5 bolts, nuts and stainless washers on both flange sides or Victaulic roll grove couplings.

2.2.2.9 Disconnect Coupling

Stainless steel assembly with dust cap for supply delivery connection. Fitting shall be coordinated with fuel supplier to assure compatibility. Installed fitting shall be at 45 degree angle pointing upward to minimize drips. Fitting shall include 40 mesh stainless steel cone strainer.

2.2.2.10 Product Label Marker

Stainless Steel band clamp with API color-coded plaque for product being stored.

2.2.2.11 Decal/Placard

Provide decal or placard affixed to the tank fill box that gives a detailed, step-by-step tank filling procedure as well as the tank calibration chart. The decal or placard must be readily visible during tank filling operations and must be of a material that does not deteriorate when exposed to weather.

2.3 FUEL DISISPENSING SYSTEM FOR DIESEL AND MOGAS

The tank shall be provided with tank manufacturer's standard cataloged product designed and UL listed for service in the fuel indicated and subject to the compliance with the following requirements; for each system, provide the following:

2.3.1 Pump

Configuration: Pump & meter/register combination with integral vacuum breaker and vapor return tubing

Performance: Up to 20 GPM'. Minimum dry vacuum - 15" of mercury.

Compatibility: For dispensing low viscosity petroleum fuels diesel, including biodiesel blends up to 20%; kerosene; and gasoline, including standard oxygenated blends. Fuel must meet the applicable ASTM standard. Not for refueling aircraft.

Meter Register: 4-wheel register (up to 999.9 gallons). Knob reset. 7 -digit (with tenths) non-resettable accumulative totalizer. Phenolic resin nutating disc metering chamber. Accuracy ±.5% at full flow. Adjustable calibration range for different fuel types. Die-cast aluminum housing.

Pump Assembly: Self-priming, rotary vane pump. Cast iron construction for long life. Sintered iron rotor with 8 carbon graphite vanes.
Fiber key connection to motor shaft. Key breaks in the event an obstruction impedes the turning of the motor shaft.

Motor & Electrical: l/3 HP intermittent duty with thermal overload protection. Direct-drive. Explosion-proof. 115VAC 60Hz.

Junction Box: Weatherproof o-ring seal. AC auxiliary line for remote solenoid valve control. External motor switch in separate internal compartment. Die-cast aluminum construction.

Strainer Assembly: Combination strainer and spring-loaded check valve with pressure relief assembly. Cast iron housing.

Anti-Siphon Valve: Integral vacuum breaker in meter discharge. Duckbill design. Copper tubing returns any drips back to tank through fitting in strainer base.

Nozzle Boot: Zinc-plated steel. Protects nozzle from rain and dirt. Accommodates standard automatic and manual nozzles without the need for spout hooks. Easy on/off lever prevents nozzle storage in on position. Nozzle can be padlocked to prevent unauthorized use.

Mounting inlet: 2" NPT male at base of strainer assembly for tank mounting. 1" NPT female suction tube inlet.

Discharge: 1" NPT female at pump. With meter/register assembly, choice of (2) 1" NPT female outlets - top or back. Plug included for unused position.

Finish: Pump and meter painted with blue polyurethane enamel. Meter/register has a black UV-resistant lexan dial face graphic.

Pressure: Working pressure up to 50 psi.

Approvals: ETL &. c-ETL Listed (conforming to UL 79, 674, and 1203 and certified to CSA Standard C22.2 No's. 145-M1986, 30-M1986, and 22-M1986). 700R Register: UL Listed

2.4 PRODUCT DISPENSERS - PRESSURIZED SUPPLY FOR DIESEL AND MOGAS

2.4.1 General

Dispenser:

Includes the following options as standard: 1" piping, j-box J, solenoid valve.

Performance: Up to 22 GPM (83 Ipm)*.

Compatibility: For dispensing low viscosity petroleum fuels - diesel; blodiesel blends up to 20%; gasoline, including oxygenated blends; kerosene; AvGas and jet fuel. Fuel must meet the applicable ASTM standard.

Note: Confirm with fuel supplier on any fluid path metal restrictions before use. If aluminum, zinc, or red metals are not desired, use appropriate option.

Register: Non-computer mechanical register with power reset with interlock. Up to 999.9 gallons per delivery. Non-resettable accumulative totalizer up to 9999999.9. Optional liters measure.

Meter: Reliable micro-accurate 2-piston positive displacement design. Weights & Measures sealable.

Solenoid Valve: 1" (2.5 cm) two-stage valve. Single stage valve.

Electrical: 115VAC, 60 Hz. Optional 230VAC 50/60 Hz operation.

Inlet Connection: 11/2." (3.8 cm) NPT. Bottom access hole sized for 1 1/2 emergency valve installation.

Discharge: 1" (2.5 cm) with 3/4" reducing bushing.

Mounting: Four 7/16" (1.1 cm) mounting holes in bottom with optional shelf-mount kit.

Cabinet Construction: All panels are fabricated from galvannealed steel for corrosion resistance. Front door includes lock and is removable for service. Outer sides, back, and top are removable for additional service access if required.

Cabinet Finish: Extremely durable powder-coated finish to give outstanding appearance and toughness. Metallic silver sides, top, and back. Blue door with black register decal. Optional black, brown, green, red, silver, yellow, or white doors.

Nozzle Boot and Hook: To fit standard UL interchangeable nozzles. Also to fit Emco Wheaton 4015 and Husky V short spout balance vapor recovery nozzles. Hook extension kits for OPW 11 VF (p/n 892081-001) and Healy 400 (p/n 892080-001) long spout vapor recovery nozzles. Lift-start nozzle hook. Provide nozzle as per owner's requirements.

Hose Hanger: Keeps hose off ground when not in use.

Approximate Dimensions: 30.25"H x 16.75"W x 14"D
(76.8cm H x 42.5cm W x 35.6cm D)

Pressure: Working pressure up to 50 psi.

Approvals: C-UL-US Listed. Sealable by U.S. Weights & Measures.

Nozzle: Diesel Husky High Flow Model Number 173310
MOGAS Husky Model Number 159404-04

Hose: Goodyear 1" Fuel Hose, malexmale - compatible with fuel used.

Options:

Shelf-Mount Kit: Carbon steel shelf brackets for mounting dispenser to tank. Black powder coat finish.

Hose Mast: Raises hose to ease hose handling.

External Filter Kit: Installs on discharge.

Liter measure and 230VAC 50/60 Hz operation.

Verify with owner if vapor recovery is required.

2.4.2 Breakaway Coupling

Catlow, Inc., Husky Corp., Richards Industries, coupling separation at 200 pounds maximum pulling force; integral flow preventing seals or valves activated upon coupling separation. U.L. listed and labeled to retain U.L. rating after separation. Husky Model 2200 or equal. Include a 150 mm whip hose at dispenser.

2.5 PRE-PIPED TANK FUEL DISTRIBUTION PIPE AND FITTINGS - DIESEL AND MOGAS

2.5.1 Accessory Equipment

Ball Valves: Stainless steel two-piece body, stainless steel ball, Teflon seats and stuffing box ring, lever handle and balancing stops, threaded ends with union.

2.5.2 Dielectric Connections

Provide dielectric connections at piping connections of dissimilar metals.

2.6 ELECTRICAL REQUIREMENTS

Provide switches and devices necessary for the tank electrical systems system; wiring, fittings, and components shall be explosion-proof in compliance with applicable requirements of UL 674, UL 698, and UL 886 for Class I, Division l, Group C and D hazardous locations. Electrical installations shall conform to requirements of NFPA 70.

2.6.1 Wiring

All wiring shall be designed and installed in strict accordance with NFPA 70.

2.6.2 Tank System

Tank system shall be factory pre-wired and supplied with remote mounted NEMA 7 emergency stop control panel. Panel to be equipped with means of disconnecting all fueling system circuits per NFPA 70 -514.

2.6.3 Panel

System shall include branch circuit panel board, pump motor starter, disconnect relays, pump running indicator, panel disconnect, with maintained mushroom head push button.

2.6.4 Feed

System shall require only one 230V Single Phase 30 amp feeder from main distribution panel. Provide by others.

2.6.5 Enclosure

NEMA 7 explosion-proof.

2.6.6 System Connection

Connect to tank with a single explosion proof UL Listed and CSA Approved for Class I, Groups B, C, D, Divisions 1 and 2 direct burial multiple conductor cable. Conductors shall be color coordinated with control panel and tank connections.

PART 3 EXECUTION

3.1 Excavation

3.1.1 Excavation, Trenching, and Backfilling

See Division 31.

3.2 Fuel Tank Installation.

3.2.1 Installation

Install tanks in strict accordance with the manufacturer's recommendations, PEI/RP200-92, and applicable fire and environmental codes.

3.2.2 Aboveground Tank Markings

Tank shall be clearly marked on all sides with warning signs: "FLAMMABLE" or "COMBUSTIBLE", "NO SMOKING", tank volume, product identification (Diesel or Mogas), and other signs as required by the applicable codes.

3.2.3 Electrical Work

Perform in accordance with applicable codes and shall be rated for hazardous area as required. Tanks shall be electrically grounded in accordance with NFPA 78.

3.2.4 Inspection

Tank installation shall be inspected and approved using services of the tank supplier or its certified contractor. Submit a comprehensive checklist of quality and safety items critical to the system and verify that the installation has been in accordance with these standards and applicable fire and environmental codes from tank supplier.

3.3 TANK LEAK AND LEVEL GAUGE INSTALLATION

3.3.1 General

Install in strict accordance with the manufacturer's recommendations, National Electrical Code NFPA 70, and NFPA 30A.

3.3.2 Electrical

Electrical work shall be rated for hazardous area as required.

3.3.3 Tank Level and Leak Mechanism

Install the tank level mechanism and the interstitial leak mechanism in the proper locations in the fuel tank.

3.4 ELECTRICAL SYSTEM

3.4.1 Wiring

Design, provide and install all branch circuit conduit and wiring for equipment installed in this section. Design and install wiring in strict accordance with NFPA 70.

3.5 FIELD TESTING

Prior to application of test pressure, remove or valve off piping components which may be damaged by test and install a calibrated test gage in the system. Maintain test pressure for at least one hour on all new piping work. In the event of leakage, locate and repair leak and repeat test. Submit a field acceptance test report for each new AST system installation and each new piping system installation.

3.5.1 Piping System Test

After tank erection and installation of valves and piping, test piping. Perform hydrostatic test of new fuel piping work at27 kPa per mm (gage)for one hour. Replace defective material disclosed by pressure test and repeat test until results are satisfactory.

3.5.2 Storage Tank Test

Pressure test tanks at not less than 1.4 kPa per mm (gage)or more than 1.9 kPa per mm (gage) and as recommended by the manufacturer.

3.5.3 Testing Fuel Distribution System

Test fuel distribution system according to NFPA 30. Replace leaking joints and connections with new materils.

3.5.4 Reports

Submit reports of tests and procedures.

3.6 COMMISSIONING

Before activating the system perform these steps:

Flush system piping with grade of fuel to be used by owner to remove any debris and foreign matter in piping prior to filling tank for the first time. Service all system filters and screens and dispose of fuel in accordance with EPA and NFPA regulations after flushing.

Open valves to correct position for system operation.

3.7 INSTRUCTION TO GOVERNMENT PERSONNEL

Furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the AST system, accessories for the AST, and the associated piping system. Instruction shall be given during the a regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. Schedule instruction time with Contracting Officer. The number of man-days (8 hours per day) of instruction furnished shall be one-half. Use approximately half of the time for classroom instruction. Use other time for instruction in the field at the equipment or system.

-- End of Section --

SECTION 33 71 02.00 20

UNDERGROUND ELECTRICAL DISTRIBUTION
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACI INTERNATIONAL (ACI)

ACI 318M	(2008; Errata 2008; Errata 2009) Metric Building Code Requirements for Structural Concrete and Commentary
ACI SP-66	(2004) ACI Detailing Manual

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO HB-17	(2002; Errata 2003; Errata 2005) Standard Specifications for Highway Bridges
AASHTO M 198	(2008) Standard Specification for Joints for Concrete Pipe, Manholes and Precast Box Sections Using Preformed Flexible Joint Sealants

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

AEIC CS8	(2000) Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV

ASTM INTERNATIONAL (ASTM)

ASTM B 1	(2001; R 2007) Standard Specification for Hard-Drawn Copper Wire
ASTM B 3	(2001; R 2007) Standard Specification for Soft or Annealed Copper Wire
ASTM B 496	(2004) Standard Specification for Compact Round Concentric-Lay-Stranded Copper Conductors
ASTM B 8	(2004) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM C 139	(2005) Standard Specification for Concrete Masonry Units for Construction of Catch Basins and Manholes

ASTM C 32	(2009) Standard Specification for Sewer and Manhole Brick (Made from Clay or Shale)
ASTM C 478M	(2009) Standard Specification for Precast Reinforced Concrete Manhole Sections (Metric)
ASTM C 857	(2007) Standard Practice for Minimum Structural Design Loading for Underground Precast Concrete Utility Structures

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2006; Errata 2007; INT 44-56 2007; INT 47, 49, 50, 52-56 2008; INT 57, 58, 51, 48 2009) National Electrical Safety Code
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms
IEEE Std 386	(2006) Standard for Separable Insulated Connector Systems for Power Distribution Systems Above 600V
IEEE Std 400.2	(2004) Guide for Field Testing of Shielded Power Cable Systems Using Very Low Frequency (VLF)
IEEE Std 404	(2006) Extruded and Laminated Dielectric Shielded Cable Joints Rated 2500 V Through 500 000 V
IEEE Std 48	(2009) Test Procedures and Requirements for Alternating-Current Cable Terminations 2.5 kV through 765 kV
IEEE Std 81	(1983) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System (Part 1) Normal Measurements

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)

ICEA S-94-649	(2004) Standard for Concentric Neutral Cable Rated 5 Through 46 KV

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2009) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA C119.1	(2006) Sealed Insulated Underground Connector Systems Rated 600 Volts

NEMA RN 1	(2005) Standard for Polyvinyl Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA TC 2	(2003) Standard for Electrical Polyvinyl Chloride (PVC) Tubing and Conduit
NEMA WC 70	(2009) Standard for Non-Shielded Power Cable 2000 V or Less for the Distribution of Electrical Energy
NEMA WC 71	(1999) Standard for Nonshielded Cables Rated 2001-5000 Volts for use in the Distribution of Electric Energy
NEMA TC 9	(2004) Standard for Fittings for Polyvinyl Chloride (PVC) Plastic Utilities Duct for Underground Installation
NEMA WC 74	(2006) Standard for 5-46 kV Shielded Power Cable for use in the Transmission and Distribution of Electric Energy

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-60005	(Basic; Notice 1) Frames, Covers, Gratings, Steps, Sump And Catch Basin, Manhole

UNDERWRITERS LABORATORIES (UL)

UL 1072	(2006; Rev thru Sep 2007) Medium-Voltage Power Cables
UL 1242	(2006; Rev thru Jul 2007) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 467	(2007) Standard for Grounding and Bonding Equipment
UL 486A-486B	(2003; Rev thru Apr 2009) Standard for Wire Connectors
UL 510	(2005; Rev thru Aug 2005) Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape
UL 514A	(2004; Rev thru Aug 2007) Standard for Metallic Outlet Boxes
UL 514B	(2004; Rev thru Aug 2007) Standard for Conduit, Tubing and Cable Fittings

UL 6	(2007) Standard for Electrical Rigid Metal Conduit-Steel
UL 651	(2005; Rev thru May 2007) Standard for Schedule 40 and 80 Rigid PVC Conduit and Fittings
UL 83	(2008) Standard for Thermoplastic-Insulated Wires and Cables
UL 854	(2004; Rev thru Oct 2007) Service-Entrance Cables

1.2 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. In the text of this section, the words conduit and duct are used interchangeably and have the same meaning.

c. In the text of this section, "medium voltage cable splices," and "medium voltage cable joints" are used interchangeably and have the same meaning.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Precast underground structures

SD-03 Product Data

Medium voltage cable; G

Medium voltage cable joints; G

Medium voltage cable terminations; G

Live end caps

Precast concrete structures

Sealing Material

Pulling-In Irons

Manhole frames and covers

Handhole frames and covers

Frames and Covers for Airfield Facilities

Cable supports (racks, arms and insulators)

Protective Devices and Coordination Study

The study shall be submitted with protective device equipment submittals. No time extension or similar contract modifications will be granted for work arising out of the requirements for this study. Approval of protective devices proposed shall be based on recommendations of this study. The Government shall not be held responsible for any changes to equipment, device ratings, settings, or additional labor for installation of equipment or devices ordered and/or procured prior to approval of the study.

SD-06 Test Reports

Arc-proofing test for cable fireproofing materials

Medium voltage cable qualification and production tests

Field Acceptance Checks and Tests; G

Arc-proofing test for cable fireproofing tape; G

Cable Installation Plan and Procedure

Six copies of the information described below in 215.9 by 279.4 mm binders having a minimum of three rings from which material may readily be removed and replaced, including a separate section for each cable pull. Sections shall be separated by heavy plastic dividers with tabs, with all data sheets signed and dated by the person supervising the pull.

a. Site layout drawing with cable pulls numerically identified.

b. A list of equipment used, with calibration certifications. The manufacturer and quantity of lubricant used on pull.

c. The cable manufacturer and type of cable.

d. The dates of cable pulls, time of day, and ambient temperature.

e. The length of cable pull and calculated cable pulling tensions.

f. The actual cable pulling tensions encountered during pull.

SD-07 Certificates

Cable splicer/terminator

Cable Installer Qualifications

1.4 QUALITY ASSURANCE

1.4.1 Precast Underground Structures

Submittal required for each type used. Provide calculations and drawings for precast manholes and handholes bearing the seal of a registered professional engineer including:

a. Material description (i.e., f'c and Fy)

b. Manufacturer's printed assembly and installation instructions

c. Design calculations

d. Reinforcing shop drawingsin accordance with ACI SP-66

e. Plans and elevations showing opening and pulling-in iron locations and details

1.4.2 Certificate of Competency for Cable Splicer/Terminator

Certification of the qualification of the cable splicer/terminator shall be submitted, for approval, 30 days before splices or terminations are to be made in medium voltage (5 kV to 35 kV) cables. The certification shall include the training, and experience of the individual on the specific type and classification of cable to be provided under this contract. The certification shall indicate that the individual has had three or more years recent experience splicing and terminating medium voltage cables. The certification shall also list a minimum of three splices/terminations that have been in operation for more than one year. In addition, the individual may be required to perform a dummy or practice splice/termination in the presence of the Contracting Officer, before being approved as a qualified cable splicer. If that additional requirement is imposed, the Contractor shall provide short sections of the approved types of cables along with the approved type of splice/termination kit, and detailed manufacturer's instructions for the cable to be spliced. The Contracting Officer reserves the right to require additional proof of competency or to reject the individual and call for certification of an alternate cable splicer.

1.4.3 Cable Installer Qualifications

Provide at least one onsite person in a supervisory position with a documentable level of competency and experience to supervise all cable pulling operations. Provide a resume showing the cable installers' experience in the last three years, including a list of references complete with points of contact, addresses and telephone numbers.

1.4.4 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.4.5 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.5.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.5.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site shall not be used, unless specified otherwise.

PART 2 PRODUCTS

2.1 CONDUIT, DUCTS, AND FITTINGS

2.1.1 Rigid Metal Conduit

UL 6.

2.1.1.1 Rigid Metallic Conduit, PVC Coated

NEMA RN 1, Type A40, except that hardness shall be nominal 85 Shore A durometer, dielectric strength shall be minimum 15.75 kV per mm at 60 Hz, and tensile strength shall be minimum 25 MPa.

2.1.2 Intermediate Metal Conduit

UL 1242.

2.1.2.1 Intermediate Metal Conduit, PVC Coated

NEMA RN 1, Type A40, except that hardness shall be nominal 85 Shore A durometer, dielectric strength shall be minimum 15.75 kV per mm at 60 Hz, and tensile strength shall be minimum 25 MPa.

2.1.3 Plastic Conduit for Direct Burial

UL 651, Schedule 80as indicatedNEMA TC 2, EPC-80-PVC.

2.1.4 Conduit Sealing Compound

Compounds for sealing ducts and conduit shall have a putty-like consistency workable with the hands at temperatures as low as 2 degrees C shall neither slump at a temperature of 150 degrees C, nor harden materially when exposed

to the air. Compounds shall adhere to clean surfaces of fiber or plastic ducts; metallic conduits or conduit coatings; concrete, masonry, or lead; any cable sheaths, jackets, covers, or insulation materials; and the common metals. Compounds shall form a seal without dissolving, noticeably changing characteristics, or removing any of the ingredients. Compounds shall have no injurious effect upon the hands of workmen or upon materials. Inflatable bladders may be used as an option.

2.1.5 Fittings

2.1.5.1 Metal Fittings

UL 514B.

2.1.5.2 PVC Conduit Fittings

UL 514B, UL 651NEMA TC 3.

2.1.5.3 PVC Duct Fittings

NEMA TC 9.

2.1.5.4 Outlet Boxes for Steel Conduit

Outlet boxes for use with rigid or flexible steel conduit shall be cast-metal cadmium or zinc-coated if of ferrous metal with gasketed closures and shall conform to UL 514A.

2.2 LOW VOLTAGE INSULATED CONDUCTORS AND CABLES

Insulated conductors shall be rated 600 volts and conform to the requirements of NFPA 70, including listing requirements, or in accordance with NEMA WC 70. Wires and cables manufactured more than 24 months prior to date of delivery to the site shall not be accepted. Service entrance conductors shall conform to UL 854, type USE.

2.2.1 Conductor Types

Cable and duct sizes indicated are for copper conductors and THHN/THWN unless otherwise noted. Conductors No. 10 AWG and smaller shall be solid copper. Conductors No. 8 AWG and larger shall be stranded copper.

2.2.2 Conductor Material

Unless specified or indicated otherwise or required by NFPA 70, wires in conduit, other than service entrance, shall be 600-volt, Type THWN/THHN conforming to UL 83. Copper conductors shall be annealed copper complying with ASTM B 3 and ASTM B 8.

2.2.3 Jackets

Multiconductor cables shall have an overall PVC outer jacket.

2.2.4 Cable Marking

Insulated conductors shall have the date of manufacture and other identification imprinted on the outer surface of each cable at regular intervals throughout the cable length.

Each cable shall be identified by means of a fiber, laminated plastic, or non-ferrous metal tags, or approved equal, in each manhole, handhole, junction box, and each terminal. Each tag shall contain the following information; cable type, conductor size, circuit number, circuit voltage, cable destination and phase identification.

Conductors shall be color coded. Conductor identification shall be provided within each enclosure where a tap, splice, or termination is made. Conductor identification shall be by color-coded insulated conductors, plastic-coated self-sticking printed markers, colored nylon cable ties and plates, heat shrink type sleeves,or colored electrical tape. Control circuit terminations shall be properly identified. Color shall be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in same raceway or box, other neutrals shall be white with a different colored (not green) stripe for each. Color of ungrounded conductors in different voltage systems shall be as follows

a. 380/220 volt, three-phase

(1) Phase A - black

(2) Phase B - red

(3) Phase C - blue

2.3 LOW VOLTAGE WIRE CONNECTORS AND TERMINALS

Shall provide a uniform compression over the entire conductor contact surface. Use solderless terminal lugs on stranded conductors.

a. For use with copper conductors: UL 486A-486B.

2.4 LOW VOLTAGE SPLICES

Provide splices in conductors with a compression connector on the conductor and by insulating and waterproofing using one of the following methods which are suitable for continuous submersion in water and comply NEMA C119.1.

2.4.1 Heat Shrinkable Splice

Provide heat shrinkable splice insulation by means of a thermoplastic adhesive sealant material which shall be applied in accordance with the manufacturer's written instructions.

2.4.2 Cold Shrink Rubber Splice

Provide a cold-shrink rubber splice which consists of EPDM rubber tube which has been factory stretched onto a spiraled core which is removed during splice installation. The installation shall not require heat or flame, or any additional materials such as covering or adhesive. It shall be designed for use with inline compression type connectors, or indoor, outdoor, direct-burial or submerged locations.

2.5 MEDIUM VOLTAGE CABLE

Cable (conductor) sizes are designated by American Wire Gauge (AWG) and Thousand Circular Mils (Kcmil). Conductor and conduit sizes indicated are

for copper conductors unless otherwise noted. Insulated conductors shall have the date of manufacture and other identification imprinted on the outer surface of each cable at regular intervals throughout cable length. Wires and cables manufactured more than 24 months prior to date of delivery to the site shall not be accepted. Provide single conductor type cables unless otherwise indicated.

2.5.1 Cable Configuration

Provide Type MV cable, conforming to NEMA WC 74 and UL 1072. Provide cables manufactured for use in duct applications. Cable shall be rated 15 kV with 133 percent insulation level.

2.5.2 Conductor Material

Provide concentric-lay-stranded, Class B compact round conductors. Provide soft drawn copper cables complying with ASTM B 3 and ASTM B 8 for regular concentric and compressed stranding or ASTM B 496 for compact stranding.

2.5.3 Insulation

Provide ethylene-propylene-rubber (EPR) insulation conforming to the requirements of NEMA WC 71 and AEIC CS8 ICEA S-94-649.

2.5.4 Shielding

Cables rated for 2 kV and above shall have a semiconducting conductor shield, a semiconducting insulation shield, and an overall copper tape shield for each phase.

2.5.5 Neutrals

Neutral conductors of shall be copper, employing the same insulation and jacket materials as phase conductors, except that a 600-volt insulation rating is acceptable. For high impedance grounded neutral systems, the neutral conductors from the neutral point of the transformer or generator to the connection point at the impedance shall utilize copper conductors, employing the same insulation level and construction as the phase conductors.

2.5.6 Jackets

Provide PVC jackets with a separator that prevents contact when underlying semiconducting insulating shield.

2.6 MEDIUM VOLTAGE CABLE TERMINATIONS

IEEE Std 48 Class 1; of the molded elastomer, prestretched elastomer, or heat-shrinkable elastomer. Acceptable elastomers are track-resistant silicone rubber or track-resistant ethylene propylene compounds, such as ethylene propylene rubber or ethylene propylene diene monomer. Separable insulated connectors may be used for apparatus terminations, when such apparatus is provided with suitable bushings. Terminations, where required, shall be provided with mounting brackets suitable for the intended installation and with grounding provisions for the cable shielding, metallic sheath, or armor. Terminations shall be provided in a kit, including: skirts, stress control terminator, ground clamp, connectors, lugs, and complete instructions for assembly and installation. Terminations shall be the product of one manufacturer, suitable for the

type, diameter, insulation class and level, and materials of the cable terminated.

2.6.1 Cold-Shrink Type

Terminator shall be a one-piece design, utilizing the manufacturer's latest technology, where high-dielectric constant (capacitive) stress control is integrated within a skirted insulator made of silicone rubber. Termination shall not require heat or flame for installation. Termination kit shall contain all necessary materials (except for the lugs). Termination shall be designed for installation in low or highly contaminated indoor and outdoor locations and shall resist ultraviolet rays and oxidative decomposition.

2.6.2 Heat Shrinkable Type

Terminator shall consist of a uniform cross section heat shrinkable polymeric construction stress relief tubing and environmentally sealed outer covering that is nontracking, resists heavy atmospheric contaminants, ultra violet rays and oxidative decomposition. Provide heat shrinkable sheds or skirts of the same material. Termination shall be designed for installation in low or highly contaminated indoor or outdoor locations.

2.6.3 Separable Insulated Connector Type

IEEE Std 386. Provide connector with steel reinforced hook-stick eye, grounding eye, test point, and arc-quenching contact material. Provide connectors of the loadbreak or deadbreak type as indicated, of suitable construction for the application and the type of cable connected, and that include cable shield adaptors. Provide external clamping points and test points.

a. 200 Ampere loadbreak connector ratings: Voltage: 15 kV, 95 kV BIL. Short time rating: 10,000 rms symmetrical amperes.

2.7 MEDIUM VOLTAGE CABLE JOINTS

Provide joints (splices) in accordance with IEEE Std 404 suitable for the rated voltage, insulation level, insulation type, and construction of the cable. Joints shall be certified by the manufacturer for waterproof, submersible applications. Upon request, supply manufacturer's design qualification test report in accordance with IEEE Std 404. Connectors for joint shall be tin-plated electrolytic copper, having ends tapered and having center stops to equalize cable insertion.

2.7.1 Heat-Shrinkable Joint

Consists of a uniform cross-section heat-shrinkable polymeric construction with a linear stress relief system, a high dielectric strength insulating material, and an integrally bonded outer conductor layer for shielding. Replace original cable jacket with a heavy-wall heat-shrinkable sleeve with hot-melt adhesive coating.

2.7.2 Cold-Shrink Rubber-Type Joint

Joint shall be of a cold shrink design that does not require any heat source for its installation. Splice insulation and jacket shall be of a one-piece factory formed cold shrink sleeve made of black EPDM rubber. Splice shall be packaged three splices per kit, including complete

installation instructions.

2.8 TAPE

2.8.1 Insulating Tape

UL 510, plastic insulating tape, capable of performing in a continuous temperature environment of 80 degrees C.

2.8.2 Buried Warning and Identification Tape

Provide detectable tape in accordance with Section 31 00 00 EARTHWORK

2.8.3 Fireproofing Tape

Provide tape composed of a flexible conformable unsupported intumescent elastomer. Tape shall be not less than 0.762 mm thick, noncorrosive to cable sheath, self-extinguishing, noncombustible, and shall not deteriorate when subjected to oil, water, gases, salt water, sewage, and fungus.

2.9 PULL ROPE

Shall be plastic or flat pull line (bull line) having a minimum tensile strength of 890 N.

2.10 GROUNDING AND BONDING

2.10.1 Driven Ground Rods

Provide copper-clad steel ground rods conforming to UL 467 not less than 19 mm in diameter by 3.1 m in length. Sectional type rods may be used for rods 20 feet or longer.

2.10.2 Grounding Conductors

Stranded-bare copper conductors shall conform to ASTM B 8, Class B, soft-drawn unless otherwise indicated. Solid-bare copper conductors shall conform to ASTM B 1 for sizes No. 8 and smaller. Insulated conductors shall be of the same material as phase conductors and green color-coded, except that conductors shall be rated no more than 600 volts. Aluminum is not acceptable.

2.11 CAST-IN-PLACE CONCRETE

Provide concrete in accordance with Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE. In addition, provide concrete for encasement of underground ducts with 20 MPa minimum 28-day compressive strength. Concrete associated with electrical work for other than encasement of underground ducts shall be 30 MPa minimum 28-day compressive strength unless specified otherwise.

2.12 UNDERGROUND STRUCTURES

Provide precast concrete underground structures or standard type cast-in-place manhole types as indicated, conforming to ASTM C 857 and ASTM C 478M . Top, walls, and bottom shall consist of reinforced concrete. Walls and bottom shall be of monolithic concrete construction. Locate duct entrances and windows near the corners of structures to facilitate cable racking. Covers shall fit the frames without undue play.

Form steel and iron to shape and size with sharp lines and angles. Castings shall be free from warp and blow holes that may impair strength or appearance. Exposed metal shall have a smooth finish and sharp lines and arises. Provide necessary lugs, rabbets, and brackets. Set pulling-in irons and other built-in items in place before depositing concrete. Install a pulling-in iron in the wall opposite each duct line entrance. Cable racks, including rack arms and insulators, shall be adequate to accommodate the cable.

2.12.1 Cast-In-Place Concrete Structures

Concrete shall conform to Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE. Construct walls on a footing of cast-in-place concrete except that precast concrete base sections may be used for precast concrete manhole risers. Concrete block shall conform to ASTM C 139 and Section 04 20 00, MASONRY.

2.12.2 Precast Concrete Structures, Risers and Tops

In lieu of cast-in-place, Contractors, at their option, may provide precast concrete underground structures subject to the requirements specified below. Precast units shall be the product of a manufacturer regularly engaged in the manufacture of precast concrete products, including precast manholes.

2.12.2.1 General

Precast concrete structures shall have the same accessories and facilities as required for cast-in-place structures. Likewise, precast structures shall have plan area and clear heights not less than those of cast-in-place structures. Concrete materials and methods of construction shall be the same as for cast-in-place concrete construction, as modified herein. Slope in floor may be omitted provided precast sections are poured in reinforced steel forms. Concrete for precast work shall have a 28-day compressive strength of not less than 30 MPa. Structures may be precast to the design and details indicated for cast-in-place construction, precast monolithically and placed as a unit, or structures may be assembled sections, designed and produced by the manufacturer in accordance with the requirements specified. Structures shall be identified with the manufacturer's name embedded in or otherwise permanently attached to an interior wall face.

2.12.2.2 Design for Precast Structures

ACI 318M. In the absence of detailed on-site soil information, design for the following soil parameters/site conditions:

a. Angle of Internal Friction (phi) = 0.523 rad

b. Unit Weight of Soil (Dry) = 1760 kg/m^3, (Saturated) = 2080 kg/m^3

c. Coefficient of Lateral Earth Pressure (Ka) = 0.33

d. Ground Water Level = 915 mm below ground elevation

e. Vertical design loads shall include full dead, superimposed dead, and live loads including a 30 percent magnification factor for impact. Live loads shall consider all types and magnitudes of vehicular traffic

to be encountered. The minimum design vertical load shall be for H20 highway loading per AASHTO HB-17.

f. Horizontal design loads shall include full geostatic and hydrostatic pressures for the soil parameters, water table, and depth of installation to be encountered. Also, horizontal loads imposed by adjacent structure foundations, and horizontal load components of vertical design loads, including impact, shall be considered, along with a pulling-in iron design load of 26,700 N.

g. Each structural component shall be designed for the load combination and positioning resulting in the maximum shear and moment for that particular component.

h. Design shall also consider the live loads induced in the handling, installation, and backfilling of the manholes. Provide lifting devices to ensure structural integrity during handling and installation.

2.12.2.3 Construction

Structure top, bottom, and wall shall be of a uniform thickness of not less than 150 mm. Thin-walled knock-out panels for designed or future duct bank entrances shall not be permitted. Quantity, size, and location of duct bank entrance windows shall be as directed, and cast completely open by the precaster. Size of windows shall exceed the nominal duct bank envelope dimensions by at least 305 mm vertically and horizontally to preclude in-field window modifications made necessary by duct bank misalignment. However, the sides of precast windows shall be a minimum of 150 mm from the inside surface of adjacent walls, floors, or ceilings. Form the perimeter of precast window openings to have a keyed or inward flared surface to provide a positive interlock with the mating duct bank envelope. Provide welded wire fabric reinforcing through window openings for in-field cutting and flaring into duct bank envelopes. Provide additional reinforcing steel comprised of at least two No. 4 bars around window openings. Provide drain sumps a minimum of 305 mm in diameter and 100 mm deep for precast structures.

2.12.2.4 Joints

Provide tongue-and-groove joints on mating edges of precast components. Shiplap joints are not allowed. Design joints to firmly interlock adjoining components and to provide waterproof junctions and adequate shear transfer. Seal joints watertight using preformed plastic strip conforming to AASHTO M 198, Type B. Install sealing material in strict accordance with the sealant manufacturer's printed instructions. Provide waterproofing at conduit/duct entrances into structures, and where access frame meets the top slab, provide continuous grout seal.

2.12.3 Manhole Frames and Covers

Provide cast iron frames and covers for manholes conforming to CID A-A-60005. Cast the words "ELECTRIC" in the top face of power and telecommunications manhole covers, respectively.

2.12.4 Handhole Frames and Covers

Frames and covers of steel shall be welded by qualified welders in accordance with standard commercial practice. Steel covers shall be rolled-steel floor plate having an approved antislip surface. Hinges shall

be of stainless steel with bronze hinge pin, 125 by 125 mmby approximately 4.75 mm thick, without screw holes, and shall be for full surface application by fillet welding. Hinges shall have nonremovable pins and five knuckles. The surfaces of plates under hinges shall be true after the removal of raised antislip surface, by grinding or other approved method.

2.12.5 Brick for Manhole Collar

Brick shall be sewer and manhole brick conforming to ASTM C 32, Grade MS.

2.12.6 Composite/Fiberglass Handholes and Covers

Provide handholes and covers of polymer concrete, reinforced with heavy weave fiberglass.

2.13 CABLE SUPPORTS (RACKS, ARMS, AND INSULATORS)

The metal portion of racks and arms shall be zinc-coated after fabrication.

2.13.1 Cable Racks

The wall bracket shall be 100 mm by approximately 38 mm by 4.76 mm channel steel, 1220 mm long (minimum) in manholes. Slots for mounting cable rack arms shall be spaced at 200 mm intervals.

2.13.2 Rack Arms

Cable rack arms shall be steel or malleable iron or glass reinforced nylon and shall be of the removable type. Rack arm length shall be a minimum of 200 mm and a maximum of 305 mm.

2.13.3 Insulators

Insulators for metal rack arms shall be dry-process glazed porcelain. Insulators are not required for nylon arms.

2.14 CABLE TAGS IN MANHOLES

Provide tags for each power cable located in manholes. The tags shall be polyethylene. Do not provide handwritten letters. The first position on the power cable tag shall denote the voltage. The second through sixth positions on the tag shall identify the circuit. The next to last position shall denote the phase of the circuit and shall include the Greek "phi" symbol. The last position shall denote the cable size. As an example, a tag could have the following designation: "11.5 NAS 1-8(Phase A)500," denoting that the tagged cable is on the 11.5kV system circuit number NAS 1-8, underground, Phase A, sized at 500 kcmil.

2.14.1 Polyethylene Cable Tags

Provide tags of polyethylene that have an average tensile strength of 22.4 MPa; and that are two millimeter thick (minimum), non-corrosive non-conductive; resistive to acids, alkalis, organic solvents, and salt water; and distortion resistant to 77 degrees C. Provide 1.3 mm (minimum) thick black polyethylene tag holder. Provide a one-piece nylon, self-locking tie at each end of the cable tag. Ties shall have a minimum loop tensile strength of 778.75 N. The cable tags shall have black block letters, numbers, and symbols 25 mm high on a yellow background. Letters, numbers, and symbols shall not fall off or change positions regardless of

the cable tags' orientation.

2.15 SOURCE QUALITY CONTROL

2.15.1 Arc-Proofing Test for Cable Fireproofing Tape

Manufacturer shall test one sample assembly consisting of a straight lead tube 305 mm long with a 65.5 mm outside diameter, and a 3.175-mm thick wall, and covered with one-half lap layer of arc and fireproofing material per manufacturer's instructions. The arc and fireproofing tape shall withstand extreme temperature of a high-current fault arc 13,000 degrees K for 70 cycles as determined by using an argon directed plasma jet capable of constantly producing and maintaining an arc temperature of 13,000 degrees K. Temperature (13,000 degrees K) of the ignited arc between the cathode and anode shall be obtained from a dc power source of 305 (plus or minus 5) amperes and 20 (plus or minus 1) volts. The arc shall be directed toward the sample assembly accurately positioned 5 (plus or minus 1) millimeters downstream in the plasma from the anode orifice by fixed flow rate of argon gas (0.18 g per second). Each sample assembly shall be tested at three unrelated points. Start time for tests shall be taken from recorded peak current when the specimen is exposed to the full test temperature. Surface heat on the specimen prior to that time shall be minimal. The end point is established when the plasma or conductive arc penetrates the protective tape and strikes the lead tube. Submittals for arc-proofing tape shall indicate that the test has been performed and passed by the manufacturer.

2.15.2 Medium Voltage Cable Qualification and Production Tests

Results of AEIC CS8 qualification and production tests as applicable for each type of medium voltage cable.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment and devices in accordance with the manufacturer's published instructions and with the requirements and recommendations of NFPA 70 and IEEE C2 and CALPUC G.O.128 as applicable.

3.2 CABLE INSPECTION

Prior to installation, each cable reel shall be inspected for correct storage positions, signs of physical damage, and broken end seals. If end seal is broken, moisture shall be removed from cable prior to installation in accordance with the cable manufacturer's recommendations.

3.3 CABLE INSTALLATION PLAN AND PROCEDURE

The Contractor shall obtain from the manufacturer an installation manual or set of instructions which addresses such aspects as cable construction, insulation type, cable diameter, bending radius, cable temperature limits for installation, lubricants, coefficient of friction, conduit cleaning, storage procedures, moisture seals, testing for and purging moisture, maximum allowable pulling tension, and maximum allowable sidewall bearing pressure. The Contractor shall then prepare a checklist of significant requirements which shall be submitted along with the manufacturers instructions in accordance with SUBMITTALS. Cable shall be installed strictly in accordance with the cable manufacturer's recommendations and

the approved installation plan.

Calculations and pulling plan shall include:

a. Site layout drawing with cable pulls identified in numeric order of expected pulling sequence and direction of cable pull.

b. List of cable installation equipment.

c. Lubricant manufacturer's application instructions.

d. Procedure for resealing cable ends to prevent moisture from entering cable.

e. Cable pulling tension calculations of all cable pulls.

f. Cable percentage conduit fill.

g. Cable sidewall bearing pressure.

h. Cable minimum bend radius and minimum diameter of pulling wheels used.

i. Cable jam ratio.

j. Maximum allowable pulling tension on each different type and size of conductor.

k. Maximum allowable pulling tension on pulling device.

3.4 UNDERGROUND FEEDERS SUPPLYING BUILDINGS

Terminate underground feeders supplying building at a point 1525 mm outside the building and projections thereof, except that conductors shall be continuous to the terminating point indicated. Coordinate connections of the feeders to the service entrance equipment with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Conduit shall be IMC from the supply equipment to a point 1525 mm outside the building and projections thereof. Protect ends of underground conduit with plastic plugs until connections are made.

3.5 UNDERGROUND CONDUIT AND DUCT SYSTEMS

3.5.1 Requirements

Depths to top of the conduit shall be in accordance with NFPA 70. Run conduit in straight lines except where a change of direction is necessary. Numbers and sizes of ducts shall be as indicated. Ducts shall have a continuous slope downward toward underground structures and away from buildings, laid with a minimum slope of 100 mm per 30 m. Depending on the contour of the finished grade, the high-point may be at a terminal, a manhole, a handhole, or between manholes or handholes. Short-radius manufactured 90-degree duct bends may be used only for pole or equipment risers, unless specifically indicated as acceptable. The minimum manufactured bend radius shall be 450 mm for ducts of less than 80 mm diameter, and 900 mm for ducts 80 mm or greater in diameter. Otherwise, long sweep bends having a minimum radius of 7.6 m shall be used for a change of direction of more than 5 degrees, either horizontally or vertically. Both curved and straight sections may be used to form long

sweep bends, but the maximum curve used shall be 30 degrees and manufactured bends shall be used. Ducts shall be provided with end bells whenever duct lines terminate in structures.

3.5.2 Treatment

Ducts shall be kept clean of concrete, dirt, or foreign substances during construction. Field cuts requiring tapers shall be made with proper tools and match factory tapers. A coupling recommended by the duct manufacturer shall be used whenever an existing duct is connected to a duct of different material or shape. Ducts shall be stored to avoid warping and deterioration with ends sufficiently plugged to prevent entry of any water or solid substances. Ducts shall be thoroughly cleaned before being laid. Plastic ducts shall be stored on a flat surface and protected from the direct rays of the sun.

3.5.3 Conduit Cleaning

As each conduit run is completed, for conduit sizes 75 mm and larger, draw a flexible testing mandrel approximately 305 mm long with a diameter less than the inside diameter of the conduit through the conduit. After which, draw a stiff bristle brush through until conduit is clear of particles of earth, sand and gravel; then immediately install conduit plugs. For conduit sizes less than 75 mm, draw a stiff bristle brush through until conduit is clear of particles of earth, sand and gravel; then immediately install conduit plugs.

3.5.4 Galvanized Conduit Concrete Penetrations

Galvanized conduits which penetrate concrete (slabs, pavement, and walls) in wet locations shall be PVC coated and shall extend from at least 50 mm within the concrete to the first coupling or fitting outside the concrete (minimum of 150 mm from penetration).

3.5.5 Multiple Conduits

Separate multiple conduits by a minimum distance of 65 mm, except that light and power conduits shall be separated from control, signal, and telephone conduits by a minimum distance of 75 mm. Stagger the joints of the conduits by rows (horizontally) and layers (vertically) to strengthen the conduit assembly. Provide plastic duct spacers that interlock vertically and horizontally. Spacer assembly shall consist of base spacers, intermediate spacers, ties, and locking device on top to provide a completely enclosed and locked-in conduit assembly. Install spacers per manufacturer's instructions, but provide a minimum of two spacer assemblies per 3050 mm of conduit assembly.

3.5.6 Conduit Plugs and Pull Rope

New conduit indicated as being unused or empty shall be provided with plugs on each end. Plugs shall contain a weephole or screen to allow water drainage. Provide a plastic pull rope having 915 mm of slack at each end of unused or empty conduits.

3.5.7 Conduit and Duct Without Concrete Encasement

Provide not less than 75 mm clearance from the conduit to each side of the trench. Grade bottom of trench smooth; where rock, soft spots, or sharp-edged materials are encountered, excavate the bottom for an

additional 75 mm, fill and tamp level with original bottom with sand or earth free from particles, that would be retained on a 6.25 mm sieve. The first 150 mm layer of backfill cover shall be sand compacted as previously specified. The rest of the excavation shall be backfilled and compacted in 75 to 150 mm layers. Provide color, type and depth of warning tape as specified in Section 31 23 00.00 20 EXCAVATION AND FILL.

3.5.7.1 Encasement Under Roads and Structures

Under roads, paved areas, and railroad tracks, install conduits in concrete encasement of rectangular cross-section providing a minimum of 75 mm concrete cover around ducts. Concrete encasement shall extend at least 1525 mm beyond the edges of paved areas and roads.

3.5.8 Connections to Manholes

Duct bank envelopes connecting to underground structures shall be flared to have enlarged cross-section at the manhole entrance to provide additional shear strength. Dimensions of the flared cross-section shall be larger than the corresponding manhole opening dimensions by no less than 300 mm in each direction. Perimeter of the duct bank opening in the underground structure shall be flared toward the inside or keyed to provide a positive interlock between the duct bank and the wall of the structure. Use vibrators when this portion of the encasement is poured to assure a seal between the envelope and the wall of the structure.

3.6 CABLE PULLING

Pull cables down grade with the feed-in point at the manhole or buildings of the highest elevation. Use flexible cable feeds to convey cables through manhole opening and into duct runs. Do not exceed the specified cable bending radii when installing cable under any conditions, including turnups into switches, transformers, switchgear, switchboards, and other enclosures. Cable with wire shield shall have a bending radius not less than 12 times the overall diameter of the completed cable. If basket-grip type cable-pulling devices are used to pull cable in place, cut off the section of cable under the grip before splicing and terminating.

3.6.1 Cable Lubricants

Use lubricants that are specifically recommended by the cable manufacturer for assisting in pulling jacketed cables.

3.7 CABLES IN UNDERGROUND STRUCTURES

Do not install cables utilizing the shortest path between penetrations, but route along those walls providing the longest route and the maximum spare cable lengths. Form cables to closely parallel walls, not to interfere with duct entrances, and support on brackets and cable insulators. Support cable splices in underground structures by racks on each side of the splice. Locate splices to prevent cyclic bending in the spliced sheath. Install cables at middle and bottom of cable racks, leaving top space open for future cables, except as otherwise indicated for existing installations. Provide one spare three-insulator rack arm for each cable rack in each underground structure.

3.7.1 Cable Tag Installation

Install cable tags in each manhole as specified, including each splice.

Tag wire and cable provided by this contract. Install cable tags over the fireproofing, if any, and locate the tags so that they are clearly visible without disturbing any cabling or wiring in the manholes.

3.8 CONDUCTORS INSTALLED IN PARALLEL

Conductors shall be grouped such that each conduit of a parallel run contains 1 Phase A conductor, 1 Phase B conductor, 1 Phase C conductor, and 1 neutral conductor.

3.9 LOW VOLTAGE CABLE SPLICING AND TERMINATING

Make terminations and splices with materials and methods as indicated or specified herein and as designated by the written instructions of the manufacturer. Do not allow the cables to be moved until after the splicing material has completely set. Make splices in underground distribution systems only in accessible locations such as manholes,handholes, or aboveground termination cabinets.

3.10 MEDIUM VOLTAGE CABLE TERMINATIONS

Make terminations in accordance with the written instruction of the termination kit manufacturer.

3.11 MEDIUM VOLTAGE CABLE JOINTS

Provide power cable joints (splices) suitable for continuous immersion in water. Make joints only in accessible locations in manholes or handholes by using materials and methods in accordance with the written instructions of the joint kit manufacturer.

3.11.1 Joints in Shielded Cables

Cover the joined area with metallic tape, or material like the original cable shield and connect it to the cable shield on each side of the splice. Provide a bare copper ground connection brought out in a watertight manner and grounded to the manhole grounding loop as part of the splice installation. Ground conductors, connections, and rods shall be as specified elsewhere in this section. Wire shall be trained to the sides of the enclosure to prevent interference with the working area.

3.12 CABLE END CAPS

Cable ends shall be sealed at all times with coated heat shrinkable end caps. Cables ends shall be sealed when the cable is delivered to the job site, while the cable is stored and during installation of the cable. The caps shall remain in place until the cable is spliced or terminated. Sealing compounds and tape are not acceptable substitutes for heat shrinkable end caps. Cable which is not sealed in the specified manner at all times will be rejected.

3.13 FIREPROOFING OF CABLES IN UNDERGROUND STRUCTURES

Fireproof (arc proof) wire and cables which will carry current at 2200 volts or more in underground structures.

3.13.1 Fireproofing Tape

Tightly wrap strips of fireproofing tape around each cable spirally in

half-lapped wrapping. Install tape in accordance with manufacturer's instructions.

3.14 GROUNDING SYSTEMS

Provide grounding system as indicated, in accordance with NFPA 70 and IEEE C2, and as specified herein.

Noncurrent-carrying metallic parts associated with electrical equipment shall have a maximum resistance to solid earth ground not exceeding the following values:

Pad-mounted transformers without protective fences	5 ohms
Ground in manholes	5 ohms
Grounding other metal enclosures of primary voltage electrical and electrically-operated equipment	5 ohms

3.14.1 Grounding Electrodes

Provide cone pointed driven ground rods driven full depth plus 150 mm 300 mm installed to provide an earth ground of the appropriate value for the particular equipment being grounded. If the specified ground resistance is not met, an additional ground rod shall be provided in accordance with the requirements of NFPA 70 (placed not less than 6 feet from the first rod). Should the resultant (combined) resistance exceed the specified resistance, measured not less than 48 hours after rainfall, the Contracting Officer shall be notified immediately.

3.14.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, by exothermic weld or compression connector.

a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.

b. Make compression connections using a hydraulic compression tool to provide the correct circumferential pressure. Tools and dies shall be as recommended by the manufacturer. An embossing die code or other standard method shall provide visible indication that a connector has been adequately compressed on the ground wire.

3.14.3 Grounding Conductors

Provide bare grounding conductors, except where installed in conduit with associated phase conductors. Ground cable sheaths, cable shields, conduit, and equipment with No. 6 AWG. Ground other noncurrent-carrying metal parts and equipment frames of metal-enclosed equipment. Ground metallic frames and covers of handholes and pull boxes with a braided, copper ground strap with equivalent ampacity of No. 6 AWG.

3.14.4 Ground Cable Crossing Expansion Joints

Protect ground cables crossing expansion joints or similar separations in structures and pavements by use of approved devices or methods of installation which provide the necessary slack in the cable across the joint to permit movement. Use stranded or other approved flexible copper cable across such separations.

3.14.5 Manhole Grounding

Loop a 4/0 AWG grounding conductor around the interior perimeter, approximately 305 mm above finished floor. Secure the conductor to the manhole walls at intervals not exceeding 914 mm . Connect the conductor to the manhole grounding electrode with 4/0 AWG conductor. Connect all incoming 4/0 grounding conductors to the ground loop adjacent to the point of entry into the manhole. Bond the ground loop to all cable shields, metal cable racks, and other metal equipment with a minimum 6 AWG conductor.

3.15 EXCAVATING, BACKFILLING, AND COMPACTING

Provide in accordance with NFPA 70 and Section 31 23 00.00 20 EXCAVATION AND FILL.

3.15.1 Reconditioning of Surfaces

3.15.1.1 Unpaved Surfaces

Restore to their original elevation and condition unpaved surfaces disturbed during installation of duct. Preserve sod and topsoil removed during excavation and reinstall after backfilling is completed. Replace sod that is damaged by sod of quality equal to that removed. When the surface is disturbed in a newly seeded area, re-seed the restored surface with the same quantity and formula of seed as that used in the original seeding, and provide topsoiling, fertilizing, liming, seeding, sodding, sprigging, or mulching.

3.16 CAST-IN-PLACE CONCRETE

Provide concrete in accordance with Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.16.1 Concrete Slabs for Equipment

Unless otherwise indicated, the slab shall be at least 200 mm thick, reinforced with a 152 mm x 152 mm - MW19 by MW19 (6 by 6 - W2.9 by W2.9) mesh, placed uniformly 100 mm from the top of the slab. Slab shall be placed on a 150 mm thick, well-compacted gravel base. Top of concrete slab shall be approximately 100 mm above finished grade with gradual slope for drainage. Edges above grade shall have 15 mm chamfer. Slab shall be of adequate size to project at least 200 mm beyond the equipment.

Stub up conduits, with bushings, 50 mm into cable wells in the concrete pad. Coordinate dimensions of cable wells with transformer cable training areas.

3.17 FIELD QUALITY CONTROL

3.17.1 Performance of Field Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations, and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.17.1.1 Medium Voltage Cables

Perform tests after installation of cable, splices, and terminators and before terminating to equipment or splicing to existing circuits.

a. Visual and Mechanical Inspection

(1) Inspect exposed cable sections for physical damage.

(2) Verify that cable is supplied and connected in accordance with contract plans and specifications.

(3) Inspect for proper shield grounding, cable support, and cable termination.

(4) Verify that cable bends are not less than ICEA or manufacturer's minimum allowable bending radius.

(5) Inspect for proper fireproofing.

(6) Visually inspect jacket and insulation condition.

(7) Inspect for proper phase identification and arrangement.

b. Electrical Tests

(1) Perform a shield continuity test on each power cable by ohmmeter method. Record ohmic value, resistance values in excess of 10 ohms per 1000 feet of cable must be investigated and justified.

(2) Perform acceptance test on new cables before the new cables are connected to existing cables and placed into service, including terminations and joints. Perform maintenance test on complete cable system after the new cables are connected to existing cables and placed into service, including existing cable, terminations, and joints. Tests shall be very low frequency (VLF) alternating voltage withstand tests in accordance with IEEE Std 400.2. VLF test frequency shall be 0.05 Hz minimum for a duration of 60 minutes using a sinusoidal waveform. Test voltages shall be as follows:

CABLE RATING	AC TEST VOLTAGE for ACCEPTANCE TESTING
15 kV	20kV rms(peak)

CABLE RATING	AC TEST VOLTAGE for MAINTENANCE TESTING
15 kV	16kV rms(peak)

3.17.1.2 Grounding System

a. Visual and mechanical inspection

Inspect ground system for compliance with contract plans and specifications

b. Electrical tests

Perform ground-impedance measurements utilizing the fall-of-potential method in accordance with IEEE Std 81. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable megohmmeter tester in accordance with manufacturer's instructions to test each ground or group of grounds. The instrument shall be equipped with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test.

3.17.2 Follow-Up Verification

Upon completion of acceptance checks and tests, the Contractor shall show by demonstration in service that circuits and devices are in good operating condition and properly performing the intended function. As an exception to requirements stated elsewhere in the contract, the Contracting Officer shall be given 5 working days advance notice of the dates and times of checking and testing.

-- End of Section --

SECTION 34 71 13.19

VEHICLE BARRIERS
04/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M (2008; Errata 2009) Structural Welding Code - Steel

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation; G, AE

Detail drawings containing details required to demonstrate that the system has been coordinated and will properly function as a unit. Drawings shall show proposed layout and relationship to other parts of the work including any necessary foundation and clearances for maintenance and operation. Detail drawings shall include a copy of the Department of State certificate of barrier performance.

SD-03 Product Data

Vehicle Barriers

A complete list of equipment, materials, including industrial standards used and how they apply to the applicable component and manufacturer's descriptive data and technical literature, catalog cuts, and installation instructions. Information necessary to document a minimum 1-year successful field operation performance history for each type of vehicle barrier installed.

Spare Parts

Spare parts data for each different item of material and equipment used, after approval of the detail drawings. The data shall include a complete list of parts and supplies, with current unit prices and source of supply.

SD-06 Test Reports

Field Testing

Test reports in booklet form showing all field tests, including component adjustments and demonstration of compliance with the specified performance criteria, upon completion and testing of the installed system. Each test report shall indicate the final position of controls.

SD-07 Certificates

DOD Certified Anti-Ram Vehicle Barriers - K12
DOS Certified Anti-Ram Vehicle Barriers - K12

1.3 GENERAL REQUIREMENTS

Vehicle Barriers furnished shall in all respects be identical to the unit tested and certified except for the width of the vehicle barrier, which is as indicated.

1.4 NAMEPLATES

Nameplate data shall be permanently attached to each vehicle barrier. The data shall be legibly marked on corrosion-resistant metal plates and shall consist of at least the following:

a. Manufacturer's name.

b. Model number.

c. Serial number.

d. Date of manufacture.

1.5 BARRIER SYSTEM

The Barrier system shall be crated or mounted on skids as necessary to prevent damage from handling. The shipping container(s) shall be of sufficient structural integrity to enable the assembly to be lifted and transported by overhead crane or forklift without failure.

1.6 DELIVERY AND STORAGE

Components placed in storage shall be protected from the weather, humidity, and temperature variation, dirt and dust, or other contaminants. Structural materials shall be stored on sleepers or pallets and shall be protected from rust and objectionable materials such as dirt, grease, or oil.

1.7 SPARE PARTS

As applicable, manufacturer's standard recommended spare parts package, with current unit prices and source of supply complete with detailed manuals on parts replacement, shall be provided with each barrier to facilitate 1 year of normal use. Particular consideration shall be given to system components which are not readily available from local or commercial sources and which are critical to the operation of the system.

PART 2 PRODUCTS

2.1 PASSIVE SURFACE BARRIER

The passive surface barrier shall be a surface mounted assembly of the indicated types that shall present a visible obstacle to approaching vehicles. The height of the barrier shall be a minimum height as indicated as measured from the surface to the top of the passive surface barrier. The passive surface barrier shall be capable of blocking any specified width. The passive surface barrier shall withstand a 6804 kg vehicle traveling at 80 km/hour, with maximum vehicle penetration of 6 m.

2.1.1 Experience

Barrier construction shall be of a proven design. Manufacturer shall have 5 years documented experience with similar vehicle barriers.

2.1.2 System Configuration

Barrier Construction. Barriers shall be a surface assembly.

"Flat-packed" systems shall consist of a prefabricated, joinable, extensible, fillable, multicellular system, comprising high strength construction such as galvanized steel mesh with non-woven polypropylene geotextile lining and appropriate fill material e.g. concrete, sand, etc.

All systems shall present a formidable obstacle to approaching vehicles. Upon vehicle impact, the force shall be absorbed by the passive surface barrier.

2.1.3 Qualification Tests

The barrier system shall have been tested in full scale configuration in accordance with the Department of State Certification Standard Test Method for Vehicle Crash Testing of Perimeter Barriers and Gates, SD-STD-02.01, Revision A, March 2003, rating K12.

2.2 FINISH

Surfaces shall be painted in accordance with requirements of Section 09 90 00 PAINTS AND COATINGS.

2.3 CONCRETE

The concrete reinforcements, and accessories shall conform to Section 03 31 00.00 10 CAST-IN-PLACE STRUCTURAL CONCRETE.

2.4 WELDING

Welding shall be in accordance with AWS D1.1/D1.1M.

2.5 PAVEMENT

Positive surface drainage, away from the vehicle barrier, shall be provided by pavement slope.

PART 3 EXECUTION

3.1 INSTALLATION

Installation shall be in accordance with manufacturers instructions and at the direction of the Contracting Officer in the presence of a representative of the manufacturer. Manufacturer's representative shall be experienced in the installation, adjustment, and operation of the system provided.

-- End of Section --