



US Army Corps of Engineers
Afghanistan Engineer District – South

ANA Camp Hero Oxygen-Vacuum System Addition, Kandahar

Design/Build Project Specifications And Drawings

**Proposal Requirements, Contract Forms,
Conditions of the Contract - Under the
O&M Small Projects Format (O&MSPF)**

April 2011

THIS IS A SINGLE-PHASE REQUEST FOR PROPOSAL

SOLICITATION, OFFER, AND AWARD <i>(Construction, Alteration, or Repair)</i>	1. SOLICITATION NO. W5J9LE-11-R-0049	2. TYPE OF SOLICITATION <input type="checkbox"/> SEALED BID (IFB) <input checked="" type="checkbox"/> NEGOTIATED (RFP)	3. DATE ISSUED 10-May-2011	PAGE OF PAGES 1 OF 54
	IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.			

4. CONTRACT NO.	5. REQUISITION/PURCHASE REQUEST NO.	6. PROJECT NO. O&M 11-049
-----------------	-------------------------------------	------------------------------

7. ISSUED BY AFGHANISTAN DISTRICT SOUTH (AES) US ARMY CORPS OF ENGINEERS APO AE 09355	CODE W5J9LE	8. ADDRESS OFFER TO <i>(If Other Than Item 7)</i> CODE
TEL: FAX:		See Item 7 TEL: FAX:

9. FOR INFORMATION CALL:	A. NAME NATHAN S TAYLOR	B. TELEPHONE NO. <i>(Include area code) (NO COLLECT CALLS)</i>
--------------------------	----------------------------	--

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS *(Title, identifying no., date):*
ANA - Camp Hero O&M Hospital Work
This procurement is for the ANA Camp Hero Hospital Oxygen-Vacuum System Addition, Camp Hero, Kandahar Province, Afghanistan.
This requirement is being completed full and open, with no set-asides.
The Magnitude of Construction is between \$100,000.00 and \$250,000.00
Performance Period: 90 days
Solicitation POC:
Mr. Nathan S. Taylor
USACE-AES
US: 540-665-6445
nathan.s.taylor@usace.army.mil
Courtesy Copy (CC)
Tas.contracting@usace.army.mil

11. The Contractor shall begin performance within 10 calendar days and complete it within 90 calendar days after receiving award, notice to proceed. This performance period is mandatory, negotiable. *(See 52.211-10 _____.)*

12 A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? <i>(If "YES," indicate within how many calendar days after award in Item 12B.)</i> <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO	12B. CALENDAR DAYS
--	--------------------

13. ADDITIONAL SOLICITATION REQUIREMENTS:

A. Sealed offers in original and 1 copies to perform the work required are due at the place specified in Item 8 by 02:00 PM (hour) local time 09 Jun 2011 (date). If this is a sealed bid solicitation, offers must be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

B. An offer guarantee is, is not required.

C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

D. Offers providing less than 120 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

Section 00010 - Solicitation Contract Form

SECTION 00010

PROPOSAL SCHEDULE

Provide a price for all items. The Government will evaluate the Contractor's entire proposal to determine which CLINs represent the best value to the Government.

The Government will award in accordance with the lowest price technically acceptable source selection process.

<u>No.</u>	<u>Description</u>	<u>Qty</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Total Amount</u>
0001	CAMP HERO HOSPITAL OXYGEN SYSTEM EXPANSION				
0001AA	Site Planning & Design Costs	1	LS	XXX	\$_____
0001AB	Mobilization & Demobilization	1	LS	XXX	\$_____
0001AC	Site Security	1	LS	XXX	\$_____
0001AD	System Analysis	1	LS	XXX	\$_____
0001AE	Construction Documents	1	LS	XXX	\$_____
0001AF	Install 32 Suction Outlets	32	EA	\$_____	\$_____
0001AG	Install 32 Oxygen Outlets	32	EA	\$_____	\$_____
0002	Defense Base Act Insurance The amount listed by the offeror on this CLIN is the estimated DBA insurance premium (estimated payroll of the offeror and its subcontractors times the applicable rate(s)). The DBA insurance premium amount varies with payroll and the nature of services and will, therefore, be taken into account during price evaluation of offers. The actual amount paid by the government under this CLIN will be based on the amount of the Rutherford invoice, stamp "paid" and submitted by the offeror after contract award. In the event of recalculation of the premium by CNA based on actual payroll amounts, the contracting officer will adjust this CLIN by contract modification to reflect the actual premium amounts paid.	1	LS	XXX	\$_____
TOTAL PROPOSAL:					\$_____

PROPOSAL SCHEDULE NOTES

1. Offeror shall submit prices on all items. Scope of work on each items are described in Section 01010. The quantities shown in the bid schedule shall take precedence and be used for developing the proposal.
2. Only one contract for the entire schedule will be awarded under this solicitation. This project will be awarded as a lump sum contract. This Proposal Schedule is an accounting tool for allocating funds to applicable budget.
3. Costs associated with this project shall include design and construction costs, site development, and utility installation.
4. DESIGN COSTS DEFINITION: Design costs shall consist of design analysis, drawings, and specifications for all facilities.
5. COST LIMITATION: Not applicable for this solicitation.
6. The government has the right to reduce the number of units in a bid item or choose to delete a base bid item entirely if necessary after the proposals are received.
7. EVALUATION OF OPTIONS: Not applicable for this solicitation.
8. EXERCISE OF OPTIONAL BID ITEMS: Not applicable for this solicitation.
9. ORDER of WORK: Not applicable for this solicitation.
10. PERIOD OF PERFORMANCE AND LIQUIDATED DAMAGES: See Section 00150 for performance schedule and liquidated damages. Period of performance is defined as the number of calendar days from receipt of notice to proceed. Liquidated damages are assessed at the stated rate per day for every day of delay past the period of performance until contract completion for either the Base Items or the Optional Items whichever is applicable.
11. Abbreviations:
 - LM = Linear meters
 - LS = Lump Sum
 - EA = Each
 - SM = Square meters
 - CM = Cubic meters
 - CMH = Cubic meters per hour
 - KL = Kilo Liters

-END OF SECTION-

SECTION 01010
SCOPE OF WORK
AND
TECHNICAL REQUIREMENTS

GENERAL

SUMMARY OF WORK

The project consists of:

1. **Construction and Construction Documents:** The design and construction of thirty-two (32) new oxygen outlets and thirty-two (32) new vacuum outlets to include the following:
 - a. Design Analysis for this portion of work.
 - b. Construction drawings for the expansion of existing medical gas systems for Patient Wards 129-132 ((32) Oxygen Outlets and (32) Vacuum Outlets) along with any required system modifications needed for Patient Ward portion of work. The design and installation will include required valves, alarms, sensors and other devices needed have a complete, functional and code compliant system within wards 129 -132 and Operating Room 121 as listed below.
 - c. Construction installation and drawings shall include standardizing to a single outlet type and replacing existing outlets as needed. The outlet type decision will be made in coordination with the Hospital management. Submit product information for review by the U. S. Army Corps of Engineers.
 - d. Relocate existing vacuum outlet to the anesthesia work area Operating Room 121 at the direction of the hospital. The distance of the relocation is approximately 5 meters.
 - e. The design shall be provided to the Contracting Officer for review and approval by the USACE Engineering Department.
 - f. See the Technical Requirements for a more information on requirements.
2. **System Analysis:** The analysis of the existing Oxygen-Vacuum systems to include the following:
 - a. Oxygen System: Create a complete system diagram, including the existing systems and the new outlets in Patient Wards 129-132 (as described below) to be installed in the Hospital. The system will include all areas served by the central Oxygen system, including the new oxygen line that serves the Hospital Addition. The plans for that project are included in the Proposal Request so that an outlet count for that area can be included in the analysis. Field shall verify all information on existing systems. Manifold sizing shall be verified. System diagrams will indicate all required sensors, area alarm panels, main medical gas alarm panel, shutoff valves, new and existing matching outlets, and all other system components needed for a complete and reliable system. The analysis shall note all deficiencies of the existing system.
 - b. The condition of installed piping shall be reviewed with consideration to pipe sizing and condition of piping. Perform gas certification testing on existing systems to determine the cleanliness of the installed systems and submit results for review.
 - c. Oxygen System: Make recommendations regarding oxygen bottle management and the medical gas storage rooms which will make the area organized, safe, and code compliant with IBC, IPC, IMC, and NFPA.

- d. Vacuum System: Create a complete system diagram, including the existing systems and the new systems to be installed in the existing Hospital, and an outlet count for the Hospital Addition currently being constructed. Assume the outlet count for the Hospital Addition will match the Oxygen outlet count. Assume the Hospital Addition system will connect into the vacuum system at the vacuum pump. System diagrams will indicate all required sensors, area alarm panels, main medical gas alarm panel, shutoff valves, new and existing matching vacuum outlets, and all other system components needed for a complete vacuum system. Confirm whether the existing vacuum pump will be sufficient for service to all areas, including the Hospital Addition. The analysis shall note all deficiencies of the existing system.
- e. See the Technical Requirements for a more information on requirements.
- f. The System Analysis shall be provided to the Contracting Officer for review and approval by the USACE Engineering Branch.
- g. A list of definable actions that need to be taken and their associated costs will be provided as part of the analysis.

CONTRACTOR REQUIREMENTS

The Contractor shall design and construct as a Design-Build contract in accordance with the requirements stated and described herein.

GENERAL REQUIREMENTS FOR FACILITIES

All standard construction amenities such as underground utilities, plumbing, heating, electrical, etc. shall be implied as a design and construction requirement.

BASE BID

1. Site Planning & Design Cost
2. Mobilization & Demobilization
3. Site Security
4. Construction and design related to the expansion of existing medical gas systems for Patient Wards 129-132 ((32) Oxygen Outlets and (32) Vacuum Outlets). Assume connection point for the expansion is at the manifold for oxygen and at the vacuum pump for vacuum. See "**Construction and Construction Documents**" above.
5. Full System Analysis for a complete system for the Hospital and the Hospital Addition as described above in "**System Analysis.**"
6. DBA Insurance.

COMPLETION OF WORK

1. All work required under this contract shall be completed within the calendar days, as described in Section 00150, from Notice to Proceed (NTP) for site work.
2. Item 1. Construction Documents for required changes to the Hospital systems
 - Work Item 1 to be completed no later than 45 calendar days after NTP.
3. Item 2. Completion of System Analysis and System Diagram.
 - Work Item 2 to be completed no later than 50 calendar days after NTP.

4. All work under this contract shall be completed and buildings ready for beneficial occupancy and/or use in ninety (90) days.

ENGLISH LANGUAGE REQUIREMENT

All information shall be presented in English. The Contractor shall have a minimum of one (1) English-speaking representative to communicate with the COR at all times when work is in progress.

SECURITY

Security is critical to construction in Afghanistan, especially on roads and remote areas away from Coalition Force bases. The Risk/Threat Level for the area surrounding this project site is **Low** Risk associated with the security environment in which this work is to be performed and is relative to the chance of attack, improvised explosive devices (IEDs), kidnapping, theft, and vandalism. The Contractor must have an appropriate amount of security/protection to match the threat in the project area and along the supply routes. A detailed security plan in accordance with Section 01040 shall be approved by the Government before Clearance for Construction.

AED DESIGN REQUIREMENTS DOCUMENTS

AED Design Requirements documents shall be adhered to in this contract. This Section shall be used as the basis for design and construction. The Contractor's design and construction must comply with technical requirements contained herein. The Contractor shall provide design and construction using the best blend of cost, construction efficiency, system durability, ease of maintenance and environmental compatibility.

MINIMUM & ALTERNATE REQUIREMENTS

The design and product requirements stated in these documents are minimum requirements. The technical requirements listed in paragraph: Codes and Technical Criteria apply to this project. Any deviation from the technical requirements shall be approved by the Contracting Officer. Request for deviations shall be submitted for approval. The Contractor is encouraged to propose alternate design or products (equipment and material) that are more commonly used in the region; however, but these variations shall be equal in performance from a technical standpoint as well as more cost effective or allow for more timely completion. Variations shall furnish the same system safety, durability, ease of maintenance and environmental compatibility. The Contractor will be required to submit information as specified in Section 01335, 4.7.4. Variations, for all proposed variations with which to make a comprehensive comparison of the proposed alternate. All variations of approved designs must be approved by the Contracting Officer.

SUBCONTRACTORS

Compliance with the provisions of this section by subcontractors will be the responsibility of the Contractor.

CODES AND TECHNICAL CRITERIA

The work within this contact shall be designed and constructed in accordance with the most current criteria listed below:

1. International Code Commission (ICC) - International Building Codes (IBC), International Mechanical Code (IMC), International Plumbing Code (IPC).

2. NFPA 70, National Electric Code.
3. NFPA 99C, Standard on Gas and Vacuum Systems.
4. NFPA 101, Life Safety Codes.
5. UFC 4-510-01, Unified Facilities Criteria, Design: Medical Military Facilities.
6. UFC 4-010-01, DOD Minimum Anti-Terrorism Standards for Buildings.
7. Unified Facilities Criteria (UFC) - (Note: Unified Facility Criteria (UFC) is available online at: <http://www.wbdg.org/>)
8. U.S. Army Corps of Engineers (USACE) - Safety: Safety and Health Requirements (EM 385-1-1).

ADDITIONAL GUIDANCE CRITERIA:

1. International Code Commission (ICC) - International Fire Codes (IFC),
2. International Electrotechnical Commission (IEC) - Standards for Safety.
3. National Fire Protection Association (NFPA) -
4. Unified Facilities Criteria (UFC) - (Note: Unified Facility Criteria (UFC) is available online at: <http://www.wbdg.org/>)
5. Standards other than those mentioned above may be accepted if the standards chosen are internationally recognized and meet the minimum requirements of the specified standards. The Contractor shall be prepared to submit proof of this for approval if requested by the Contracting Officer.

SPECIFICATIONS

1. Unified Facilities Guide Specifications (UFGS)
(Note: Unified Facilities Guide Specifications (UFGS) is available online at: <http://www.wbdg.org/>)
2. U.S. Army Corps of Engineers (USACE) - Austere Standard Design Specifications, etc.

Specification sources, other than those mentioned above, may be accepted if they are internationally recognized and meet the minimum requirements of the specified subject. The Contractor shall be prepared to submit proof of this if requested by the Contracting Officer.

SITE DEVELOPMENT

In addition to the following requirements, the Contractor shall also incorporate the project-specific requirements as stated in the paragraph, Technical Requirements.

PROJECT SITE SURVEYS AND REPORTS

Contractor, as part of the design analysis, shall conduct a field survey of existing conditions to determine the configuration of the existing systems and conditions related to the installation of new outlets in the Main Hospital and the Hospital Addition.

UNEXPLODED ORDNANCE (UXO)-MINE REMOVAL AND CLEARANCE

Contractor IS **NOT** responsible for initial clearance/removal.

The Contractor **IS NOT** responsible for the clearance or removal of mines and unexploded ordnance (UXO) from the site prior to the commencement of construction. The site has been cleared to a minimum depth of 1.0 m (40") and the certificate of clearance is available for review. No construction activities are to be conducted without review of the written clearance certification for the site. If sub-surface construction activities will be performed on this site the clearance certification must state that the clearance depth was conducted to a minimum 1.0 m (40") in depth.

NOTE 1: For previous UXO/mine information, and a copy of the clearance certification the following points of contact from the UN Mine Action Center of Afghanistan are provided:

Mohammad Sediq, Chief of Operations,
Email: sediq@unmaca.org
Cell: +93 070 295207

Hansie Heymans, Chief Information Officer,
Email: hansie@unmaca.org
Cell: +93 070 294286

UXO Safety/ Demining COR, USACE
tan.uxo.demining.safety@usace.army.mil
Comm: 540-667-2127

NOTE 2: For construction in excess of 1.0 m (40") in depth on areas previously cleared. If the contract parameters for sub-surface construction exceed the minimum 1.0 m (40") clearance depth the Contractor WILL be responsible for clearance to these depths.

The Contractor may only provide clearance/removal services via UN Mine Action Center for Afghanistan (UNMACA) accredited entities and Clearance/removal may only be undertaken in accordance with International Mine Action Standards (IMAS), Afghanistan Mine Action Standards (AMAS), and applicable U.S. Army Corps of Engineer (USACE) Ordnance & Explosives (OE) safety standards.

The Contractor will provide a standard UXO/Demining safety work plan to the US Army Corps of Engineers UXO / Demining COR for review prior to commencement of all UXO clearance/demining activities on the project sites. Once the UXO/ Demining clearance has concluded, the Contractor shall provide the US Army Corps of Engineers UXO / Demining COR a clearance certificate for review and approval before any construction activities are to commence.

NOTE 3: The Contractor should be aware that many areas demined by NGOs and other groups may have only been cleared to a depth of 130 mm (5") for humanitarian purposes. If construction will take place, a minimum of 1.0 m (40") in depth is mandatory.

It is the responsibility of the Contractor to be aware of the risk of encountering UXO/mines and to take all actions necessary to assure a safe work area to perform the requirements of this contract. The Contractor assumes the risk of any and all personal injury, property damage or other liability arising out of or resulting from any Contractor action taken hereunder. The Contractor and its subcontractors may not handle, work with, move, transport, render safe, or disarm any UXO/mine, unless they have appropriate accreditations from the MAC.

If a UXO/mine is encountered during project construction, the Contractor shall immediately stop work in the affected area, mark the area of the UXO/Mine and immediately notify the Contracting Officer, COR or the Government Construction Representative. UXO/Mine disposal will not be the responsibility of the Contractor unless the area exceeds the 1.0 m (40") clearance depth of the original clearance certificate.

LIMITATION OF WORKING SPACE

The Contractor shall, except where required for service connections or other special reasons, confine the operations strictly within the boundaries of the site. Workmen will not be permitted to trespass on adjoining property. Any operations or use of space outside the boundaries of the site shall be by arrangement with all interested parties. It must be emphasized that the Contractor must take all practical steps to prevent his workmen from entering adjoining property and in the event of trespass occurring the Contractor will be held entirely responsible.

Areas located immediately outside the construction area are known to contain mines and unexploded ordnance (UXO). Contractors assume all risks when venturing in or out of the designated work area.

ENVIRONMENTAL PROTECTION

APPLICABLE REGULATIONS

The Contractor shall comply with all Host Nation laws, rules, regulations or standards concerning environmental pollution control and abatement with regard to discharge of liquid waste into natural streams or manmade channels. The Contractor shall review host nation and U.S. Government environmental regulations with the contracting officer prior to design and discharge of any liquid wastes into natural streams or manmade channels.

SPILLAGES

Measures shall be taken to prevent chemicals, fuels, oils, greases, bituminous materials, waste washings, herbicides and insecticides, and construction materials from polluting the construction site and surrounding area.

DISPOSAL

Disposal of any materials, wastes, effluents, trash, garbage, oil, grease, chemicals, etc., shall be subject to the approval of the Contracting Officer. Burning at the project site for the disposal of refuse and debris will not be permitted.

DEMOLITION

Demolition shall include removal of all structures, foundations, pavements, and utilities, and clear and grubbing prior to commencement of new work. All refuse and debris shall be disposed of off-site. The Contractor shall verify the location of debris disposal with the Contracting Officer in accordance with the paragraph: Environmental Protection.

PORTABLE SANITARY FACILITIES

Portable latrines: Contractor shall furnish and install portable latrine units with hand-sanitizer dispenser at site location. Portable latrines shall be western or eastern style units as determined by Contracting Officer.

TECHNICAL REQUIREMENTS

In addition to the following requirements, all designs and installations shall meet the requirements in paragraph: Codes and Technical Criteria and be complete with design analysis (DA), plans, and specifications.

MECHANICAL

OXYGEN SUPPLY SYSTEM:

Contractor is to design and construct an oxygen supply system to meet specifications of proper grounding, venting, piping, and other protocols regarding safety and explosion prevention. It is further specified that the Contractor handling the oxygen supply system have not less than five (5) years of experience in the installation and design of supply and distribution of medical gas systems.

The oxygen system shall be connected to the oxygen system in the existing hospital facility. Contractor will modify the existing oxygen system so it is in compliance with internationally acceptable constructions standards. Surface mounted patient service outlets at each bed will also be coordinated with customer

(CSTC-A, MED OPER PLAN) prior to installation. Outlet type shall be coordinated with the Hospital Management and reviewed by the USACE engineer. All oxygen supply runs will have protective cover strips where located outdoors or in exposed areas. Oxygen Supply system will run to all Ward Rooms with connection above each bed and terminate at an outlet mounted to the wall, This specification will apply to optional areas of work where such options have been authorized. Contractor shall test the newly installed Oxygen System for contamination and decontaminate the complete Oxygen Supply System upon completion of the installation if required.

THE FOLLOWING SPECIFIC CRITERIA SHALL BE ADDRESSED AS PART OF THE SCOPE OF WORK FOR OXYGEN SYSTEMS:

1. **Construction:** Contractor is to provide design and installation for the extension of thirty-two (32) oxygen outlets to Patient Wards 129 - 132 in the Main Hospital. See attached drawings showing the general installation area. Coordinate mounting requirements into bed heads with existing conditions.
2. **Construction:** Label medical gas devices and piping so that personnel can understand what the alarms are for and how to use the system, and so maintenance personnel can identify pipes and equipment. Provide labeling in English, Pashto, and Dari.
3. **Construction:** After a site survey along with the agreement of Hospital management, decide which type of oxygen outlet will become the new Hospital standard to be used for the new outlets.
4. **Construction:** Provide a two (2) hour training session to clinical personnel on understanding the alarms, proper care of the system, proper use of vacuum devices, etc. Provide written material that includes the presented information.
5. **System Analysis:** Produce drawings showing the correct layout for oxygen storage including labeling of areas, restraint of bottles, access and outdoor storage area requirements.
6. **System Analysis:** Indicate makeup air opening requirements to the outdoors for the gas storage room exhaust fan.
7. **System Analysis:** Verify and correct the oxygen manifold to supply the needed amount of oxygen for all areas currently in use as well as all future uses listed. Indicate the use of correct connection hoses and tank restraints as needed.
8. **System Analysis:** Make recommendations regarding the functionality and labeling of medical gas devices so that personnel can understand what the alarms are for and how to use the system. Provide labeling in English, Pashto, and Dari.
9. **System Analysis:** Include the pipe routing and sizing and calculated consumption of gases from the Hospital Addition project into the overall system analysis and show these systems on the system diagram.

TESTING AND COMMISSIONING

OXYGEN SYSTEM DECONTAMINATION PROCEDURE

Contractor shall use 414 to 448 kPag (60 to 65 psig) oil free dry nitrogen to purge and clean the oxygen system continuously for a minimum of 24 hours. Purge nitrogen shall impinge upon a white cloth, at a minimum flow rate of 100 lpm (3.5 cfm), until no evidence of discoloration is present and test gas (used during the previous gas test) has been completely removed from the piping systems. Source gas shall be bled for a minimum of one (1) minute continuously through each copper piping installed. After completion of purging and cleaning, completely remove temporary piping, adaptors, and connectors.

SYSTEM CONTAMINANT LEVEL TESTS BY TESTING AGENCY

Upon completion of required testing the testing agent shall issue a medical gas certification document indicating the tests performed, the methodology, and date of the test. Certification shall be for the entire system.

TEST GAS PURITY, CONTAMINATE LEVELS, AND TEST METHODS

The contamination limits and concentration minimums required to test gases used for purging and the testing of nitrogen systems are listed below:

1. Test Gas: 99 percent by volume minimum; gas chromatography or equivalent.
2. Solid Particulate: 2 mg/cu.m maximum; 0.8 micron pore size filter.
3. Hydrocarbon Compounds: One part per million, concentration volume per volume, maximum expressed as methane equivalents; gas chromatography or equivalent.
4. Halogenated Hydrocarbon Compounds: 2 parts per million, concentration volume per volume, maximum; mass spectrometry, infrared spectrometry, or gas chromatography.
5. Carbon Monoxide: 2 parts per million, concentration volume per volume, maximum gas chromatography, electrochemical carbon monoxide analyzer, or equivalent.
6. Water (Moisture): Minus 50 degrees C (-60 degrees F) dew point; Pittsburg cup, dew point hygrometer, or electronic hydrometer.

PERCENT TESTING PERCENT TESTING:

Test 10 percent of the medical gas outlets in areas which are supplied only with oxygen. Test such outlets to ensure the gas traversed the greatest length of pipeline.

CONTAMINATED SYSTEMS:

Clean and retest contaminated sections with one or more contaminated outlets. In rooms or areas where the oxygen is supplied, retest 20 percent of the outlets including the original 10 percent first tested. Each time contamination is found, repeat cleaning operation and increase number of outlets tested by 10 percent until zero percent contamination is obtained. Take care to vent purged oxygen to outside of building and away from flames.

VACUUM SYSTEMS

Contractor is to provide design and installation for the extension of thirty-two (32) vacuum outlets to Patient Wards 129-132 in the Main Hospital. Design and installation for the area of work will include all items needed for a complete, code compliant, and functional system including, but not limited to, shutoff valves, alarms, and sensors.

The System Analysis is for understanding the existing installation, establishing future requirements, and making recommendations to assure that the installation meets code requirements. The analysis, and that pump controls are configured so that one pump will perform 100% of the capacity requirements and that pumps alternate. Loss of pump shall generate an alarm.

It is further specified that the contractor handling the medical vacuum systems have not less than five (5) years of experience in the installation and design of supply and distribution for medical gas systems. Contractor shall test the Vacuum System according to accepted testing criteria listed in the code references above. Provide test results and certification of system before completion.

The following specific criteria shall be addressed as part of the Scope of Work for the vacuum system:

1. **Construction:** The Main Hospital will require 32 new vacuum outlets. Verify owner is using acceptable suction devices at the vacuum outlets and not allowing fluids to be drawn into the vacuum system. Verify the exact locations to install vacuum outlets with the COR. See attached drawings showing the general installation area. Coordinate mounting requirements into bed heads with existing conditions, and confirm locations with owner.
2. **Construction:** Check the functionality and labeling of medical gas devices so that personnel can understand what the alarms are for and how to use the system. Provide labeling in English, Pashto, and Dari.
3. **Construction:** Label medical gas devices and piping so that personnel can understand what the alarms are for and how to use the system, and so maintenance personnel can identify pipes and equipment. Provide labeling in English, Pashto, and Dari.
4. **Construction:** After a site survey along with the agreement of Hospital management, decide which type of vacuum outlet will become the new Hospital standard to be used for the new outlets.
5. **Construction:** Provide a two (2) hour training session to clinical personnel on understand the alarms, proper care of the system, proper use of vacuum devices, etc. Provide written material that includes the presented information.
6. **System Analysis:** Produce drawings showing the layout of the vacuum system piping and components.
7. **System Analysis:** Make recommendations regarding the functionality and labeling of medical gas devices so that personnel can understand what the alarms are for and how to use the system. Provide labeling in English, Pashto, and Dari.
8. **System Analysis:** Include the pipe routing, sizing and consumption of vacuum devices from the Hospital Addition project into the overall system analysis and show these systems on the system diagram.

- END OF SECTION -

SECTION 00113
PROCEDURES FOR SUBMITTAL OF OFFERS
AND
PROPOSAL EVALUATION CRITERIA

GENERAL

BASIS AND INTENT

The intent of this Request for Proposal (**Solicitation**) is to select one (1) Contractor for the design-build (DB) Afghan National Security Forces (ANSF) ANA Camp Hero Oxygen-Vacuum System Addition

The basis of award is Lowest Price Technically Acceptable (LPTA).

The Contracting Officer will award a fixed price contract to the successful Offeror whom the Source Selection Authority determines conforms to the **Solicitation** and is technically acceptable, is fair and reasonable, and offers the lowest price to the Government. The contract will NOT be awarded solely on the basis of lowest price.

DEFINITIONS

When the word 'Offeror' is encountered throughout Section 00113, it is intended to mean a company seeking to do business with the Government that submits a proposal in response to this solicitation.

A proposal is documentation prepared by the Offeror and submitted to the Government for evaluation purposes in response to this solicitation.

When the word 'Government' is encountered throughout this Section, it is intended to mean US Army Corps of Engineers Afghanistan Engineer District - South (AES).

SUBMITTALS

As this is a competitive negotiation acquisition, there is no public bid opening and no information given out as to the number of Offerors or the results of the competition until all awards are made.

GENERAL SUBMISSION REQUIREMENTS

Offerors submitting proposals for this project should limit submissions to data essential for evaluation of proposals so that a minimum of time and monies will have been expended in preparing information required herein. However, in order to be effectively and equitably evaluated, the proposals must include information sufficiently detailed to clearly describe the Offeror's capabilities to successfully complete the project. Proposals should follow in the order of sequence set forth in the **Solicitation**. Information provided out of sequence may not be evaluated and may result in the Offeror's disqualification from award. **Attached forms shall be used.** Requirements stated in this **Solicitation** are minimums.

Proposals may be withdrawn in writing via an email notice at any time before award.

SUBMISSION ADDRESS

Proposals for this solicitation will be accepted until the date and time indicated on Standard Form 1442. Offerors shall submit their proposals electronically, in PDF format, to the following email addresses:

Nathan.S.Taylor@usace.army.mil with a courtesy copy to tas.contracting@usace.army.mil.

Correspondence shall be to:

U.S. Army Corps of Engineers (USACE)
Afghanistan Engineer District – South (AES)
ATTN: Nathan S. Taylor

All questions and inquiries shall be submitted by email to:

Nathan.S.Taylor@usace.army.mil with a courtesy copy to tas.contracting@usace.army.mil.

Electronic (as email) inquiries to this solicitation must be received by this office not later than ten (10) calendar days prior to the due date of proposals. Questions received less than ten days prior to the due date of proposals will not be entertained.

Faxed Proposals, Modifications Thereto, Or Cancellations Will Not Be Accepted. However, offers may be withdrawn in writing by letter or e-mail. Any written notice to withdraw an offer sent to this office must be received in the office designated for receipt of offers not later than the exact date and time set for receipt of proposals.

Telephone Inquiries Will Not Be Accepted. Oral explanations or instructions are not binding. Any information given to an Offeror which impacts the solicitation and/or offer will be given in the form of a written amendment to the solicitation.

SITE VISIT

No site visit is currently is planned for this solicitation.

PROPOSAL EVALUATION PROCESS

A Source Selection Evaluation Board (SSEB) comprised of representatives of the US Army Corps of Engineers (USACE), User/Customer, and other required personnel, will evaluate the proposals. Offerors are advised that the technical evaluation and rating of proposals will be conducted in strict confidence so that the Technical and Performance Capability parts of the proposals are reviewed and rated without knowledge of the price offered. The number and identities of the Offerors are not revealed to anyone who is not involved in the evaluation and award process or to other Offerors. Proposals will be evaluated based on the factors described herein, and the basis of award is Lowest Price Technically Acceptable (LPTA).

The evaluation process essentially consists of three (3) parts:

1. Proposal Compliance Review - Responsibility Determination
2. Technical and Performance Capability Evaluation
3. Price and Pro Forma Information Evaluation

PROPOSAL COMPLIANCE REVIEW - RESPONSIBILITY DETERMINATION

This is an initial review to ensure that all required forms and certifications are complete and that both a technical and price proposal were received. **Incomplete Submissions Will Not Be Evaluated Further.**

VOLUME I - TECHNICAL & PERFORMANCE CAPABILITY EVALUATION

The SSEB will evaluate and rate those proposals passing the first review, above. Proposals will be evaluated against the **Solicitation** requirements. Factors will be rated either 'Go' or 'No-Go'. If a proposal is determined a 'No Go,' further evaluation by the SSEB is not warranted.

PRICE & PRO FORMA INFORMATION EVALUATION

The SSEB can evaluate Price and Pro Forma Information independent of the Technical and Performance Capability evaluation. The SSEB will not have access to price information until completion of the Technical and Performance Capability evaluation.

PROPOSAL SUBMISSION REQUIREMENTS & INSTRUCTIONS

Offerors are required to submit a proposal made up of a Technical and Performance Capability proposal (Volume I) and a Price and Pro Forma Information proposal (Volume II). All proposal materials shall be submitted in **Two (2) PDF Files** ("Volume I" and "Volume II") with a table of contents and continuous page numbering for each Volume. **The Proposal Shall Not Mix the Contents of Volume I and II; Each Volume Shall Be a Separate Electronic File.** The sections should parallel the submission requirements identified below. Failure to place the required submission information under the appropriate tab may result in a lower rating if the evaluators cannot readily find the appropriate information.

There is a limit of 50 pages total for the entire package using a minimum font size of 11 and a minimum margin size of 13 mm (1/2") on all sides. **Information Submitted Which Exceeds The Specified Limit Will Not Be Evaluated.** Page size to be based on A4 (210 mm x 300 mm) or 8-1/2" x 11" Letter Size, and must be readily formatted for printing on a standard printer. **Format Restrictions Will Be Strictly Adhered To And Enforced.**

PROPOSAL INFORMATION & RELATED EVALUATION FACTORS

Proposals will be evaluated (in English) in accordance with the evaluation factors. Offerors are reminded to include their best technical and price terms in their initial offer and not to automatically assume that they will have an opportunity to participate in discussions or be asked to submit a revised offer. The Government may make award of a conforming proposal without discussions if deemed to be within the best interests of the Government.

Volume I - Technical and Performance Capability:

- Factor 1 Experience
- Factor 2 Personnel
- Factor 3 Past Performance

Volume II - Price and Pro Forma Information:

- Tab A Standard Form 1442
- Tab B Section 00010, Proposal Bid Schedule
- Tab C Section 00600, representations and Certifications
- Tab D Joint Venture Agreement (if applicable)

Additional Information Provided Beyond The Required Documentation May Not Be Evaluated.

TECHNICAL & PERFORMANCE CAPABILITY

FACTOR 1 - EXPERIENCE SUBMISSION REQUIREMENTS

Each Offeror shall complete a minimum of one (1) but no more than three (3) 'Project Experience' form(s) attached at the end of this Section. All blocks must be filled-in and all data must be accurate, current, and complete. At least one (1) of the projects listed must be as Prime Contractor. Submission requirements (in English) for experience are:

- A. If claiming Prime Contractor Experience, a Prime Contractor must have self-performed, on site, at least 15% of the direct contract labor exclusive of other general condition or field overhead personnel, material, equipment, design, or subcontractors.
- B. Each project provided to demonstrate experience must have awarded contract value of over \$100,000(USD).
- C. At least one (1) of the projects to demonstrate experience must have been or is being constructed in Afghanistan.
- D. Each project used to demonstrate experience must have been completed within the last five (5) years as of the date of the proposal submission.
- E. Each project description must demonstrate experience with the following construction facilities, features, or activities:
 Medical Gas System Installation
- F. Individual task order (TO) of a Multiple Award Task Order Contract (MATOC) may be submitted as a single project to demonstrate experience. Combining contract values of individual task orders of a MATOC is not allowed.

EVALUATION CRITERIA

The SSEB will evaluate experience submitted. Offerors must meet all the above experience requirements to receive a 'Go' rating.

Proposals that do not include substantial evidence that the Offeror has experience, qualifications, and production capability to successfully construct the proposed project will be considered to not meet the minimum requirements of the **Solicitation** and will be rated a 'No-Go.' Substantial evidence is defined as documenting experience in the above experience requirements.

FACTOR 2 - PERSONNEL SUBMISSION REQUIREMENTS

Provide resumes for the following key personnel:

1. Overall Project Manager
2. Construction Superintendent
3. Quality Control Manager
4. Senior Design Engineer

Project Manager, Construction Superintendent, and Quality Control Manager shall have:

1. Documentation identifying each person as a current full-time employee of the Prime Contractor or a letter of intent signifying their employment for this project.
2. Minimum 4-year college degree graduate.
3. Minimum of five (5) years of relevant experience in their assigned job position.

The Senior Design Engineer shall have:

1. Documentation identifying this person as a current full-time employee of either the Prime Contractor or sub-contractor or a letter of intent signifying their employment for this project.

- A Design Engineer may be a sub-consultant to the Contractor, but will still need to provide a Personnel Resume along with a letter of intent by the Design Engineer's firm stating the named individual will be retained for the project, if the Contractor is awarded the contract. A sub-consultant Design Engineer shall meet all requirements for Design Engineer.

2. 4-year College graduate with Bachelor of Science or engineering degree.
3. Minimum five (5) years experience with Medical Gas Systems.
4. Licensed or accredited professional engineer.

Resumes must include the information on '**Personnel Resume-Experience**' form attached at the end of this section. All information must be filled in and all data should be accurate, current, and complete.

NOTE: Identified personnel must be used on the project. Any substitution of identified persons will not be permitted without prior approval of the Contracting Officer. Identification of two (2) individuals proposed for a single position will result in the evaluation of **only the least qualified person**. A single individual cannot be identified a 'key personnel' for more than one (1) 'key personnel' position.

EVALUATION CRITERIA

The SSEB will evaluate the resumes of the key personnel for compliance with requirements. The key personnel must meet all of the following to receive a 'Go' rating:

1. A completed 'Personnel Resume-Experience' form for each key personnel.
2. The Project Manager, Project Superintendent, and Quality Control Manager must have a college degree and a minimum of 5 years professional experience in their field.
3. The Senior Design Engineer must have a college degree in the field of work governed by the position they are assigned, be a Licensed or accredited Professional Engineer, and demonstrate a minimum of 5 years of expertise in designing Medical Gas Systems.
4. Documentation identifying each person as a current full-time employee of the Prime Contractor or a letter of intent signifying their employment for this project.

Failure to meet standards under this factor will result in a 'No Go' rating.

FACTOR 3 - PAST PERFORMANCE SUBMISSION REQUIREMENTS

Each offeror must ensure a "Past Performance Questionnaire" (attached at the end of this section), to be completed by the offeror, is provided for each of the projects used to demonstrate experience referenced in Section 5.1.1; minimum of one (1) and no more than three (3). The offeror shall provide the correlated past performance questionnaire with two CURRENT Points of Contact (POCs) who meet the following criteria:

- a. Familiar with the project, but not affiliated with the offeror;
- b. Can provide an independent evaluation of the offeror's performance on the referenced project,
and;
- c. Can be contracted by the Government to verify the submitted Past Performance Questionnaire details.

The questionnaire must be directly related to the project(s) listed under Factor 1 (Experience).

The Offeror may provide in the package additional ratings, letters of recommendation, commendations, and awards on projects which demonstrate past construction performance. Additional materials in the proposal are included in the total submittal page count.

EVALUATION CRITERIA

The SSEB will evaluate successful past performance identified in this **Solicitation** in response to information provided. Documentation of satisfactory past performance for each project used to meet criteria must be submitted to meet requirement of this criterion and will be rated a 'Go.' Offerors that do not demonstrate satisfactory past performance for each project used to meet criteria will be considered not to have met requirement of this criterion and will be rated a 'No-Go.' The Government reserves the right to check any or all cited references to verify supplied information and to assess owner satisfaction. The Government may also use the Federal Awardee Performance Integrity and Information system (FAPPIS), Past performance Information Retrieval System (PPIRS), Dun & Bradstreet, or any other relevant information of projects to assist in its evaluation of an Offeror's past performance.

If a Project Reference 'Point of Contact' is not provided in the 'Project Experience' form, then the minimum requirement of this criterion will not have met and the offeror will receive a "No-Go" for this factor.

VOLUME II - PRICE & PRO FORMA INFORMATION

TAB A, STANDARD FORM 1442 SUBMISSION REQUIREMENTS

Submit original only in a separate sealed envelope. The Offeror shall submit Standard Form 1442. Form is included in Section 00010 of this **Solicitation**.

EVALUATION CRITERIA

Standard form 1442 is to be completed; to include Block #19 Acknowledge Amendments if applicable - and duly executed with an original signature by an official authorized to bind the company in accordance with FAR 4.102.

TAB B, SECTION 00010, PROPOSAL BID SCHEDULE SUBMISSION REQUIREMENTS

The Offeror shall complete and submit in its entirety Section 00010, Proposal Bid Schedule. This form is included in Section 00010 of this **Solicitation**.

EVALUATION CRITERIA

The price (Proposal Bid Schedule) may be evaluated by the SSEB for reasonableness through the use of cost and or price analysis.

TAB C, SECTION 00600, REPRESENTATIONS AND CERTIFICATIONS

The Offeror shall complete and submit in its entirety Section 00600, Representations and Certifications.

TAB D, JOINT VENTURE AGREEMENT SUBMISSION REQUIREMENTS

If the Offeror is a Joint Venture (JV), a copy of the JV Agreement must be provided. If a JV Agreement has not yet been finalized/approved, then indicate status.

EVALUATION CRITERIA

JV Agreements shall clearly indicate the percentages of the JV participants, in particular the percent of the controlling party. In addition, the JV Agreement shall provide a clear delineation of responsibilities and authorities between the JV parties and provide that each party is jointly and severally liable for the performance of all contract requirements. Other informal relationships without a JV agreement will be considered to be subcontractors of the Offeror.

■ **END OF SECTION –**

PERSONNEL RESUME - EXPERIENCE

Your Name and Title: _____

Name of Your Firm: _____

No. of Years Presently With This Firm: _____ Years with Other Firms **doing the same job**: _____

Your Job title on the Proposed Project: _____

Education

Education (Degree(s)/Year/Specialization): _____

Name of College, University, or Trade School: _____

Registration/Accreditation: No. _____ Country/State _____ Year _____

Your Specific Experience and Qualifications Relevant to This Project (Include a POC with phone number for the two (2) most recent projects **where you performed in the same role** as proposed for this project):

Project Experience

Project #1 Name and Location: _____

General Project Description:

Your Job Title in the Project and a Description of the Duties You Performed:

Owner's POC for reference (Name, Company, Role in the Project, email address and phone number):

Project #2 Name and Location: _____

General Scope of Project:

Your Job Title in the Project and a Description of the Duties You Performed:

Owner's POC for reference (Name, Company, Role in the Project, email address and phone number):

PROJECT EXPERIENCE
(To be completed by the Offeror)

Offeror's Firm Name: _____

Reference Point of Contact (POC) (additional points of contact may be attached)

POC Name: _____ Title: _____

POC Email Address: _____ Phone: _____

POC Role in the Project: _____

POC Company Name: _____

POC Company Address: _____

Project Information

Project Title: _____

Project Location: _____

Project Contract/Task Order (TO)/Purchase Order (PO) Number: _____

Your Role (Prime or Subcontractor) and Work Your Company Self-Performed:

Was this a Joint Venture? ____ If yes, Your % interest in the Joint Venture: ____%

Name of the other Joint Venture firm: _____

General Project Description: _____

Percentage of Your Contract Completed by Your Firm: ____%

Construction Cost for Your Portion of the Project:

At Award: \$ _____ Reason for Cost Growth: _____

Final Cost \$ _____

Award Date: _____

Reason for Time Growth

Scheduled Completion Date: _____

Actual Completion Date: _____

Type of Work You Subcontracted Out:

PAST PERFORMANCE QUESTIONNAIRE

PAST PERFORMANCE (To be completed by Offeror)	
1. Contract / Task Order (TO) / Purchase Order (PO) Number:	
2. Contractor Data Universal Numbering System (DUNS) Number:	
3. Contract / TO / PO Dollar Value:	
4. Project Title:	
Location (City and Province):	
Percent complete:	
Date Complete:	
Was project completed on time (within schedule) and within cost?	
5. If you answered "No" above, provide a brief synopsis on corrective actions that were taken:	
6. List current / on-going projects, Dollar value, Contract Number, percentage (%) complete:	
7: Provide points of Contact (POC) / References (minimum requirement of 2) for individuals the Government may contact at companies that are present or previous customers of the Offeror:	
Name:	Name:
Phone #:	Phone #:
e-mail:	e-mail:
Project:	Project:

Section 00100 - Bidding Schedule/Instructions to Bidders

CLAUSES INCORPORATED BY REFERENCE

52.215-1 Instructions to Offerors--Competitive Acquisition JAN 2004

CLAUSES INCORPORATED BY FULL TEXT

52.214-5000 APPARENT CLERICAL MISTAKES (MAR 1995)--EFARS

(a) For the purpose of initial evaluations of bids, the following will be utilized in the resolving arithmetic discrepancies found on the face of bidding schedule as submitted by the bidder:

- (1) Obviously misplaced decimal points will be corrected;
- (2) Discrepancy between unit price and extended price, the unit price will govern;
- (3) Apparent errors in extension of unit prices will be corrected;
- (4) Apparent errors in addition of lump-sum and extended prices will be corrected.

(b) For the purpose of bid evaluation, the government will proceed on the assumption that the bidder intends his bid to be evaluated on basis of the unit prices, the totals arrived at by resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.

(c) These correction procedures shall not be used to resolve any ambiguity concerning which bid is low.

(End of statement)

52.216-1 TYPE OF CONTRACT (APR 1984)

The Government contemplates award of a Firm Fixed Price contract resulting from this solicitation.

(End of provision)

52.236-28 PREPARATION OF PROPOSALS--CONSTRUCTION (OCT 1997)

(a) Proposals must be (1) submitted on the forms furnished by the Government or on copies of those forms, and (2) manually signed. The person signing a proposal must initial each erasure or change appearing on any proposal form.

(b) The proposal form may require offerors to submit proposed prices for one or more items on various bases, including--

(1) Lump sum price;

(2) Alternate prices;

(3) Units of construction; or

(4) Any combination of paragraphs (b)(1) through (b)(3) of this provision.

(c) If the solicitation requires submission of a proposal on all items, failure to do so may result in the proposal being rejected without further consideration. If a proposal on all items is not required, offerors should insert the words "no proposal" in the space provided for any item on which no price is submitted.

(d) Alternate proposals will not be considered unless this solicitation authorizes their submission.

(End of provision)

52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

<http://farsite.hill.af.mil/>

<http://acquisition.gov/comp/far/index.html>

(End of provision)

DEFENSE BASE ACT INSURANCE RATES – LIMITATION – FIXED-PRICE

(a) The U.S. Army Corps of Engineers (USACE) has entered into a contract with **CNA Insurance** to provide all Defense Base Act (DBA) insurance to USACE and C3 contractors and subcontractors at a contracted fixed rate. The fixed rates for this insurance are as follows:

Service	\$3.50	per \$100 of employee remuneration
Construction	\$4.25	per \$100 of employee remuneration
Security	\$10.00	per \$100 of employee remuneration
Aviation	\$17.00	per \$100 of employee remuneration

(b) Bidders/Offerors should **compute the total compensation or total payroll**, (salary, plus overseas recruitment incentive and post differential, but *excludes* per diem, housing allowance, travel expenses, temporary quarters allowance, education allowance and other miscellaneous post allowances to include fee or profit) to be paid to employees who will be covered by DBA insurance. Compute the cost of DBA Insurance by utilizing the spaces provided below for the base period and whatever extension there may be thereafter, if applicable.

(1) Compensation of Covered Employees: _____
(Total Payroll Not Total Contract Value) Ex: If total Payroll is \$100,000.00

(2) Applicable DBA Rate: _____
(Use appropriate Rate) Ex: If a Service, the rate is \$3.50/\$100 or 3.5%

(3) Total DBA Cost: _____

(Amount of DBA Premium) Ex: \$100 K multiplied by 3.5% is \$3,500.00

(c) Bidders/Offerors shall include a statement as to whether or not local nationals or third country nationals will be employed on the resultant contract.

(d) CNA Insurance is utilizing Rutherford International as their managing Broker. The primary POC is the USACE DBA Program Administrator is Nikki Hounghmany, (703) 813-6571 usace@rutherford.com. The alternate POC is Sara Payne, Senior Vice President, (703) 813-6503 sara.payne@rutherford.com.

(e) Labor Category/Job Classification Definitions:

SERVICE: \$3.50/\$100 "White collar" workers such as IT Consultants, Engineers, Administrative type Office workers and light housekeeping. Security Consultants could be included as long as they are just assessing risk and not providing armed protection.

CONSTRUCTION: \$4.25/\$100 "Blue collar" workers providing Construction services such as Carpentry, Electrical, Plumbing, Concrete, Asphalt, Day Laborers, Operation and Maintenance of Heavy Equipment

SECURITY: \$10.00/\$100 Personal Security Detail (PSD) and Static or Convoy Guarding property of Personnel

AVIATION: \$17.00/\$100 Pilot and Crew of any aircraft excluding ground personnel who provide maintenance or services but stay on the ground

Section 00600 - Representations & Certifications

CLAUSES INCORPORATED BY FULL TEXT

52.209-5 CERTIFICATION REGARDING RESPONSIBILITY MATTERS (APR 2010)

(a)(1) The Offeror certifies, to the best of its knowledge and belief, that-

(i) The Offeror and/or any of its Principals-

(A) Are () are not () presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any Federal agency;

(B) Have () have not (), within a three-year period preceding this offer, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) contract or subcontract; violation of Federal or State antitrust statutes relating to the submission of offers; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, violating Federal criminal tax laws, or receiving stolen property (if offeror checks "have", the offeror shall also see 52.209-7, if included in this solicitation); and

(C) Are () are not () presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in paragraph (a)(1)(i)(B) of this provision.; and

(D) Have [ballot], have not [ballot], within a three-year period preceding this offer, been notified of any delinquent Federal taxes in an amount that exceeds \$3,000 for which the liability remains unsatisfied.

(1) Federal taxes are considered delinquent if both of the following criteria apply:

(i) The tax liability is finally determined. The liability is finally determined if it has been assessed. A liability is not finally determined if there is a pending administrative or judicial challenge. In the case of a judicial challenge to the liability, the liability is not finally determined until all judicial appeal rights have been exhausted.

(ii) The taxpayer is delinquent in making payment. A taxpayer is delinquent if the taxpayer has failed to pay the tax liability when full payment was due and required. A taxpayer is not delinquent in cases where enforced collection action is precluded.

(2) Examples. (i) The taxpayer has received a statutory notice of deficiency, under I.R.C. Sec. 6212, which entitles the taxpayer to seek Tax Court review of a proposed tax deficiency. This is not a delinquent tax because it is not a final tax liability. Should the taxpayer seek Tax Court review, this will not be a final tax liability until the taxpayer has exercised all judicial appeal rights.

(ii) The IRS has filed a notice of Federal tax lien with respect to an assessed tax liability, and the taxpayer has been issued a notice under I.R.C. Sec. 6320 entitling the taxpayer to request a hearing with the IRS Office of Appeals contesting the lien filing, and to further appeal to the Tax Court if the IRS determines to sustain the lien filing. In the course of the hearing, the taxpayer is entitled to contest the underlying tax liability because the taxpayer has had no prior opportunity to contest the liability. This is not a delinquent tax because it is not a final tax liability. Should the taxpayer seek tax court review, this will not be a final tax liability until the taxpayer has exercised all judicial appeal rights.

(iii) The taxpayer has entered into an installment agreement pursuant to I.R.C. Sec. 6159. The taxpayer is making timely payments and is in full compliance with the agreement terms. The taxpayer is not delinquent because the taxpayer is not currently required to make full payment.

(iv) The taxpayer has filed for bankruptcy protection. The taxpayer is not delinquent because enforced collection action is stayed under 11 U.S.C. 362 (the Bankruptcy Code).

(ii) The Offeror has () has not (), within a three-year period preceding this offer, had one or more contracts terminated for default by any Federal agency.

(2) Principal, for the purposes of this certification, means an officer, director, owner, partner, or a person having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a division or business segment; and similar positions).

(b) The Offeror shall provide immediate written notice to the Contracting Officer if, at any time prior to contract award, the Offeror learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

(c) A certification that any of the items in paragraph (a) of this provision exists will not necessarily result in withholding of an award under this solicitation. However, the certification will be considered in connection with a determination of the Offeror's responsibility. Failure of the Offeror to furnish a certification or provide such additional information as requested by the Contracting Officer may render the Offeror nonresponsible.

(d) Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by paragraph (a) of this provision. The knowledge and information of an Offeror is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

(e) The certification in paragraph (a) of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Offeror knowingly rendered an erroneous certification, in addition to other remedies available to the Government, the Contracting Officer may terminate the contract resulting from this solicitation for default.

(End of provision)

52.225-20 PROHIBITION ON CONDUCTING RESTRICTED BUSINESS OPERATIONS IN SUDAN-- CERTIFICATION (AUG 2009)

(a) Definitions. As used in this provision--

Business operations means engaging in commerce in any form, including by acquiring, developing, maintaining, owning, selling, possessing, leasing, or operating equipment, facilities, personnel, products, services, personal property, real property, or any other apparatus of business or commerce.

Marginalized populations of Sudan means--

(1) Adversely affected groups in regions authorized to receive assistance under section 8(c) of the Darfur Peace and Accountability Act (Pub. L. 109-344) (50 U.S.C. 1701 note); and

(2) Marginalized areas in Northern Sudan described in section 4(9) of such Act.

Restricted business operations means business operations in Sudan that include power production activities, mineral extraction activities, oil-related activities, or the production of military equipment, as those terms are defined in the Sudan Accountability and Divestment Act of 2007 (Pub. L. 110-174). Restricted business operations do not include

business operations that the person (as that term is defined in Section 2 of the Sudan Accountability and Divestment Act of 2007) conducting the business can demonstrate--

- (1) Are conducted under contract directly and exclusively with the regional government of southern Sudan;
- (2) Are conducted pursuant to specific authorization from the Office of Foreign Assets Control in the Department of the Treasury, or are expressly exempted under Federal law from the requirement to be conducted under such authorization;
- (3) Consist of providing goods or services to marginalized populations of Sudan;
- (4) Consist of providing goods or services to an internationally recognized peacekeeping force or humanitarian organization;
- (5) Consist of providing goods or services that are used only to promote health or education; or
- (6) Have been voluntarily suspended.

(b) Certification. By submission of its offer, the offeror certifies that the offeror does not conduct any restricted business operations in Sudan.

(End of provision)

52.225-25 PROHIBITION ON ENGAGING IN SANCTIONED ACTIVITIES RELATING TO IRAN-- CERTIFICATION (SEP 2010)

(a) Definition.

Person--

(1) Means--

- (i) A natural person;
 - (ii) A corporation, business association, partnership, society, trust, financial institution, insurer, underwriter, guarantor, and any other business organization, any other nongovernmental entity, organization, or group, and any governmental entity operating as a business enterprise; and
 - (iii) Any successor to any entity described in paragraph (1)(ii) of this definition; and
- (2) Does not include a government or governmental entity that is not operating as a business enterprise.

(b) Certification. Except as provided in paragraph (c) of this provision or if a waiver has been granted in accordance with FAR 25.703-2(d), by submission of its offer, the offeror certifies that the offeror, or any person owned or controlled by the offeror, does not engage in any activities for which sanctions may be imposed under section 5 of the Iran Sanctions Act of 1996. These sanctioned activities are in the areas of development of the petroleum resources of Iran, production of refined petroleum products in Iran, sale and provision of refined petroleum products to Iran, and contributing to Iran's ability to acquire or develop certain weapons.

(c) Exception for trade agreements. The certification requirement of paragraph (b) of this provision does not apply if--

(1) This solicitation includes a trade agreements certification (e.g., 52.225-4, 52.225-11 or comparable agency provision); and

(2) The offeror has certified that all the offered products to be supplied are designated country end products or designated country construction material.

(End of provision)

252.209-7001 DISCLOSURE OF OWNERSHIP OR CONTROL BY THE GOVERNMENT OF A TERRORIST COUNTRY (JAN 2009)

(a) "Definitions."

As used in this provision --

(a) "Government of a terrorist country" includes the state and the government of a terrorist country, as well as any political subdivision, agency, or instrumentality thereof.

(2) "Terrorist country" means a country determined by the Secretary of State, under section 6(j)(1)(A) of the Export Administration Act of 1979 (50 U.S.C. App. 2405(j)(i)(A)), to be a country the government of which has repeatedly provided support for such acts of international terrorism. As of the date of this provision, terrorist countries subject to this provision include: Cuba, Iran, Sudan, and Syria.

(3) "Significant interest" means --

(i) Ownership of or beneficial interest in 5 percent or more of the firm's or subsidiary's securities. Beneficial interest includes holding 5 percent or more of any class of the firm's securities in "nominee shares," "street names," or some other method of holding securities that does not disclose the beneficial owner;

(ii) Holding a management position in the firm, such as a director or officer;

(iii) Ability to control or influence the election, appointment, or tenure of directors or officers in the firm;

(iv) Ownership of 10 percent or more of the assets of a firm such as equipment, buildings, real estate, or other tangible assets of the firm; or

(v) Holding 50 percent or more of the indebtedness of a firm.

(b) "Prohibition on award."

In accordance with 10 U.S.C. 2327, no contract may be awarded to a firm or a subsidiary of a firm if the government of a terrorist country has a significant interest in the firm or subsidiary or, in the case of a subsidiary, the firm that owns the subsidiary, unless a waiver is granted by the Secretary of Defense.

(c) "Disclosure."

If the government of a terrorist country has a significant interest in the Offeror or a subsidiary of the Offeror, the Offeror shall disclose such interest in an attachment to its offer. If the Offeror is a subsidiary, it shall also disclose any significant interest the government of a terrorist country has in any firm that owns or controls the subsidiary. The disclosure shall include --

(1) Identification of each government holding a significant interest; and

(2) A description of the significant interest held by each government.

(End of provision)

252.225-7031 SECONDARY ARAB BOYCOTT OF ISRAEL (JUN 2005)

(a) Definitions. As used in this provision--

(1) Foreign person means any person (including any individual, partnership, corporation, or other form of association) other than a United States person.

(2) United States means the 50 States, the District of Columbia, outlying areas, and the outer Continental Shelf as defined in 43 U.S.C. 1331.

(3) United States person is defined in 50 U.S.C. App. 2415(2) and means--

(i) Any United States resident or national (other than an individual resident outside the United States who is employed by other than a United States person);

(ii) Any domestic concern (including any permanent domestic establishment of any foreign concern); and

(iii) Any foreign subsidiary or affiliate (including any permanent foreign establishment) of any domestic concern that is controlled in fact by such domestic concern.

(b) Certification. If the offeror is a foreign person, the offeror certifies, by submission of an offer, that it--

(1) Does not comply with the Secondary Arab Boycott of Israel; and

(2) Is not taking or knowingly agreeing to take any action, with respect to the Secondary Boycott of Israel by Arab countries, which 50 U.S.C. App. 2407(a) prohibits a United States person from taking.

(End of provision)

252.225-7042 AUTHORIZATION TO PERFORM (APR 2003)

The offeror represents that it has been duly authorized to operate and to do business in the country or countries in which the contract is to be performed.

(End of provision)

Section 00700 - Contract Clauses

CLAUSES INCORPORATED BY REFERENCE

52.203-12	Limitation On Payments To Influence Certain Federal Transactions	OCT 2010
52.204-10	Reporting Executive Compensation and First-Tier Subcontract Awards	JUL 2010
52.222-29	Notification Of Visa Denial	JUN 2003
52.222-50	Combating Trafficking in Persons	FEB 2009
52.225-13	Restrictions on Certain Foreign Purchases	JUN 2008
52.228-3	Worker's Compensation Insurance (Defense Base Act)	APR 1984
52.232-5	Payments under Fixed-Price Construction Contracts	SEP 2002
52.232-17	Interest	OCT 2010
52.232-27	Prompt Payment for Construction Contracts	OCT 2008
52.232-33	Payment by Electronic Funds Transfer--Central Contractor Registration	OCT 2003
52.233-1	Disputes	JUL 2002
52.233-3	Protest After Award	AUG 1996
52.233-4	Applicable Law for Breach of Contract Claim	OCT 2004
52.236-2	Differing Site Conditions	APR 1984
52.236-3	Site Investigation and Conditions Affecting the Work	APR 1984
52.236-7	Permits and Responsibilities	NOV 1991
52.236-14	Availability and Use of Utility Services	APR 1984
52.236-15	Schedules for Construction Contracts	APR 1984
52.236-17	Layout of Work	APR 1984
52.236-21	Specifications and Drawings for Construction	FEB 1997
52.236-26	Preconstruction Conference	FEB 1995
52.243-5	Changes and Changed Conditions	APR 1984
52.244-6	Subcontracts for Commercial Items	DEC 2010
52.246-21	Warranty of Construction	MAR 1994
52.249-2 Alt I	Termination for Convenience of the Government (Fixed-Price) (May 2004) - Alternate I	SEP 1996
52.249-10	Default (Fixed-Price Construction)	APR 1984
52.253-1	Computer Generated Forms	JAN 1991
252.201-7000	Contracting Officer's Representative	DEC 1991
252.203-7000	Requirements Relating to Compensation of Former DoD Officials	JAN 2009
252.203-7001	Prohibition On Persons Convicted of Fraud or Other Defense-Contract-Related Felonies	DEC 2008
252.203-7002	Requirement to Inform Employees of Whistleblower Rights	JAN 2009
252.209-7004	Subcontracting With Firms That Are Owned or Controlled By The Government of a Terrorist Country	DEC 2006
252.215-7000	Pricing Adjustments	DEC 1991
252.222-7002	Compliance With Local Labor Laws (Overseas)	JUN 1997
252.225-7005	Identification Of Expenditures In The United States	JUN 2005
252.225-7041	Correspondence in English	JUN 1997
252.225-7044 Alt I	Balance of Payments Program--Construction Material (2010) Alternate I	OCT 2010
252.229-7000	Invoices Exclusive of Taxes or Duties	JUN 1997
252.232-7003	Electronic Submission of Payment Requests and Receiving Reports	MAR 2008
252.232-7008	Assignment of Claims (Overseas)	JUN 1997

252.232-7010	Levies on Contract Payments	DEC 2006
252.233-7001	Choice of Law (Overseas)	JUN 1997
252.236-7000	Modification Proposals-Price Breakdown	DEC 1991
252.243-7001	Pricing Of Contract Modifications	DEC 1991
252.247-7023	Alt III Transportation of Supplies by Sea (May 2002) Alternate III	MAY 2002

CLAUSES INCORPORATED BY FULL TEXT

52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (DEC 2010)

(a) Definition. Commercially available off-the-shelf (COTS) item, as used in this clause--

(1) Means any item of supply (including construction material) that is--

(i) A commercial item (as defined in paragraph (1) of the definition in FAR 2.101);

(ii) Sold in substantial quantities in the commercial marketplace; and

(iii) Offered to the Government, under a contract or subcontract at any tier, without modification, in the same form in which it is sold in the commercial marketplace; and

(2) Does not include bulk cargo, as defined in section 3 of the Shipping Act of 1984 (46 U.S.C. App. 1702), such as agricultural products and petroleum products.

(b) The Government suspends or debar Contractors to protect the Government's interests. Other than a subcontract for a commercially available off-the-shelf item, the Contractor shall not enter into any subcontract, in excess of \$30,000 with a Contractor that is debarred, suspended, or proposed for debarment by any executive agency unless there is a compelling reason to do so.

(c) The Contractor shall require each proposed subcontractor whose subcontract will exceed \$30,000, other than a subcontractor providing a commercially available off-the-shelf item, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principals, is or is not debarred, suspended, or proposed for debarment by the Federal Government.

(d) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party (other than a subcontractor providing a commercially available off-the-shelf item) that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the Excluded Parties List System). The notice must include the following:

(e) Subcontracts. Unless this is a contract for the acquisition of commercial items, the Contractor shall include the requirements of this clause, including this paragraph (e) (appropriately modified for the identification of the parties), in each subcontract that--

(1) Exceeds \$30,000 in value; and

(2) Is not a subcontract for commercially available off-the-shelf items.

(End of clause)

52.252-2 CLAUSES INCORPORATED BY REFERENCE (FEB 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

<http://farsite.hill.af.mil/>

<http://acquisition.gov/comp/far/index.html>

(End of clause)

52.252-6 AUTHORIZED DEVIATIONS IN CLAUSES (APR 1984)

(a) The use in this solicitation or contract of any Federal Acquisition Regulation (48 CFR Chapter 1) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the clause.

(b) The use in this solicitation or contract of any [Defense Federal Acquisition Regulation](#) (48 CFR [2](#)) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

(End of clause)

252.225-7997 ADDITIONAL REQUIREMENTS AND RESPONSIBILITIES RELATING TO ALLEGED CRIMES BY OR AGAINST CONTRACTOR PERSONNEL IN IRAQ AND AFGHANISTAN (DEVIATION 2010-O0014)(AUGUST 2010)

(a) The Contractor shall report to the appropriate investigative authorities, identified in paragraph (c) below, any alleged offenses under—

(1) The Uniform Code of Military Justice (chapter 47 of title 10, United States code) (applicable to contractors serving with or accompanying an armed force in the field during a declared war or a contingency operation); or

(2) The Military Extraterritorial Jurisdiction Act (chapter 212 of title 18, United States Code).

(b) The Contractor shall provide to all contractor personnel who will perform work on a contract in Iraq or Afghanistan, before beginning such work, information on the following:

(1) How and where to report an alleged crime described in paragraph (a) of this clause.

(2) Where to seek victim and witness protection and assistance available to contractor personnel in connection with an alleged offense described in paragraph (a) of this clause.

(c) The appropriate investigative authorities to which suspected crimes shall be reported include the following officials--

(i) US Army Criminal Investigative Division at <http://www.cid.army.mil/reportacrime.html>;

(ii) Air Force Office of Special Investigations at
<http://www.osi.andrews.af.mil/library/factsheets/factsheet.asp?id=14522>;

(iii) Navy Criminal Investigative Service at <http://www.ncis.navy.mil/Pages/publicdefault.aspx>;
 or

(iv) To the command of any supported military element or the command of any base.

(d) Personnel seeking whistleblower protection from reprisals for reporting criminal acts shall seek guidance through the DoD Inspector General hotline at (800) 424-9098 or www.dodig.mil/HOTLINE/index.html. Personnel seeking other forms of victim or witness protections should contact the nearest military law enforcement office.

(End of clause)

252.236-7001 CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall--

- (1) Check all drawings furnished immediately upon receipt;
- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;
- (4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and
- (5) Reproduce and print contract drawings and specifications as needed.

(c) In general--

- (1) Large-scale drawings shall govern small-scale drawings; and
- (2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

(e) The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

Title	File	Drawing No.
See Plans & Specs for a Complete List of any Drawings Provided		
(End of clause)		

252.246-7004 SAFETY OF FACILITIES, INFRASTRUCTURE, AND EQUIPMENT FOR MILITARY OPERATIONS (OCT 2010)

(a) Definition. Discipline Working Group, as used in this clause, means representatives from the DoD Components, as defined in MIL-STD-3007F, who are responsible for the unification and maintenance of the Unified Facilities Criteria (UFC) documents for a particular discipline area.

(b) The Contractor shall ensure, consistent with the requirements of the applicable inspection clause in this contract, that the facilities, infrastructure, and equipment acquired, constructed, installed, repaired, maintained, or operated under this contract comply with Unified Facilities Criteria (UFC) 1-200-01 for--

(1) Fire protection;

(2) Structural integrity;

(3) Electrical systems;

(4) Plumbing;

(5) Water treatment;

(6) Waste disposal; and

(7) Telecommunications networks.

(c) The Contractor may apply a standard equivalent to or more stringent than UFC 1-200-01 upon a written determination of the acceptability of the standard by the Contracting Officer with the concurrence of the relevant Discipline Working Group.

(End of clause)

CONTRACTOR PERSONNEL IN THE UNITED STATES CENTRAL COMMAND AREA OF RESPONSIBILITY (DEVIATION 2007-00010)

(a) *Definitions.* As used in this clause--

"Chief of mission" means the principal officer in charge of a diplomatic mission of the United States or of a United States office abroad which is designated by the Secretary of State as diplomatic in nature, including any individual assigned under section 502(c) of the Foreign Service Act of 1980 (Public Law 96-465) to be temporarily in charge of such a mission or office.

"Combatant commander" means the commander of a unified or specified combatant command established in accordance with 10 U.S.C. 161.

(b) *General.* (1) This clause applies when contractor personnel are required to perform in the United States Central Command (USCENTCOM) Area of Responsibility (AOR), and are not covered by the clause at DF ARS 252.225-7040, Contractor Personnel Authorized to Accompany U.S. Armed Forces Deployed Outside the United States.

(2) Contract performance may require work in dangerous or austere conditions. Except

as otherwise provided in the contract, the Contractor accepts the risks associated with required contract performance in such operations.

(3) Contractor personnel are civilians.

(i) Except as provided in paragraph (b)(3)(ii) of this clause, and in accordance with paragraph (i)(3) of this clause, contractor personnel are only authorized to use deadly force in self defense.

(ii) Contractor personnel performing security functions are also authorized to use deadly force when use of such force reasonably appears necessary to execute their security mission to protect assets/persons, consistent with the terms and conditions contained in the contract or with their job description and terms of employment.

(4) Service performed by contractor personnel subject to this clause is not active duty or service under 38 U.S.C. 106 note.

(c) *Support.* Unless specified elsewhere in the contract, the Contractor is responsible for all logistical and security support required for contractor personnel engaged in this contract.

(d) *Compliance with laws and regulations.* The Contractor shall comply with, and shall ensure that its personnel in the USCENCOM AOR are familiar with and comply with, all applicable-

(1) United States, host country, and third country national laws;

(2) Treaties and international agreements;

(3) United States regulations, directives, instructions, policies, and procedures; and

(4) Force protection, security, health, or safety orders, directives, and instructions issued by the Combatant Commander; however, only the Contracting Officer is authorized to modify the terms and conditions of the contract.

(e) *Preliminary personnel requirements.* (1) Specific requirements for paragraphs (e)(2)(i) through (e)(2)(vi) of this clause will be set forth in the statement of work, or elsewhere in the contract.

(2) Before contractor personnel depart from the United States or a third country, and before contractor personnel residing in the host country begin contract performance in the USCENCOM AOR, the Contractor shall ensure the following:

(i) All required security and background checks are complete and acceptable.

(ii) All personnel are medically and physically fit and have received all required vaccinations.

(iii) All personnel have all necessary passports, visas, entry permits, and other documents required for contractor personnel to enter and exit the foreign country, including those required for in-transit countries.

(iv) All personnel have received theater clearance, if required by the Combatant Commander.

(v) All personnel have received personal security training. The training must at minimum-

(A) Cover safety and security issues facing employees overseas;

(B) Identify safety and security contingency planning activities; and

(C) Identify ways to utilize safety and security personnel and other resources appropriately.

(vi) All personnel have received isolated personnel training, if specified in the contract. Isolated personnel are military or civilian personnel separated from their unit or organization in an environment requiring them to survive, evade, or escape while awaiting rescue or recovery.

(vii) All personnel who are US. citizens are registered with the US. Embassy or Consulate with jurisdiction over the area of operations on-line at <http://www.travel.state.gov>.

(3) The Contractor shall notify all personnel who are not a local national or ordinarily resident in the host country that-

(i) Such employees, and dependents residing with such employees, who engage in conduct outside the United States that would constitute an offense punishable by imprisonment for more than one year if the conduct had been engaged in within the special maritime and territorial jurisdiction of the United States, may potentially be subject to the criminal jurisdiction of the United States (see the Military Extraterritorial Jurisdiction Act of 2000 (18 U.S.C. 3261 *et seq.*);

(ii) Pursuant to the War Crimes Act, 18 U.S.C. 2441, Federal criminal jurisdiction also extends to conduct that is determined to constitute a violation of the law of war when committed by a civilian national of the United States;

(iii) Other laws may provide for prosecution of US. nationals who commit offenses on the premises of United States diplomatic, consular, military or other Government missions outside the United States (18 U.S.C. 7(9)).

(f) *Processing and departure points.* The Contractor shall require its personnel who are arriving from outside the area of performance to perform in the USCENTCOM AOR to--

(1) Process through the departure center designated in the contract or complete another process as directed by the Contracting Officer;

(2) Use a specific point of departure and transportation mode as directed by the Contracting Officer; and

(3) Process through a reception center as designated by the Contracting Officer upon arrival at the place of performance.

(g) *Personnel data.* (1) The Contractor shall enter, before deployment, or if already in the USCENTCOM AOR, enter upon becoming an employee under this contract, and maintain current data, including departure date, for all contractor personnel, including US. citizens, US. legal aliens, third country nationals, and local national contractor

personnel, who are performing this contract in the USCENTCOM AOR. This requirement excludes-

- Personnel hired under contracts for which the period of performance is less than 30 days; and
- Embarked contractor personnel, while afloat, that are tracked by the Diary Message Reporting System.

(2) The automated web-based system to use for this effort is the Synchronized Predeployment and Operational Tracker (SPOT). Follow these steps to register in and use SPOT:

(i) SPOT registration can be accomplished by either a Common Access Card or through an Army Knowledge Online (AKO) account.

(ii) In order to obtain an AKO account, the Contractor shall-

- (A) Request the Contracting Officer or other Government point of contact to sponsor its AKO guest account;
- (B) Go to <http://www.us.army.mil>;
- (C) Enter the AKO sponsor username; and
- (D) After AKO registration, contact the sponsor to confirm registration.

(iii) *Registration in SPOT*

- (A) Register for a SPOT account at <https://iel.kc.us.army.mil/spotregistration/>.
- (B) The customer support team must validate user need. This process may take 2 business days. Company supervisors will be contacted to determine the appropriate level of user access.

(iv) *Access to SPOT* Upon approval, all users will access SPOT at <https://iel.kc.us.army.mil/spotracker>.

(v) *SPOT Questions.* Refer SPOT application assistance questions to the Customer Support Team at 717-506-1358 or SPOT@technisource.com.

(3) The Contractor shall ensure that all employees in the database have a current DD Form 93, Record of Emergency Data Card, on file with both the Contractor and the designated Government official. The Contracting Officer will inform the Contractor of the Government official designated to receive the data card.

(h) *Contractor personnel.* The Contracting Officer may direct the Contractor, at its own expense, to remove and replace any contractor personnel who fail to comply with or violate applicable requirements of this contract. Such action may be taken at the Government's discretion without prejudice to its rights under any other provision of this contract, including termination for default or cause.

(i) *Weapons.* (1) If the Contracting Officer, subject to the approval of the Combatant Commander, authorizes the carrying of weapons-

(i) The Contracting Officer may authorize an approved Contractor to issue Contractor-owned weapons and ammunition to specified employees; however

(ii) USACE DOES NOT ARM PERSONNEL.

(2) The Contractor shall provide to the Contracting Officer a specific list of personnel for whom authorization to carry a weapon is requested.

(3) The Contractor shall ensure that its personnel who are authorized to carry weapons-

(i) Are adequately trained to carry and use them-

(A) Safely;

(B) With full understanding of, and adherence to, the rules of the use of force issued by the Combatant Commander; and

(C) In compliance with applicable Department of Defense and agency policies, agreements, rules, regulations, and other applicable law;

(ii) Are not barred from possession of a firearm by 18 U.S.C. 922; and

(iii) Adhere to all guidance and orders issued by the Combatant Commander regarding possession, use, safety, and accountability of weapons and ammunition.

(4) Upon revocation by the Contracting Officer of the Contractor's authorization to possess weapons, the Contractor shall ensure that all Government-furnished weapons and unexpended ammunition are returned as directed by the Contracting Officer.

(5) Whether or not weapons are Government-furnished, all liability for the use of any weapon by contractor personnel rests solely with the Contractor and the Contractor employee using such weapon.

(j) *Vehicle or equipment licenses.* Contractor personnel shall possess the required licenses to operate all vehicles or equipment necessary to perform the contract in the area of performance.

(k) *Military clothing and protective equipment.* (1) Contractor personnel are prohibited from wearing military clothing unless specifically authorized by the Combatant Commander. If authorized to wear military clothing, contractor personnel must wear distinctive patches, arm bands, nametags, or headgear, in order to be distinguishable from military personnel, consistent with force protection measures.

(2) Contractor personnel may wear specific items required for safety and security, such as ballistic, nuclear, biological, or chemical protective equipment.

(1) *Evacuation.* (1) If the Chief of Mission or Combatant Commander orders a mandatory evacuation of some or all personnel, the Government will provide to United States and third country national contractor personnel the level of assistance provided to private United States citizens.

(2) In the event of a non-mandatory evacuation order, the Contractor shall maintain personnel on location sufficient to meet contractual obligations unless instructed to

evacuate by the Contracting Officer.

(m) *Personnel recovery.* In the case of isolated, missing, detained, captured or abducted contractor personnel, the Government will assist in personnel recovery actions in accordance with DoD Directive 2310.2, Personnel Recovery.

(n) *Notification and return of personal effects.* (1) The Contractor shall be responsible for notification of the employee-designated next of kin, and notification as soon as possible to the U.S. Consul responsible for the area in which the event occurred, if the employee-

(i) Dies;

(ii) Requires evacuation due to an injury; or

(iii) Is isolated, missing, detained, captured, or abducted.

(2) The Contractor shall also be responsible for the return of all personal effects of deceased or missing contractor personnel, if appropriate, to next of kin.

(o) *Mortuary affairs.* Mortuary affairs for contractor personnel who die in the area of performance will be handled in accordance with DoD Directive 1300.22, Mortuary Affairs Policy.

(p) *Changes.* In addition to the changes otherwise authorized by the Changes clause of this contract, the Contracting Officer may, at any time, by written order identified as a change order, make changes in place of performance or Government-furnished facilities, equipment, material, services, or site. Any change order issued in accordance with this paragraph shall be subject to the provisions of the Changes clause of this contract.

(q) *Subcontracts.* The Contractor shall incorporate the substance of this clause, including this paragraph (q), in all subcontracts that require subcontractor personnel to perform in the USCENTCOM AOR.

(End of clause)

Section 00800 - Special Contract Requirements

CLAUSES INCORPORATED BY REFERENCE

52.211-13	Time Extensions	SEP 2000
52.236-5	Material and Workmanship	APR 1984
52.242-14	Suspension of Work	APR 1984
52.246-12	Inspection of Construction	AUG 1996

CLAUSES INCORPORATED BY FULL TEXT

52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984)

The Contractor shall be required to (a) commence work under this contract within **10** calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than **90 calendar days**. **The time stated for completion shall include final cleanup of the premises.**

(End of clause)

52.211-12 LIQUIDATED DAMAGES--CONSTRUCTION (SEP 2000)

(a) If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of \$620.75 for each calendar day of delay until the work is completed or accepted.

(b) If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

(End of clause)

252.236-7004 PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DEC 1991)

(a) The Government will pay all costs for the mobilization and demobilization of all of the Contractor's plant and equipment at the contract lump sum price for this item.

(1) **60** percent of the lump sum price upon completion of the contractor's mobilization at the work site.

(2) The remaining **40** percent upon completion of demobilization.

(b) The Contracting Officer may require the Contractor to furnish cost data to justify this portion of the bid if the Contracting Officer believes that the percentages in paragraphs (a) (1) and (2) of this clause do not bear a reasonable relation to the cost of the work in this contract.

(1) Failure to justify such price to the satisfaction of the Contracting Officer will result in payment, as determined by the Contracting Officer, of --

- (i) Actual mobilization costs at completion of mobilization;
 - (ii) Actual demobilization costs at completion of demobilization; and
 - (iii) The remainder of this item in the final payment under this contract.
- (2) The Contracting Officer's determination of the actual costs in paragraph (b)(1) of this clause is not subject to appeal.

C3 CLAUSE 952.222-0001 PROHIBITION AGAINST HUMAN TRAFFICKING, INHUMANE LIVING CONDITIONS, AND WITHHOLDING OF EMPLOYEE PASSPORTS (JUL 2010)

- (a) All contractors (“contractors” refers to both prime contractors and all subcontractors at all tiers) are reminded of the prohibition contained in Title 18, United States Code, Section 1592, against knowingly destroying, concealing, removing, confiscating, or possessing any actual or purported passport or other immigration document, or any other actual or purported government identification document, of another person, to prevent or restrict or to attempt to prevent or restrict, without lawful authority, the person’s liberty to move or travel, in order to maintain the labor or services of that person.
- (b) Contractors are also required to comply with the following provisions:
- (1) Contractors shall only hold employee passports and other identification documents discussed above for the shortest period of time reasonable for administrative processing purposes.
 - (2) Contractors shall provide all employees with a signed copy of their employment contract, in English as well as the employee’s native language that defines the terms of their employment/compensation.
 - (3) Contractors shall not utilize unlicensed recruiting firms, or firms that charge illegal recruiting fees.
 - (4) Contractors shall be required to provide adequate living conditions (sanitation, health, safety, living space) for their employees. Fifty square feet is the minimum acceptable square footage of personal living space per employee. Upon contractor’s written request, contracting officers may grant a waiver in writing in cases where the existing square footage is within 20% of the minimum, and the overall conditions are determined by the contracting officer to be acceptable. A copy of the waiver approval shall be maintained at the respective life support area.
 - (5) Contractors shall incorporate checks of life support areas to ensure compliance with the requirements of this Trafficking in Persons Prohibition into their Quality Control program, which will be reviewed within the Government’s Quality Assurance process.
 - (6) Contractors shall comply with International and Host Nation laws regarding transit/exit/entry procedures, and the requirements for visas and work permits.
- (c) Contractors have an affirmative duty to advise the Contracting Officer if they learn of their employees violating the human trafficking and inhumane living conditions provisions contained herein. Contractors are advised that contracting officers and/or their representatives will conduct random checks to ensure contractors and subcontractors at all tiers are adhering to the law on human trafficking, humane living conditions and withholding of passports.
- (d) The contractor agrees to incorporate the substance of this clause, including this paragraph, in all subcontracts under his contract.

C3 CLAUSE 952.223-0001 REPORTING KIDNAPPINGS, SERIOUS INJURIES AND DEATHS

(JUL 2010)

Contractors shall notify the Contracting Officer, as soon as practicable, whenever employee kidnappings, serious injuries or deaths occur.

Report the following information:

Contract Number
Contract Description & Location
Company Name

Reporting party:

Name
 Phone number
 e-mail address

Victim:

Name
 Gender (Male/Female)
 Age
 Nationality
 Country of permanent residence

Incident:

Description
 Location
 Date and time

Other Pertinent Information**C₃ CLAUSE 952.225-0003 FITNESS FOR DUTY AND MEDICAL/DENTAL CARE LIMITATIONS (NOV 2010)**

(a) The contractor shall perform the requirements of this contract notwithstanding the fitness for duty of deployed employees, the provisions for care offered under this section, and redeployment of individuals determined to be unfit. Contractor personnel who deploy for multiple tours, for more than 12 months total must be re-evaluated for fitness to deploy. An examination will remain valid for 15 months from the date of the physical. The contractor bears the responsibility for ensuring all employees are aware of the conditions and medical treatment available at the performance location. The contractor shall include this information and requirement in all subcontracts with performance in the theater of operations.

(b) The contractor shall not deploy an individual with any of the following conditions unless approved by the appropriate CENTCOM Service Component (i.e. ARCEN, AFCEN, etc.) Surgeon: Conditions which prevent the wear of personal protective equipment, including protective mask, ballistic helmet, body armor, and chemical/biological protective garments; conditions which prohibit required theater immunizations or medications; conditions or current medical treatment or medications that contraindicate or preclude the use of chemical and biological protective's and antidotes; diabetes mellitus, Type I or II, on pharmacological therapy; symptomatic coronary artery disease, or with myocardial infarction within one year prior to deployment, or within six months of coronary artery bypass graft, coronary artery angioplasty, or stenting; morbid obesity (BMI \geq 40%); dysrhythmias or arrhythmias, either symptomatic or requiring medical or electrophysiological control; uncontrolled hypertension, current heart failure, or automatic implantable defibrillator; therapeutic anticoagulation; malignancy, newly diagnosed or under current treatment, or recently diagnosed/treated and requiring frequent subspecialist surveillance, examination, and/or laboratory testing; dental or oral conditions requiring or likely to require urgent dental care within six months' time, active orthodontic care, conditions requiring prosthodontic care, conditions with immediate restorative dentistry needs, conditions with a current requirement for oral-maxillofacial surgery;

new onset (< 1 year) seizure disorder, or seizure within one year prior to deployment; history of heat stroke; Meniere's Disease or other vertiginous/motion sickness disorder, unless well controlled on medications available in theater; recurrent syncope, ataxias, new diagnosis (< 1 year) of mood disorder, thought disorder, anxiety, somatoform, or dissociative disorder, or personality disorder with mood or thought manifestations; unrepaired hernia; tracheostomy or aphonia; renalithiasis, current; active tuberculosis; pregnancy; unclosed surgical defect, such as external fixeter placement; requirement for medical devices using AC power; HIV antibody positivity; psychotic and bipolar disorders. (Reference: Mod 10 to USCENTCOM Individual Protection and Individual/Unit Deployment Policy, Tab A: Amplification of the Minimal Standards of Fitness for Deployment to the CENTCOM AOR).

(c) In accordance with military directives (DoDI 3020.41, DoDI 6000.11, CFC FRAGO 09-1038, DoD PGI 225.74), resuscitative care, stabilization, hospitalization at Level III (emergency) military treatment facilities and assistance with patient movement in emergencies where loss of life, limb or eyesight could occur will be provided. Hospitalization will be limited to emergency stabilization and short-term medical treatment with an emphasis on return to duty or placement in the patient movement system. Subject to availability at the time of need, a medical treatment facility may provide reimbursable treatment for emergency medical or dental care such as broken bones, lacerations, broken teeth or lost fillings.

(d) Routine and primary medical care is not authorized. Pharmaceutical services are not authorized for routine or known, routine prescription drug needs of the individual. Routine dental care, examinations and cleanings are not authorized.

(e) Notwithstanding any other provision of the contract, the contractor shall be liable for any and all medically-related services or transportation rendered. To view reimbursement rates that will be charged for services at all DoD deployed medical facilities please go to the following website:
<http://comptroller.defense.gov/rates/fy2010.html> (change fiscal year as applicable).

C3 CLAUSE 952.225 □ 0004 COMPLIANCE WITH LAWS AND REGULATIONS (JUL 2010)

(a) The Contractor shall comply with, and shall ensure that its employees and its subcontractors and their employees, at all tiers, are aware of and obey all U.S. and Host Nation laws, Federal or DoD regulations, and Central Command orders and directives applicable to personnel in Iraq and Afghanistan, including but not limited to USCENTCOM, Multi-National Force and Multi-National Corps operations and fragmentary orders, instructions, policies and directives.

(b) Contractor employees shall particularly note all laws, regulations, policies, and orders restricting authority to carry firearms, rules for the use of force, and prohibiting sexual or aggravated assault. Contractor employees are subject to General Orders Number 1, as modified from time to time, including without limitation, their prohibition on privately owned firearms, alcohol, drugs, war souvenirs, pornography and photographing detainees, human casualties or military security measures.

(c) Contractor employees may be ordered removed from secure military installations or the theater of operations by order of the senior military commander of the battle space for acts that disrupt good order and discipline or violate applicable laws, regulations, orders, instructions, policies, or directives. Contractors shall immediately comply with any such order to remove its contractor employee.

(d) Contractor employees performing in the USCENTCOM Area of Responsibility (AOR) may be subject to the jurisdiction of overlapping criminal codes, including, but not limited to, the Military Extraterritorial Jurisdiction Act (18 U.S.C. Sec. 3261, et al) (MEJA), the Uniform Code of Military Justice (10 U.S.C. Sec. 801, et al)(UCMJ), and the laws of the Host Nation. Non-US citizens may also be subject to the laws of their home country while performing in the USCENTCOM AOR. Contractor employee status in these overlapping criminal jurisdictions may be modified from time to time by the United States, the Host Nation, or by applicable status of forces agreements.

(e) Under MEJA, a person who engages in felony misconduct outside the United States while employed by or accompanying the Armed Forces is subject to arrest, removal and prosecution in United States federal courts. Under the UCMJ, a person serving with or accompanying the Armed Forces in the field during a declared war or contingency operation may be disciplined for a criminal offense, including by referral of charges to a General Court Martial. Contractor employees may be ordered into confinement or placed under conditions that restrict movement within the AOR or administratively attached to a military command pending resolution of a criminal investigation.

(f) Contractors shall immediately notify military law enforcement and the Contracting Officer if they suspect an employee has committed an offense. Contractors shall take any and all reasonable and necessary measures to secure the presence of an employee suspected of a serious felony offense. Contractors shall not knowingly facilitate the departure of an employee suspected of a serious felony offense or violating the Rules for the Use of Force to depart Iraq or Afghanistan without approval from the senior U.S. commander in the country.

C3 CLAUSE 952.225-0005 MONTHLY CONTRACTOR CENSUS REPORTING (JUL 2010)

Contractor shall provide monthly employee census information to the Contracting Officer, by province, for this contract. Information shall be submitted either electronically or by hard-copy. Information shall be current as of the 25th day of each month and received by the Contracting Officer no later than the first day of the following month. The following information shall be provided for each province in which work was performed:

- (1) The total number (prime and subcontractors at all tiers) employees.
- (2) The total number (prime and subcontractors at all tiers) of U.S. citizens.
- (3) The total number (prime and subcontractors at all tiers) of local nationals (LN).
- (4) The total number (prime and subcontractors at all tiers) of third-country nationals (TCN).
- (5) Name of province in which the work was performed.
- (6) The names of all company employees who enter and update employee data in the Synchronized Pre-deployment & Operational Tracker (SPOT) IAW DFARS

C3 CLAUSE 952.225-0009 MEDICAL SCREENING AND VACCINATION REQUIREMENTS FOR LOCALLY HIRED EMPLOYEES (NOV 2010)

(a) Contractors and subcontractors at any tier shall ensure and provide satisfactory evidence that all locally hired employees, including Local National (LN), Third Country National (TCN), and U.S. employees, working on bases have been screened for and do not currently have active tuberculosis (TB).

(1) Contractors may initially utilize a testing method of either a chest x-ray or TB skin test (TST), depending on the originating country of a contracted employee.

(i) Chest x-rays (CXR's), symptom survey, and Body Mass Index (BMI) shall be taken, and TSTs administered within 12 months prior to the start of deployment/employment. Contractors are required to bring in a physical copy of the pre-employment CXR film as it is the only way to verify interval changes should an active case of TB occur.

(A) Third Country Nationals (TCNs) and Local Nationals (LNs) cannot be screened with the TST. They need the pre-employment screening with a quality CXR, BMI and symptom survey.

(B) Small-Risk Nationals (SRNs), those with less than 25 TB cases per 100,000 persons annually (mostly expats from Europe and US), can be screened via the TST.

(ii) Annual re-screening for TCNs, and LNs will be performed with a CXR conducted by the Contractor's medical provider or local economy provider who will look for interval changes from prior CXR's and review any changes in the symptom survey.

(iii) SRN's do not require annual TB re-screening. However, for a TB contact investigation, a TST or Interferon Gamma Release Assay (IGRA) is required.

(iv) For a contact investigation, all personnel with a positive TST or IGRA will be evaluated for potential active TB with a symptom screen, exposure history, BMI, and CXR. All cases of suspected or confirmed active TB must be reported to the theater Preventive Medicine (PM) physician and/or TB Consultant as soon as possible. TB reporting is required within 24 hours to the PM POC. Contact tracing, and medical coding have specific requirements. All Small-Risk National (SRN) contract personnel are required to be MEDEVAC'd out of theater, at the contractor's expense, for treatment of active TB, after consultation with the Theater PM or TB Consultant. For SRN personnel, the contractor is responsible for management and compliance with all prescribed public health actions.

(v) Screening may be performed either by a licensed medical provider from the local economy or by the contractors' licensed medical staffs. Contractors shall maintain medical screening documentation and make it available to the Contracting Officer upon request.

(2) TB screening and documentation is a requirement prior to receiving badges to work in the CENTCOM Area of Operations. A copy of the TB screening documentation shall be provided to the responsible Base Operations Center prior to issuance of base access badges.

(b) Contractor employees, including subcontractors at any tier, who work in food service positions and/or water and ice production facilities, shall have current Typhoid and Hepatitis "A" (full series) immunizations in accordance with the Centers for Disease Control and Prevention guidelines (e.g. typhoid vaccination booster is required every 2 years), in addition to the required TB tests. The contractor medical provider must complete a pre-placement examination to include a stool sample test for ova and parasites, and annual medical screening form or equivalent for food service, ice and water production workers.

(c) Proof of individual employee vaccinations shall be provided to the Contracting Officer and COR showing that their employees and their subcontractor employees at any tier have received the above vaccinations. The contractor shall maintain their employees' vaccination records for examination by the Contracting Officer. The contractor shall ensure that their subcontractors at any tier maintain their respective employees' vaccination records for examination by the Contracting Officer.

(d) The contractor is responsible for management and compliance with all prescribed public health actions regarding TB in the contracted personnel. The contractor also bears the responsibility of ensuring that adequate health management for TB (screening/diagnosis/treatment/isolation) is available at the contractor's chosen health care provider for their contracted and subcontracted personnel.

NOTE: Contractors are reminded of the requirement to comply with their contract and all regulatory guidance (DoD Instructions/Regulations, Federal Acquisition Regulation/Defense Federal Acquisition Regulation Supplement, and FRAGO's) as applicable regarding Medical Screening and Vaccination Requirements.

C3 CLAUSE 952.225-0011 GOVERNMENT FURNISHED CONTRACTOR SUPPORT (JUL 2010)

The following is a summary of the type of support the Government will provide the contractor, on an "as-available" basis. In the event of any discrepancy between this summary and the description of services in the Statement of Work, this clause will take precedence.

U.S. Citizens Accompanying the Force

APO/FPO/MPO/Postal Services

Authorized Weapon

Billeting

CAAF

DFACs

Excess Baggage

Fuel Authorized

Govt Furnished Meals

Mil Issue Equip

MILAIR

MWR

Resuscitative Care

<input checked="" type="checkbox"/> Controlled Access (CAC)/ID Card	<input type="checkbox"/> Military Banking	<input type="checkbox"/> Transportation
<input type="checkbox"/> Commissary	<input type="checkbox"/> Military Clothing	<input type="checkbox"/> All
<input type="checkbox"/> Dependents Authorized	<input type="checkbox"/> Military Exchange	<input type="checkbox"/> None

Third-Country National (TCN) Employees

<input type="checkbox"/> APO/FPO/MPO/Postal Services	<input type="checkbox"/> DFACs	<input type="checkbox"/> Mil Issue Equip
<input type="checkbox"/> Authorized Weapon	<input type="checkbox"/> Excess Baggage	<input type="checkbox"/> MILAIR
<input type="checkbox"/> Billeting	<input type="checkbox"/> Fuel Authorized	<input type="checkbox"/> MWR
<input type="checkbox"/> CAAF	<input type="checkbox"/> Govt Furnished Meals	<input checked="" type="checkbox"/> Resuscitative Care
<input checked="" type="checkbox"/> Controlled Access (CAC)/ID Card	<input type="checkbox"/> Military Banking	<input type="checkbox"/> Transportation
<input type="checkbox"/> Commissary	<input type="checkbox"/> Military Clothing	<input type="checkbox"/> All
<input type="checkbox"/> Dependents Authorized	<input type="checkbox"/> Military Exchange	<input type="checkbox"/> None

Local National (LN) Employees

<input type="checkbox"/> APO/FPO/MPO/Postal Services	<input type="checkbox"/> DFACs	<input type="checkbox"/> Mil Issue Equip
<input type="checkbox"/> Authorized Weapon	<input type="checkbox"/> Excess Baggage	<input type="checkbox"/> MILAIR
<input type="checkbox"/> Billeting	<input type="checkbox"/> Fuel Authorized	<input type="checkbox"/> MWR
<input type="checkbox"/> CAAF	<input type="checkbox"/> Govt Furnished Meals	<input checked="" type="checkbox"/> Resuscitative Care
<input checked="" type="checkbox"/> Controlled Access (CAC)/ID Card	<input type="checkbox"/> Military Banking	<input type="checkbox"/> Transportation
<input type="checkbox"/> Commissary	<input type="checkbox"/> Military Clothing	<input type="checkbox"/> All
<input type="checkbox"/> Dependents Authorized	<input type="checkbox"/> Military Exchange	<input type="checkbox"/> None

C₃ CLAUSE 952.225-0013 CONTRACTOR HEALTH AND SAFETY (NOV 2010)

(a) Contractors shall comply with all National Electrical Code (NEC 2008), Specifications as outlined, and MIL Standards and Regulations. All infrastructure to include, but not limited to, living quarters, showers, and restrooms shall be installed and maintained in compliance with these standards and must be properly supported and staffed to ensure perpetual Code compliance, prevent hazards and to quickly correct any hazards to maximize safety of those who use or work at the infrastructure. The government has the authority to enter and inspect contractor employee living quarters at any time to ensure the prime contractor is complying with safety compliance standards outlined in the 2008 National Electric Code (NEC).

(b) The contractor shall correct all deficiencies within a reasonable amount of time of contractor becoming aware of the deficiency either by notice from the government or a third party, or discovery by the contractor. Further guidance on mandatory compliance with NFPA 70: NEC 2008 can be found on the following link <http://www.nfpa.org>.

C₃ CLAUSE 952.225-0016 CONTRACTOR DEMOBILIZATION (NOV 2010)

(a) Full demobilization of contractors and subcontractor(s) in the Iraq/Afghanistan Combined/Joint Operations Area (CJOA) is critical to Responsible Drawdown. The prime contractor is required to submit a demobilization plan to the Contracting Officer a minimum of 30 days prior to the end of the contract performance period or when requested by the Contracting Officer. The demobilization plan shall address, as a minimum, the following procedures detailed below. The procedures outline specific guidance to ensure a timely and responsible exit from theater. Prime contractors are responsible and accountable to ensure their subcontractor(s) at all tiers comply with responsible and timely exit from theater immediately following contract performance completion or termination.

(1) Exit from Iraq: The prime contractor shall follow the exit guidance issued by the United States (U.S.) Embassy Baghdad and shall ensure subcontractor(s) at all tiers also follow the exit procedures. The prime contractor is responsible to remain cognizant of Iraqi laws regarding exit from Iraq. Currently, all foreigners traveling out of Iraqi airports via commercial air transportation must have exit visas. Department of Defense, U.S. Forces-Iraq, Letters of Authorization (LOAs), and/or Embassy Badges are no longer the accepted means of exiting Iraq. All U.S. citizens and foreign national contractors must obtain an Iraqi exit sticker before departing the country. The exit sticker may be obtained from selected police stations or Ministry of Interior (MOI) offices. It is the prime contractor's responsibility to ensure that the most recent exit procedures are followed and to ensure that subcontractor(s) at all tiers are in compliance with exit procedures. Assistance for this procedure may be obtained by e-mailing baghdadregmgt@state.gov or phone 240-553-0581, ext 2782 or ext 2092.

(2) Letter of Authorization (LOA): The prime contractor is responsible for demobilizing its workforce, including subcontractor employees at all tiers, and all contractor owned and subcontractor owned equipment out of theater as part of the prime contractor's exit strategy. This exit strategy must include reasonable timeframes starting with the end of the contract performance period and not exceeding 30 days. The Contracting Officer has the authority to extend selected LOAs up to, but not exceeding 30 calendar days after the contract completion date to allow the prime contractor to complete demobilization of its workforce and contractor owned equipment, as well as subcontractor(s) workforce and owned equipment, out of the Iraq/Afghanistan CJOA. The prime contractor shall notify the Contracting Officer a minimum of 30 days prior to the end of the contract period to request up to a 30-day extension of selected LOAs beyond the contract completion date to complete demobilization. The request shall include at a minimum:

- (i) the name of each individual requiring a new LOA;
- (ii) the number of days for the LOA (no more than 30 calendar days); and
- (iii) justification for the request (e.g., what function the individual(s) will be performing during the demobilization period).

The Contracting Officer may request additional information for an LOA extension. Any LOA extension granted beyond the contract completion date shall not exceed 30 days and the contractor is not entitled to additional compensation for this period. If approved by the contracting officer, this is a no cost extension of an employee's LOA due to demobilization and in no way is an extension of the contract performance period.

(3) Badging: The prime contractor is responsible to ensure all employee badges, including subcontractor employees at all tiers, are returned to the local Access Control Badging Office for de-activation and destruction. The prime contractor shall submit a Badge Termination Report to ensure each record is flagged and the badge is revoked. If a prime and/or subcontractor employee's badge is not returned, the prime contractor shall submit a Lost, Stolen or Unrecovered Badge Report to the appropriate Access Control Badging Office. Contractor employees in possession of a Common Access Card (CAC) shall be responsible for turning in the CAC upon re-deployment through a CONUS Replacement Center in the U.S. Failure to return employee badges in a timely manner may result in delay of final payment.

(4) Contractor Controlled Facility Space: If the prime contractor has entered into a Memorandum of Understanding with the Installation Mayor or Garrison for site space, buildings, facilities, and/or Containerized Housing Units (CHU) to house prime and/or subcontractor employees (at all tiers), the prime contractor is responsible to notify the Installation Mayor or Garrison Commander of intent to vacate at least 90 calendar days prior to the end of the contract performance period. All United States Government (USG) provided property in the prime contractor's possession must be returned to the USG in satisfactory condition. The prime contractor is responsible and liable for any and all damages to USG property caused by prime and/or subcontractor employees, and shall be further liable for all cleanup, clearing, and/or environmental remediation expenses incurred by the USG in returning prime contractor and/or subcontractor facilities including surrounding site to a satisfactory condition, including expenses incurred in physically moving property, trash, and refuse from such premises, removing/ remediating hazardous wastes on the premises, and repairing structures, buildings, and facilities used by the prime contractor and/or subcontractor. The prime contractor shall provide notification to the Installation Mayor or Garrison Commander to perform an inspection of all facilities as soon as practicable, but no more than 30 days, after the end of the contract

period. If damages are discovered, the prime contractor shall make the necessary repairs. The prime contractor shall notify the Installation Mayor or Garrison Commander for re-inspection of the facilities upon completion of the repairs. If the Installation Mayor or Garrison Commander inspects the property, site space, buildings, facilities, and/or CHUs and finds they have not been properly cleaned, cleared, and/or environmentally remediated, or if the prime contractor fails to repair any damages within 30 calendar days after the end of the contract performance period, the final contract payment shall be reduced by the amount of the specified damages/repairs or the expenses incurred by the USG to properly clean, clear, and/or environmentally remediate the premises.

(5) Government Furnished Equipment/Materials: The prime contractor is responsible to return all USG furnished equipment, as defined in Federal Acquisition Regulation (FAR) Part 45, clauses 52.245-1, 52.245-2, and 52.245-5, if included in the contract. Prime contractors who are not in compliance with the FAR, Defense Federal Acquisition Regulation Supplement, Department of Defense Directives and Instructions, United States Forces-Iraq (USF-I) FRAGOs, United States Forces-Afghanistan (USFOR-A) FRAGOs, policies, or procedures will be responsible and liable for damages to the government property. The prime contractor may apply for a "relief of responsibility" from the Contracting Officer anytime during the contract performance period. A joint inventory shall be conducted of the equipment by the prime contractor, USG representative, and the Contracting Officer or their representative, within 10 calendar days after the end of the contract performance period. The prime contractor shall report lost, damaged or destroyed property immediately to the Contracting Officer, but no later than the joint inventory at the end of the contract period. If the prime contractor fails to report lost, damaged or destroyed equipment or materials during the contract performance period, the prime contractor shall be responsible for the replacement and/or repair of the equipment or materials. The replaced equipment shall be new, of the same quality, and shall perform at the same functional level as the missing piece of equipment. If the prime contractor fails to repair and/or replace damaged or missing equipment, the final payment shall be reduced by the appropriate amount of the specified damages or cost to replace missing equipment with new.

(6) Synchronized Predeployment Operational Tracker (SPOT): The prime contractor is responsible to close out the deployment of personnel, including subcontractor employees at all tiers, at the end of the contract completion period and to release the personnel from the prime contractor's company in the SPOT database. The release of employee information must be accomplished no more than 30 calendar days after the end of the contract completion date.

(7) Accountability of Prime and Subcontractor Personnel: Whether specifically written into the contract or not, it is the expectation of the USG that for any persons brought into the Iraq/Afghanistan CJOA for the sole purposes of performing work on USG contracts, contract employers will return employees to their point of origin/home country once the contract is completed or their employment is terminated for any reason. If the prime contractor fails to re-deploy an employee, or subcontractor employee at any tier, the USG shall notify the applicable U.S. Embassy to take appropriate action. Failure by the prime contractor to re-deploy its personnel, including subcontractor personnel at any tier, at the end of the contract completion date, could result in the contractor being placed on the Excluded Parties List System (EPLS) and not be allowed to propose on future U.S. contracts anywhere in the world.

(b) CENTCOM Contracting Command (C3) and external agencies will utilize all available contracting remedies to guarantee compliance with demobilization requirements. Such actions include, but are not limited to withholding payment, issuing a cure notice, issuing a negative Contractor Performance Assessment Reporting System (CPARS) evaluation, reduction of award fee, debarment, reimbursement of U.S. Government expenses, and/or any other legal remedy available to a contracting officer. The USG reserves the right to **withhold payment** from the prime contractor not in compliance with the above procedures included herein. Additionally, the Contracting Officer shall document all unresolved contractor compliance issues in CPARS, which shall have an adverse past performance affect on future contracts with the USG, anywhere in the world.

C3 CLAUSE 952.236-0001 ELECTRICAL AND STRUCTURAL BUILDING STANDARDS FOR CONSTRUCTION PROJECTS (JUL 2010)

(a) The standards set forth herein are the minimum requirements for the contract. These standards must be followed unless a more stringent standard is specifically included. In such case the most stringent standard shall be required for contract acceptance.

(b) The contractor, in coordination with the Contracting Officer, Base Camp Mayor, Base/Unit Engineers, and requiring activity shall evaluate, upgrade, build, and/or refurbish buildings to a safe and livable condition. This work may include refurbishment, construction, alterations, and upgrades. All work shall be in accordance with accepted standards of quality.

(c) As dictated by the Unified Facilities Criteria (UFC) the contract shall meet:

- (1) "the minimum requirements of United States' National Fire Protection Association (NFPA) 70,
- (2) 2008 National Electrical Code (NEC),
- (3) American National Standards Institute (ANSI) C2, and
- (4) United States' National Electrical Safety Code (NESC).

(d) These standards must be met when it is reasonable to do so with available materials. When conditions dictate deviation, then provisions within the International Electrical Code (IEC) or British Standard (BS 7671) shall be followed. Any deviations from the above necessary to reflect market conditions, shall receive prior written approval from a qualified engineer and the Contracting Officer.

(e) The following internet links provide access to some of these standards:

UFC: http://65.204.17.188/report/doc_ufc.html

NFPA 70: <http://www.nfpa.org>

NESC: <http://www.standards.ieee.org/nesc>

TRAVEL WARNINGS

The contractor shall provide all personnel working under this contract, and shall require subcontractors to provide their personnel, with a written notification advising such personnel to be aware of US State Department Travel Warnings with respect to Afghanistan, available at <http://travel.state.gov>, in the event they wish to consider bringing their dependants into Afghanistan. A copy of the notice *shall be furnished to the contracting officer upon award of the contract*, along with a certification by an authorized company representative attesting to the provision of the notification to contractor personnel. At no time, subject to the written approval of the contracting officer, may the contractor allow such dependants, or any other unauthorized individuals, to be present on the project site grounds, whether in transit or otherwise.

(End of clause)

APPLICATION OF US CRIMINAL JURISDICTION

Reference DODI 5525.11. The contractor is directed to provide all of its personnel working under this contract, and to require all of its subcontractors to provide their personnel, with written notification that - with the exception of nationals of Afghanistan and those ordinarily resident in Afghanistan - contractor and subcontractor personnel, and the dependents of contractor and subcontractor personnel who are residing with such personnel, may be subject to US criminal jurisdiction as provided for in the Military Extraterritorial Jurisdiction Act, 18 USC 3261-3267; see Section 3267(1)(A)(iii)(I) and (2)(A)(iii). A copy of the notice *shall be furnished to the contracting officer upon award of the contract*, along with a certification by an authorized company representative attesting to the provision of the notification to contractor personnel.

(End of clause)

SECTION 00150

THE DESIGN-BUILD PROCESS

1.0 DESIGN-BUILD (DB) PROCESS

The facility shall be designed and built by a single DB Contractor. The DB Contractor may be a single firm or a team of firms that includes registered Architects and Engineers either employed by or subcontracted to the DB Contractor. Licensing jurisdiction of Architects and Engineers of record shall be verifiable. The DB Contractor shall be the Architect/Engineer-of-Record, whether the DB Contractor utilizes services of licensed architects and engineers employed by its firm or subcontracts with independent architectural and/or engineering firm(s). The DB Contractor shall be solely liable for design errors and/or omissions and should be insured as the A-E firm against design errors and omissions. For this specification, the term "Government" is defined as the Contracting Officer for the US Army Corps of Engineers, Afghanistan Engineer District-South (AED-S).

Section 00555, Design Concept Documents, identifies project documents furnished herein to be used as the basis for the project design and construction documents. The successful Offeror shall be required to complete the design and construction documentation, and construct the project in compliance with these completed requirements.

No work can begin on any phase of the process until an authorization Clearance For Construction (CFC) for that phase is issued.

1.1 PROPOSAL PHASE

The Proposal Phase includes the period from the time from the issuance of the Request for Proposals (RFP) through the selection process and the final award of the DB contract.

The proposals to be submitted include a Technical and Performance Capability Proposal and Price Proposal. The contents and organization of the proposal is described in Section 00113. The Government will evaluate and award the DB contract to a single Offeror based upon the criteria which are outlined in Section 00113.

1.2 DESIGN PHASE

The successful DB Contractor shall develop and submit for formal review Design Phase Submittals as indicated below and in the project schedule. The DB Contractor is encouraged to develop and submit multiple cost saving proposals for innovative design alternatives.

1.2.1 SYSTEM ANALYSIS PHASE SUBMITTALS

Systems Analysis Submittal will be the basic services as described in Section 01010 which represents items necessary for recommendations and costs for the recommendations: Verification of existing systems, pipe sizes, pipe routing, valves, control panels, alarm panels, oxygen storage, system diagrams etc.

1.2.2 DESIGN CONSTRUCTION PHASE SUBMITTALS

Design Construction Submittal shall include, as required, complete design analysis (DA), drawings and specifications for installation of new medical gas and vacuum outlets in the Hospital Patient Wards 129-132. After Government acceptance of the Design Construction Submittal, the Government may issue a CFC letter to commence with the Build Phase.

2.0 BUILD PHASE

The Build Phase shall be initiated by a Clearance For Construction (CFC) letter issued by the Contracting Officer.

A CFC will be provided separately by the Contracting Officer for each phase of the work. The Government may give the DB Contractor authorization for the Build Phase for portions of the work following review and approval of the particular Design Construction Submittal.

Weekly coordination meetings will be held at which, as a minimum, the DB Contractor's Project Manager, a representative of the Designer, the site Superintendent, and the Contractor's Quality Control (CQC) Manager shall be present.

3.0 PROJECT SCHEDULE:

The following is an internal design schedule and is subject to modification by the Offeror to suit their particular method of operation. Overall time constraints are required and cannot be changed except by contract modification. Prospective Offerors shall be required to submit a complete schedule for design and construction that meets or exceeds the overall time goals of the Government for this project.

MILESTONE <i><u>All days are in calendar days.</u></i>	Written Notice to Proceed (NTP) following Contract Award (Day 0)
DESIGN PHASE	
Pre-design Meeting	Within Seven (7) days from NTP.
Completion of Construction Documents and Associated Design Analysis	Within Thirty (30) days following NTP.
Submittal Review Conference	Within Seven (7) days following Submittal Review.
Incorporate Changes to Submittal and Re-Submit for Review & Approval	Within Seven (7) days following Review Conference.
Construction Document Package Due	Within Forty-five (45) days following NTP.
System Analysis list of Recommendations and Associated Costs	Within Fifty (50) days following NTP.
Construction Documents (CD) Submittal Review Conference	Within Seven (7) days following Design Package Submittal Review.

Incorporate Changes to CD Submittal and Re-Submit for Review & Approval	Within Seven (7) days following Review Conference.
Systems Analysis Submittal Review Conference	Within Seven (7) days following submittal of System Analysis.
Incorporate Changes to System Analysis Due to Review Conference.	Within Seven (7) days following System Analysis Review Conference.
BUILD PHASE	
Clearance For Construction (CFC)	See paragraph, Design Construction Phase Submittals.
Total Design and Construction Period Of For the Scope defined by the Construction Documents Package	Ninety (90) days -performance period includes design and construction phases.

4.0 LIQUIDATED DAMAGES:

Liquidated damages in the amount of **\$620.75** every calendar day of delay shall be assessed and charged to the Contractor.

--END OF SECTION--

SECTION 00555

DESIGN CONCEPT DOCUMENTS

1. GENERAL

This section identifies documents issued with this RFP which establish the concept or basis for the project construction design. These requirements are minimum standards and may be exceeded by the Offeror. Deviations from these concepts and standards may be approved if considered by the Government to be in its best interests.

The extent of development of these requirements in no way relieves the successful Offeror from the responsibility of completing the construction design, construction documentation, and construction of the facility in conformance with applicable criteria and codes.

1.1 ENGINEERING AND DESIGN CRITERIA

General design requirements are set forth in Section 01010.

1.2 APPENDIX DOCUMENTS

See Appendices for further technical requirements, criteria, and parameters that are a part of this contract.

1.3 SPECIFICATIONS

General specification requirements are set forth in Section 01010.

1.4 ORDER OF PRECEDENCE

In case of conflict, duplication, or overlap of design criteria specified in the documents referenced in this section, the following order of precedence shall be followed:

1. Minimum requirements of the RFP.
2. Written requirements supersede drawings.

All other conflicts, duplications, or overlaps shall be referred to the Contracting Officer as a request for information for resolution.

1.5 ADDITIONAL DOCUMENTS/CRITERIA FURNISHED BY THE GOVERNMENT

The following documents will be furnished to the Design-Build Contractor when requested by the Offeror or Contractor:

Design Criteria published by the Government, such as Technical Manuals (TM), Engineer Manuals (EM), Engineer Technical Letters (ETL) and other documents related to the design referenced herein which are not available on the Internet (including the <http://www.wbdg.org/> website), shall be provided by the US Army Corps of Engineers.

The Following Will Not Be Furnished To The Contractor.

Commercial design criteria and specifications will not be furnished by the Government.

Conversion of electronic media to other formats shall be the responsibility of the Design-Build Contractor.

-- END OF SECTION --

SECTION 01040 SECURITY

1.0 SPECIFIC CONTRACT SECURITY ASSESSMENT

The Contractor will construct the Project in an active war zone where International Security Assistance Forces (ISAF) may conduct offensive and defensive operations against a variety of hostile forces, to include members of the Taliban. The Contractor understands that it may not receive any support whatsoever in securing the Project site and in securing the transportation of materials to the Project site. Neither U.S. Government nor other ISAF forces are available to provide exclusive security for the Project. The Contractor is responsible for securing the Project site and in securing the transportation of materials to the Project site. The Contracting Officer possesses no ability to control the operations of either ISAF or hostile forces. The Government, acting in its sovereign capacity in its prosecution of its operations, may take actions which directly or indirectly affect the Contractor. These kinds of acts are general in application, not specifically directed at the Contractor. The Contractor recognizes that such actions may be taken, and that they will not entitle the Contractor to make claims for excusable or compensable delays. The Contractor possesses sufficient information about the specific security situation at the site to enable it to formulate an appropriate security plan. The Contractor understands that the security situation at the Project is subject to significant transformation in a short time span based on the changing operational picture in the region. The Contractor's security plan will take this factor into account.

2.0 GOVERNMENT PREREQUISITES TO CONTRACTOR DEPLOYMENT OF SITE SECURITY PERSONNEL

The following regulations and policies apply to Contractor-Provided Site Security Personnel:

- a. DODI 3020.41; **Contractor Personnel Authorized to Accompany the U.S. Armed Forces**; 3 OCT 2005 (available at www.dtic.mil/whs/directives/corres/pdf/302041p.pdf).
- b. DODI 3020.50; **Private Security Contractors (PSCs) Operating in Contingency Operations**; 22 JUL 2009 (available at www.dtic.mil/whs/directives/corres/pdf/302050p.pdf).
- c. USCENTCOM Contracting Command, **Acquisition Instruction**; 5 NOV 2010 (available at <http://c3-training.net/policy.html>).
- d. DFARS Subpart 225.74, Defense Contractors Outside the United States.

The Contractor understands its responsibilities under these regulations, policies, and standard contract clauses, as well as its responsibilities under Afghan law, with regard to its contracts for and employment of security personnel. The Contractor is not authorized to deploy any site security personnel until it complies with all prerequisites identified in these references. The Contractor acknowledges that its repeated failure to comply with these regulations, policies, and standard contract clauses constitute grounds for the Government to terminate the Contractor for default.

3.0 GOVERNMENT REPRESENTATIVES

During the Project, USACE may disseminate essential security information to the Contractor and will attempt to assist with any Contractor's questions and concerns. The USACE Area Office OIC/NCOIC will serve as the Area Office Security Officer and the Resident Office OIC/NCOIC will serve as the Resident Office Security Officer (collectively "the Security Officers").

4.0 SECURITY COORDINATION

Contractor will be required to coordinate construction site security with any Afghan or Coalition Forces and Local Governments that are available, if any, to assist the Contractor on a case-by-case basis. Coordination does **not** include nor imply making any unauthorized or illegal payments to the local

ANA/ANP or Local/Provincial Government Officials for permission or protection to construct the project. The Contractor will immediately inform the Government if asked to make any such payments, and the Government will provide further direction to the Contractor. Corruption will not be tolerated at any level, under any circumstances. Conducting business in this manner will be grounds for termination of the contract.

5.0 SECURITY PLAN

The Security Officers will review and approve all current and future Contractor security plans prior to submittal approval by the authorized representative of the Contracting Officer. The Security Officers shall ensure that all Contractor security plans are in accordance with the Contract requirements. The security plans shall address movement of Contractor labor, material, and equipment. The Security Officers will lead the quality assurance program to ensure Contractors are executing their approved security plans. The Government will not allow the Contractor to start work on the Project site without an approved security plan.

5.1 SECURITY RATING

Each contract or task order will be assigned a rating by the Area Office Security Officer. This rating will determine the level of approval for the security plan. Assistance from the District's J2/J3 may be required to assess the rating. Ratings and approval levels are below:

- a. Extremely High Risk: District Commander
- b. High Risk: Deputy CDR, Chief of E&C, Area OIC, J2 OIC, or J3 OIC
- c. Moderate Risk: Chief of Construction, Area OIC/NCOIC, or Area Engineer
- d. Low Risk: Resident OIC/NCIOC, Resident Engineer

The rating assigned is in no way an indication that the security situation at the site will remain at a constant level throughout the Project.

5.2 SITE SECURITY FOR PROJECTS OUTSIDE OF ACTIVE COALITION FORCE BASES

The Contractor shall develop a site security plan and program to provide 24 hr/7 days a week security for the Project throughout its performance. The security plan must consider all construction-related sites; batch plants, material sources, stockpiles, worker camps and any other location where there is a major construction effort. The plan must also address security as it relates to the transportation of materials, equipment, personnel, and other items and individuals to the site. The Contractor is expected to perform all required actions to protect the construction site compound from theft and vandalism and personnel from physical harm. These measures are strictly for the protection and defense of the on-site people and property; Contractors are not authorized to conduct any type of offensive operations. For security of road construction, transportation of supplies, and equipment convoys, see the appropriate section below.

5.3 ESTIMATED THREAT ASSESSMENT

The Contractor is expected to develop a site security plan to cover a range of security operations from low to high threat. Included in this security plan will be the capability for a surge of manpower and equipment required during high threat conditions. The Contractor is expected to notify all on-site personnel of increased threats and protective action to take.

5.4 ADDITIONAL CIVILIAN ARMING REQUIREMENTS

The Contractor must include in its security plan, and must continue to maintain throughout the Project, current information on the following items for all its armed civilian personnel: MOI license number, AISA license, armed Contractor & subcontractor company names, contract number/title, contracting agency (USACE-AES), type of work, number/type of weapons authorized, POC for company with contact details, Government Contracting Officer and COR with contact details, number of security personnel by type (U.S., Afghan, Other), company's country of registration/origin, names, photos, and tazkira numbers of security personnel as well as those personnel with access to weapons/ammo and those persons who will

be handling or transporting explosives. In addition the Contractor will immediately update any change to the coordinates of the Contractor's base camps, quarries, and current work locations. The Contractor shall submit, prior to the commencement of construction, a plan for security protection, with a list of the chain of command. Perimeter security shall prevent unauthorized site access and provide safety protection to the Contractor workforce and government personnel for the duration of the project.

6.0 SECURITY PLAN SUBMITTAL REQUIREMENTS

Contractors will submit all security plans in accordance with contract Section 01335 – Submittal Procedures for Projects.

7.0 COMMUNICATION

The Contractor will operate a 24/7 security operations center with communication capability to each guard on duty and the ability to notify all on-site personnel of increased threats and protective actions to take. The operations center will also have 24/7 communication with the local Coalition, ANA, or ANP security forces. The Contractor shall have communication with the Resident Office Security Officer at all times for rapid emergency response; the Resident Office Security Officer will give the Contractor the District J2/J3 contact information. Communication can be via cell phone, email, satellite phones, VHF, HF, CODAN, text, or other communication technologies compatible with the Government's capabilities. The Contractor will provide the Government with their contact information (names, numbers, frequencies, email addresses, transponder IDs, etc.) for the site encompassing all available communication means.

8.0 CONTRACTOR PROVIDED EQUIPMENT

The Contractor will provide the operational security equipment including but not limited to weapons, radios, uniforms, vehicles, vehicle fuel, phones, and other equipment as proposed by the Contractor to provide complete site security.

9.0 KEY CONTROL

The Contractor shall establish and implement methods in writing to ensure that all keys issued by the Contractor are not lost or misplaced and are not used by unauthorized persons. The Contractor shall develop procedures covering key control that will be included in their quality control system (See Section 01451). The project managers will keep a master log of all keys and provide a copy to the contracting officer's representative (COR) for verification. If a key is lost or stolen, the Contractor shall pay to have all impacted locks changed/rekeyed immediately.

10.0 CRITICAL INFORMATION TO REPORT

The Government is responsible for the management and oversight of DOD Contracted AC/PSCs delivering services throughout Afghanistan. Given the impact of either Contractor misbehavior or catastrophic attacks against Contractors, it is critical that information regarding AC/PSC incidents is communicated quickly and accurately to the Government for purposes of management, fact-finding, and mitigation where necessary. The Government must receive the information addressed below. The Contractor will report any of these information requirements immediately to the Resident Office Security Officer:

- a. AC/PSC Escalation of Force to include the use of weapons resulting in the death or injury of an Afghan citizen, coalition, or U.S. service member, other government official, or Contractor
- b. AC/PSC accidents, traffic, or otherwise, resulting in the death or injury of an Afghan citizen, coalition, or U.S. service member, governmental official, or Contractor.
- c. Attacks against AC/PSC activities by Anti-Afghan Forces resulting in the death or injury of an Afghan citizen, coalition or US service member, governmental official, or Contractor.
- d. Reports of "lost convoys." These are AC/PSC escort or independent activities which have lost contact with their companies.
- e. AC/PSC Escalation of Force, accidents, or other activities that result in significant damage to Afghan or USG vehicles, materials or facilities.
- f. Anti-Afghan Force actions including small arms fires (SAF), RPG fire, indirect fire (IDF), improvised explosive devices (IEDs), and/or complex attacks against AC/PSC activities.

- g. Contractor accidental or negligent discharge of a weapon.

SECTION 01060
SPECIAL CLAUSES

1. GENERAL

1.1 PRECONSTRUCTION CONFERENCE

1.1.1 SCHEDULE OF MEETING

At the earliest practicable time, prior to commencement of the work, the Contractor and any Subcontractors whose presence is necessary or requested, shall meet in conference with representatives of the Contracting Officer to discuss and develop a mutual understanding relative to the details of the administration and execution of this contract. This will include but not necessarily be limited to the Contractor's Quality Control (CQC) Program, the Contractors Accident Prevention Program, submittals, correspondence, schedule, access to the work site, security requirements, interface requirements, temporary facilities and services, hazards and risks, working after normal hours or on weekends or holidays, assignment of inspectors, representations, special requirements, phasing, and other aspects of this project that warrant clarification and understanding.

1.1.2 MEETING MINUTES

It shall be the responsibility of the Contractors CQC System Manager to prepare detailed minutes of this meeting and submit those minutes to the Contracting Officer for approval within three (3) workdays. Any corrections deemed necessary by the Contracting Officer shall be incorporated and resubmitted within two (2) calendar days after receipt. Upon approval of the minutes by the Contracting Officer, the Contractor shall distribute the minutes to all parties present or concerned.

1.2 AREA USE PLAN

The Contractor shall submit to the Contracting Officer, within 10 calendar days after award of this contract, an Area Use Plan designating intended use of all areas within the project boundaries. This plan shall include, but not necessarily be limited to the following:

1. Proposed location and dimensions of any area to be fenced and used by the Contractor.
2. Avenues of ingress and egress to the fenced areas and details of the fence installation.
3. Proposed location, dimensions, and number of any trailers and facilities to be used.
4. Drawings showing temporary electrical, water, and sewage disposal installations.
5. Drawings showing temporary material storage and hazardous storage areas.

The plan shall also include a narrative description of the building structural system, the site utility system and the office or administration facilities. The Contractor shall also indicate if the use of a supplemental or other staging area is desired. **The Contractor shall not begin construction of the mobilization facilities prior to approval by the Contracting Officer of the Area Use Plan described herein.**

1.3 CONTRACTOR'S MOBILIZATION AREA

The Contractor will be permitted to use an area approved by the Contracting Officer within the contract limits for operation of his construction equipment, shops, warehouses, and offices. Utilities will be provided for the Contractor as described below. The Contractor is responsible for obtaining any required additional mobilization area above that designated. The construction site shall be cleared of construction debris and other materials and the area restored to its final grade.

1.3.1 CONTRACTOR'S TEMPORARY FACILITIES

1.3.1.1 GENERAL

All facilities within the Contractor's mobilization area shall be of substantial construction suitable for the local weather conditions. Sanitary facilities shall meet the requirements of Corps of Engineers, Safety and Health Requirements Manual EM 385-1-1. Local nationals will not be granted any privileges under this contract. Government provided services are for American and Foreign national Contractors only.

1.3.1.2 ADMINISTRATIVE FIELD OFFICES

The Contractor may provide and maintain administrative field office facilities within the mobilization area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

1.3.1.3 STORAGE AREA

The Contractor shall construct a temporary 1.8 m (6 ft) high chain link fence around trailers and materials. The fence shall include plastic strip inserts, colored green or brown, so that visibility through the fence is obstructed. Fence posts may be driven, in lieu of concrete bases, where soil conditions permit. Trailers, materials, or equipment shall not be placed or stored outside the fenced area unless approved in writing by the Contracting Officer.

1.3.1.4 APPEARANCE OF MOBILIZATION SITE FACILITIES AND/OR TRAILERS

Mobilization Site Facilities and/or Trailers utilized by the Contractor for administrative or material storage purposes shall present a clean and neat exterior appearance and shall be in a state of good repair. Trailers or other transportable structures which, in the opinion of the Contracting Officer, require exterior painting or maintenance will not be allowed on the construction site until such work or maintenance has been performed to the satisfaction of the Contracting Officer.

1.3.1.5 SECURITY PROVISIONS

Adequate outside security lighting shall be provided at the Contractor's temporary facilities. The Contractor shall be responsible for the security of its own facilities and equipment in accordance with Contract Section 01040.

1.3.1.6 SANITATION

- a. Sanitary Facilities: The Contractor shall be responsible for maintaining such facilities at no expense to the Government.
- b. Trash Disposal: The Contractor shall be responsible for collection and disposal of trash from the work areas and from the mobilization area. General construction debris and demolition debris shall be collected and transported by the Contractor to a location designated by the Government. Construction debris, waste materials, packaging material and the like shall be removed from the work site daily. Loose debris capable of being windblown, shall be immediately placed in sealed or covered containers to prevent it from being blown onto taxiways or runways. Any dirt or soil that is tracked onto paved or surfaced roadways shall be cleaned daily. Materials resulting from demolition activities that are salvageable shall be stored within the fenced area described above. Stored material not indoors, whether new or salvaged, shall be neatly stacked when stored.

1.3.1.7 TELEPHONE

The Contractor shall make arrangements to install and pay all costs for telephone facilities desired.

1.3.1.8 RESTORATION OF STORAGE AREA

Upon completion of the project and after removal of mobilization facilities, trailers, materials, and equipment from within the fenced area, the fence shall be removed and will become the property of the Contractor. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition. Gravel used to traverse unpaved areas shall be removed and all such areas restored to their original conditions.

1.3.1.9 EMPLOYEE PARKING

The Contractor is responsible for transporting workers (local nationals) from off post to the worksite, coordinating security identification screening, and cooperating in gate searches with the base authorities.

1.3.2 TEMPORARY PROJECT SAFETY FENCING AND BARRICADES

The Contractor shall impose all measures necessary to limit public access to hazardous areas and to ensure the restriction of workers to the immediate area of the construction and mobilization site. The Contracting Officer may require in writing that the Contractor remove from the work area any employee found to be in violation of this requirement.

1.4 RESPONSIBILITY FOR PHYSICAL SECURITY

Prior to mobilization, the Contractor shall submit his proposed means of providing project security to meet the requirements of Contract Section 01040 and prevent unauthorized access to equipment, facilities, materials and documents, and to safeguard them against sabotage, damage, and theft. The Contractor shall be responsible for physical security of all materials, supplies, and equipment of every description, including property which may be Government-furnished or owned, for all areas occupied jointly by the Contractor and the Government, as well as for all work performed.

1.5 OUTAGES & CONNECTIONS TO EXISTING SERVICES

To minimize temporary outage impacts to the mission of the installation, all outages shall be scheduled as directed by Contracting Officer Representative (COR). The period proposed for performance of the outage shall include sufficient contingencies to preclude impact to the peak working hours 0530 – 1800 hours during the workweek.

1.5.1 GENERAL

Any outage involving disruption of medical gas service beyond the site area shall be requested in writing at least 10 days in advance of the date requested for the commencement of the outage. The Contractor shall provide a request, detailing the type of outage needed (water, sewer, electrical, steam, etc.), the time needed to perform the work, the reason for the outage, and the known affected facilities. The Contracting Officer shall be contacted prior to the outage to confirm the time and date. If the Contractor fails to initiate work at the approved time, the Contracting Officer may cancel the approved outage and may direct the Contractor to resubmit a new request. No part of the time lost due to the Contractor's failure to properly schedule an outage shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

1.6 ELECTRICITY (GOVERNMENT PROVIDED)

Electrical service is to be provided by the Government within this contract since electrical power connection shall be to existing nearby Government owned electrical power system. However, the Contractor may be required to provide temporary construction power until permanent power system is connected. The means of doing so, such as by temporary distribution systems, shall be the responsibility

of the Contractor. All temporary connections for electricity shall be subject to the approval of the Contracting Officer and shall comply with Corps of Engineers manual EM 385-1-1 entitled Safety and Health Requirements Manual. All temporary lines shall be furnished, installed, connected and maintained by the Contractor in a workmanlike manner satisfactory to the Contracting Officer. Before final acceptance of systems, or facilities, all temporary connections installed by the Contractor shall be removed at his expense in a manner satisfactory to the Contracting Officer.

1.7 WORK OUTSIDE REGULAR HOURS

If the Contractor desires to carry on work outside regular base duty hours, or on holidays, including the following U.S. holidays: New Year's Day, Martin Luther King Jr Birthday, President's Day, Memorial Day, Independence Day, Labor Day, Columbus Day, Veteran's Day, Thanksgiving and Christmas. the Contractor shall submit an application to the Contracting Officer. Due to reliance upon local national laborers and time off due to local observances, there may be disruptions. Potentials dates are the following local observances: National Islamic Holiday of Ashura, Ramadan (actual date varies – check with local authorities). The Contractor shall allow ample time to enable satisfactory arrangements to be made by the Government for inspecting the work in progress. At night, exterior lighting shall be provided in conformance with EM-385-1-1 entitled "Safety and Health Requirements Manual".

1.8 SCHEDULING OF WORK IN EXISTING FACILITIES

As soon as practicable, but in any event not later than 30 calendar days after award of this contract, the Contractor shall meet in conference with the Contracting Officer, or his duly authorized representatives, to discuss and develop mutual understanding relative to the scheduling of work in and access to the existing facilities where work has to be performed under this contract, so that the Contractor's proposed construction schedule is coordinated with the operating and security requirements of the installation.

1.9 CERTIFICATES OF COMPLIANCE

Any certificates required for demonstrating proof of compliance of materials with specification requirements shall be executed in accordance with Section 01335, Submittal Procedures For Design-Build. Each certificate shall be signed by an official authorized to certify in behalf of the manufacturing company involved and shall contain the name and address of the Contractor, the project name and location, description and the quantity of the items involved, and date or dates of shipment or delivery to which the certificates apply. Copies of laboratory test reports submitted with certificates shall contain the name and address of the testing laboratory and the date or dates of the tests to which the report applies. Certification shall not be construed as relieving the Contractor from furnishing satisfactory material.

1.10 ACCIDENT PREVENTION

The Contractor shall comply with all applicable Host Country laws and with such additional measures as the Contracting Officer may find necessary in accordance with Contract Clause 52.236-13 entitled Accident Prevention (Nov 1991)-Alternate 1 (Apr 1984). Applicable provisions of the Corps of Engineers manual entitled Safety and Health Requirements Manual EM 385-1-1 will be applied to all work under this contract. The referenced manual may be obtained from the Contracting Officer at the jobsite or from the Afghanistan Engineer District-South (AED-S), Afghanistan.

1.10.1 GROUND FAULT CIRCUIT INTERRUPTER (GFCI) REQUIREMENT – OVERSEAS CONSTRUCTION

The Corps of Engineers Health and Safety Manual, EM 385-1-1, section 11.D.05.b. states: "The GFCI device shall be calibrated to trip within the threshold values of 5 ma +/- 1 ma as specified in Underwriters Laboratory (UL) Standard 943." A variance from USACE has been granted allowing 10 ma, in lieu of 5 ma, for overseas activities that use 220 Volts (V)/50 hertz (Hz) electrical power.

1.11 HAZARDOUS MATERIALS

Should the Contractor encounter asbestos or other hazardous materials, during the construction period of this contract, he shall immediately stop all work activities in the area where the hazardous material is discovered. The Contractor shall then notify the Contracting Officer; identify the area of danger; and not proceed with work in that area until given approval from the Contracting Officer to continue work activities. Hazardous material is considered to be asbestos, explosive devices, toxic waste, or material hazardous to health and safety. The Contractor shall secure the area from daily traffic until it is safe to resume normal activities.

1.12 SPARE PARTS

1.12.1 GENERAL

The requirements of this clause are in addition to any requirements for the provision of specific spare parts to be provided by the Contractor included in Technical Provisions. The Contractor shall furnish spare parts as directed by the Contracting Officer under the provisions of this clause for all equipment for which O&M data is to be provided under the clause, Operation And Maintenance (O&M) Data, of this contract. The term "spare parts" as used herein shall include spare parts, special tools, and test equipment.

1.12.2 WARRANTY

All spare parts provided by the Contractor under this clause are subject to the general warranty clauses of this contract.

1.13 OPERATION AND MAINTENANCE (O&M) DATA

1.13.1 GENERAL

The requirements contained herein are in addition to all shop drawings submission requirements stated in other sections of the specifications. The Contractor shall include the provisions for all items required under this clause in all purchase orders and sub-contract agreements. Submittals required hereinafter will not relieve the Contractor of any responsibilities under the Warranty of Construction Provisions of this contract or under the various Guarantee Clauses of the Technical Provisions.

1.13.2 SUBMITTALS

The Contractor shall submit all items requiring submission of O&M data under this and other sections of these specifications in accordance with Section 01335, Submittal Procedures For Design-Build, of the specifications.

1.13.3 OPERATION AND MAINTENANCE (O&M) DATA

The Contractor shall furnish operation and maintenance manuals for all facilities constructed under this contract. The manuals shall be loose leaf, indexed and shall consist of manufacturer's brochures, manufacturer's operation and maintenance manuals, service and repair manuals, catalogs, service bulletins, instruction charts, diagrams, other information as necessary to support the operation and maintenance of the end items of equipment, assemblies and systems. Each type of facility (housing, barracks, mosque, etc.) shall be covered by a separate manual (or manuals) consisting of all data pertaining to the equipment and/or systems within that facility. Identical equipment within a single major system shall require only one submittal of data. The Contractor shall furnish all O&M manuals to the Contracting Officer not less than fifteen (15) calendar days prior to contract completion. Required number of submittals (number of sets) shall be as specified in Section 01335, Submittal Procedures For

DesignBuild.

1.13.4 RECOMMENDED SPARE PARTS LIST

The Contractor shall furnish a recommended spare parts list containing equipment manufacturers' recommendations for five (5) years; two (2) years and one (1) year spare parts stock levels in Afghanistan. Current unit price and effective date, lead time, shelf life for each individual part, and total cost of all recommended parts shall be furnished.

1.13.5 SUPPLEMENTAL SUBMITTALS OF DATA

After initial submittal of O&M manuals and until final acceptance of all equipment, the Contractor shall prepare and deliver to the Contracting Officer supplemental technical data as previously described for all changes, modifications, revisions and substitutions to equipment and components. For equipment or systems introduced into the contract under change order, or modified by change order, supplemental data shall be furnished within 45 calendar days after issuance of the change order. The supplemental data furnished shall be properly prepared and identified for insertion into the O&M manuals.

1.13.6 ADDITIONAL SUBMITTALS/RE-SUBMITTALS

The Contracting Officer reserves the right to determine whether the above specified information, as furnished by the Contractor, is adequate and complete and to require such additional submittals by the Contractor as necessary to insure that adequate information has been furnished to provide the satisfactory operation and maintenance of the various items of equipment and to fulfill the intent of the specifications. Additional submittals or resubmittals supplementing incorrect or incomplete data shall be made within 30 calendar days after receiving notice by the Contracting Officer. All costs arising from these resubmissions shall be borne by the Contractor.

1.14 INSTRUCTIONS AND TRAINING FOR OPERATION AND MAINTENANCE

1.14.1 GENERAL

The Contractor shall be responsible for the instruction and training of operating and maintenance personnel as specified below and in the Technical Provisions of the specifications. Unless otherwise indicated in the Technical Provisions, operating and maintenance instructions shall be given for a minimum period as follows:

Title	Duration of Training
Mechanical Systems	10 Days
Electrical Systems	10 Days

1.14.2 OPERATION AND MAINTENANCE TRAINING

The Contractor shall provide competent instructors for training of personnel designated by the Contracting Officer to operate mechanical and electrical building systems and equipment, perform the required preventive maintenance to minimize breakdown, and to perform necessary repairs when malfunction or breakdown of equipment occurs. Such training shall consist of classroom and on-the-equipment training for the period specified, which shall be completed prior to acceptance of a system or equipment, as applicable. The operating and maintenance manual data, as specified to be furnished in these Special Clauses, shall be used as the base material for training.

The instructor(s) shall have no other duties during the period of training. Classroom instruction shall not exceed fifty percent (50%) of the total training time, with the balance devoted to on-the-equipment

demonstration and familiarization. Emphasis will be given to both electrical and mechanical features, in accordance with approved training plans.

1.14.3 ARRANGEMENTS

The training shall be for not less than the periods of time specified, five (5) days per week, and eight (8) hours per day, subject to review and approval by the Contracting Officer.

The Government reserves the right to copy, in any manner, the subject training material, or training sessions given by the Contractor, without additional cost to the Government.

1.15 TIME EXTENSIONS

1.15.1 GENERAL

This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance with the Contract Clause 52.249-10 entitled, Default (Fixed-Price Construction) Apr 1984. The listing below defines the anticipated monthly unusually severe weather for the contract period and is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the geographic location of the project. The schedule of anticipated unusually severe weather will constitute the baseline for determining monthly weather time evaluations. Upon award of this contract and continuing throughout the contract each month, actual unusually severe weather days will be recorded on a calendar day basis (including weekends and holidays) and compared to the monthly anticipated unusually severe weather in the schedule below. The term "actual unusually severe weather days" shall include days actually impacted by unusually severe weather. The Contractor's schedule must reflect the anticipated unusually severe weather days on all weather dependent activities.

Kandahar Province - Kandahar

Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
14	7	4	6	1	0	1	1	0	1	6	12	53

The number of actual unusually severe weather days shall be calculated chronologically from the first to the last day in each month. Unusually severe weather days must prevent work for fifty percent (50%) or more of the Contractor's workday and delay work critical to the timely completion of the project. If the number of actual unusually severe weather days exceeds the number of days anticipated in the paragraph above, the Contracting Officer will determine whether the Contractor is entitled to a time extension. The Contracting Officer will convert any qualifying delays to calendar days and issue a modification in accordance with the Contract Clause 52.249-10 entitled, Default (Fixed-Price Construction) Apr 1984.

1.15.2 OTHER DELAYS

Construction delays due to full or partial base closures due to incidents such as demonstrations, civil unrest and outright attacks will be examined on an individual basis for consideration of time extensions.

1.16 STANDARDIZATION

Where two (2) or more items of the same type or class of product, system or equipment furnished in this project are required, the units shall be products of the same manufacturer and shall be interchangeable when of the same size, capacity, performance characteristics, and rating. The only exception to this requirement is where the items are interchangeable due to conformance with industry standards (valves, fittings, etc.); they need not be by the same manufacturer. This requirement applies to all manufactured items in the project that normally require repair or replacement during the life of the equipment.

1.17 COMPLIANCE WITH HOST COUNTRY RULES AND CUSTOMS

The laws of Host Country may prohibit access to certain areas of the country that are under military control. The Contractor shall furnish the Contracting Officer the names of personnel, type, and amounts of equipment, dates and length of time required at the site, and the purpose of entering the host country. It is understood that areas to which rights of entry are provided by the Host Government are to be used only for work carried out under the contract and no destruction or damages shall be caused, except through normal usage, without concurrence of the Host Government.

1.17.1 CONTRACTOR'S RESPONSIBILITIES

The following items are the sole responsibility of the Contractor to investigate, estimate as to cost, and assume the risk, as normally encountered by Contractors. The Contractor shall be responsible for determining the effect of the following on his own cost of performance of the contract and for including sufficient amount in the contract price:

- a. Official language and type of accounts required to satisfy the officials of the Local Government.
- b. Entry and exit visas, residence permits, and residence laws applicable to aliens. This includes any special requirements of the Host Government, including those required by local Labor Offices, which the Contractor may have to fulfill before an application for a regular block of visas will be accepted.
- c. Passports, health and immunization certificates, and quarantine clearance.
- d. Compliance with local labor and insurance laws, including payment of employer's share of contribution, collecting balance from employee and paying into insurance funds.
- e. Strikes, demonstrations and work stoppage.
- f. Collection through withholding and payment to local Government, of any Host Country income tax on employees subject to tax.
- g. Arranging to perform work in the Host Country, to import personnel, to employ non-indigenous labor, to receive payments and to remove such funds from the country.
- h. Operating under local laws, practices, customs and controls, and with local unions, in connection with hiring and firing, mandatory wage scales, vacation pay, severance pay, overtime, holiday pay, 7th day of rest, legal notice or pay in lieu thereof for dismissal of employees, slowdown and curtailed schedules during religious holidays and ratio of local labor employed in comparison to others.
- i. Possibility of claims in local bureaus, litigation in local courts, or attachment of local bank accounts.
- j. Compliance with workmen's compensation laws and contributions into funds. Provisions of necessary medical service for Contractor employees.
- k. Special license required by the local Government for setting up and operating any manufacturing plant in the Host Country, e.g. concrete batching, precast concrete, concrete blocks, etc.
- l. Sales within the host country of Contractor-owned materials, and equipment.
- m. Special licenses for physicians, mechanics, tradesmen, drivers, etc.
- n. Identification and/or registration with local police of imported personnel.
- o. Stamp tax on documents, payments and payrolls.
- p. Base passes for permanent staff, day laborers, motor vehicles, etc.
- q. Compliance with all customs and import rules, regulations and restrictions, including, but not limited to, local purchase requirements.

1.18 EMPLOYEE ACCESS TO PROJECT SITE

1.18.1 EMPLOYEE IDENTIFICATION

The Contractor shall be responsible for furnishing to each employee and for requiring each employee engaged on the work, to display identification as approved and directed by the Contracting Officer. Prescribed identification shall immediately be delivered to the Contracting Officer for cancellation upon release of any employee. When required, the Contractor shall obtain and provide fingerprints of persons employed on the project. Contractor and subcontractor personnel shall wear identifying markings on hard hats clearly identifying the company for whom the employee works.

1.18.1.1 PREPARATION OF IDENTIFICATION BADGES

The Contractor shall be required to prepare a written application inclusive color photographs and provide all materials and labor necessary to prepare an identification badge, laminated in plastic, containing the employee's name, badge number, color photo, height and weight, the name of the Contractor's organization and for requiring each employee engaged on the work to display this identification as directed by the Contracting Officer. The Contractor shall submit each application and draft badge through the Contracting Officer to the Base Security Office. A minimum of thirty-five workdays shall be allowed for Government review and certification of badges. The Base Security Office will certify each draft badge by signature, stamp, seal or any combination thereof. Upon certification by the Base Security Office, the badges will be returned to the Contractor for final preparation, lamination, and issuance. Badges shall not be taken out of country during periods of travel or absence. During such periods, the Contractor may be permitted to issue temporary identification badges.

1.18.1.2 EMPLOYEE BACKGROUND AND HISTORICAL INFORMATION

The Contractor shall be required to prepare and maintain personal background and historical information forms on each employee. These forms may be reviewed by the Base Security Office. The required information shall include but not necessarily be limited to the following:

- a. Full name.
- b. Place and date of birth.
- c. Three (3) current color photographs.
- d. Copy of Citizenship/Nationality identification.
- e. Copy of Passport.
- f. Copy of drivers license.
- g. Police Background Check.
- h. Work History.
- i. Personal background information.
- j. Copy of Work Permit and/or Visa.
- k. Permanent home of record and in-country address.
- l. Other information mandated by local law, the Base Security Regulations or that may be required to coordinate and process the necessary documentation with the government offices responsible for the approval.
- m. Registration, insurance company, policy number and expiration date for each vehicle.

1.18.2 IDENTIFICATION OF CONTRACTOR VEHICLES

The Contractor shall be responsible for requiring each vehicle engaged in the work to display permanent vehicular identification as approved and directed by the Contracting Officer. If acceptable to the Base Security Office and approved by the Contracting Officer, the Contractor may institute a system of non-permanent temporary identification for one-time delivery and transit vehicles. Each Contractor vehicle, machine, piece of equipment, or towed trailers, shall show the Contractor's name such that it is clearly visible on both front doors of the vehicle and both sides of a towed trailer. A valid license plate shall be

displayed at all times. Contractor vehicles operated on Government property shall be maintained in a good state of repair, shall be insured, and shall be registered in accordance with Afghan Law.

1.18.3 SECURITY PLAN

The Contractor shall submit to the Contracting Officer a security plan as required in Contract Section 01040.

1.19 RADIO TRANSMITTER RESTRICTIONS

To preclude accidental actuation of sensitive electronic equipment, the Contractor shall not use radio-transmitting equipment without prior approval of the Contracting Officer.

1.20 PUBLIC RELEASE OF INFORMATION

1.20.1 PROHIBITION

There shall be no public release of information or photographs concerning any aspect of the materials or services relating to this bid, contract, purchase order, or other documents resulting therefrom without the prior written approval of the Contracting Officer.

1.20.2 SUBCONTRACT AND PURCHASE ORDERS

The Contractor agrees to insert the substance of this clause in all purchase orders and subcontract agreements issued under this contract.

2. LOCAL CLAUSES

2.1 APPLICATION OF US CRIMINAL JURISDICTION

Reference DODI 5525.11. The Contractor is directed to provide all of its personnel working under this contract, and to require all of its subcontractors to provide their personnel, with written notification that - with the exception of nationals of Afghanistan and those ordinarily resident in Afghanistan - Contractor and subcontractor personnel, and the dependents of Contractor and subcontractor personnel who are residing with such personnel, may be subject to US criminal jurisdiction as provided for in the Military Extraterritorial Jurisdiction Act, 18 USC 3261-3267; see Section 3267(1)(A)(iii)(I) and (2)(A)(iii). A copy of the notice ***shall be furnished to the contracting officer upon award of the contract***, along with a certification by an authorized company representative attesting to the provision of the notification to contractor personnel.

2.2 ATTACKS FROM HOSTILE ENTITIES

This contract is firm fixed-price. Costs incurred in the performance of project execution that arise from the attacks of hostile entities, such as costs arising from damage to or destruction of Contractor equipment and facilities, and damage to or destruction of the project prior to Government acceptance, are the sole responsibility of the Contractor. The Government makes no guarantee to provide the Contractor with security, and bears no obligation to reimburse the Contractor for costs arising from the attacks of hostile entities. When appropriate, the Contracting Officer may provide the Contractor with an equitable adjustment with respect to time – but not cost – in accordance with clause 52.249-10; see 52.249-10(b)(1)(i) and (2).

2.3 INSTALLATION ACCESS AND BADGING

This contract is firm fixed-price. It is the responsibility of the Contractor to be knowledgeable of and to abide by any and all applicable installation access procedures and requirements, to include any and all badging procedures and requirements, which may be necessary for Contractor access to the project site. Such procedures and requirements may change over the course of contract performance; it is the responsibility of the Contractor to plan accordingly in order to meet its existing obligations under this contract. The US Army Corps of Engineers, Afghanistan Engineer District-South (AED-S), neither controls nor is responsible for any such installation access procedures, requirements or changes thereto.

2.4 CUSTOMS CLEARANCE

Reference clauses 52.229-6 and 52.225-13. This contract is firm fixed-price. It is the responsibility of the Contractor to be knowledgeable of and to abide by any and all applicable customs clearance procedures and requirements that may be necessary for the transportation of supplies and equipment into Afghanistan. Such procedures and requirements may change over the course of contract performance; it is the responsibility of the Contractor to plan accordingly in order to meet its existing obligations under this contract. The US Army Corps of Engineers, Afghanistan Engineer District-South (AED-S), neither controls nor is responsible for any such customs clearance procedures, requirements or changes thereto.

2.5 TRAVEL WARNINGS

The Contractor shall provide all personnel working under this contract, and shall require subcontractors to provide their personnel, with a written notification advising such personnel to be aware of US State Department Travel Warnings with respect to Afghanistan, available at <http://travel.state.gov>, in the event they wish to consider bringing their dependants into Afghanistan. A copy of the notice **shall be furnished to the contracting officer upon award of the contract**, along with a certification by an authorized company representative attesting to the provision of the notification to Contractor personnel. At no time, subject to the written approval of the contracting officer, may the Contractor allow such dependants, or any other unauthorized individuals, to be present on the project site grounds, whether in transit or otherwise.

-- END OF SECTION --

SECTION 01312

QUALITY CONTROL SYSTEM (QCS)

1. GENERAL

The Government will use the Resident Management System for Windows (RMS) to assist in its monitoring and administration of this contract. The Contractor shall use the Government-furnished Construction Contractor Module of RMS, referred to as QCS, to record, maintain, and submit various information throughout the contract period. The Contractor module, user manuals, updates, and training information can be downloaded from the RMS web site: the Contractor can obtain the current address from the Government. This joint Government-Contractor use of RMS and QCS will facilitate electronic exchange of information and overall management of the contract. QCS provides the means for the Contractor to input, track, and electronically share information with the Government in the following areas:

Administration	Submittal Monitoring
Finances	Scheduling
Quality Control	Import/Export of Data

1.1.1 CORRESPONDENCE AND ELECTRONIC COMMUNICATIONS

For ease and speed of communications, both Government and Contractor will, to the maximum extent feasible, exchange correspondence and other documents in electronic format. Correspondence, pay requests and other documents comprising the official contract record shall also be provided in paper format, with signatures and dates where necessary. Paper documents will govern, in the event of discrepancy with the electronic version.

1.1.2 OTHER FACTORS

Particular attention is directed to specifications "Submittal Procedures", "Contractor Quality Control", "Project Schedule", and Contract Clause, "Payments", which have a direct relationship to the reporting to be accomplished through QCS. Also, there is no separate payment for establishing and maintaining the QCS database; all costs associated therewith shall be included in the contract pricing for the work.

1.2 QCS SOFTWARE

QCS is a Windows-based program that can be run on a stand-alone personal computer or on a network. Prior to the Pre-Construction Conference, the Contractor shall be responsible to download, install and use the latest version of the QCS software from the Government's RMS Internet Website. Any program updates of QCS will be made available to the Contractor via the Government RMS Website as they become available. It shall be the responsibility of the contractor to maintain the QCS software and install updates as they become available.

1.3 SYSTEM REQUIREMENTS

The following listed hardware and software is the minimum system configuration that the Contractor shall have to run QCS. No separate payment shall be made for updating or maintaining the necessary hardware configurations necessary to run QCS:

Hardware:

IBM-compatible PC with 1000 MHz Pentium or higher processor

256+ MB RAM for workstation / 512+ MB RAM for server
1 GB hard drive disk space for sole use by the QCS system
Digital Video Disk (DVD)-Compact Disk (CD) Reader-Writer (RW/ROM)
Monitor with a resolution of AT LEAST 1024x768, 16bit colors
Mouse or other pointing device
Windows compatible printer. (Laser printer must have 4 MB+ of RAM)
Connection to the Internet, minimum 56k BPS

Software:

MS Windows 2000 or higher
QAS-Word Processing software: MS Word 2000 or newer
Internet browser supporting HTML 4.0 or higher
Electronic mail (E-mail) MAPI compatible
Virus protection software regularly upgraded with all issued manufacturer's updates

1.4 RELATED INFORMATION

1.4.1 QCS USER GUIDE

After contract award, the Contractor shall download instructions for the installation and use of QCS from the Government RMS Internet Website; the Contractor can obtain the current address from the Government. In case of justifiable difficulties, the Government will provide the Contractor with a CD-ROM containing these instructions.

1.4.2 CONTRACTOR QUALITY CONTROL (CQC) TRAINING

The use of QCS will be discussed with the Contractor's QC System Manager during the mandatory CQC Training class. The government will provide QCS training if requested by the contractor.

1.5 CONTRACT DATABASE

Prior to the pre-construction conference, the Government shall provide the Contractor with basic contract award data to use for QCS. The Government will provide data updates to the Contractor as needed, generally by files attached to E-mail or via CD-ROM. These updates will generally consist of submittal reviews, correspondence status, QA comments, and other administrative and QA data.

1.6 DATABASE MAINTENANCE

The Contractor shall establish, maintain, and update data for the contract in the QCS database throughout the duration of the contract. Data updates to the Government shall be submitted via either E-mail or electronic media with printed/file attachments, e.g., daily reports, schedule updates, payment requests. If permitted by the Contracting Officer. The QCS database typically shall include current data on the following items:

1.6.1 ADMINISTRATION

1.6.1.1 CONTRACTOR INFORMATION

The database shall contain the Contractor's name, address, telephone numbers, management staff, and other required items. Within 14 calendar days of receipt of QCS software from the Government, the Contractor shall deliver Contractor administrative data in electronic format via E-mail.

1.6.1.2 SUBCONTRACTOR INFORMATION

The database shall contain the name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor must be listed separately for each trade to be performed. Each subcontractor/trade shall be assigned a unique Responsibility Code, provided in QCS. Within 14 calendar days of receipt of QCS software from the Government, the Contractor shall deliver subcontractor administrative data in electronic format via E-mail.

1.6.1.3 CORRESPONDENCE

All Contractor correspondence to the Government shall be identified with a serial number. Correspondence initiated by the Contractor's site office shall be prefixed with "S". Letters initiated by the Contractor's home (main) office shall be prefixed with "H". Letters shall be numbered starting from 0001. (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C".

1.6.1.4 EQUIPMENT

The Contractor's QCS database shall contain a current list of equipment planned for use or being used on the jobsite, including the most recent and planned equipment inspection dates.

1.6.1.5 MANAGEMENT REPORTING

QCS includes a number of reports that Contractor management can use to track the status of the project. The value of these reports is reflective of the quality of the data input, and is maintained in the various sections of QCS. Among these reports are: Progress Payment Request worksheet, QA/QC comments, Submittal Register Status, Three-Phase Inspection checklists.

1.6.2 FINANCES

1.6.2.1 PAY ACTIVITY DATA

The QCS database shall include a list of pay activities that the Contractor shall develop in conjunction with the construction schedule. The sum of all pay activities shall be equal to the total contract amount, including modifications. Pay activities shall be grouped by Contract Line Item Number (CLIN), and the sum of the activities shall equal the amount of each CLIN. The total of all CLINs equals the Contract Amount.

1.6.2.2 PAYMENT REQUESTS

All progress payment requests shall be prepared using QCS. The Contractor shall complete the payment request worksheet and include it with the payment request. The work completed under the contract, measured as percent or as specific quantities, shall be updated at least monthly. After the update, the Contractor shall generate a payment request report using QCS. A signed paper copy of the approved payment request is also required, which shall govern in the event of discrepancy with the electronic version.

1.6.3 QUALITY CONTROL (QC)

QCS provides a means to track implementation of the 3-phase QC Control System, prepare daily reports, identify and track deficiencies, document progress of work, and support other contractor QC requirements. The Contractor shall maintain this data on a daily basis. Entered data will automatically output to the QCS generated daily report.

1.6.3.1 DAILY CONTRACTOR QUALITY CONTROL (CQC) REPORTS

QCS includes the means to produce the Daily CQC Report. The Daily CQC Report generated by QCS shall be the Contractor's official report. Data from any supplemental reports by the Contractor shall be summarized and consolidated onto the QCS-generated Daily CQC Report. Daily CQC Reports shall be submitted as required by specification 01451 "CONTRACTOR QUALITY CONTROL".

1.6.3.2 DEFICIENCY TRACKING

The Contractor shall use QCS to track deficiencies. Deficiencies identified by the Contractor will be numerically tracked using QC punch list items. The Contractor shall maintain a current log of its QC punch list items in the QCS database. The Government will log the deficiencies it has identified using its QA punch list items. The Government's QA punch list items will be included in its export file to the Contractor. The Contractor shall regularly update the correction status of both QC and QA punch list items.

1.6.3.3 THREE-PHASE CONTROL MEETINGS

The Contractor shall maintain scheduled and actual dates and times of preparatory and initial control meetings in QCS.

1.6.3.4 ACCIDENT/SAFETY TRACKING

The Government will issue safety comments, directions, or guidance whenever safety deficiencies are observed. The Government's safety comments will be included in its export file to the Contractor. The Contractor shall regularly update the correction status of the safety comments. In addition, the Contractor shall utilize QCS to advise the Government of any accidents occurring on the jobsite. This brief supplemental entry is not to be considered as a substitute for completion of mandatory reports.

1.6.3.5 FEATURES OF WORK

The Contractor shall include a complete list of the features of work in the QCS database. A feature of work may be associated with multiple pay activities. However, each pay activity (see subparagraph "Pay Activity Data" of paragraph "Finances") will only be linked to a single feature of work.

1.6.3.6 QC REQUIREMENTS

The Contractor shall develop and maintain a complete list of QC testing, transferred and installed property, and user training requirements in QCS. The Contractor shall update all data on these QC requirements as work progresses, and shall promptly provide this information to the Government via QCS.

1.6.4 SUBMITTAL MANAGEMENT

The Contractor shall maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file

to the Contractor. The Contractor shall use QCS to track and transmit all submittals. ENG Form 4025, submittal transmittal form, and the submittal register update, ENG Form 4288, shall be produced using QCS. RMS will be used to update, store and exchange submittal registers and transmittals, but will not be used for storage of actual submittals.

1.6.5 SCHEDULE

The Contractor shall develop a construction schedule consisting of pay activities, in accordance with Specification Section Project Schedule. This schedule shall be input and maintained in the QCS database either manually or by using the Standard Data Exchange Format (SDEF). The updated schedule data shall be included with each pay request submitted by the Contractor.

1.6.6 REQUESTS FOR INFORMATION (RFI)

The Contractor shall use the two-way RFI system contained in QCS for tracking all RFI's generated during the contract. Hard copies of all RFI's shall be provided to the government, and will govern in the event of a discrepancy between electronic and printed mediums.

1.6.7 IMPORT/EXPORT OF DATA

QCS includes the ability to export Contractor data to the Government and to import submittal register and other Government-provided data, and schedule data using SDEF.

1.7 IMPLEMENTATION

Contractor use of QCS as described in the preceding paragraphs is mandatory. The Contractor shall ensure that sufficient resources are available to maintain its QCS database, and to provide the Government with regular database updates. QCS shall be an integral part of the Contractor's management of quality control.

1.8 DATA SUBMISSION VIA COMPUTER DISKETTE OR CD-ROM

The Government-preferred method for Contractor's submission of updates, payment requests, correspondence and other data is by E-mail with file attachment(s). For locations where this is not feasible, the Contracting Officer may permit use of computer diskettes or CD-ROM for data transfer. Data on the disks or CDs shall be exported using the QCS built-in export function.

1.9 MONTHLY COORDINATION MEETING

The Contractor shall update the QCS database each workday. At least monthly, the Contractor shall generate and submit an export file to the Government with schedule update and progress payment request. As required in Contract Clause "Payments", at least one week prior to submittal, the Contractor shall meet with the Government representative to review the planned progress payment data submission for errors and omissions. The Contractor shall make all required corrections prior to Government acceptance of the export file and progress payment request. Payment requests accompanied by incomplete or incorrect data submittals will be returned. The Government will not process progress payments until an acceptable QCS export file is received.

1.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the requirements of this specification. The Contractor shall take immediate corrective action after receipt of such notice. Such

notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification.

-- END OF SECTION --

SECTION 01321

PROJECT SCHEDULE

1. GENERAL

1.1 REFERENCES

The publications listed below form a part of the specification to the extent referenced. The publications are referenced in the text by basic designation only.

U.S. Army Corps Of Engineers (USACE) ER 1-1-11 (1995) Progress, Schedules, and Network Analysis Systems

1.2 QUALIFICATIONS

The Contractor shall designate an authorized representative who shall be responsible for the preparation of all required project schedule reports.

2. PRODUCTS (NOT APPLICABLE)

3. EXECUTION

3.1 GENERAL REQUIREMENTS

Pursuant to the Contract Clause, Schedule For Construction Contracts, a Project Schedule as described below shall be prepared. The scheduling of Construction design and construction shall be the responsibility of the Contractor. Contractor management personnel shall actively participate in its development. Designers, Subcontractors and suppliers working on the project shall also contribute in developing and maintaining an accurate Project Schedule. The approved Project Schedule shall be used to measure the progress of the work, to aid in evaluating time extensions, and to provide the basis of all progress payments.

3.2 BASIS FOR PAYMENT

The schedule shall be a factor for measuring Contractor progress. Lack of an approved schedule or scheduling personnel will result in an inability of the Contracting Officer to evaluate Contractor's progress for the purposes of payment. Failure of the Contractor to provide all information, as specified below, shall result in the disapproval of the entire Project Schedule submission and the inability of the Contracting Officer to evaluate Contractor progress for payment purposes.

In the case where Project Schedule revisions have been directed by the Contracting Officer and those revisions have not been included in the Project Schedule, the Contracting Officer may hold, retain up to the maximum allowed by contract, each payment period, until revisions to the Project Schedule have been made.

3.3 PROJECT SCHEDULE

The computer software system utilized by the Contractor to produce the Project Schedule shall be capable of providing all requirements of this specification. Failure of the Contractor to meet the requirements of this specification shall result in the disapproval of the schedule. Manual methods used to produce any required information shall require approval by the Contracting Officer.

3.3.1 USE OF THE CRITICAL PATH METHOD

The Critical Path Method (CPM) of network calculation shall be used to generate the Project Schedule. The Contractor shall provide the Project Schedule in the Precedence Diagram Method (PDM).

3.3.2 LEVEL OF DETAIL REQUIRED

The Project Schedule shall include an appropriate level of detail. Failure to develop or update the Project Schedule or provide data to the Contracting Officer at the appropriate level of detail, as specified by the Contracting Officer, shall result in the disapproval of the schedule. The Contracting Officer will use, but is not limited to, the following conditions to determine the appropriate level of detail to be used in the Project Schedule:

3.3.2.1 ACTIVITY DURATIONS

Contractor submissions shall follow the direction of the Contracting Officer regarding reasonable activity durations. Reasonable durations are those that allow the progress of activities to be accurately determined between payment periods (usually less than two (2) percent of all non-procurement activities' Original Durations are greater than 20 days).

3.3.2.2 DESIGN AND PERMIT ACTIVITIES

Design and permitting activities, including necessary conferences and follow up actions and design package submission dates, shall be integrated into the schedule.

3.3.2.3 PROCUREMENT ACTIVITIES

Tasks related to the procurement of long lead materials or equipment shall be included as separate activities in the project schedule. Long lead materials and equipment are those materials that have a procurement cycle of over 90 days. Examples of procurement process activities include, but are not limited to: submittals, approvals, procurement, fabrication, and delivery.

3.3.2.4 CRITICAL ACTIVITIES

The following activities, as applicable, shall be listed as separate line activities on the Contractor's project schedule:

- a. Submission and approval of mechanical/electrical layout drawings.
- b. Submission and approval of O & M manuals.
- c. Submission and approval of as-built drawings.
- d. Submission and approval of 1354 data and installed equipment lists.
- e. Submission and approval of testing and air balance (TAB).
- f. Submission of TAB specialist design review report.
- g. Submission and approval of fire protection specialist.
- h. Submission and approval of testing and balancing of HVAC plus
- i. commissioning plans and data.
- j. Controls testing plan.
- k. Controls testing.
- l. Performance Verification testing.

- m. Other systems testing, if required.
- n. Pre-final inspection.
- o. Correction of punch list from pre-final inspection.
- p. Final inspection.

3.3.2.5 GOVERNMENT ACTIVITIES

Government and other agency activities that could impact progress shall be shown. These activities include, but are not limited to: design reviews, environmental permit approvals by State regulators, inspections, utility tie in, and Government Furnished Equipment (GFE).

3.3.2.6 RESPONSIBILITY

All activities shall be identified in the project schedule by the party responsible to perform the work. Responsibility includes, but is not limited to, the subcontracting firm, Contractor work force, or government agency performing a given task. Activities shall not belong to more than one (1) responsible party. The responsible party for each activity shall be identified by the Responsibility Code.

3.3.2.7 WORK AREAS

All activities shall be identified in the project schedule by the work area in which the activity occurs. Activities shall not be allowed to cover more than one (1) work area. The work area of each activity shall be identified by the Work Area Code.

3.3.2.8 MODIFICATION OR CLAIM NUMBER

Any activity that is added or changed by contract modification or used to justify claimed time shall be identified by a mod or claim code that changed the activity. Activities shall not belong to more than one (1) modification or claim item. The modification or claim number of each activity shall be identified by the Mod or Claim Number. Whenever possible, changes shall be added to the schedule by adding new activities. Existing activities shall not normally be changed to reflect modifications.

3.3.2.9 WORK ITEM

All activities shall be identified in the project schedule by the Work Item to which the activity belongs. An activity shall not contain work in more than one (1) work item. The work item for each appropriate activity shall be identified by the Work Item Code.

3.3.2.10 PHASE OF WORK

All activities shall be identified in the project schedule by the phases of work in which the activity occurs. Activities shall not contain work in more than one (1) phase of work. The project phase of each activity shall be the unique Phase of Work Code.

3.3.2.11 CATEGORY OF WORK

All Activities shall be identified in the project schedule according to the category of work which best describes the activity. Category of work refers, but is not limited, to the procurement chain of activities including such items as designs, design package submissions design reviews, review conferences, permits, submittals, approvals, procurement, fabrication, delivery, installation, start-up, and testing. The category of work for each activity shall be identified by the Category of Work Code.

3.3.2.12 FEATURE OF WORK

All activities shall be identified in the project schedule according to the feature of work to which the activity belongs. Feature of work refers, but is not limited to, a work breakdown structure for the project. The feature of work for each activity shall be identified by the Feature of Work Code.

3.3.3 SCHEDULED PROJECT COMPLETION

The schedule interval shall extend from award of contract to the contract completion date.

3.3.3.1 PROJECT START DATE

The schedule shall start no earlier than the date on which award of contract was acknowledged. The Contractor shall include as the first activity in the project schedule an activity called "Start Project". The "Start Project" activity shall have an "ES" constraint date equal to the date that the award of task order was acknowledged, and a zero (0) day duration.

3.3.3.2 CONSTRAINT OF LAST ACTIVITY

Completion of the last activity in the schedule shall be constrained by the contract completion date. Calculation on project updates shall be such that if the early finish of the last activity falls after the contract completion date, then the float calculation shall reflect a negative float on the critical path. The Contractor shall include as the last activity in the project schedule an activity called "End Project". The "End Project" activity shall have an "LF" constraint date equal to the completion date for the project, and a zero (0) day duration.

3.3.3.3 EARLY PROJECT COMPLETION

In the event the project schedule shows completion of the project prior to the contract completion date, the Contractor shall identify those activities that have been accelerated and/or those activities that are scheduled in parallel to support the Contractor's "early" completion. Contractor shall specifically address each of the activities noted in the narrative report at every project schedule update period to assist the Contracting Officer in evaluating the Contractor's ability to actually complete prior to the contract period.

3.3.4 INTERIM COMPLETION DATES

Contractually specified interim completion dates shall also be constrained to show negative float if the early finish date of the last activity in that phase falls after the interim completion date.

3.3.4.1 START PHASE

The Contractor shall include as the first activity for a project phase an activity called "Start Phase X" where "X" refers to the phase of work. The "Start Phase X" activity shall have an "ES" constraint date equal to the date on which the award of task order was acknowledged, and a zero (0) day duration.

3.3.4.2 END PHASE

The Contractor shall include as the last activity in a project phase an activity called "End Phase X" where "X" refers to the phase of work. The "End Phase X" activity shall have an "LF" constraint date equal to the completion date for the project, and a zero (0) day duration.

3.3.4.3 PHASE X

The Contractor shall include a hammock type activity for each project phase called "Phase X" where "X" refers to the phase of work. The "Phase X" activity shall be logically tied to the earliest and latest activities in the phase.

3.3.5 DEFAULT PROGRESS DATA DISALLOWED

Actual Start and Finish dates shall not be automatically updated by default mechanisms that may be included in CPM scheduling software systems. Actual Start and Finish dates on the CPM schedule shall match those dates provided from Contractor Quality Control Reports. Failure of the Contractor to document the Actual Start and Finish dates on the Daily Quality Control report for every in-progress or completed activity, and failure to ensure that the data contained on the Daily Quality Control reports is the sole basis for schedule updating shall result in the disapproval of the Contractor's schedule and the inability of the Contracting Officer to evaluate Contractor progress for payment purposes. Updating of the percent complete and the remaining duration of any activity shall be independent functions. Program features which calculate one (1) of these parameters from the other shall be disabled.

3.3.6 OUT-OF-SEQUENCE PROGRESS

Activities that have posted progress without all preceding logic being satisfied (Out-of-Sequence Progress) will be allowed only on a case-by-case approval of the Contracting Officer. The Contractor shall propose logic corrections to eliminate all out of sequence progress or justify not changing the sequencing for approval prior to submitting an updated project schedule.

3.3.7 NEGATIVE LAGS

Lag durations contained in the project schedule shall not have a negative value.

3.4 PROJECT SCHEDULE SUBMISSIONS

The Contractor shall provide the submissions as described below. The data disk, reports, and network diagrams required for each submission are contained in paragraph Submission Requirements.

3.4.1 INITIAL PROJECT SCHEDULE SUBMISSION

The Initial Project Schedule shall be submitted for approval within 30 calendar days after award of contract. The schedule shall provide a reasonable sequence of activities which represent work through the entire project and shall be at a reasonable level of detail. The baseline schedule shall be reviewed and deemed acceptable prior to the Contractor entering (manually or electronically via SDEF file) in QCS.

3.4.2 PERIODIC SCHEDULE UPDATES

Based on the result of progress meetings, specified in "Periodic Progress Meetings," the Contractor shall submit periodic schedule updates. These submissions shall enable the Contracting Officer to assess Contractor's progress. If the Contractor fails or refuses to furnish the information and project schedule data, which in the judgment of the Contracting Officer or authorized representative is necessary for verifying the Contractor's progress, the Contractor shall be deemed not to have provided an estimate upon which progress payment may be made.

3.4.3 STANDARD ACTIVITY CODING DICTIONARY

The Contractor shall use the activity coding structure defined in the Standard Data Exchange Format (SDEF) in ER 1-1-11, Appendix A. This exact structure is mandatory, even if some fields are not used.

3.5 SUBMISSION REQUIREMENTS

The following items shall be submitted by the Contractor for the preliminary submission, initial submission, and every periodic project schedule update throughout the life of the project:

3.5.1 DATA DISKS

Two (2) Data Compact Disks containing the project schedule shall be provided. Data on the disks shall adhere to the SDEF format specified in ER 1-1-11, Appendix A.

3.5.1.1 FILE MEDIUM

Required data shall be submitted on Compact Disk, formatted to hold 700 MB of data, under the MS-DOS Version 5. or 6.x, unless otherwise approved by the Contracting Officer.

3.5.1.2 DISK LABEL

A permanent exterior label shall be affixed to each disk submitted. The label shall indicate the type of schedule (Preliminary, Initial, Update, or Change), full contract number, project name, project location, data date, name and telephone number of person responsible for the schedule, and the MSDOS version used to format the disk.

3.5.1.3 FILE NAME

Each file submitted shall have a name related to either the schedule data date, project name, or contract number. The Contractor shall develop a naming convention that will ensure that the names of the files submitted are unique. The Contractor shall submit the file naming convention to the Contracting Officer for approval.

3.5.2 NARRATIVE REPORT

A Narrative Report shall be provided with the preliminary, initial, and each update of the project schedule. This report shall be provided as the basis of the Contractor's progress payment request. The Narrative Report shall include: a description of activities along the two (2) most critical paths, a description of current and anticipated problem areas or delaying factors and their impact, and an explanation of corrective actions taken or required to be taken. The narrative report is expected to relay to the Government, the Contractor's thorough analysis of the schedule output and its plans to compensate for any problems, either current or potential, which are revealed through that analysis.

3.5.3 APPROVED CHANGES VERIFICATION

Only project schedule changes that have been previously approved by the Contracting Officer shall be included in the schedule submission. The Narrative Report shall specifically reference, on an activity by activity basis, all changes made since the previous period and relate each change to documented, approved schedule changes.

3.5.4 SCHEDULE REPORTS

The format for each activity for the schedule reports listed below shall contain: Activity Numbers, Activity Description, Original Duration, Remaining Duration, Early Start Date, Early Finish Date, Late Start Date,

Late Finish Date, Total Float. Actual Start and Actual Finish Dates shall be printed for those activities in progress or completed.

3.5.4.1 ACTIVITY REPORT

A list of all activities sorted according to activity number.

3.5.4.2 LOGIC REPORT

A list of Preceding and Succeeding activities for every activity in ascending order by activity number. Preceding and succeeding activities shall include all information listed above in paragraph Schedule Reports. A blank line shall be left between each activity grouping.

3.5.4.3 TOTAL FLOAT REPORT

A list of all incomplete activities sorted in ascending order of total float. Activities which have the same amount of total float shall be listed in ascending order of Early Start Dates. Completed activities shall not be shown on this report.

3.5.4.4 EARNINGS REPORT

An Earnings Report is a compilation of the Contractor's Total Earnings on the project from award of contract until the most recent Monthly Progress Meeting. This report shall reflect the Earnings of specific activities based on the agreements made in the field and approved between the Contractor and Contracting Officer at the most recent Monthly Progress Meeting. Provided that the Contractor has provided a complete schedule update, this report shall serve as the basis of determining Contractor Payment. Activities shall be grouped by work item and sorted by activity numbers. This report shall: sum all activities in a work item and provide a work item percent; and complete and sum all work items to provide a total project percent complete. The printed report shall contain, for each activity: the Activity Number, Activity Description, Original Budgeted Amount, Total Quantity, Quantity to Date, Percent Complete (based on cost), and Earnings to Date.

3.5.5 NETWORK DIAGRAM

The network diagram shall be required on the initial schedule submission and on monthly schedule update submissions. The network diagram shall depict and display the order and interdependence of activities and the sequence in which the work is to be accomplished. The Contracting Officer will use, but is not limited to, the following conditions to review compliance with this paragraph:

3.5.5.1 CONTINUOUS FLOW

Diagrams shall show a continuous flow from left to right with no arrows from right to left. The activity number, description, duration, and estimated earned value shall be shown on the diagram.

3.5.5.2 PROJECT MILESTONE DATES

Dates shall be shown on the diagram for start of project, any contract required interim completion dates, and contract completion dates.

3.5.5.3 CRITICAL PATH

The critical path shall be clearly shown.

3.5.5.4 BANDING

Activities shall be grouped to assist in the understanding of the activity sequence. Typically, this flow will group activities by category of work, work area and/or responsibility.

3.5.5.5 S-CURVES

Earnings curves showing projected early and late earnings and earnings to date.

3.6 PERIODIC PROGRESS MEETINGS

Progress meetings to discuss payment shall include a monthly onsite meeting or other regular intervals mutually agreed to at the preconstruction conference. During this meeting the Contractor shall describe, on an activity by activity basis, all proposed revisions and adjustments to the project schedule required to reflect the current status of the project. The Contracting Officer will approve activity progress, proposed revisions, and adjustments as appropriate.

3.6.1 MEETING ATTENDANCE

The Contractor's Project Manager and Scheduler shall attend the regular progress meeting.

3.6.2 UPDATE SUBMISSION FOLLOWING PROGRESS MEETING

A complete update of the project schedule containing all approved progress, revisions, and adjustments, based on the regular progress meeting, shall be submitted not later than four (4) working days after the monthly progress meeting.

3.6.3 PROGRESS MEETING CONTENTS

Update information, including Actual Start Dates, Actual Finish Dates, Remaining Durations, and Cost-to-Date shall be subject to the approval of the Contracting Officer. As a minimum, the Contractor shall address the following items on an activity by activity basis during each progress meeting.

3.6.3.1 START AND FINISH DATES

The Actual Start and Actual Finish dates for each activity currently in progress or completed.

3.6.3.2 TIME COMPLETION

The estimated Remaining Duration for each activity in-progress. Time-based progress calculations shall be based on Remaining Duration for each activity.

3.6.3.3 COST COMPLETION

The earnings for each activity started. Payment will be based on earnings for each in-progress or completed activity. Payment for individual activities will not be made for work that contains quality defects. A portion of the overall project amount may be retained based on delays of activities.

3.6.3.4 LOGIC CHANGES

All logic changes pertaining to change orders, change orders to be incorporated into the schedule, Contractor proposed changes in work sequence, corrections to schedule logic for out-of-sequence

progress, lag durations, and other changes that have been made pursuant to contract provisions shall be specifically identified and discussed.

3.6.3.5 OTHER CHANGES

Other changes required due to delays in completion of any activity or group of activities include: 1) delays beyond the Contractor's control, such as strikes and unusual weather. 2) delays encountered due to submittals, Government Activities, deliveries or work stoppages which make re-planning the work necessary. 3) Changes required to correct a schedule which does not represent the actual or planned prosecution and progress of the work.

3.7 REQUESTS FOR TIME EXTENSIONS

In the event the Contractor requests an extension of the contract completion date, or any interim milestone date, the Contractor shall furnish the following for a determination as to whether or not the Contractor is entitled to an extension of time under the provisions of the contract: justification, project schedule data, and supporting evidence as the Contracting Officer may deem necessary. Submission of proof of delay, based on revised activity logic, duration, and costs (updated to the specific date that the delay occurred) is obligatory to any approvals.

3.7.1 JUSTIFICATION OF DELAY

The project schedule shall clearly display that the Contractor has used, in full, all the float time available for the work involved with this request. The Contracting Officer's determination as to the number of allowable days of contract extension shall be based upon the project schedule updates in effect for the time period in question, and other factual information. Actual delays that are found to be caused by the Contractor's own actions, which result in the extension of the schedule, will not be a cause for a time extension to the contract completion date.

3.7.2 SUBMISSION REQUIREMENTS

The Contractor shall submit a justification for each request for a change in the contract completion date of under two (2) weeks based upon the most recent schedule update at the time of the constructive direction issued for the change. Such a request shall be in accordance with the requirements of other appropriate Contract Clauses and shall include, as a minimum:

- a. A list of affected activities, with their associated project schedule activity number.
- b. A brief explanation of the causes of the change.
- c. An analysis of the overall impact of the changes proposed.
- d. A sub-network of the affected area.

Activities impacted in each justification for change shall be identified by a unique activity code contained in the required data file.

3.7.3 ADDITIONAL SUBMISSION REQUIREMENTS

For any requested time extension of over two (2) weeks, the Contracting Officer may request an interim update with revised activities for a specific change request. The Contractor shall provide this disk within four (4) days of the Contracting Officer's request.

3.8 DIRECTED CHANGES

If changes are issued prior to settlement of price and/or time, the Contractor shall submit proposed schedule revisions to the Contracting Officer within two (2) weeks of this task order being issued. The

proposed revisions to the schedule will be approved by the Contracting Officer prior to inclusion of those changes within the project schedule. If the Contractor fails to submit the proposed revisions, the Contracting Officer may furnish the Contractor with suggested revisions to the project schedule. The Contractor shall include these revisions in the project schedule until revisions are submitted, and final changes and impacts have been negotiated. If the Contractor has any objections to the revisions furnished by the Contracting Officer, the Contractor shall advise the Contracting Officer within two (2) weeks of receipt of the revisions. Regardless of the objections, the Contractor shall continue to update the schedule with the Contracting Officer's revisions until a mutual agreement in the revisions is reached. If the Contractor fails to submit alternative revisions within two (2) weeks of receipt of the Contracting Officer's proposed revisions, the Contractor will be deemed to have concurred with the Contracting Officer's proposed revisions. The proposed revisions will then be the basis for an equitable adjustment for performance of the work.

3.9 OWNERSHIP OF FLOAT

Float available in the schedule, at any time, shall not be considered for the exclusive use of either the Government or the Contractor.

-- End of Section --

SECTION 01335
SUBMITTAL PROCEDURES
FOR
DESIGN-BUILD (DB) PROJECTS

1. REFERENCE

The publication listed below forms a part of this specification to the extent referenced. The publication is referenced to in the text by basic designation only.

National Institute Of Building Sciences (NIBS)
Unified Master Reference List (UMRL)

National Institute of Building Sciences
1090 Vermont Avenue, NW, Suite 700
Washington, DC 20005-4905
Email: nibs@nibs.org
FAX: (202) 289-1092
Tele: (202) 289-7800

2. SUBMITTAL CLASSIFICATION

Submittals are classified as follows.

2.1 DESIGN CONSTRUCTION SUBMITTALS

Contractor furnished design construction submittals include the various design documents, as applicable, which primarily consist of field investigations, calculations, design analysis (DA), drawings, and specifications.

The Contractor shall clearly label and date all Design Construction Submittals and clearly indicate on the ENG Form 4025 what is being submitted for review to avoid confusion between current and previous submittals. The Design-Build Contractor shall not begin construction work until the Government has reviewed the Design-Build Contractor's Existing Conditions Site Plan and has cleared it for construction. Clearance for construction shall not be construed as meaning Government approval. Unless otherwise indicated, the risk for the design is the sole responsibility of the Design-Build Contractor.

As a minimum, design construction submittals shall be submitted as follows:

Project Site Surveys & Reports
Design Construction Review
Final Design Construction Re-Submittal

2.1.1 PRELIMINARY PROJECT SITE SURVEYS & REPORTS

The review of this construction submittal shall primarily ensure that the Contractor has, as a minimum, followed ALL the requirements of the contract including the paragraphs in Section 01010. In addition, the review of this submittal is to ensure that the Contractor has taken an inventory of the existing conditions at the proposed site(s) and has established the most desirable functional relationships between the various project elements. **This work shall be completed in less than 60 days from Notice To Proceed (NTP). Failure to do so at the satisfaction of the Government shall constitute grounds for withholding of all progress payments.**

- a. Existing Conditions Site Plan(s); Existing conditions site plans for the site shall be based on the above referenced Sections.

2.1.2 DESIGN CONSTRUCTION REVIEWS

The review of this construction submittal shall primarily ensure that the Contractor has, as a minimum, followed ALL the requirements of the contract including the paragraphs in Section 01010 and ensure that the Contractor has correctly understood and adhered to the contract. In addition, the review of this submittal is to ensure that the Contractor has provided the technical solution as to how the functional and technical requirements will be met and to show Contractor compliance (or justify noncompliance) with the design parameters and/or requirements. As a minimum, the following documents shall be submitted:

- a. Technical Requirements: Technical requirements for specific items, appendages, and equipment shall be based on the above referenced Sections and be compete with, if required, design analysis (DA), plans, and specifications.

2.2 USE OF DRCHECKS_{SM} FOR DESIGN SUBMITTAL COMMENT AND RESPONSE

2.2.1 DRCHECKS_{SM} WEB LINK

All AED Design Submittal review comments will be documented using the standard design review tool for the U.S. Army Corps of Engineers, a web-based application called "DrChecks_{SM}". The web link to DrChecks_{SM} is:

<https://www.projnet.org/projnet/binKornHome/index.cfm>

2.2.2 DRCHECKS_{SM} VENDOR IDENTIFICATION AND TUTORIAL

Upon notification of award, the Contractor shall immediately coordinate with the Chief, Engineering Branch, AED to acquire a vendor identification and a brief tutorial on the use of DrChecks_{SM}. Firms with multiple locations need to coordinate with AED the location where Dr. Checks will be used and verify after setup that the access has in fact been provided. The Contractor is responsible for providing their own DrChecks_{SM} Administrator within their own design staff personnel to access and accomplish actions within DrChecks_{SM}.

2.2.3 NOTIFICATION OF DRCHECKS_{SM} FILE ACCESS

The Afghanistan Engineer District will complete a review at every Design Submittal stage for conformance with the technical requirements of the Contract and document all comments in DrChecks_{SM}. At completion of the review, a notification will be issued to the Contractor by the Contracting Officer's representative that the particular DrChecks_{SM} file will be opened to the Contractor. Until this time, the Contractor is not able to view any AED comments for that particular Design Submittal.

2.2.4 FURTHER CONTRACTOR INFORMATION AFTER DRCHECKS_{SM} REVIEWS

See Paragraph, Government Review, for further procedures and requirements associated with Design Submittal reviews.

2.3 CONSTRUCTION SUBMITTALS

2.3.1 CONTRACTOR FURNISHED GOVERNMENT APPROVED CONSTRUCTION SUBMITTALS (GA)

Government approved construction submittals are primarily related to plans (Security, Contractor Quality Control, Accident Prevention, Resident Management System, Area Use, etc.), schedules (Project Schedule/Network Analysis), and certificates of compliance, reports and records/statements. They may also include proposed variations to approved design documents in accordance with the paragraph, Variations.

In addition, GA construction submittals are required for the following:

a. MECHANICAL FEATURES

EQUIPMENT SUBMITTALS: Manufacturer's standard catalog data showing dimensions, performance data, electrical requirements, drawings indicating location and installation of equipment and materials, Operation and Maintenance (O&M) manuals and construction details for water wells, water tanks, control valves, pipe insulation, water pumps, air handling units, condensers, variable air volume (VAV) boxes, and compliance with standards as stated in Section 01010.

TESTING RESULTS: For oxygen systems and vacuum system, submit six (6) copies of each test containing the following information in bound letter-size booklets:

- 1) The date the tests were performed.
- 2) A list of equipment used, with calibration certifications.
- 3) A copy of measurements taken.
- 4) The parameters to be verified.
- 5) The condition specified for the parameter.
- 6) The inspection results, signed, dated, and certified by the installer. The certification shall state that required procedures were accomplished, that the procedures were conducted in compliance the plans and specifications.
- 7) A description of adjustments performed.

Individual reports shall be provided for, system performance tests, alarm test, and the system leak tests. Drawings shall be folded blue lines, with the title block visible.

2.3.2 FOR INFORMATION ONLY (FIO) CONSTRUCTION SUBMITTALS

All submittals not requiring Designer of Record or Government approval will be for information only. These construction submittals shall be checked, stamped, signed and dated by the Contractor's Quality Control Engineer, certifying that such submittal complies with the contract requirements. All Contractor submittals shall be subject to review by the Government at any time during the course of the contract. Any Contractor submittal found to contain errors or omissions shall be resubmitted as one requiring "approval". No adjustment for time or money will be allowed for corrections required as a result of noncompliance with plans or specifications. Normally submittals For Information Only will not be returned. Approval of the Contracting Officer is not required on FIO submittals. These submittals will be used for information purposes. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications and will not prevent the Contracting Officer from requiring removal and replacement if nonconforming material is incorporated in the work.

2.3.3 VARIATIONS AFTER CONSTRUCTION REVIEW

After design submittals have been reviewed and cleared for construction by the Contracting Officer, no submittal for the purpose of substituting materials, equipment, systems, and patented processes will be considered by the Government unless submitted in accordance with paragraph, Variations.

2.3.4 ADDITIONAL SHOP DRAWINGS AND SUBMITTALS

In accordance with the paragraph, Design Discrepancies, the Government may request the Design-Build Contractor to provide additional shop drawing and submittal type data subsequent to completion of the design.

2.3.5 INCOMPLETE DESIGN

The Design-Build Contractor shall not use construction submittals as a means to supplant and/or supplement an incomplete design effort.

2.4 SUBMITTAL CERTIFICATION

The Contractor Quality Control (CQC) organization shall be responsible for certifying that all submittals and deliverables have been reviewed in detail for completeness, are correct, and are in strict conformance with the contract drawings, specifications, and reference documents.

2.4.1 EFFECTIVE QUALITY CONTROL (CQC) SYSTEM

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with Contract Clause 52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION - ALTERNATE I, and SECTION 01451 CONTRACTOR QUALITY CONTROL.

2.4.2 ORGANIZATIONAL RESPONSIBILITY

The quality control system shall cover all design, construction, sub-contractor, manufacturer, vendor, and supplier operations at any tier, both onsite and offsite.

2.4.3 CQC SYSTEM MANAGER REVIEW AND APPROVAL

Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) System Manager. If found to be in strict conformance with the contract requirement, each item shall be stamped, signed, and dated by the CQC System Manager. Copies of the CQC organizations review comments indicating action taken shall be included within each submittal.

2.4.4 DETERMINATION OF COMPLIANCE

Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements by the Contracting Officer. The Contractor shall submit all required documentation with submittals. The U.S. Army Corps of Engineer (USACE) will not accept partial submittals.

2.4.5 RESPONSIBILITY FOR ERRORS OR OMISSIONS

It is the sole responsibility of the Contractor to ensure that submittals do or do not comply with the contract documents. Government review, clearance for construction, or approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract.

2.4.6 GOVERNMENT REVIEW

Government review, clearance for construction, or approval of construction submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as it is the sole responsibility of the Contractor to certify that each Submittal has been reviewed in detail and is in strict conformance with all the contract documents and design criteria referenced therein.

2.4.7 SUBSTITUTIONS

After submittals have been reviewed and cleared for construction by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless justified as indicated herein.

2.4.8 ADDITIONAL SUBMITTALS

In conjunction with Contract Clause 52.236-5 MATERIAL AND WORKMANSHIP, the Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work.

2.4.9 UNTIMELY AND UNACCEPTABLE SUBMITTALS

If the Contractor fails to submit submittals in a timely fashion, or repetitively submits submittals that are incomplete or not in strict conformance with the contract documents, no part of the time lost due to such actions shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

2.4.10 STAMPS

Stamps shall be used by the Contractor on all design and post design construction submittals to certify that the submittal meets contract requirements and shall be similar to the following:

Contractor (Firm Name): _____

Contract Number: _____

Contract Name: _____

I certify that this submittal accurate, is in strict conformance with all contract requirements, has been thoroughly coordinated and cross checked against all other applicable disciplines to prevent the omission of vital information, that all conflicts have been resolved, and that repetition has been avoided and, it is complete and in sufficient detail to allow ready determination of compliance with contract requirements by the Contracting Officer.

Name of CQC System Manager: _____

Signature of CQC System Manager: _____

Date: _____

2.5 ENGLISH LANGUAGE

All specifications, drawings, design analysis, design calculations, shop drawings, catalog data, materials lists, and equipment schedules submitted shall be in the English language. However, the local language of host country shall be added to project As-Built drawings.

2.6 UNITS OF MEASUREMENT

Design documents shall be prepared in accordance with the guidance offered in SECTION 01415 METRIC MEASUREMENTS.

The metric units used are the International System of Units (SI) developed and maintained by the General Conference on Weights and Measures (CGPM); the name International System of Units and the international abbreviation SI were adopted by the 11th CGPM in 1960.

2.7 DRAWINGS

2.7.1 DESIGN CALCULATIONS

Calculations shall be in SI units to meet the requirements of the design. Quantities on the contract drawings stated in SI units, shall also be stated in SI units in the design analysis to match the drawings.

2.7.2 SPECIFICATIONS

All equipment and products shall be specified according to U.S. standards and described by appropriate units as required herein.

2.8 WITHHOLDING OF PAYMENT FOR SUBMITTALS

2.8.1 DESIGN SUBMITTALS

Payment for Design work will not be made in whole or in part until the Government has reviewed and cleared the design for construction.

2.8.2 CONSTRUCTION SUBMITTALS

Payment for materials incorporated in the work will not be made if required approvals have not been obtained. In event under separate clause of the contract, the Contractor is allowed partial or total invoice payment for materials shipped from the Continental United States (CONUS), and/or stored at the site, the Contractor shall with his request for such payment, submit copies of approvals (ENG Form 4025) certifying that the materials that are being shipped and/or stored have been approved and are in full compliance with the contract technical specifications.

3. CONTRACT DELIVERABLES

The following are contract deliverables which expound upon and finalize the design parameters/requirements outlined within the contract documents. They shall be prepared in such a fashion that the Prime Contractor is responsible to the Government and not as an internal document between the Prime Contractor and its sub-contractors, Vendors, Suppliers, etc.

3.1 PROJECT NARRATIVE

The Project Narrative shall be a bound set and shall contain the contract Request For Proposal (RFP) Section 01010 (and any additional RFP sections that are appropriate). The RFP Section 01010 shall be the latest version. Any subsequent changes to the RFP shall be clearly marked and highlighted with explanation for the changes. The Project Narrative shall also contain the general description of the project and a discussion of the design approach and design features for the project.

3.2 DESIGN ANALYSIS (DA)

3.2.1 SUBMITTAL

A design analysis (DA), written in the English language with SI units of measure, shall be submitted for review by the Government. The design analysis is a written explanation of the project design which is expanded and revised (updated) as the design progresses. The design analysis shall contain all explanatory material giving the design rationale for any design decisions which would not be obvious to an engineer reviewing the final drawings and specifications. The design analysis contains the criteria for and the history of the project design, including criteria furnished by the Government, letters, codes, references, conference minutes, and pertinent research. Design calculations, computerized and manual, are included in the design analysis. Narrative descriptions of design solutions are also included. Written material may be illustrated by diagrams and sketches to convey design concepts. Catalog cuts and manufacturer's data for all equipment items, shall be submitted.

3.2.2 FORMAT

Format of design analysis shall closely match the standard format referenced within the RFP.

3.3 DESIGN CALCULATIONS

All design calculations shall be presented such that they are easily understood, correlated with RFP requirements (Section 1010 criteria, codes, and all other applicable or pertinent criteria) and all final conclusions clearly documented and summarized. The Design Submittal must include complete information (Soil Report, percolation test results, concrete design strengths, steel material properties, electrical loads, heat gain/loss assumptions, etc.) necessary to support all design calculations in order to easily and efficiently verify the accuracy of this information and the resulting project components shown in plans and specifications.

3.3.1 SUBMITTAL

When design calculations are voluminous, they shall be bound separately from the narrative part of the design analysis. Design calculations will include a title page, table of contents, and be indexed (tabbed) to separate distinct parts of the various analysis and design actions being accomplished to support plan drawings submitted. They shall be presented in a clear, consistent and legible format in order to quickly understand the analysis and design accomplished. Presentation shall be such that a person unfamiliar with the project features and associated analysis and design can quickly understand the overall design process and procedures, review the information in conjunction with the given set of plans and specifications, and verify the suitability of all information submitted.

All design calculations shall explain the source of loading conditions with assumptions and conclusions explained. The analysis and design methods shall also be explained, including assumptions, theories and formulae. Include applicable diagrams that are clearly explained and correlated with related computations, whether computer or hand generated. The design calculations shall include a complete and comprehensive list of the criteria (and date or version of the criteria) that the design/analysis will be compared to (codes, Corps of Engineers Engineering Regulations, Engineering Manuals, AED Design Requirements Documents, etc.). Within the separable elements of design calculations, the engineer shall cite the specific code or reference paragraph or section as appropriate to indicate conformance to requirements.

At the beginning of each project component design section, present a summary of all load conditions and combinations required per applicable code or Corps of Engineers manual or regulation. Then clearly identify the particular load case governing the design and clearly show how the particular analysis, construction materials to be used, and the specific design meet the governing load combination.

Calculation sheets shall carry the names or initials of the engineer and the checker and the dates of calculations and checking. No portion of the calculations shall be computed and checked by the same person.

3.3.2 COMPUTER ANALYSIS

Provide a clear summary of all computer outputs and highlight in the outputs information used in the analysis and design accomplished elsewhere in the calculations.

If a computerized analysis or design program is used (either commercial software packages or unique, designer-written computer analysis/design tools), the computations shall provide clear reference to the software program and version being used and an explanation of the validity of the particular program to the given application (where has the program been used before, what input and output does the program provide, is the program a recognized Corps of Engineers or industry standard). If the program is proprietary to the Contractor (not recognized by the Corps of Engineers or industry), the Contractor shall provide a sample hand calculation to verify the results of one set of data generated by the computer program.

State exactly the computation performed by the computer. Include applicable diagrams, adequately identified. Provide all necessary explanations of the computer printout format, symbols, and abbreviations. Use adequate and consistent notation. Provide sufficient information to permit manual checks of the results.

Each set of computer printouts shall be preceded by an index and by a description of the computation performed. If several sets of computations are submitted, they shall be accompanied by a general table of contents in addition to the individual indices.

When the computer output is large, it shall be divided into volumes at logical division points. All final computer results used in design shall be separated from the total pages of computer output that might be included in the design calculations for ease of review.

3.4 SPECIFICATIONS

Specifications shall be prepared in accordance with the UFGS (Uniform Facilities Guide Specifications) format. The Contractor-prepared specifications shall include as a minimum, all applicable specification sections referenced by the UFGS. Where the does not reference a specification section for specific work to be performed by this contract, the Design-Build Contractor shall be responsible for creating the required specification in the UFGS format.

3.4.1 USE OF UNIFIED FACILITIES GUIDE SPECIFICATIONS (UFGS)

UFGS (Unified Facilities Guide Specifications) are required for this project. Current UFGS information may be obtained at the following location: <http://www.wbdg.org/>.

Specifications for UFGS are in SpecsIntact format. SpecsIntact is government sponsored software used to edit specifications for government contracts. The software is available at the following link: <http://specsintact.ksc.nasa.gov/index.asp>.

3.4.2 QUALITY CONTROL AND TESTING

Specifications shall include required quality control and further indicate all testing to be conducted by the Contractor, its sub-contractors, vendors and/or suppliers.

3.4.3 AMBIGUITIES AND INDEFINITE SPECIFICATIONS

Ambiguities, indefinite specification requirements (e.g., highest quality, workmanlike manner, as necessary, where appropriate, as directed etc) and language open to interpretation is unacceptable.

3.5 INDUSTRY STANDARDS

3.5.1 U.S. INDUSTRY STANDARDS

The Specifications shall be based on internationally accepted U.S. industry Standards. Customarily accepted publications may be found in the UNIFIED MASTER REFERENCE LIST (UMRL) which may be located at the following URL: <http://www.hnd.usace.army.mil/techinfo/UFGS/UFGSref.htm>.

To access the UMRL select the "Unified Facilities Guide Specifications" tab and scroll down to Unified Master Reference List (UMRL) (PDF version).

Examples of U.S. standards are: National Fire Protection Association (NFPA), International Building Code (IBC), American Concrete Institute (ACI), American Water Works Association (AWWA), ADAAG (ADA Accessibility Guidelines) for Buildings and Facilities, etc. Standards referenced shall be by specific issue; the revision letter, date or other specific identification shall be included.

This document lists publications referenced in the Unified Facilities Guide Specifications (UFGS) of the Corps of Engineers (USACE), the Naval Facilities Engineering Command (NAVFAC), the Air Force Civil Engineer Support Agency (AFCESA), and the guide specifications of the National Aeronautics and Space Administration (NASA). This document is maintained by the National Institute of Building Sciences (NIBS) based on information provided by the agencies involved and the standards producing organizations. The listing is current with information available to NIBS on the date of this publication.

Standards referenced in specifications and drawings prepared by the Contractor shall be by specific issue; the revision letter, date or other specific identification shall be included.

3.5.2 AED DESIGN REQUIREMENTS DOCUMENTS

AED Design Requirements (latest version) documents listed in Section 01010, shall be adhered to in this contract. These documents are available from the COR. These documents shall be used as the basis for design and construction, and for selecting options within the Unified Facilities Guide Specifications (UFGS). It is the Contractor's option to use specifications contained in the AED Design Requirements Documents, when provided, or to adapt the UFGS specifications to match the requirements provided in the AED Design Documents and specifications. Site or project specific data and requirements in the AED Design Requirements documents shall supersede UFGS language where there are perceived conflicts.

3.6 DRAWINGS

3.6.1 COMPUTER ASSISTED DESIGN AND DRAFTING (CADD)

Computer Assisted Design and Drafting (CADD) is required for all work related to this contract. Only personnel proficient in the preparation of CADD drawings shall be employed to modify the contract drawings or prepare new drawings. The CADD deliverables shall meet the requirements of the A/E/C CADD Standard (Release 3.0). Emphasis is on drawings meeting sheet layout standards, level/layer naming standards and sheet naming conventions. The CADD standards may be downloaded at the CAD/BIM Technology Center at the following link:
<https://caddim.usace.army.mil/default.aspx?p=s&t=13&i=4>.

The Contractor shall furnish all softcopy design submittals (and As-Builts) using software applications in either .dwg (AutoCAD, AutoDesk release 2005 or later) or in .dgn (MicroStation, Bentley Systems version 8.0 or later) format. In addition, the Contractor is required to submit the softcopy design submittals in .pdf (Adobe Acrobat) format. Drawings prepared in any convention other than CADD, must have the written approval of the Contracting Officer.

3.6.2 PLANS

Plans shall be prepared in the English language with metric (SI) units of measure. All the drawings and details of the working drawings shall be adequately labeled and cross-referenced. Complete, thoroughly checked, and coordination with other engineering disciplines design drawings shall be submitted. At the final design construction submittal, the Contractor shall have incorporated all design review comments generated by previous design review(s), have completed all of the constructability and coordination comments, and have the drawings in a Ready-to-Build condition. The drawings shall be complete at this time and contain all the details necessary to ensure a clear understanding of the work throughout construction.

3.6.3 DRAWING BORDER SHEETS

All drawings shall be prepared in size "A1" border sheets (594 mm by 841 mm). Hardcopy design submissions may be printed on half size drawing sheets ("A3", 279 mm by 420 mm) for purposes of saving paper and for ease of review. If drawings are not readable in the half size reduction, the Contractor shall submit all drawings in A1 border sheets. All final contract drawing sets (As-Builts) shall be submitted on A1 border sheets. Drawing sheets shall be trimmed to specified size if necessary.

3.6.4 SEQUENCE OF DESIGN DRAWINGS

Referencing the A/E/C CADD Standard (pg. 13, Table 2-1 of the A/E/C CADD standards) the sequence of drawings shall follow the sequence as shown below:

Discipline

1. General
2. Survey/Mapping
3. Equipment
4. Plumbing
5. Mechanical
6. Electrical

3.6.5 DRAWING FOLDER STRUCTURE

CADD files shall be organized in a folder structure to what is described herein. For multi-building projects a folder of each building type shall be created and the applicable folders shown in each building type folder.

3.6.6 DRAWING SHEET ASSEMBLY

CADD files shall be organized to what is described in "Option 2 – Use of Design Model Only" (page 10, Figure 2-3 of the A/E/C CADD Standard). This method will utilize one view and the use of "paper space" is not used. The border sheet shall be X-REF into each model file and scaled up to the applicable scale.

3.6.7 MODEL FILES

Model files represent the building's physical layout and components such as floor plans and elevations. Model files shall be drawn to full size (1:1) in the default view. Floor Plan Model files represent one floor. Model files shall have coordinates (x,y,z) of 0,0,0 in paper space on layout. The exception for model files with coordinates 0,0,0 shall be the civil site plan (see paragraph, Geo-Reference).

3.6.8 BORDER SHEET FILES

Border sheet files are used to assemble model files for plotting and viewing purposes. Every border sheet file has a drawing area, title block, border and represents one plotted drawing.

3.6.9 LAYER/LEVEL NAMES

Layer or level files names shall follow the guidelines of appendix A and B of the A/E/C CADD standards. For AutoCAD, .dwt (drawing template files) shall be used to import the proper layers that will be inclusive of the correct line type, color, and line thickness of the respective layer.

3.6.10 DRAWING FILE NAMING CONVENTION

CADD files shall follow the naming convention as described in the A/E/C CADD Standards. For model files reference pg 12 - 16, figure 2-4, tables 2-1 and 2-2. for sheet files reference pg 18 – 22, figure 2-5, table 2-3.

3.6.11 SHEET IDENTIFICATION BLOCK

The sheet identifier will follow the name of the border sheet file. This will consist of the discipline designator, the sheet type designator and the sheet sequence number as referenced in pg 23, figure 2-6 of the A/E/C CADD Standards.

3.6.12 DRAWING SCALES

The scales indicated on the following list shall, in general, be used for all drawings. The Contractor may, at its option, make exceptions to scales indicated, if approved in writing by the Contracting Officer.

TYPICAL DRAWING SCALES	
DRAWING TYPE	METRIC
SITE PLAN	1:200
	1:400
	1:500
	1:600
	1:700
	1:1000
	1:2000
	1:5000
	1:6000
	1:10000
	1:20000
FLOOR PLAN	1:50
	1:100
	1:200
ROOF PLAN	1:200

EXTERIOR ELEVATIONS	1:100
	1:200
INTERIOR ELEVATIONS	1:50
	1:100
CROSS SECTIONS	1:50
	1:100
	1:200
WALL SECTIONS	1:20
STAIR DETAILS	1:10
DETAILS	1:5

3.6.13 SYMBOLS, LINE STYLES, & PATTERNS

Approved symbols, line styles, and patterns shall be in accordance with AEC CAD Standard Release 3.0 or current version (see Appendix D of the A/E/C CADD Standards). The approved symbols, line styles, and patterns associated with AutoCAD software maybe downloaded in the following link:

<https://tsc.wes.army.mil/products/standards/aec/aecstdsym.asp>

3.6.14 PLOTTER PREPARED ORIGINAL DRAWINGS

Plotter prepared original drawings shall be prepared on 20 pound bond paper, unless otherwise approved and shall be plotted on the matte side. Raster plotters must provide a minimum resolution of 400 dpi while vector plotters shall provide a minimum resolution of 0.0010 inch with an accuracy of +0.1% of the move and a repeatability error of not more than 0.005 inch. Drawings produced from dot matrix plotters are not acceptable. Plots accompanied by the digital design file may be prepared on vellum: translucent bond is not acceptable. Line density shall be equivalent to that produced by black India ink: half tone plots are only acceptable where the half-tone color setting of RGB (red, green blue) settings equal a value of 153 (see pg. 27, Table 3-4 of the A/E/C CADD Standards). Drawings plotted in color is not acceptable. Manual changes to plotted originals are not acceptable.

3.6.15 TITLE AND REVISION BLOCK

Title and revision block shall match examples shown in 1335a-Attachments-AED.pdf, Figures 1 through 4, furnished as an attachment to this RFP.

3.6.16 LEGENDS

For each submittal, legends of symbols and lists of abbreviations shall be placed on the drawings. They shall include all of the symbols and abbreviations used in the drawing set, but shall exclude any symbols and abbreviations not used. Since many symbols are limited to certain design disciplines, there is a definite advantage to the use of separate legends on the initial sheet of each design discipline or in the Standard Details package for each discipline. If legends have not been shown by discipline, a legend shall be placed on the first drawing.

3.6.17 LOCATION GRID

To facilitate the location of project elements and the coordination of the various disciplines' drawings, all plans shall indicate a column line or planning grid, and all floor plans (except structural plans) shall show room numbers.

3.6.18 COMPOSITE AND KEY PLANS

If the plan of a large building or structure must be placed on two or more sheets in order to maintain proper scale, the total plan shall be placed on one sheet at a smaller scale. Appropriate key plans and match lines shall appear on segmented drawings. Key plans shall be used not only to relate large scale plans to total floor plans but also to relate individual buildings to complexes of buildings. Key plans shall be drawn in a convenient location and shall indicate the relative location of the represented plan area by crosshatching.

3.6.19 SPECIFICATIONS PLACED ON THE DRAWINGS

Details of standard products or items which are adequately covered by specifications shall not be included on the drawings.

3.6.20 REVISIONS

Drawing revisions shall be prepared only on the original CADD files. A revision area is required on all sheets.

3.6.21 BINDING

All volumes of drawing prints shall be firmly bound and shall have covers of heavier bond than the drawing sheets. If posts are used to fasten sheets together, the drilled holes on the bond edges of the sheets shall be on 8-1/2-inch centers.

3.6.22 GOVERNMENT PROVIDED FILES

At the Preconstruction meeting, the Contractor shall be provided a CD that shall contain the AED border sheet, the latest version of the AED Design Requirements documents, the A/E/C CADD standards, and various other files related to the compliancy of CADD files to the A/E/C CADD standards.

4. GENERAL STARTUP

4.1 DESIGN COORDINATION MEETING

Shortly after Notice To Proceed (NTP), the Government or Contractor may suggest meeting(s) to review the Design Submittal process or discuss various aspects of the contract to enable prompt and efficient initiation of contract actions. Meeting(s) will be held to assure attention is focused on key project requirements (necessary Contractor design and Government review that is required to provide Construction Clearance), to discuss features and items of work that need to be submitted early due to long lead time items, or discuss other concepts/ideas that will help accelerate the contract work. Other Design Coordination meetings may be requested throughout the contract period if Government review of various Contractor Design Submittals indicate poor design and plan or specification quality in order to clearly explain the changes and improvements required of the Contractor, assure understanding of Government comments, code references and required investigations and calculations, to move forward with acceptable design and satisfactory plans and specifications.

4.1.1 GOVERNMENT DESIGN CHANGES

Government design changes which do not increase construction costs shall be made at no charge to the Government. The Contracting Officer may request design submittals in addition to those listed when deemed necessary to adequately describe the work covered in the contract documents. Submittals shall be made in the respective number of copies and to the respective addresses set forth in the paragraph, Submittal Procedure. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

4.2 SUBMITTAL REGISTER

4.2.1 DESIGN SUBMITTALS

The Contractor shall submit, as part of this Project Schedule, Design Submittal milestone dates. The Contractor shall post all actual dates of submittal actions (including clearance for construction) as they occur.

4.2.2 CONSTRUCTION SUBMITTAL REGISTER (ENG FORM 4288)

Attached to this section is ENG Form 4288 which the Contractor is responsible for developing for this contract. All Design and construction submittals shall be shown on this register. The submittal register shall be the controlling document and will be used to control all submittals throughout the life of the contract. The Contractor shall maintain and update the register on a monthly basis for the Contracting Officer's approval.

4.3 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both design and construction submittals in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. This form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care will be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.

4.4 PROGRESS SCHEDULE

The Contractor shall prepare and submit a design progress schedule to the Contracting Officer. The Critical Path Method (CPM) of network calculation shall be used to generate the Project Schedule. The progress schedule shall show, as a percentage of the total design price, the various items included in the contract and the order in which the Contractor proposes to carry on the work, with dates on which he will start the features of the work and the contemplated dates for completing same. Significant milestones such as review submittals shall be annotated. The Contractor shall assign sufficient technical, supervisory and administrative personnel to insure the prosecution of the work in accordance with the progress schedule. The Contractor shall correct the progress schedule at the end of each month and submit as required to the Contracting Officer. The approved Project Schedule shall be used to measure the progress of the work, to aid in evaluating time extensions, and to provide the basis of all progress payments.

4.5 SCHEDULING

4.5.1 DESIGN SUBMITTALS

Adequate time (a minimum of 7 full calendar days exclusive of mailing time) shall be allowed for Government review and comment in DrChecks_{SM}. If the Contractor fails to submit design submittals in a

timely fashion, or repetitively submits design submittals that are not in strict conformance with the Contract documents, no part of the time lost due to such actions shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

4.5.2 CONSTRUCTION SUBMITTALS

Contractor furnished Government Approved Construction Submittals (GA) for items noted in this Section, or others as required by the COR, shall be submitted to the Area or Resident Office, per directions given at the Pre-Construction meeting. Adequate time (a minimum of 14 full calendar days exclusive of mailing time) shall be allowed for AED review and comment.

4.5.3 POST DESIGN CONSTRUCTION SUBMITTALS

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 14 full calendar days exclusive of mailing time) shall be allowed for review and approval. If the Contractor fails to submit post design construction submittals in a timely fashion, or repetitively submits submittals that are not in strict conformance with the Contract documents, no part of the time lost due to actions shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

4.6 SUBMITTAL PROCEDURE

4.6.1 AFGHANISTAN ENGINEER DISTRICT – SOUTH (AES)

DESIGN SUBMITTAL PROCEDURE

For all submittals the following must be included in the submittal package to be considered acceptable. Submittal package will include one (1) half-size hard copy and two (2) soft copies on CD-ROM (electronic version), ENG Form 4025, submittal cover sheet, ALL design drawings, ALL specifications, design analysis, site analysis, geotechnical report, and water quality report. All hard copies and soft copies should be arranged in identical format (See Section 1335 of contract and attachments). If Submittal is deemed unacceptable at pick up, submittal will be pushed back and a new arrangement for drop off will be coordinated at a future time and date.

POINT OF CONTACT

Arrangement for meeting and drop off must be coordinated 24-hrs prior to drop off. The preferred meeting time is during off peak hours between 11:00 am and 2:00 pm. Individual participating in submittal drop off must speak English or a translator must be present during transaction.

Area and/or Resident Engineer (AE/RE) Contacts:

Paul Apodaca – cell 079-366-7847, office 540-722-1079

Richard Jamar – cell 079-796-5142, office 540-662-2923

Note: Please state your name, company, contract title, and contract number that shall be discussed and received by USACE-AES personnel.

The Contractor shall scan the soft copy (electronic version) of each Design Submittal using most up-to-date version of recognized Industry-standard anti-virus software (Symantec, Norton, etc.) to insure that no viruses are contained in it prior to acceptance by AES. The label shall indicate it has been scanned for viruses and the anti-virus software and version clearly indicated.

4.6.2 RESIDENT/AREA ENGINEER OFFICE

Complete construction submittals shall be provided to the Area and/or Resident Engineer (AE/RE) Office. At the Pre-Construction meeting, the Contractor will be furnished the Area and/or Resident Office addresses to which these submittals shall be provided and the specific number of hard copies (full and half sizes) and soft copies (CD-ROM) required by the Area and/or Resident Office as stated herein. Soft copies are to be properly labeled and checked for viruses by the Contractor prior to delivery.

4.6.3 USE OF THE DESIGN

This is a Design-Build project and in accordance with Contract Clause 52.227-7022 GOVERNMENT RIGHTS (UNLIMITED), the Government has non-exclusive rights to use the design on other projects. Therefore, the As-Builts furnished to the Government must be in an editable format. See Section 01780A for all requirements associated with submission of editable CADD format As-Builts required as part of this contract.

4.6.4 POST DESIGN CONSTRUCTION SUBMITTALS

One (1) copy of all post design construction submittals shall be transmitted to:

Paul Apodaca, Area Engineer Office
U.S. Army Corps of Engineers
FOB Lindsey, Afghanistan

4.7 SUBMITTAL NUMBERING SYSTEM

Instructions on the numbering system to be used for construction submittals follows.

4.7.1.1 SUBMITTALS

Shop drawings and materials are listed on the Submittal Register (ENG Form 4288) as follows:

- a. List is prepared according to contract specifications and drawings, picking up all items involved in the project.
- b. This list is divided into Sections as indicated in the specifications. For example:

Section 01010	"SOW & Technical Requirements"
Section 01335	"Submittal Procedures For Design-Build Projects"
Section 02831	"Chain-Link Fence"
Section 02710	"Subdrainage System"
Section 03300	"Concrete For Building Construction"
Section 04200	"Masonry"

4.7.2 NUMBERING PROCEDURES FOR TRANSMITTAL ON ENG FORM 4025

Each specification section will have various requirements for submittals (design information, product data, test reports, procedures, etc.) to the Government for Approval (GA) or For Information Only (FIO). Items from different Sections cannot be submitted on the same ENG Form 4025. When furnishing one or more items from the same Section at a given time, a single ENG Form 4025 can be used to identify and submit these items. Block 'b' of the 4025 entitled "DESCRIPTION OF ITEM SUBMITTED" should provide an accurate and unique description of each item being proposed by the Contractor. Item numbers (block "a")

of the 4025 entitled "ITEM NO.") will be automatically generated in QCS for each ENG Form 4025. QCS will track and automatically generate the "ITEM NO." for all following ENG Form 4025s for the same Section number. To illustrate, a transmittal for Preliminary Project Site Surveys and Reports, required by Section 01335, might have the following Items:

- ITEM NO. 1 Topographic Information
- ITEM NO. 2 Geotechnical Report
- ITEM NO. 3 Foundation Design
- ITEM NO. 4 Plans
- ITEM NO. 5 Outline of Construction Specifications to be used (i.e. Specification list with Section number and title only)

If this was the first submittal furnished by the Contractor for Section 01335, then a Transmittal Number of 01335-1 would be generated using QCS. As new transmittals are generated in QCS, the last digit of the transmittal is increased incrementally, as follows:

Transmittal No. 01335-2

Transmittal No. 01335-3

Transmittal No. 01335-4

and so forth. The first transmittal submitted from each Specification Section will be "-1", in other words, there will never be a "Transmittal No. 01335-0".

The above illustration is true for all other Sections included in the Request for Proposal or in the Construction Specifications compiled by the Contractor in the prosecution of work under the RFP.

4.7.3 RESUBMITTALS

Should the Contractor be required to resubmit any transmittal due to one or more items on that transmittal being Coded "C" (Cleared for Construction, except as noted in attached comments, Resubmission Required) or "E" (NOT Cleared for Construction, see attached comments, Resubmission Required) by the Government, QCS will be used to generate the same transmittal number followed by the number "-1" for the first resubmittal, "-2" for the second resubmittal, "-3" for the third resubmittal, etc.

As an example, assume the Design Construction Review Submittal is provided to the Government as Transmittal 01335-9. Due to omissions or errors in that Submittal which result in a Code "E" being given, then the subsequent Design Construction Review Resubmittal #1 would be "Transmittal 01335-9.1". Should a resubmittal again be necessary, it would be Design Resubmittal #2 and would be submitted as "Transmittal 01335-9.2".

The purpose of this system is to avoid deviations from the Submittal Register and to track submittals in both RMS and DrChecks_{SM}. It should be noted that a new transmittal number following the above system CANNOT be generated in QCS unless the prior transmittal has been given a Code If the Contractor is having difficulty generating the correct transmittal number, contact the COR to resolve the matter.

The Contractor use the above nomenclature and date of submission to the Government for Plan Cover Sheets; title blocks for all drawings; all Specification Cover Sheets; all specification pages; all Design Analysis Cover Sheets and associated pages; and similar labeling for all other documents included in the submittal.

See the attachment titled "1335a-Attachments-AED.pdf" (Figures 1-4) for required Title Block Required Annotations drawing guidance.

4.7.4 VARIATION SUBMITTALS

If Design or construction submittals show variations from the contract parameters and/or requirements, the Contractor shall justify such variations in writing, at the time of submission. Additionally, the Contractor shall also annotate block "h" entitled "variation" of ENG FORM 4025. After design submittals have been reviewed and cleared for construction by the Contracting Officer, no resubmittal for the purpose of substituting materials, equipment, systems, and patented processes will be considered unless accompanied by the following:

- a. Reason or purpose for proposed variation, substitution, or revision.
- b. How does quality of variation compare with quality of the specified item? This shall be in the form of a technical evaluation tabulating differences between the item(s) originally specified and what is proposed.
- c. Provide a cost comparison. This shall include an acquisition and life cycle cost comparison.
- d. For proprietary materials, products, systems, and patented processes a certification signed by an official authorized to certify in behalf of the manufacturing company that the proposed substitution meets or exceeds what was originally specified.
- e. For all other actions, a certification signed by a licensed professional engineer or architect certifying that the proposed variation or revision meets or exceeds what was originally specified.
- f. Advantage to the Government, if variation is approved, i.e. Operation and Maintenance considerations, better product, etc.
- g. Ramifications and impact, if not approved.

If the Government review detects any items not in compliance with contract requirements or items requiring further clarification, the Contractor will be so advised. Lack of notification by the Contracting Officer of any non-complying item does not relieve the Contractor of any contractual obligation.

4.7.5 NON-COMPLIANCE NOTICE

The Contracting Officer will notify the Contractor of any detected noncompliance with the requirements of this specification. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the worksite, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

4.8 REVIEW OF CONTRACTOR PREPARED DESIGN CONSTRUCTION DOCUMENTS

4.8.1 GENERAL

The work under contract will be subject to continuous review by representatives of the Contracting Officer. Additionally, joint design review conferences with representation by all organizations having a direct interest in the items under review may be held. The Contractor shall furnish copies of all drawings and related documents to be reviewed at the review conference on or before the date indicated by the Government. Additional conferences pertaining to specific problems may be requested by the Contractor or may be directed by the Contracting Officer as necessary to progress the work. The Contractor shall prepare minutes of all conferences and shall furnish two copies to the Contracting Officer within seven (7) days after the conference.

4.8.2 INDEPENDENT DESIGN REVIEW

The Contractor shall have someone other than the Designer or Design Team perform an Independent Technical Review (ITR) of all specifications, drawings, design analysis, calculations, and other required data prior to submission to the Government. This review shall insure the professional quality, technical accuracy, and the coordination of all design analysis, drawings and specifications, and other services furnished under this contract have been accomplished. Work must be organized in a manner that will assure thorough coordination between various details on drawings, between the various sections of the specifications, and between the drawings and specifications. The Contractor shall thoroughly cross-check and coordinate all work until he is professionally satisfied that no conflicts exist, vital information has not been omitted, and that indefinite language open to interpretation has been resolved. Upon completion of this review, the Contractor shall certify that each design submittal is complete, accurate, is in strict conformance with all contract requirements, that repetition has been avoided, that all conflicts have been resolved, and that the documents have thoroughly coordinated and cross checked against all the applicable disciplines to prevent the omission of vital information.

4.8.3 CONTRACTOR'S QUALITY CONTROL (CQC) ORGANIZATION REVIEW

The Contractor shall thoroughly review each submittal prior to submission to the Contracting Officer to assure it is complete, correct and unified. This review shall be for the purposes of eliminating errors, interferences, and inconsistencies, and of incorporating design criteria, review comments, specifications, and any additional information required. The Contractor will give evidence of such review of all items in each submittal ENG Form 4025, by annotating Column "g" (titled "For Contractor Use Code") of this Form with the letter "A," meaning the Contractor has reviewed it and is indicating it is "Approved as Submitted". Design submittals submitted to the Contracting Officer without evidence of the above requirements or the Contractor's certified approval will be returned for resubmission. No part of the time lost due to such resubmissions shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

4.8.4 GOVERNMENT REVIEW

- a. Within 14 days after Notice to Proceed, the Contractor shall submit, for approval, a complete design schedule with all submittals and review times indicated in calendar dates. The Contractor shall update this schedule monthly. After receipt, the Government will be allowed 14 full days to review and comment on all Design Submittals, except as noted below. This time period starts on the next full day after delivery of the Design Submittal to the Government.
- b. If a design submittal is deficient (errors on ENG Form 4025, incorrect drawing title block information, missing or incomplete features required in the Submittal, etc.), it will be returned immediately without further review for correction and resubmission. The review time will begin when the corrected submittal is received. The Contractor may be liable for liquidated damages owed to the Government for returned design submittals due to deficiencies.
- c. The Contractor shall not begin construction work until the Government has reviewed the Contractor's Design Submittal and cleared it for construction. Clearance for construction does not mean Government approval. Government review shall not be construed as a complete check but will evaluate the general design approach and adherence to contract parameters. The Government Review is often limited in time and scope. Therefore, the Contractor shall not consider any review performed by the Government as an excuse for incomplete work.
- d. Upon completion of the review the Contractor will be notified by the Contracting Officer Representative that the DrChecks_{SM} file is open for viewing and response to AED comments. The Contracting Officer will indicate whether the Design Submittal, or portions thereof, has or has not been cleared for construction using the following action codes:

A – Cleared for Construction

- B – Cleared for Construction, except as noted in attached comments
- C – Cleared for Construction, except as noted in attached comments,
Re-submission required
- E - NOT Cleared for Construction, see attached comments,
Re-submission required
- FX – Receipt acknowledged, does not comply as noted with contract requirements.

These codes shall **NOT** be used by the Contractor.

Design submittals Cleared for Construction by the Contracting Officer shall NOT relieve the Contractor from responsibility for any design errors or omissions and any liability associated with such errors, nor from responsibility for complying with the requirements of this contract.

4.8.5 INCORPORATION OF GOVERNMENT REVIEW COMMENTS

- a. The Contractor shall review each comment, furnish a complete response in DrChecks_{SM} as to how the comment will be addressed in the Design Analysis, Plans and Specifications, or other Design Submittal stipulations required in this Contract. The Contractor will then incorporate each comment into the design submittal along with other work required at the next Design Submittal stage. The Contractor shall furnish disposition of all comments in DrChecks_{SM}, with the next scheduled submittal. The disposition shall identify action taken with citation of location within the relevant design document. Generalized statements of intention such as "will comply" or "will revise the specification" are not acceptable. During the design review process, comments will be made on the design submittals that will change the drawings and specifications. The Government will make no additional payments to the Contractor for the incorporation of comments. Review comments are considered part of the contract administration process.
- b. If the Contractor disagrees technically with any comment or comments and does not intend to comply with the comment, he must clearly outline, with ample justification, the reasons for noncompliance within five (5) days after close of review period in order that the comment can be resolved.
- c. The Contractor is cautioned that if he believes the action required by any comment exceeds the requirements of this contract, he should flag the comment in DrChecks_{SM} as a scope change, and notify the COR in writing immediately.
- d. If a design submittal is over one (1) day late in accordance with the latest design schedule, the Government review period may be extended seven (7) days. Submittal date revisions must be made in writing at least five (5) days prior to the submittal.

4.8.6 CONFERENCES

As necessary, conferences will be conducted between the Contractor and the Government to resolve review comments.

A review conference may be held at the completion of AED review and subsequent Contractor response for each design submittal. The review conference will be held at the Corps Area/Resident Engineer (AE/RE) Office. The Contractor shall bring the personnel that developed the design construction submittal to the review conference.

4.9 DESIGN DEFICIENCIES

Design deficiencies noted by the Government shall be corrected prior to the start of design for subsequent features of work which may be affected by, or need to be built upon, the deficient design work.

4.9.1 DESIGN DISCREPANCIES

The Contractor shall be responsible for the correction of incomplete design data, omissions, and design discrepancies which become apparent during construction. The Contractor shall provide the Contracting Officer with a proposed recommendation for correcting a design error, within three (3) calendar days after notification by the Contracting Officer. The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the worksite, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor. Should extensions of design, fabrication plans and/or specific manufacturer's details be required as a result of a Government issued Change Order, the Government will make an equitable adjustment in accordance with Contract Clause 52.243-4 entitled CHANGES.

4.10 PHASED OR "FAST-TRACK" DESIGN

4.10.1 GENERAL PROCEDURES

If approved by the Government, design and construction sequencing may be effected on an incremental basis as each approved phase or portion (e.g., demolition, geotechnical, site work, exterior utilities, foundations, substructure, superstructure, exterior closure, roofing, interior construction, mechanical, electrical, etc.) of the design is completed.

4.10.2 DESIGN PHASES

Complete or partial design phasing may or may not have been specified by the Government elsewhere in this contract. For construction sequencing or phasing that the Government has not specifically mandated, the Design-Build Contractor may submit a proposed phasing plan. Design phasing proposed by the Design-Build Contractor shall be submitted to the Government for approval.

4.10.3 SEQUENCE OF DESIGN-CONSTRUCTION (FAST-TRACK)

After receipt of the Contract Notice to Proceed (NTP) the Contractor shall initiate design, comply with all design submission requirements and obtain Government review of each submission. The contractor may begin construction on portions of the work for which the Government has reviewed the final design submission and has determined satisfactory for purposes of beginning construction. The Contracting Officer will notify the Contractor when the design is cleared for construction. The Government will not grant any time extension for any design resubmittal required when, in the opinion of the Government, the initial submission failed to meet the minimum quality requirements as set forth in the contract.

4.10.4 CLEARANCE FOR CONSTRUCTION FOR LIMITED CONSTRUCTION

If the Government allows the Contractor to proceed with limited construction based on pending minor revisions to the reviewed design construction submission, no payment will be made for any in-place construction related to the pending revisions until they are completed, resubmitted, and satisfactory to the Government.

4.10.5 IN-PLACE CONSTRUCTION PAYMENT

No payment will be made for any in-place construction until all required submittals have been made, reviewed and are satisfactory to the Government.

4.10.6 COMMENCEMENT OF CONSTRUCTION

Construction of work may begin after receipt of the clearance for construction for each design phase. Any work performed by the Contractor prior to receipt of the clearance for construction, shall be at the Contractor's own risk and expense. Work cleared for construction that does not conform to the design parameters and/or requirements of this contract shall be corrected by the Contractor at no additional cost or time to the Government.

4.11 CONDUCTION OF WORK

4.11.1 PERFORMANCE

Perform the work diligently and aggressively, and promptly advise the Contracting Officer of all significant developments.

4.11.2 TELEPHONE CONVERSATIONS

Prepare a summary, and promptly furnish a copy thereof to the Contracting Officer, of all telephone conversations relating to the design work under this contract.

4.11.3 COOPERATION WITH OTHERS

Cooperate fully with other firms, consultants and Contractors performing work under the program to which this contract pertains, upon being advised by the Contracting Officer that such firms or individuals have a legitimate interest in the program, have need-to-know status, and proper security clearance where required.

4.11.4 TECHNICAL CRITERIA

All designs, drawings, and specifications shall be prepared in accordance with the contract documents and with the applicable publications referenced therein. As soon as possible, the Contractor shall obtain copies of all publications applicable to this contract. Any deviations from the technical criteria contained in the contract documents or in the applicable publications, including the use of criteria obtained from the user or other sources, must receive prior approval of the Contracting Officer. Where the technical criteria contained or referred to herein are not met, the Contractor will be required to conform his design to the same at his own time and expense.

4.11.5 CONFLICTS

Any conflicts, ambiguities, questions or problems encountered by the Contractor in following the criteria shall be immediately submitted in writing to the Contracting Officer with the Contractor's recommendations. Prior to submission to the Government the Contractor shall take appropriate measures to obtain clarification of design criteria requirements, to acquire all pertinent design information, and to incorporate such information in the work being performed.

4.11.6 DESIGN PRIORITIES

The design of this project shall consider the remote location and harsh environment of this project and the impact this will have on sources of technical supply, the cost of construction, the low level of maintenance, and the difficulty of obtaining replacement parts. Unless stated otherwise in this contract, the following design priorities shall be followed.

4.11.6.1 CONSTRUCTION LIFE SPAN LEVELS

Permanent Construction. Buildings and facilities shall be designed and constructed to serve a life expectancy of more than 25 years, to be energy efficient, and to have finishes, materials, and systems that are low maintenance and low life-cycle cost.

4.11.6.2 OPERABILITY

Systems including but not necessarily limited to mechanical, electrical, communications, etc., must be simple to operate and easy to maintain.

4.11.6.3 STANDARDIZATION

Use of standardized materials, products, equipment, and systems is necessary to minimize the requirements for replacement parts, storage facilities, and service requirements.

4.11.6.4 TOPOGRAPHIC SURVEYS, EASEMENTS, & UTILITIES

Unless otherwise stated in the contract, the Contractor will be responsible for detailed topographic mapping, available easements, and utility information for the project.

4.11.6.5 HORIZONTAL & VERTICAL CONTROL

The mapping shall be based on the base coordinate system. If the base system cannot be found, the surveyor shall use any established monuments. If monuments have been destroyed or do not exist, an assumed horizontal and vertical datum shall be established, using arbitrary coordinates of 10,000n and 10,000e and an elevation of 1,000 meters. The horizontal and vertical control established on site shall be a closed loop with third order accuracy and procedures. Provide three (3) concrete survey monuments at the survey site. All of the control points established at the site shall be plotted at the appropriate coordinate point and shall be identified by name or number, and adjusted elevations. The location of the project site, as determined by the surveyor shall be submitted in writing to the Contracting Officer. The site location shall be identified by temporary markers, approved by the Contracting Officer before proceeding with the surveying work.

4.11.6.6 TOPOGRAPHY REQUIREMENTS

A sufficient quantity of horizontal and vertical control shall be established to provide a detailed topographic survey at 1:500 scale with one quarter meter contour intervals minimum. Intermediate elevations shall be provided as necessary to show breaks in grade and changes in terrain.

The contours shall accurately express the relief detail and topographic shapes. In addition, 90 percent of the elevations or profiles interpolated from the contours shall be correct to within one-half of the contour interval and spot elevations shall be correct within plus or minus 20 millimeters.

Spot elevations affecting design of facilities shall be provided. Specifically, break points or control points in grades of terrain such as tops of hills, bottoms of ditches and gullies, high bank elevations, etc.

All surface and sub-surface structures features within the area to be surveyed shall be shown and identified on the topographic maps. In addition, these features shall be located by sufficient distance ties and labeled on the topographic sheets to permit accurate scaling and identification.

The location and sizes of potable, sanitary, electrical and mechanical utilities within the survey site shall be shown on the survey map. Sanitary manholes and appurtenances shall show top elevations and invert elevations.

4.11.6.7 CATHODIC PROTECTION & EARTH RESISTANCE

Unless otherwise stated in the contract, the Contractor will be responsible for determining whether cathodic protection on buried structures and underground utility systems are needed for special electrical grounding and counterpoise systems, and for gathering the field data necessary for design.

4.11.6.8 WATER SUPPLY & QUALITY DATA

Unless otherwise stated in the contract, the Contractor will be responsible for obtaining all water supply and water quality data. This data will include information on the locations and depths of all viable water supply sources at the site(s) involved and a water quantity and water quality analysis for each source.

4.11.6.9 OCCUPATIONAL SAFETY & HEALTH ACT

The facilities, systems, and equipment designed under this contract shall comply with the Occupational Safety and Health Act (OSHA), Code of Federal Regulations, Title 29, Chapter XVII, Parts 1910 and 1926. Any problems in incorporating these standards due to conflicts with other technical criteria shall be submitted to the Contracting Officer for resolution.

4.11.6.10 ASBESTOS CONTAINING MATERIALS

Asbestos containing material (ACM) will not be used in the design of new structures or systems. In the event no other material is available which will perform the required function or where the use of other material would be cost prohibitive, a waiver for the use of asbestos containing materials must be obtained from AED.

4.11.6.11 EXISTING CONSTRUCTION

Asbestos containing materials (ACM) presently included in existing construction to be rehabilitated or otherwise modified as a result of this project shall be removed and a non-asbestos containing material substituted in lieu thereof.

4.11.6.12 SUSPECTED ASBESTOS CONTAINING MATERIALS

All such structures and systems shall be inspected to determine the presence or probable presence of ACM. When ACM is suspected, a documented survey will be performed. The survey will be developed into an abatement design and will be made a part of the design documents. In the event no other material is available which will perform the required function or the use of a substitute material would be cost prohibitive due to initial cost and tear-out of existing construction, a waiver for the retention of the asbestos containing material must be obtained from the Contracting Officer.

4.12 ATTACHMENTS

The following attachments form an integral part of this specification:

ENG FORM 4025R, Mar 95 - Transmittal of Shop Drawings, Equipment Data, Material Samples, or Manufacturer's Certificate of Compliance (2 pages).

ENG FORM 4288-R, Mar 95 - Submittal Register.

Figure 1 – AED Title Block.

Figure 2 - AED Management Block.

Figure 3 - AED Issue Block & Required Notations.

Figure 4 - Border Sheet Size.

--END OF SECTION--

INSTRUCTIONS

1. Section I will be initiated by the Contractor in the required number of copies.
2. Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial number for identifying each submittal. For new submittals or resubmittals mark the appropriate box; on resubmittals, insert transmittal number of last submission as well as the new submittal number.
3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288-R for each entry on this form.
4. Submittals requiring expeditious handling will be submitted on a separate form.
5. Separate transmittal form will be used for submittals under separate sections of the specifications.
6. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications--also, a written statement to that effect shall be included in the space provided for "Remarks".
7. Form is self-transmittal, letter of transmittal is not required.
8. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I.
9. U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below in Section I, column g, to each item submitted.

THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED

- | | | | |
|------|--|-------|---|
| A -- | Approved as submitted. | E -- | Disapproved (See attached). |
| B -- | Approved, except as noted on drawings. | F -- | Receipt acknowledged. |
| C -- | Approved, except as noted on drawings.
Refer to attached sheet resubmission required. | FX -- | Receipt acknowledged, does not comply
as noted with contract requirements. |
| D -- | Will be returned by separate correspondence. | G -- | Other (Specify) |
10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

(Reverse of ENG Form 4025-R)

PROJECT INFO
4 LINES ALLOWED

PROJECT ID BLOCK
SHEET TITLE BLOCK

SHEET IDENTIFICATION BLOCK

DISCIPLINE DESIGNATOR

SHEET NUMBER

TOTAL NUMBER OF SHEETS

PROJECT TITLE	PROJECT LOCATION	DESCRIPTION OF DRAWING
	BUILDING TYPE	

SHEET REFERENCE NUMBER:	
X-XXX	
SHEET --	OF --

SHEET TITLE
3 LINES ALLOWED

SHEET SEQUENCE NUMBER

Figure 1: AED-S Title Block

MANAGEMENT BLOCK

U.S. ARMY CORPS OF ENGINEERS AFGHANISTAN ENGINEER DISTRICT - SOUTH APO AE 09355 KANDAHAR, AFGHANISTAN	DESIGNED BY:		DATE:	REV.
	DWN BY:	CKD BY:	xx-xx-xx DESIGN FILE NO.	___
	REVIEWED BY:		DRAWING CODE:	
	SUBMITTED BY:		FILE NAME:	___
ENGINEERING AND CONSTRUCTION DIVISION			PLOT SCALE:	___
			PLOT DATE:	xx-xx-xx

AE DESIGN FIRM
COMPANY LOGO
COMPANY INFORMATION

Figure 2: AED-S Management Block

Figure 3: AED-S Issue Block

<p>DESIGNER IDENTIFICATION BLOCK (DO NOT ALTER)</p> 		<p>ISSUE BLOCK</p>		G		H	
				G		H	
SYMBOL	DESCRIPTION	DATE	APPR.	SYMBOL	DESCRIPTION	DATE	APPR.
	AS-BUILT SUBMITTAL	15 DEC 10			REVISED AS-BUILT	28 DEC 10	
	100% DESIGN SUBMITTAL	15 APR 10		▲			
	99% DESIGN RESUBMITTAL NO. 1	1 APR 10					
	98% DESIGN SUBMITTAL	15 MAR 10					
	65% DESIGN RESUBMITTAL NO. 1	1 MAR 10		▲	MOD P0003	8 MAR 10	
	65% DESIGN SUBMITTAL	1 FEB 10		▲	MOD P0002	27 FEB 10	
	35% DESIGN SUBMITTAL	1 JAN 10		▲	AMMENDMENT P0001	13 JAN 10	

594

570

841
748




Figure 4: AED-S Sheet Dimensions

A1 Size 594mm x 841mm

SHEET NUMBER TOTAL NUMBER OF SHEETS

SHEET IDENTIFICATION BLOCK DISCIPLINE DESIGNATOR SHEET SEQUENCE NUMBER

PROJECT INFO 4 LINES ALLOWED PROJECT TITLE SHEET TITLE 3 LINES ALLOWED

MANAGEMENT BLOCK AE DESIGN FIRM COMPANY LOGO COMPANY INFORMATION

ISSUE BLOCK

DESIGNER IDENTIFICATION BLOCK (DO NOT ALTER)

SECTION 01415

METRIC MEASUREMENTS

1. REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E 621	(1994; R 1999e1) Use of Metric (SI) Units in Building Design and Construction (Committee E-6 Supplement to E380)
ASTM SI 10	(2002) American National Standard for Use of the International System of Units (SI): The Modern Metric System

2. GENERAL

This project includes metric units of measurements. The metric units used are the International System of Units (SI) developed and maintained by the General Conference on Weights and Measures (CGPM); the name International System of Units and the international abbreviation SI were adopted by the 11th CGPM in 1960. A number of circumstances require that both metric SI units and English inch-pound (I-P) units be included in a section of the specifications. When both metric and I-P measurements are included, the section may contain measurements for products that are manufactured to I-P dimensions and then expressed in mathematically converted metric value (soft metric) or, it may contain measurements for products that are manufactured to an industry recognized rounded metric (hard metric) dimensions but are allowed to be substituted by I-P products to comply with the law. Dual measurements are also included to indicate industry and/or Government standards, test values or other controlling factors, such as the code requirements where I-P values are needed for clarity or to trace back to the referenced standards, test values or codes.

3. USE OF MEASUREMENTS IN SPECIFICATIONS

Measurements in specifications shall be either in SI or I-P units as indicated, except for soft metric measurements or as otherwise authorized. When only SI or I-P measurements are specified for a product, the product shall be procured in the specified units (SI or I-P) unless otherwise authorized by the Contracting Officer. The Contractor shall be responsible for all associated labor and materials when authorized to substitute one (1) system of units for another and for the final assembly and performance of the specified work and/or products.

3.1 HARD METRIC

A hard metric measurement is indicated by an SI value with no expressed correlation to an I-P value. Hard metric measurements are often used for field data such as distance from one (1) point to another or distance above the floor. Products are considered to be hard metric when they are manufactured to metric dimensions or have an industry recognized metric designation.

3.2 SOFT METRIC

- a. A soft metric measurement is indicated by an SI value which is a mathematical conversion of the I-P value shown in parentheses (e.g. 38.1 mm (1-1/2 inches)). Soft metric measurements are used for measurements pertaining to products, test values, and other situations where the I-P

units are the standard for manufacture, verification, or other controlling factor. The I-P value shall govern while the metric measurement is provided for information.

- b. A soft metric measurement is also indicated for products that are manufactured in industry designated metric dimensions but are required by law to allow substitute I-P products. These measurements are indicated by a manufacturing hard metric product dimension followed by the substitute I-P equivalent value in parentheses (e.g., 190 x 190 x 390 mm (7-5/8 x 7-5/8 x 15-5/8inches)).

3.3 NEUTRAL

A neutral measurement is indicated by an identifier which has no expressed relation to either an SI or an I-P value (e.g., American Wire Gage (AWG) which indicates thickness but in itself is neither SI nor I-P).

3.4 COORDINATION

Discrepancies, such as mismatches or product unavailability, arising from use of both metric and non-metric measurements and discrepancies between the measurements in the specifications and the measurements in the drawings shall be brought to the attention of the Contracting Officer for resolution.

3.5 RELATIONSHIP TO SUBMITTALS

Submittals for Government approval or for information only shall cover the SI or I-P products actually being furnished for the project. The Contractor shall submit the required drawings and calculations in the same units used in the contract documents describing the product or requirement unless otherwise instructed or approved. The Contractor shall use ASTM SI 10 and ASTM E 621 as the basis for establishing metric measurements required to be used in submittals.

-- END OF SECTION --

SECTION 01451

CONTRACTOR QUALITY CONTROL (CQC)

1. GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. Army Corps Of Engineers (USACE)

ER 1110-1-12 (1993)

Quality Management

EM 385-1-1

Safety and Health Requirements Manual

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

2. EXECUTION

2.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clauses and this specification section. The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

2.2 CONSTRUCTION QUALITY MANAGEMENT (CQM) TRAINING REQUIREMENT

Before project design and construction begin, the Contractor's Quality Control Manager is required to have completed the U.S. Army Corps of Engineers (USACE) Construction Quality Management (CQM) course, or equivalent. The CQM course will be offered periodically by the Afghanistan Engineer District-South (AED-S), USACE. Additional approved CQM courses include those offered by the Commercial Technical Training Center (in Jalalabad) and the Champion Technical Training Center (in Kabul). The Quality Assurance Branch (QAB) of the AED-S can provide information related to AED-S offerings of the

CQM course, as well as contact information for training centers. Alternative CQM courses, other than those mentioned above, must be approved by QAB.

The contractor's quality control plan, as defined in USACE Guide Specification 01451 (or 01 45 04.00 10), entitled "Contractor Quality Control," must include "The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function." For the QC Manager, qualifications must include a certificate demonstrating completion of an approved CQM course.

2.3 QUALITY CONTROL PLAN

The Contractor shall furnish for review by the Government, not later than five (5) days after receipt of Notice-to-Proceed (NTP) the proposed Contractor Quality Control (CQC) Plan. The plan shall identify personnel, procedures, control, instructions, records, and forms to be used.

2.3.1 CONTENT OF THE CQC PLAN

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both on site and off-site, including work by subcontractors, fabricators, suppliers and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the 3-phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project superintendent.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, consultants, and purchasing agents. These procedures shall be in accordance with Specification 01335, Submittal Procedures.
- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test.
- f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be

considered as a definable feature of work, there are frequently more than one (1) definable features under a particular section. This list will be agreed upon during the coordination meeting.

2.3.2 ADDITIONAL REQUIREMENTS FOR DESIGN QUALITY CONTROL (DQC) PLAN

The following additional requirements apply to the Design Quality Control (DQC) plan:

- a. The Contractor shall provide and maintain a Design Quality Control (DQC) Plan as an effective quality control program which will assure that all services required by this design construction contract are performed and provided in a manner that meets professional architectural and engineering quality standards. As a minimum, all documents shall be technically reviewed by competent, independent reviewers identified in the DQC Plan. The same element that produced the product shall not perform the independent technical review (ITR). The Contractor shall correct errors and deficiencies in the design documents prior to submitting them to the Government.
- b. The Contractor shall include the design schedule in the master project schedule, showing the sequence of events involved in carrying out the project design tasks within the specific contract period. This should be at a detailed level of scheduling sufficient to identify all major design tasks, including those that control the flow of work. The schedule shall include review and correction periods associated with each item. This should be a forward planning as well as a project monitoring tool. The schedule reflects calendar days and not dates for each activity. If the schedule is changed, the Contractor shall submit a revised schedule reflecting the change within 7 calendar days. The Contractor shall include in the DQC Plan the discipline-specific checklists to be used during the design and quality control of each submittal. These completed checklists shall be submitted at each design phase as part of the project documentation. Example checklists can be found in ER 1110-1-12.
- c. The DQC Plan shall be implemented by an Design Quality Control Manager who has the responsibility of being cognizant of and assuring that all documents on the project have been coordinated. This individual shall be a person who has verifiable engineering or architectural design experience and is a registered professional engineer or architect. The Contractor shall notify the Contracting Officer, in writing, of the name of the individual, and the name of an alternate person assigned to the position.

The Contracting Officer will notify the Contractor in writing of the acceptance of the DQC Plan. After acceptance, any changes proposed by the Contractor are subject to the acceptance of the Contracting Officer.

2.3.3 ACCEPTANCE OF PLAN

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in the CQC plan and operations including removal of personnel, as necessary, to obtain the quality specified.

2.3.4 NOTIFICATION OF CHANGES

Notification of Changes. After acceptance of the QC plan, the Contractor shall notify the Contracting Officer in writing a minimum of seven (7) calendar days prior to any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

2.4 COORDINATION MEETING

After the Pre-construction Conference, before start of construction, and prior to acceptance by the Government of the Quality Control Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted for review a minimum of 5 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both on-site and off-site work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures, which may require corrective action by the Contractor.

2.5 QUALITY CONTROL ORGANIZATION

2.5.1 PERSONNEL REQUIREMENTS

The requirements for the CQC organization are a CQC System Manager, and sufficient number of additional qualified personnel to ensure safety and contract compliance. Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly will also be included as part of the CQC organization. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, shop drawing submittals, schedules and all other project documentation shall be promptly furnished to the CQC organization by the Contractor. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

2.5.2 CQC SYSTEM MANAGER

The Contractor shall identify an individual within his organization at the site of the work who shall be responsible for overall management of the CQC and have the authority to act in all CQC matters for the Contractor. The CQC system manager shall be a graduate engineer, graduate architect, or a graduate construction manager, with experience on construction projects similar in type to this contract OR a construction person with a minimum of ten (10) years in related work. The CQC System Manager shall be on the site at all times during construction and shall be employed by the Contractor. The CQC System Manager shall be assigned no other duties. An alternate for the CQC System Manager will be identified in the plan to serve in the event of the CQC system manager's absence. The requirements for the alternate will be the same as for the designated CQC manager.

2.5.3 ADDITIONAL REQUIREMENT

In addition to the above experience and/or education requirements, the CQC System Manager shall have completed the course entitled "Construction Quality Management For Contractors". This course is periodically offered by the government, and inquiries as to the next course offering may be directed to the local construction field office.

2.5.4 ORGANIZATIONAL CHANGES

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

2.6 SUBMITTALS & DELIVERABLES

Submittals, if needed, shall be made as specified in the STR titled SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements.

2.7 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three (3) phases of control shall be conducted by the CQC System Manager for each definable feature of the construction work as follows:

2.7.1 PREPARATORY PHASE

This phase shall be performed prior to beginning work on each definable feature of work, after all required documents and materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards, in the English language unless specifically approved otherwise by the Contracting Officer, applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.
- b. A review of the contract drawings.
- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. A check to assure that provisions have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to verify that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.

- g. Reviews of the appropriate activity hazard analysis to ensure safety requirements are met.
- h. Discussion of procedures for constructing the work including repetitive deficiencies, construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the Contracting Officer has accepted the portion of the plan for the work to be performed.
- j. Discussion of the initial control phase.
- k. The Government shall be notified at least 24-hours in advance of beginning any of the required action of the preparatory phase. This phase shall include a meeting conducted by the CQC system manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC system manager and attached to the daily QC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

2.7.2 INITIAL PHASE

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of preliminary work to ensure that it is in compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verification of full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with sample panels as appropriate.
- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 24-hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC system manager and attached to the daily QC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work on-site, or any time acceptable specified quality standards are not being met.

2.7.3 FOLLOW-UP PHASE

Daily checks shall be performed to assure continuing compliance with contract requirements, including control testing, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted, and all noted deficiencies corrected, prior to the start of additional features of work that may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

2.7.4 ADDITIONAL PREPARATORY AND INITIAL PHASES

Additional preparatory and initial phases may be required by the Contracting Officer on the same definable features of work if the quality of on-going work is unacceptable; if there are changes in the applicable QC staff or in the on-site production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

2.8 TESTS

2.8.1 TESTING PROCEDURE

The Contractor shall perform tests specified or required to verify that control measures are adequate to provide a product that conforms to contract requirements. Upon request, the Contractor shall furnish to the Government duplicate samples of test specimens for possible testing by the Government. Costs incidental to the transportation of samples or materials shall be borne by the Contractor.

Testing includes operation and/or acceptance tests when specified. A list of tests to be performed shall be furnished as a part of the CQC plan. The list shall give the test name, frequency, specification paragraph containing the test requirements, the personnel and laboratory responsible for each type of test, and an estimate of the number of tests required. The Contractor shall perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.
- e. Results of all tests taken, both passing and failing tests, shall be recorded on the Quality Control report for the date taken. Specification paragraph/item reference, location where tests were taken, and the sequential control number identifying the test will be given. Actual test reports may be submitted later, if approved by the Contracting Officer, with a reference to the test number and date taken. An information copy of tests performed by an off-site or commercial test facility will be provided directly to the Contracting Officer. Failure to submit timely test reports, as stated, may result in nonpayment for related work performed and disapproval of the test facility for this contract.

2.9 COMPLETION INSPECTION

2.9.1 PUNCH-OUT INSPECTION

Near the end of the work, or any increment of the work established by a time stated in the Special Contract Requirements Clause, "Commencement, Prosecution, and Completion of Work", or by the specifications, the CQC Manager shall conduct an inspection of the work. A punch list of items which do not conform to the approved drawings and specifications shall be prepared and included in the CQC documentation, as required by paragraph, Documentation. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.9.2 Pre-Final Inspection

The Government will perform the pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates.

2.9.2 FINAL ACCEPTANCE INSPECTION

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at the final acceptance inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14-days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3. DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Offsite surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.

j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one (1) copy of these records in report form shall be furnished to the Government daily within 48-hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one (1) report shall be prepared and submitted for every seven (7) days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.1 SAMPLE FORMS

In accordance with Specification 01312, Quality Control System, the contractor shall use the forms produced by and printed from QCS. Samples of any forms required to meet the requirements of this section which are not produced by that system shall be included in the contractors Quality Control Plan.

3.2 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

-- END OF SECTION --

SECTION 01525

SAFETY & OCCUPATIONAL HEALTH REQUIREMENTS

1. GENERAL

For Contractor safety on projects associated with this program, compliance with EM 385-1-1 (latest edition) safety requirements will be the long-term goal reached by growing a safety culture. This compliance will, by necessity, be achieved through a phased-in process. In the Commander's letter at the preface of the EM 385-1-1, he acknowledges that in OCONUS locations, strict compliance with the manual may not be possible – and through the hazard analysis process, safety measures can be developed to attain the same degree of safety.

This specification consists of two (2) parts:

1. Sections 1.1 through 2.10.1, which are the standard safety specifications for work in Afghanistan District and the references listed below:
2. Appendix A, Phasing approach for safety in emerging countries where there is little or no national safety standards.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE)

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/ASSE A10.32 Personal Fall Protection - Safety Requirements for Construction and Demolition Operations

ANSI/ASSE Z359.1 (2007) Safety Requirements for Personal Fall Arrest Systems, Subsystems and Components

ASME INTERNATIONAL (ASME)

ASME B30.3 (2009) Construction Tower Cranes

ASME B30.22 (2005) Articulating Boom Cranes

ASME B30.5 Mobile and Locomotive Cranes

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10 (2010) Portable Fire Extinguishers

NFPA 241 (2010) Safeguarding Construction, Alteration, and Demolition Operations

NFPA 51B (2009) Fire Prevention During Welding, Cutting, and Other Hot Work

NFPA 70(2008) National Electrical Code

NFPA 70E (2009) Electrical Safety in the Workplace

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2008) Safety and Health Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards (OSHA)
29 CFR 1910.146	Permit-required Confined Spaces
29 CFR 1915	Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment
29 FR 1919	Gear Certification
20 FR 1926	Safety and Health Regulations for Construction
29 FR 1926.500	Fall Protection

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with the Section, Submittal Procedures:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G, ACC

Activity Hazard Analysis (AHA); G, ACC

SD-06 Test Reports

Reports: Submit reports as their incidence occurs, in accordance with the requirements of the paragraph titled, "Reports."

Accident Reports

Monthly Exposure Reports

Regulatory Citations and Violations

SD-07 Certificates

Confined Space Entry Permit

Contractor Safety Self-Evaluation Checklist; G, ACC

Submit one (1) copy of each permit/certificate attached to each Daily Quality Control Report.

1.3 DEFINITIONS

- a. Competent Person for Fall Protection. A person who is capable of identifying hazardous or dangerous conditions in the personal fall arrest system or any component thereof, as well as their application and use with related equipment, and has the authority to take prompt corrective measures to eliminate the hazards of falling.
- b. High Visibility Accident. Any mishap which may generate publicity and/or high visibility.
- c. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.
- d. Qualified Person for Fall Protection. A person with a recognized degree or professional certificate, extensive knowledge, training and experience in the field of fall protection who is capable of performing design, analysis, and evaluation of fall protection systems and equipment.
- e. Recordable Injuries or Illnesses. Any work-related injury or illness that results in:

1. Death, regardless of the time between the injury and death, or the length of the illness;
 2. Days away from work (any time lost after day of injury/illness onset);
 3. Restricted work;
 4. Transfer to another job;
 5. Medical treatment beyond first aid;
 6. Loss of consciousness; or
 7. (7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above.
- f. "USACE" property and equipment specified in USACE EM 385-1-1 should be interpreted as Government property and equipment.

1.4 DRUG PREVENTION PROGRAM

Conduct a proactive drug and alcohol use prevention program for all workers, prime and sub-contractor, on the site. Ensure that no employee uses illegal drugs or consumes alcohol during work hours. Ensure there are no employees under the influence of drugs or alcohol during work hours. After accidents, collect blood, urine, or saliva specimens and test the injured and involved employees for the influence of drugs and alcohol. A copy of the test shall be made available to the Contracting Officer upon request.

1.5 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, work performed shall comply with USACE EM 385-1-1.

1.6 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.6.1 PERSONNEL QUALIFICATIONS

1.6.1.1 SITE SAFETY AND HEALTH OFFICER (SSHO)

Site Safety and Health Officer (SSHO) shall be provided at the work site at all times to perform safety and occupational health management, surveillance, inspections, and safety enforcement for the Contractor. The Contractor Quality Control (QC) person can only be the SSHO on this project if approved by the Contracting Officer. Any project exceeding one (1) Million US dollars in value shall have a full time SSHO. The SSHO shall meet the following requirements:

1. A minimum of one (1) year safety work on similar projects.
2. 30-hour OSHA construction safety class or equivalent within the last three (3) years.
3. Competent person training as needed.

1.6.1.2 COMPETENT PERSON FOR CONFINED SPACE ENTRY

Provide a competent person meeting the requirements of EM 385-1-1 who is assigned in writing by the Government Designated Authority (GDA) to assess confined spaces and who possesses demonstrated knowledge, skill and ability to:

- a. Identify the structure, location, and designation of confined and permit-required confined spaces where work is done.

- b. Calibrate and use testing equipment including but not limited to, oxygen indicators, combustible gas indicators, carbon monoxide indicators, and carbon dioxide indicators, and to interpret accurately the test results of that equipment.
- c. Perform all required tests and inspections specified in Section 06.I of EM 385-1-1.
- d. Assess hazardous conditions including atmospheric hazards in confined space and adjacent spaces and specify the necessary protection and precautions to be taken.
- e. Determine ventilation requirements for confined space entries and operations.
- f. Assess hazards associated with hot work in confined and adjacent space and determine fire watch requirements.
- g. Maintain records required.

1.6.1.3 CRANE OPERATORS

Crane operators shall meet the requirements in USACE EM 385-1-1, Section 16, Appendix I.

1.6.2 PERSONNEL DUTIES

1.6.2.1 SITE SAFETY AND HEALTH OFFICER (SSHO)

- a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Safety inspection logs shall be attached to the Contractors' daily quality control report.
- b. Conduct mishap investigations and complete required reports. Maintain an accident/injury log such as the OSHA Form 300 or host nation equivalent, and Daily Production reports for prime and sub-contractors.
- c. Maintain applicable safety reference material on the job site.
- d. Attend the pre-construction conference, pre-work meetings including preparatory inspection meeting, and periodic in-progress meetings.
- e. Implement and enforce accepted APPS and AHAs.
- f. Maintain a safety and health deficiency tracking system that monitors outstanding deficiencies until resolution. A list of unresolved safety and health deficiencies shall be posted on the safety bulletin board.
- g. Ensure sub-contractor compliance with safety and health requirements.

Failure to perform the above duties will result in dismissal of the superintendent and/or SSHO, and a project work stoppage. The project work stoppage will remain in effect pending approval of a suitable replacement.

1.6.3 MEETINGS

1.6.3.1 PRECONSTRUCTION CONFERENCE

- a. Contractor representatives who have a responsibility or significant role in accident prevention on the project shall attend the preconstruction conference. This includes the project superintendent, site safety and health officer, quality control supervisor, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

- b. The Contractor shall discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer's representative as to which phases will require an analysis. In addition, a schedule for the preparation, submittal, review, and acceptance of AHAs shall be established to preclude project delays.
- c. Deficiencies in the submitted APP will be brought to the attention of the Contractor at the preconstruction conference, and the Contractor shall revise the plan to correct deficiencies and re-submit it for acceptance. Work shall not begin until there is an accepted APP.
- d. The functions of a Preconstruction conference may take place at the Post-Award Kickoff meeting.

1.6.3.2 SAFETY MEETINGS

Shall be conducted and documented as required by EM 385-1-1. Minutes showing contract title, signatures of attendees and a list of topics discussed shall be attached to the Contractors' daily quality control report.

1.7 TRAINING

1.7.1 NEW EMPLOYEE INDOCTRINATION

New employees (prime and sub-contractor) will be informed of specific site hazards before they begin work. Documentation of this orientation shall be kept on file at the project site.

1.7.2 PERIODIC TRAINING

Provide Safety and Health Training in accordance with USACE EM 385-1-1 and the accepted APP. Ensure all required training has been accomplished for all onsite employees.

1.7.3 TRAINING ON ACTIVITY HAZARD ANALYSIS (AHA)

Prior to beginning a new phase, training will be provided to all affected

1.8 ACCIDENT PREVENTION PLAN (APP)

The Contractor shall use a qualified person to prepare the written site-specific APP in both English and in the host nation language. Prepare the APP in accordance with the format and requirements of USACE EM 385-1-1 and as supplemented herein. Cover all paragraph and sub-paragraph elements in USACE EM 385-1-1, Appendix A, "Minimum Basic Outline for Accident Prevention Plan". Specific requirements for some of the APP elements are described below. The APP shall be job-specific and shall address any unusual or unique aspects of the project or activity for which it is written. The APP shall interface with the Contractor's overall safety and health program. Any portions of the Contractor's overall safety and health program referenced in the APP shall be included in the applicable APP element and made site-specific. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the sub-contractors. Contractors are responsible for informing their sub-contractors of the safety US Army Corps of Engineers Compound provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one (1) craft from interfering with or creating hazardous working conditions for other crafts, and inspecting sub-contractor operations to ensure that accident prevention responsibilities are being carried out. The APP shall be signed by the

person and firm (senior person) preparing the APP, the Contractor, the on-site superintendent, the designated site safety and health officer.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP.

Once accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP will be cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified.

Once work begins, changes to the accepted APP shall be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and quality control manager. Should any hazard become evident, stop work in the area, secure the area, and develop a plan to remove the hazard. Notify the Contracting Officer within 24-hours of discovery. In the interim, all necessary action shall be taken to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ASSE/ANSI-34), and the environment.

Copies of the accepted plan will be maintained at the Contracting Officer's office and at the job site.

The APP shall be continuously reviewed and amended, as necessary, throughout the life of the contract. Unusual or high-hazard activities not identified in the original APP shall be incorporated in the plan as they are discovered.

1.8.1 EM 385-1-1 CONTENTS

In addition to the requirements outlines in Appendix A of USACE EM 385-1-1, the following is required:

- a. Names and qualifications (resumes including education, training, experience and certifications) of all site safety and health personnel designated to perform work on this project to include the designated site safety and health officer and other competent and qualified personnel to be. The duties of each position shall be specified.
- b. Qualifications of competent and of qualified persons. As a minimum, competent persons shall be designated and qualifications submitted for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; personal protective equipment and clothing to include selection, use and maintenance.
- c. Confined Space Entry Plan. Develop a confined space entry plan in accordance with USACE EM 385-1-1, Section 34, and any other federal, state and local regulatory requirements identified in this contract. Identify the qualified person's name and qualifications, training, and experience. Delineate the qualified person's authority to direct work stoppage in the event of hazardous conditions. Include procedure for rescue by Contractor personnel and the coordination with emergency responders. (If there is no confined space work, include a statement that no confined space work exists and none will be created.)
- d. Crane Critical Lift Plan. Prepare and sign weight handling critical lift plans for lifts over 75 percent of the capacity of the crane or hoist (or lifts over 50 percent of the capacity of a barge mounted mobile crane's hoists) at any radius of lift; lifts involving more than one (1) crane or hoist; lifts of personnel; and lifts involving non-routine rigging or operation, sensitive equipment, or unusual safety risks. The plan shall be submitted 15 calendar days prior to on-site work and include the requirements of USACE EM 385-1-1, paragraph 16.H, and the following:
 1. For lifts of personnel, the plan shall demonstrate compliance with the requirements of 29CFR 1926.550(g).
 2. For barge mounted mobile cranes, barge stability calculations identifying barge list and trim based on anticipated loading; and load charts based on calculated list and

trim. The amount of list and trim shall be within the crane manufacturer's requirements.

- e. Fall Protection and Prevention (FP&P) Plan. The plan shall be site specific and address all fall hazards in the work place and during different phases of construction. It shall address how to protect and prevent workers from falling to lower levels when they are exposed to fall hazards above 1.8 m (6'). A qualified person for fall protection shall prepare and sign the plan. The plan shall include fall protection and prevention systems, equipment and methods employed for every phase of work, responsibilities, assisted rescue, self-rescue and evacuation procedures, training requirements, and monitoring methods. Fall Protection and Prevention Plan shall be revised every six (6) months for lengthy projects, reflecting any changes during the course of construction due to changes in personnel, equipment, systems or work habits. The accepted Fall Protection and Prevention Plan shall be kept and maintained at the job site for the duration of the project. The Fall Protection and Prevention Plan shall be included in the Accident Prevention Plan (APP).

1.9 ACTIVITY HAZARD ANALYSIS (AHA)

The Activity Hazard Analysis (AHA) format shall be in accordance with USACE EM 385-1-1, and shall be written in both English and the host nation language. Submit the AHA for review at least 15 calendar days prior to the start of each phase. The Contractor shall format subsequent AHAs as amendments to the APP. The analysis should be used during daily inspections to ensure the implementation and effectiveness of the activity's safety and health controls.

The AHA list will be reviewed periodically (at least monthly) at the Contractor supervisory safety meeting and updated as necessary when procedures, scheduling, or hazards change.

The activity hazard analyses shall be developed using the project schedule as the basis for the activities performed. Any activities listed on the project schedule will require an AHA. The AHAs will be developed by the Contractor, supplier or sub-contractor and provided to the prime Contractor for submittal to the Contracting Officer.

1.10 DISPLAY OF SAFETY INFORMATION

Within one (1) calendar day after commencement of work, erect a safety bulletin board at the job site. The safety bulletin board shall include information and be maintained as required by EM 385-1-1, section 01.A.06.

1.11 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project. Maintain applicable equipment manufacturer's manuals.

1.12 EMERGENCY MEDICAL TREATMENT

Contractors will arrange for their own emergency medical treatment. The Government has no responsibility to provide emergency medical treatment. Military medical clinics may provide emergency treatment for serious injuries; the Contractor is responsible for coordination with the local military medical clinic prior to mobilization.

1.13 REPORTS

1.13.1 ACCIDENT REPORTS

For recordable injuries and illnesses and property damage accidents resulting in at least \$2,000 in damages, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident complete the USACE Accident Report Form 3394 and provide the report to the Contracting Officer within five (5) calendar day(s) of the accident. The Contracting Officer will provide copies of any required or special forms.

1.13.2 ACCIDENT NOTIFICATION

Notify the Contracting Officer as soon as practical, but not later than four (4) hours, after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than \$2,000. Information shall include Contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of construction equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted.

1.13.3 MONTHLY EXPOSURE REPORTS

Monthly exposure reporting to the Contracting Officer is required to be attached to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both prime and sub-contractor. The Contracting Officer will provide copies of any special forms.

1.13.4 CRANE REPORTS

Submit crane inspection reports required in accordance with USACE EM 385-1-1, Appendix H and as specified herein with Daily Reports of Inspections.

1.14 HOT WORK

Prior to performing "Hot Work" (welding, cutting, etc.) or operating other flame-producing/spark producing devices, a written permit shall be requested from the Installation. **Contractors Are Required To Meet All Criteria Before A Permit Is Issued.** The Contractor will provide at least two (2) 6.0 kg (13 lb) ABC rated extinguishers for normal "Hot Work". All extinguishers shall be current inspection tagged, approved safety pin and tamper resistant seal. It is also mandatory to have a designated **Fire Watch** for any "Hot Work" done at this activity. The Fire Watch shall be trained in fire fighting techniques and remain on-site for a minimum of 120 minutes after completion of the task or as specified on the hot work permit.

When starting work in the facility, Contractors shall require their personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency phone numbers. **Any Fire, No Matter How Small, Shall Be Reported To The Responsible Fire Division/Department Immediately.**

2. EXECUTION

2.1 CONSTRUCTION AND/OR OTHER WORK

Before initiation of work at the job site, an accident prevention plan, written by the Contractor for the specific work and hazards of the contract and implementing in detail the pertinent requirements of EM

385-1-1, will be reviewed and found acceptable by designated Government personnel. Specific requirements for development of the accident prevention plan are found in Appendix A of EM 385-1-1.

Before beginning each activity involving a type of work presenting hazards not experienced in previous project operations or where a new work crew or sub-contractor is to perform the work, activity hazard analysis (AHA) shall be prepared by the Contractor performing the work activity. See paragraph 01.A.13 of EM 385-1-1.

The Contractor shall require sub-contractors to submit their plan of operations showing methods they propose to use in accomplishing major phases of work.

The Contractor shall be prepared to discuss the plans in conferences convened by the Contracting Officer prior to starting work on each major phase of operation. Plans shall include all pertinent information such as layout of haul roads, access roads, storage areas, electrical distribution lines, methods of providing minimum exposure to overhead loads, and methods of access to work areas. The plan for accomplishing the initial work phase shall be submitted within 15 calendar days after award of the contract. Plans for subsequent major phases of work shall be submitted not later than 15 calendar days prior to initiation of work on each major phase.

All areas where construction, demolition, alteration, building, or similarly related activities take place, all workers shall have the following minimum personal protective clothing and equipment:

1. Short sleeve shirt.
2. Long trousers.
3. Steel-toed safety boots.
4. Hard hat.

2.1.1 FALLING OBJECT PROTECTION

All areas must be barricaded to safeguard employees. When working overhead, barricade the area below to prevent entry by unauthorized employees. Construction warning tape and signs shall be posted so they are clearly visible from all possible access points. When employees are working overhead all tools and equipment shall be secured so that they will not fall. When using guardrail as falling object protection, all openings shall be small enough to prevent passage of potential falling objects.

2.1.2 HAZARDOUS MATERIAL USE

Each hazardous material must receive approval prior to being brought onto the job site or prior to any other use in connection with this contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material. Any work or storage involving hazardous chemicals or materials must be done in a manner that will not expose Government or Contractor employees to any unsafe or unhealthful conditions. Adequate protective measures must be taken to prevent Government or Contractor employees from being exposed to any hazardous condition that could result from the work or storage. The Prime Contractor shall keep a complete inventory of hazardous materials brought onto the work-site. Approval by the Contracting Officer of protective measures and storage area is required prior to the start of the work.

2.1.3 HAZARDOUS MATERIAL EXCLUSIONS

Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with USACE EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocyanates, lead-based paint are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials.

2.1.4 UNFORESEEN HAZARDOUS MATERIAL

The design should have identified materials such as PCB, lead paint, and friable and non-friable asbestos. If material, not indicated, that may be hazardous to human health upon disturbance during construction operations is encountered, stop that portion of work and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to "FAR 52.243-4, Changes" and "FAR 52.236-2, Differing Site Conditions."

2.2 FALL HAZARD PROTECTION AND PREVENTION PROGRAM

The Contractor shall establish a fall protection and prevention program, for the protection of all employees exposed to fall hazards. The program shall include company policy, responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures.

2.2.1 TRAINING

The Contractor shall institute a fall protection training program. As part of the Fall Hazard Protection and Prevention Program, the Contractor shall provide training for each employee who might be exposed to fall hazards. A competent person for fall protection shall provide the training. Training requirements shall be in accordance with USACE EM 385-1-1, section 21.B.

2.2.2 FALL PROTECTION EQUIPMENT AND SYSTEMS

The Contractor shall enforce use of the fall protection equipment and systems designated for each specific work activity in the Fall Protection and Prevention Plan and/or AHA at all times when an employee is exposed to a fall hazard. Employees shall be protected from fall hazards as specified in EM 385-1-1, section 21. In addition to the required fall protection systems, safety skiff, personal floatation devices, life rings etc., are required when working above or next to water in accordance with USACE EM 385-1-1, paragraphs 21.N through 21.N.04. Personal fall arrest systems are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall arrest systems are required when operating other equipment such as scissor lifts if the work platform is capable of being positioned outside the wheelbase. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, or travel. Fall protection must comply with USACE EM 385-1-1 and host nation requirements, whichever is more stringent.

2.2.2.1 PERSONAL FALL ARREST EQUIPMENT

Personal fall arrest equipment, systems, subsystems, and components shall meet ANSI Z359.1 or European Union equivalent. Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. Harnesses shall have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Only locking snap hooks and carabineers shall be used. Webbing, straps, and ropes shall be made of synthetic fiber. The maximum free fall distance when using fall arrest equipment shall not exceed 1.8 m (6'). The total fall distance and any swinging of the worker (pendulum-like motion) that can occur during a fall shall always be taken into consideration when attaching a person to a fall arrest system.

2.2.3 FALL PROTECTION FOR ROOFING WORK

Fall protection controls shall be implemented based on the type of roof being constructed and work being performed. The roof area to be accessed shall be evaluated for its structural integrity including weight-bearing capabilities for the projected loading.

- a. Low Sloped Roofs:
 - (1) For work within 1.8 m (6') of an edge, on low-slope roofs, personnel shall be protected from falling by use of personal fall arrest systems, guardrails, or safety nets. A safety monitoring system is not adequate fall protection and is not authorized.
 - (2) For work greater than 1.8 m (6') from an edge, warning lines shall be erected and installed in accordance with USACE EM 385-1-1.
- b. Steep-Sloped Roofs: Work on steep-sloped roofs requires a personal fall arrest system, guardrails with toe-boards, or safety nets. This requirement also includes residential or housing type construction.

2.2.4 EXISTING ANCHORAGE

Existing anchorages, to be used for attachment of personal fall arrest equipment, shall be certified (or re-certified) by a qualified person for fall protection in accordance with ANSI/ANSI Z359.1 or European Union equivalent. Existing horizontal lifeline anchorages shall be certified (or re-certified) by a registered professional engineer with experience in designing horizontal lifeline systems.

2.2.5 HORIZONTAL LIFELINES

Horizontal lifelines shall be designed, installed, certified and used under the supervision of a qualified person for fall protection as part of a complete fall arrest system which maintains a safety factor of 2.

2.2.6 GUARDRAILS AND SAFETY NETS

Guardrails and safety nets shall be designed, installed and used in accordance with EM 385-1-1 or Host Nation requirements, whichever is more stringent.

2.2.7 RESCUE AND EVACUATION PROCEDURES

When personal fall arrest systems are used, the Contractor must ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. A Rescue and Evacuation Plan shall be prepared by the Contractor and include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. The Rescue and Evacuation Plan shall be included in the Activity Hazard Analysis (AHA) for the phase of work, in the Fall Protection and Prevention (FP&P) Plan, and the Accident Prevention Plan (APP).

2.3 SCAFFOLDING

Employees shall be provided with a safe means of access to the work area on the scaffold. Climbing of any scaffold braces or supports not specifically designed for access is prohibited. Access to scaffold platforms greater than 6 m (20') in height shall be accessed by use of a scaffold stair system. Vertical ladders commonly provided by scaffold system manufacturers shall not be used for accessing scaffold platforms greater than 6 m (20') in height. The use of an adequate gate is required. Contractor shall ensure that employees are qualified to perform scaffold erection and dismantling. Do not use scaffold without the capability of supporting at least four (4) times the maximum intended load or without

appropriate fall protection as delineated in the accepted fall protection and prevention plan. Stationary scaffolds must be attached to structural building components to safeguard against tipping forward or backward. Special care shall be given to ensure scaffold systems are not overloaded. Side brackets used to extend scaffold platforms on self-supported scaffold systems for the storage of material are prohibited. The first tie-in shall be at the height equal to four (4) times the width of the smallest dimension of the scaffold base. Work platforms shall be placed on mud sills. Scaffold or work platform erectors shall have fall protection during the erection and dismantling of scaffolding or work platforms that are more than 1.8 m (6'). Delineate fall protection requirements when working above 1.8 m (6') or above dangerous operations in the Fall Protection and Prevention (FP&P) Plan and Activity Hazard Analysis (AHA) for the phase of work.

2.4 EQUIPMENT

2.4.1 MATERIAL HANDLING EQUIPMENT

- a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.
- b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions.
- c. Operators of forklifts or power industrial trucks shall be trained/licensed in accordance with Host Nation requirements.

2.4.2 WEIGHT HANDLING EQUIPMENT

- a. Cranes and derricks shall be equipped as specified in EM-385-1-1 section 16.
- b. The Contractor shall notify the Contracting Officer 24-hours in advance of any cranes entering the activity so that necessary quality assurance spot checks can be coordinated. Contractor's operator shall remain with the crane during the spot check.
- c. The Contractor shall comply with the crane manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Erection shall be performed under the supervision of a designated person. All testing shall be performed in accordance with the manufacturer's recommended procedures.
- d. Under no circumstance shall a Contractor make a lift at or above 90 percent of the cranes rated capacity in any configuration.
- e. When operating in the vicinity of overhead transmission lines, operators and riggers shall be alert to this special hazard and shall follow the requirements of USACE EM 385-1-1 section 11.
- f. Crane suspended personnel work platforms (baskets) shall not be used unless the Contractor proves to the satisfaction of the Contracting Officer that using any other access to the work location would provide a greater hazard to the workers or is impossible. Personnel shall not be lifted with a line hoist or friction crane.
- g. Portable fire extinguishers shall be inspected, maintained, and recharged.
- h. All employees shall be kept clear of loads about to be lifted and of suspended loads.
- i. The Contractor shall use cribbing when performing lifts on outriggers.
- j. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.
- k. A physical barricade must be positioned to prevent personnel from entering the counterweight swing (tail swing) area of the crane.

- l. Certification records which include the date of inspection, signature of the person performing the inspection, and the serial number or other identifier of the crane that was inspected shall always be available for review by Contracting Officer personnel.
- m. Written reports listing the load test procedures used along with any repairs or alterations performed on the crane shall be available for review by Contracting Officer personnel.
- n. Certify that all crane operators have been trained in proper use of all safety devices (e.g. anti-two (2) block devices).
- o. Take steps to ensure that wind speed does not contribute to loss of control of the load during lifting operations. Prior to conducting lifting operations the Contractor shall set a maximum wind speed at which a crane can be safely operated based on the equipment being used, the load being lifted, experience of operators and riggers, and hazards on the work site. This maximum wind speed determination shall be included as part of the activity hazard analysis plan for that operation.

2.5 EXCAVATIONS

The competent person for excavations performed as a result of contract work shall be on-site when excavation work is being performed, and shall inspect, and document the excavations daily prior to entry by workers. The competent person must evaluate all hazards, including atmospheric, that may be associated with the work, and shall have the resources necessary to correct hazards promptly.

2.5.1 UTILITY LOCATIONS

Prior to any excavation, all underground utilities in the work area must be positively identified by the Contractor utilizing a) a private utility locating service in addition to any station locating service, and/or b) a metal and/or cable-detecting device along the route of the excavation. All underground utilities discovered will be flagged a distance of 0.5 m (20") on each side of the location, and any markings made during the utility investigation must be maintained throughout the contract.

Damage occurring to existing utilities, when the above procedures are not followed, will be repaired at the Contractor's expense.

2.5.2 UTILITY LOCATION VERIFICATION

The Contractor must physically verify underground utility locations by hand digging using wood or fiberglass handled tools when any adjacent construction work is expected to come within 1.0 m (40") of the underground system. Digging within 0.6 m (24") of a known utility must not be performed by means of mechanical equipment; hand digging shall be used. If construction is parallel to an existing utility the utility shall be exposed by hand digging every 30 m (100') if parallel within 1.5 m (5') of the excavation.

2.5.3 SHORING SYSTEMS

Trench and shoring systems must be identified in the accepted safety plan and AHA. Manufacture tabulated data and specifications or registered engineer tabulated data for shoring or benching systems shall be readily available on-site for review. Job-made shoring or shielding shall have the registered professional engineer stamp, specifications, and tabulated data. Extreme care must be used when excavating near direct burial electric underground cables.

2.5.4 TRENCHING MACHINERY

Trenching machines with digging chain drives shall be operated only when the spotters/laborers are in plain view of the operator. Operator and spotters/laborers shall be provided training on the hazards of the

digging chain drives with emphasis on the distance that needs to be maintained when the digging chain is operating. Documentation of the training shall be kept on file at the project site.

2.6 UTILITIES WITHIN CONCRETE SLABS

Utilities located within concrete slabs or pier structures, bridges, and the like, are extremely difficult to identify due to the reinforcing steel used in the construction of these structures. Whenever contract work involves concrete chipping, saw cutting, or core drilling, the existing utility location must be coordinated with station utility departments in addition to a private locating service. Outages to isolate utility systems shall be used in circumstances where utilities are unable to be positively identified. The use of historical drawings does not alleviate the Contractor from meeting this requirement.

2.7 ELECTRICAL

2.7.1 CONDUCT OF ELECTRICAL WORK

Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Positive cable identification must be made prior to submitting any outage request for electrical systems. Arrangements are to be coordinated with the Contracting Officer and Station Utilities for identification. The Contracting Officer will not accept an outage request until the Contractor satisfactorily documents that the circuits have been clearly identified. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator will be allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method. When working in energized substations, only qualified electrical workers shall be permitted to enter. When work requires Contractor to work near energized circuits as defined by the NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves with leather protective sleeves, fire retarding shirts, coveralls, face shields, and safety glasses. In addition, provide electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA.

2.7.2 PORTABLE EXTENSION CORDS

Portable extension cords shall be sized in accordance with manufacturer ratings for the tool to be powered and protected from damage. All damaged extension cords shall be immediately removed from service. Portable extension cords shall meet the requirements of NFPA 70 or European Union equivalent.

2.8 WORK IN CONFINED SPACES

The Contractor shall comply with the requirements in Section 34 of USACE EM 385-1-1. Any potential for a hazard in the confined space requires a permit system to be used.

- a. Entry Procedures. Prohibit entry into a confined space by personnel for any purpose, including hot work, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. All hazards pertaining to the space shall be reviewed with each employee during review of the AHA.
- b. Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its' action level.

- c. Ensure the use of rescue and retrieval devices in confined spaces greater than 1.5 m (5') in depth. Conform to 29 CFR 1910-14.
- d. Sewer wet wells require continuous atmosphere monitoring with audible alarm for toxic gas detection.
- e. Daily Entry Permit. Post the permit in a conspicuous place close to the confined space entrance.

2.9 CRYSTALLINE SILICA

Grinding, abrasive blasting, and foundry operations of construction materials containing crystalline silica, shall comply with USACE EM 385-1-1, Section 06.M. Work Place Evaluation consistent with EM 385-1-1 Section 06.M.02 must be completed and documented in the AHA for the job/task producing airborne crystalline silica. The Contractor shall develop and implement effective exposure control and elimination procedures to include dust control systems, engineering controls, and establishment of work area boundaries, as well as medical surveillance, training, air monitoring, and personal protective equipment.

2.10 DEMOLITION

2.10.1 DEMOLITION PLAN

The Contractor shall submit a written demolition plan for all demolition work to be carried on the site. In addition, the demolition plan shall be signed by a Professional Registered Engineer and meet the requirements of the Corps of Engineers Safety and Health Manual, EM 385-1-1, section 23. The demolition plan shall be submitted to the COR at least one (1) week before the beginning of the work, including structural calculations for the demolition, if necessary. The demolition work shall not begin before the Contractor has received a written approval from the COR.

2.10.2 PROTECTION OF PERSONNEL

During the demolition work the Contractor shall continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the demolition site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workers remove debris or perform other work in the immediate area.

2.10.3 PROTECTION OF STRUCTURES

Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, shall remain standing without additional bracing, shoring, or lateral support until demolished, unless directed otherwise by the COR. The Contractor shall ensure that no elements determined to be unstable are left unsupported and shall be responsible for placing and securing bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, or demolition work performed under this contract.

Interior concrete or masonry walls shall be demolished from the top down unless a Registered Engineer can demonstrate that an alternate method poses no additional safety hazards

2.11 HOUSEKEEPING

2.11.1 CLEAN-UP

The Contractor shall be responsible for cleaning up. The Contractor shall require his personnel to keep the immediate work site clean of all dirt and debris resulting from work under this contract. Accumulated

dirt and debris shall be hauled off and disposed of in accordance with local law and at least once a week by the Contractor. Additionally, all debris in work areas shall be cleaned up daily or more frequently if necessary. Construction debris may be temporarily located in an approved location; however garbage accumulation must be removed each day.

Stairwells used by the Contractor during execution of work shall be cleaned daily. Cloths, mops, and brushes containing combustible materials shall be disposed of or stored outside of the buildings in tight covered metal containers. Paints and thinners shall not be poured into inlets of the interior or exterior sewage system. Paint, stains, and other residues on adjacent surfaces or fixtures caused by the Contractor shall be carefully removed and cleaned to original finish. Upon completion of the work, the Contractor shall remove all construction equipment, materials and debris resulting from the work. The entire work site and the area used by Contractor personnel shall be left clean.

---END OF SECTION---

SECTION 01770

CLOSEOUT PROCEDURES

1. GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01335, Submittal Procedures:

SD-10 Operation and Maintenance Data

Equipment/Product Warranty List; G

Submit Data Package 1 in accordance with Section 01781, Operation And Maintenance Data.

SD-11 Closeout Submittals

As-Built Drawings; G

Record Of Materials; G

Equipment/Product Warranty Tag; G

1.2 PROJECT RECORD DOCUMENTS

1.2.1 AS-BUILT DRAWINGS

As-built drawings shall be submitted in accordance with Section 01780A, Closeout Submittals.

1.2.2 AS-BUILT RECORD OF MATERIALS

Furnish a record of materials.

Where several manufacturers' brands, types, or classes of the item listed have been used in the project, designate specific areas where each item was used. Designations shall be keyed to the areas and spaces depicted on the contract drawing. Furnish the record of materials used in the following format:

MATERIALS DESIGNATION	SPECIFICATION	MANUFACTURER	MATERIALS USED (MANUFACTURER'S DESIGNATION)	WHERE USED

1.3 EQUIPMENT/PRODUCT WARRANTIES

1.3.1 EQUIPMENT/PRODUCT WARRANTY LIST

The Contractor shall develop a warranty management plan which shall contain information relevant to the clause Warranty of Construction. At least 30-days before the planned pre-warranty conference, the Contractor shall submit the warranty management plan for Government approval. The warranty management plan shall include all required actions and documents to assure that the Government receives all warranties to which it is entitled. The plan shall be in narrative form and contain sufficient detail to render it suitable for use by future maintenance and repair personnel, whether tradesmen, or of engineering background, not necessarily familiar with this contract. The term "status" as indicated below shall include due date and whether item has been submitted or was accomplished. Warranty information made available during the construction phase shall be submitted to the Contracting Officer for approval prior to each monthly pay estimate. Approved information shall be assembled in a binder and shall be turned over to the Government upon acceptance of the work. The construction warranty period shall begin on the date of project acceptance and shall continue for the full product warranty period. A joint fourth (4th) month and ninth (9th) month warranty inspection shall be conducted, measured from time of acceptance, by the Contractor, Contracting Officer and the Customer Representative. Information contained in the warranty management plan shall include, but shall not be limited to, the following:

- a. Roles and responsibilities of all personnel associated with the warranty process, including points of contact and telephone numbers within the organizations of the Contractors, subcontractors, manufacturers or suppliers involved.
- b. Listing and status of delivery of all Certificates of Warranty for extended warranty items, to include roofs, HVAC balancing, pumps, motors, transformers, and for all commissioned systems such as fire protection and alarm systems, sprinkler systems, lightning protection systems, etc.
- c. A list for each warranted equipment, item, feature of construction or system indicating:
 1. Name of item.
 2. Model and serial numbers.
 3. Location where installed.
 4. Name and phone numbers of manufacturers or suppliers.
 5. Names, addresses and telephone numbers of sources of spare parts.
 6. Warranties and terms of warranty. This shall include 1-year overall warranty of construction. Items which have extended warranties shall be indicated with separate warranty expiration dates.
 7. Cross-reference to warranty certificates as applicable.
 8. Starting point and duration of warranty period.
 9. Summary of maintenance procedures required to continue the warranty in force.
 10. Cross-reference to specific pertinent Operation and Maintenance manuals.
 11. Organization, names and phone numbers of persons to call for warranty service.
 12. Typical response time and repair time expected for various warranted equipment.
- d. The Contractor's plans for attendance at the fourth (4th) and ninth (9th) month post-construction warranty inspections conducted by the Government.
- e. Procedure and status of tagging of all equipment covered by extended warranties.

f. Copies of instructions to be posted near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

1.3.2 PERFORMANCE OF WARRANTY WORK

In the event the Contractor fails to commence and diligently pursue any construction warranty work required, the Contracting Officer will have the work performed by others, and after completion of the work, will charge the remaining construction warranty funds of expenses incurred by the Government while performing the work, including, but not limited to administrative expenses.

Following oral or written notification of required construction warranty repair work, the Contractor shall respond in a timely manner. Written verification will follow oral instructions. Failure of the Contractor to respond will be cause for the Contracting Officer to proceed against the Contractor.

1.3.3 PRE-WARRANTY CONFERENCE

Prior to contract completion, and at a time designated by the Contracting Officer, the Contractor shall meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this section. Communication procedures for Contractor notification of construction warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty shall be established/reviewed at this meeting. In connection with these requirements and at the time of the Contractor's quality control completion inspection, the Contractor shall furnish the name, telephone number and address of a licensed and bonded company which is authorized to initiate and pursue construction warranty work action on behalf of the Contractor. This point of contact will be located within the local service area of the warranted construction, shall be continuously available, and shall be responsive to Government inquiry on warranty work action and status. This requirement does not relieve the Contractor of any of its responsibilities in connection with other portions of this provision.

1.3.4 WARRANTY TAGS

At the time of installation, each warranted item shall be tagged with a durable, oil and water resistant tag approved by the Contracting Officer. Each tag shall be attached with a copper wire and shall be sprayed with a silicone waterproof coating. The date of acceptance and the QC signature shall remain blank until project is accepted for beneficial occupancy. The tag shall show the following information.

- a. Type of product/material _____
- b. Model number _____
- c. Serial number _____
- d. Contract number _____
- e. Warranty period _____ from _____ to _____
- f. Inspector's signature _____
- g. Construction Contractor _____
Address _____
Telephone number _____
- h. Warranty contact _____
Address _____
Telephone number _____
- i. Warranty response time priority code _____

j. WARNING - PROJECT PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE DURING THE WARRANTY PERIOD.

1.4 MECHANICAL TESTING AND BALANCING

All contract requirements for testing/adjusting/balancing shall be fully completed, including all testing, prior to contract completion date. The time required to complete all testing/adjusting/balancing is included in the allotted calendar days for completion.

1.5 FINAL CLEANING

The premises shall be left broom clean. Stains, foreign substances, and temporary labels shall be removed from surfaces. Carpet and soft surfaces shall be vacuumed. Equipment and fixtures shall be cleaned to a sanitary condition. Filters of operating equipment shall be replaced. Debris shall be removed from roofs, drainage systems, gutters, and downspouts. Paved areas shall be swept and landscaped areas shall be raked clean. The site shall have waste, surplus materials, and rubbish removed. The project area shall have temporary structures, barricades, project signs, and construction facilities removed. A list of completed clean-up items shall be submitted on the day of final inspection.

-- END OF SECTION --

SECTION 01780A

CLOSEOUT SUBMITTALS

1. GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control (CQC) approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted to the Area/Resident Engineer (AE/RE) Office in accordance with Section 01335, Submittal Procedures:

SD-02 Shop Drawings

As-Built Drawings

Drawings showing final as-built conditions of the project.

- One (1) set to the O&M Field Office

SD-03 Product Data

As-Built Record of Equipment and Materials

Records showing final as-built materials and equipment of the project. The local language of Afghanistan shall be added to project As-Built records. The final as-built records shall consist of:

Four (4) sets of English-language electronic report files in the specified format and distributed by the AE/RE Office as follows:

- One (1) set to stay in the AE/RE Office.
- One (1) set to Operations and Maintenance (O&M) Branch at Kandahar Air Field (KAF).
- One (1) set to the Customer (i.e. CSTC-A, etc.).
- One (1) set to the O&M Field Office

1.2 PROJECT RECORD DOCUMENTS

1.2.1 AS-BUILT DRAWINGS

This paragraph covers as-built drawings complete, as a requirement of the contract. The terms "drawings," "contract drawings," "drawing files," "working as-built drawings" and "final as-built drawings" refer to contract drawings which are revised to be used for final as-built drawings.

1.2.1.1 GOVERNMENT FURNISHED MATERIALS

One (1) set of electronic CADD files in the specified software and format revised to reflect all bid amendments will be provided by the Government at the preconstruction conference for projects requiring CADD file as-built drawings.

1.2.1.2 DRAWING PREPARATION

The as-built drawings shall be modified as may be necessary to correctly show the features of the project as it has been constructed by bringing the contract set into agreement with approved working as-built

prints, and adding such additional drawings as may be necessary. These working as-built marked prints shall be neat, legible and accurate. These drawings are part of the permanent records of this project and shall be returned to the Contracting Officer after approval by the Government. Any drawings damaged or lost by the Contractor shall be satisfactorily replaced by the Contractor at no expense to the Government.

1.2.2 AS-BUILT RECORD OF EQUIPMENT AND MATERIALS

The Contractor shall furnish one (1) copy of preliminary record of equipment and materials used on the project 15 days prior to final inspection. This preliminary submittal will be reviewed and returned two (2) days after final inspection with Government comments. Two (2) sets of final record of equipment and materials shall be submitted 10 days after final inspection. The designations shall be keyed to the related area depicted on the contract drawings. The record shall list the following data:

Record Of Designated Equipment And Materials Data

Description	Specification Section	Manufacturer and Catalog, Model, and Serial Number	Composition and Size	Where Used
-------------	-----------------------	--	----------------------	------------

1.2.3 FINAL APPROVED SHOP DRAWINGS

The Contractor shall furnish final approved project shop drawings 30 days after transfer of the completed facility.

1.2.4 CONSTRUCTION CONTRACT SPECIFICATIONS

The Contractor shall furnish final as-built construction contract specifications, including modifications thereto, 30 days after transfer of the completed facility.

1.3 WARRANTY MANAGEMENT

1.4 MECHANICAL TESTING, ADJUSTING, BALANCING, AND COMMISSIONING

Prior to final inspection and transfer of the completed facility; all reports, statements, certificates, and completed checklists for testing, adjusting, balancing, and commissioning of mechanical systems shall be submitted to and approved by the Contracting Officer as specified in applicable technical specification sections.

1.5 OPERATION AND MAINTENANCE MANUALS

Operation and Maintenance (O&M) manuals shall be submitted showing operation manuals and maintenance manuals in a common volume, complete, clearly differentiated, and separately indexed. The local language of Afghanistan shall be added to project O&M manuals. The final O&M manuals shall consist of:

- Four (4) sets of English-language electronic manuals in the specified format and distributed by the AE/RE Office as follows:
- One (1) set to stay in the AE/RE Office.
- One (1) set to Operations and Maintenance (O&M) Branch at Kandahar Air Field (KAF).
- One (1) set to the Customer (i.e. CSTC-A, etc.).
- One (1) set to the O&M Field Office

-- END OF SECTION --

SECTION 01781

OPERATION AND MAINTENANCE DATA

1. GENERAL

1.1 SUBMISSION OF OPERATION & MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data specifically applicable to this contract and a complete and concise depiction of the provided equipment, product, or system. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01335, Submittal Procedures.

1.1.1 PACKAGE QUALITY

Documents must be fully legible. Poor quality copies and material with hole punches obliterating the text or drawings will not be accepted.

1.1.2 PACKAGE CONTENT

Data package content shall be as shown in the paragraph titled "Schedule of Operation and Maintenance Data Packages." Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission.

1.1.3 CHANGES TO SUBMITTALS

Manufacturer-originated changes or revisions to submitted data shall be furnished by the Contractor if a component of an item is so affected subsequent to acceptance of the O&M Data. Changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data, shall be submitted by the Contractor within 30 calendar days of the notification of this change requirement.

1.2 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

1.2.1 OPERATING INSTRUCTIONS

Include specific instructions, procedures, and illustrations for the following phases of operation:

1.2.1.1 SAFETY PRECAUTIONS

List personnel hazards and equipment or product safety precautions for all operating conditions.

1.2.1.2 OPERATOR PRESTART

Include procedures required to set up and prepare each system for use.

1.2.1.3 STARTUP, SHUTDOWN, AND POST-SHUTDOWN PROCEDURES

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.2.1.4 NORMAL OPERATIONS

Provide narrative description of Normal Operating Procedures. Include Control Diagrams with data to explain operation and control of systems and specific equipment.

1.2.1.5 EMERGENCY OPERATIONS

Include Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Include Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of all utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.2.1.6 OPERATOR SERVICE REQUIREMENTS

Include instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gage readings.

1.2.1.7 ENVIRONMENTAL CONDITIONS

Include a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.2.2 PREVENTIVE MAINTENANCE

Include the following information for preventive and scheduled maintenance to minimize corrective maintenance and repair.

1.2.2.1 LUBRICATION DATA

Include preventative maintenance lubrication data, in addition to instructions for lubrication provided under paragraph titled "Operator Service Requirements":

- a. A table showing recommended lubricants for specific temperature ranges and applications.
- b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.
- c. A Lubrication Schedule showing service interval frequency.

1.2.2.2 PREVENTIVE MAINTENANCE PLAN AND SCHEDULE

Include manufacturer's schedule for routine preventive maintenance, inspections, tests and adjustments required to ensure proper and economical operation and to minimize corrective maintenance. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

1.2.3 CORRECTIVE MAINTENANCE (REPAIR)

Include manufacturer's recommended procedures and instructions for correcting problems and making repairs.

1.2.3.1 TROUBLESHOOTING GUIDES AND DIAGNOSTIC TECHNIQUES

Include step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the check-out is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.2.3.2 WIRING DIAGRAMS AND CONTROL DIAGRAMS

Wiring diagrams and control diagrams shall be point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.2.3.3 MAINTENANCE AND REPAIR PROCEDURES

Include instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.2.3.4 REMOVAL AND REPLACEMENT INSTRUCTIONS

Include step-by-step procedures and a list required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Instructions shall include a combination of text and illustrations.

1.2.3.5 SPARE PARTS AND SUPPLY LISTS

Include lists of spare parts and supplies required for maintenance and repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.2.4 CORRECTIVE MAINTENANCE WORK-HOURS

Include manufacturer's projection of corrective maintenance work-hours including requirements by type of craft. Corrective maintenance that requires completion or participation of the equipment manufacturer shall be identified and tabulated separately.

1.2.5 APPENDICES

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.2.6 PARTS IDENTIFICATION

Provide identification and coverage for all parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and

source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing shall show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Parts shown in the listings shall be grouped by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one (1) model or series of equipment, components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog

1.2.6.1 WARRANTY INFORMATION

List and explain the various warranties and include the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components such as the compressor of air conditioning system.

1.2.6.2 PERSONNEL TRAINING REQUIREMENTS

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.2.6.3 TESTING EQUIPMENT AND SPECIAL TOOL INFORMATION

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components.

1.2.6.4 CONTRACTOR INFORMATION

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

2. EXECUTION

2.1 TRAINING


Unless provided for elsewhere, the Contractor shall provide operational and maintenance training for all systems furnished under this contract in accordance with this section. The training shall not take place until the operation and maintenance manuals are submitted and approved.

Training will be given to personnel responsible for the operation and maintenance of the system at the installation. Orient training to the specific system being installed under this contract. Use operation and maintenance manual as the primary instructional aid in Contractor provided activity personnel training. Manuals shall be delivered for each trainee with an electronic copy delivered for archiving at the project site. Submit a training course schedule, syllabus, and training materials 14 days prior to the start of training. Obtain approval of the training course before beginning that phase of training. Furnish a qualified instructor approved by the system manufacturer to conduct training for the specific system.

Training manuals shall include an agenda, defined objectives and a detailed description of the subject matter for each lesson. Furnish audio-visual equipment and all other training materials and supplies. A training day is defined as 8-hours of classroom or lab instruction, including two (2) 15-minute breaks and excluding lunch time, Monday through Friday, during the daytime shift in effect at the training facility. For guidance, the Contractor should assume the attendees will have a high school education.

The Contractor shall videotape the training session on VHS tapes and provide the tapes to the Government.

-- END OF SECTION --



Rev	Description	Date
1	AS-BUILT DRAWINGS	15/09/07

DESIGNED BY: DATE: 15/09/07
 DRAWN BY: SUBMITTED BY:
 CHK BY: E.S.S. FILE NO.:
 G.M.T. HO-P-06FN


Client: US Army Corps of Engineers
 Afghanistan Engineer District
 Kandahar
 Designer: **CONTRACT**
 1000 N. 17th Street, Suite 1000
 Fort Worth, TX 76107-1000

**ANA REGIONAL HOSPITAL
 KANDAHAR, AFGHANISTAN
 HOSPITAL BUILDING
 MEDICAL GAS PIPING PLAN**


Sheet reference number:
HO-P-06
 Sheet # of 109

1 MEDICAL GAS PIPING PLAN
 HO-P-06 HO-P-06
 Scale: 1:250



Hospital Addition Oxygen System- Information Only




KEY PLAN




01 | OXYGEN SUPPLY SYSTEM GROUND FLOOR PLAN (PART-A)
HA-P-15 | REF:HA-P-15 | SCALE 1:200




02 | AREA ALARM MICROPROCESSOR BASED WITH LOCAL OR REMOTE SENSORS
HA-P-15 | REF:HA-P-15 | SCALE 1:200



03 | SINGLE ZONE VALVE
HA-P-15 | REF:HA-P-15 | SCALE 1:200



04 | WALL OUTLET DISS
HA-P-15 | REF:HA-P-15 | SCALE 1:200




NO.	DATE	DESCRIPTION
4	100% REUBUNTAL IV	
3	100% REUBUNTAL III	
2	100% REUBUNTAL II	
1	100% REUBUNTAL (BY OTHER)	

DATE:	DESIGNED BY:	US ARMY CORPS OF ENGINEERS
SEP 2010	AFGHANISTAN ENGINEER DISTRICT	
JUNE 2010		
MAY 2010		
OCT 11, 2009		

HOSPITAL ADDITION
ANA GARRISON, KANDEHAR, AFGHANISTAN
OXYGEN SUPPLY SYSTEM GROUND FLOOR PLAN
PART-A

SHEET REFERENCE NUMBER:
HA-P-15
153 of 217

Hospital Addition Oxygen System- Information Only




NO.	DATE	DESCRIPTION
1	OCT. 11, 2008	100% REURMITTAL (BY OTHERS)
2	MAY 10, 2010	100% REURMITTAL II
3	JUNE 20, 2010	100% REURMITTAL III
4	SEP 20, 2010	100% REURMITTAL IV

DESIGNED BY:	US ARMY CORPS OF ENGINEERS AFGHANISTAN ENGINEER DISTRICT
DATE:	
DESIGNED BY:	AFGHANISTAN ENGINEER DISTRICT KABUL, AFGHANISTAN
DATE:	
DESIGNED BY:	AMIR COMBAT/ENG. CONTRIBUTION & ENGINEERING CO.
DATE:	






HOSPITAL ADDITION
ANA GARISON, KANDEHAR, AFGHANISTAN

OXYGEN SUPPLY SYSTEM GROUND FLOOR PLAN
PART-B

SHEET
REFERENCE
NUMBER:
HA-P-16
154 of 217




LEGEND	
	SHUT OFF VALVES
	ZONE ALARM PANEL
	OXYGEN PIPE
	2x5 OXYGEN MANIFOLD






Hospital Addition Oxygen System- Information Only




KEY PLAN




01 | OXYGEN SUPPLY SYSTEM GROUND FLOOR PLAN
HA-P-17 | REF: SCALE 1:300



AREA ALARM MICROPROCESSOR BASED WITH LOCAL OR REMOTE SENSORS
HA-P-17 | REF: SCALE 1:200



03 | SINGLE ZONE VALVE
HA-P-17 | REF: SCALE 1:200



PART PLAN FOR EXISTING
Ø15 COPPER TUBE FOR NEW EXTENSION
Ø15 COPPER TUBE FOR EXISTING BUILDING
OXYGEN STORAGE
GRAPHIC SCALE 1:300



NO.	DATE	DESCRIPTION
1	OCT 11, 2008	100% REURMANTAL (BY OTHER)
2	MAY 10, 2010	100% REURMANTAL II
3	JUNE 20, 2010	100% REURMANTAL III
4	SEP 20, 2010	100% REURMANTAL IV

DATE:	DESIGNED BY:	US ARMY CORPS OF ENGINEERS
REVISION:	CHECKED BY:	AFGHANISTAN ENGINEER DISTRICT
DESIGNED BY:	DATE:	AFGHANISTAN ENGINEER DISTRICT
REVISION:	DATE:	AFGHANISTAN ENGINEER DISTRICT
DESIGNED BY:	DATE:	AFGHANISTAN ENGINEER DISTRICT
REVISION:	DATE:	AFGHANISTAN ENGINEER DISTRICT

HOSPITAL ADDITION
ANA GARRISON, KANDEHAR, AFGHANISTAN
OXYGEN SUPPLY SYSTEM GROUND FLOOR PLAN

SHEET REFERENCE NUMBER:
HA-P-17
155 of 217