

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES	
2. AMENDMENT/MODIFICATION NO. 0002		3. EFFECTIVE DATE 11-Jun-2011	4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable) PFBW040701/2
6. ISSUED BY AFGHANISTAN DISTRICT SOUTH (AES) US ARMY CORPS OF ENGINEERS APO AE 09355		CODE W5J9LE	7. ADMINISTERED BY (If other than item 6) See Item 6		CODE
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			X	9A. AMENDMENT OF SOLICITATION NO. W5J9LE-11-R-0054	
			X	9B. DATED (SEE ITEM 11) 21-May-2011	
				10A. MOD. OF CONTRACT/ORDER NO.	
				10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE			
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. ACCOUNTING AND APPROPRIATION DATA (If required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.					
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).					
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.					
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Project: Construction of Two (2) Class B Fire Stations in Herat City, Herat Province. Herat Sites #2 & #3. PN: PFBW040701 & 02 Contracting POC: evan.n.carter@usace.army.mil Questions and Answers pt. 1					
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.					
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
			TEL: _____ EMAIL: _____		
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)		15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 11-Jun-2011

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION 00800 - SPECIAL CONTRACT REQUIREMENTS

The following have been added by full text:

Q&A Pt.1
Herat Fire Departments

Q1. What is the area, and how many LM for the Perimeter Walls, Fencing and Gates?

A1. Bid as shown on standard drawings.

Q2. What is the payment Mode/Milestones?

A2. Payment will be made via Electronic Bank Deposit. Construction payments are scheduled for a Standard 30 day payment cycle, assuming billing is continual.

Q4. The scope calls for one 25,000 gallons cistern tank, but drawings 00-C-101 and 00-C-102 show a 3,000 gallons tank and a 25,000 gallons tank respectively. Please Clarify.

A4. See below.

Q5. The scope page 12, paragraph 4.9 calls for one well, and the technical specifications on page 16 calls for two wells, please confirm the correct number of Wells.

A5. See below.

Q6. Please confirm the contractor is not required to fuel at the handover time and the furniture is not part of this contract.

A6a. Fuel Supply - Bid as shown in Section 01010, 4.11 Site Power, Electrical, Distribution System and Fuel Storage and Section 01015, 7.9 Generator Fuel Storage/Distribution

A6b. Furniture – See below.

Q7. Please provide a delivery address should we decide to hand deliver the proposal.

A7. Hand Delivered offers will not be accepted for this Solicitation. Per Pg. 17 of the RFP (Sec 00113, 2.4) All Proposals must be delivered to the email address(es) provided.

Q10. In scope of work 4.9 WATER SYSTEM, it is stipulated “construction of one 5000-gallon (18,940-liter) elevated water storage tank with an accompanying 25,000-gallon (94,500-liter) cistern water storage tank and also in technical section stipulated “construction of Water Tank - Capacity shall be 7000 Gallons (26,500 liters)+ booster pump. Booster pump and construction of Water Tank - Capacity 7000 Gallons (26,500 liters) it is not mentioned in scope of works, please clarify that elevated water tank or booster pump + Water Tank - Capacity 7000 Gallons (26,500 liters) will system be provided for each site?

A10. See below

Q11. Specification section 01015pra 3.4.5 specified to provide waste water treatment plant, but SOW dot not specified mentioned the item, Please clarify should we consider WWTP to our price proposal?

A11. Bid as shown in Section 01010, Paragraph 4.10 Sanitary Sewer System and Standard Drawings.

Q12. Specification section 01015pra 3.3.4 specified to provide aggregate roads within compounds ,but in drawing page 00-C-001 it is mentioned to provide asphalt road. Please clarify.

A12. See below

Q14. Scope of work section 01010pra 4.8 specified to provide concrete walkways between building and an parking , but in drawing page 00-C-002 mentioned compacted aggregate walk way should be provided . Please clarify; should we calculate concrete or aggregate walkways?

A14. See below

Q15. Scope of work section 01010 Pra 4.19 mentioned about 30-meter (100ft) height communication steel tower with micro-wave dish, but Communication tower drawing is not provided in this solicitation, please provide drawing.

A15. See below

Q16. In price schedule electrical generator shed is mentioned (0001AY), but scope of works 01010 mentioned to provide shed for both generator and fuel storage, should we calculate shed for generator and fuel storage? If yes, drawing needs to be provided.

A16. See below

Q17. In the experience form, in block 10a and 10b, English speaking Technical point of contact for the Project Owner (name, title, e-mail address, phone number) is this the name and information of the Contractor or the name or information of the Client?

A15. The Point of Contact for the project that is provided is required to be English Speaking. This person is not the Employee of the offeror. The Point of Contact is required to be a member of the referenced Client.

****Notice to Offerors****

Question Numbers 3, 8, 9, and 13 have been left off intentionally. They will be answered in a separate amendment to be published later.

SECTION 01010

4.3 STANDARD NON-BUILDING DESIGNS - Change Tabular List of Facilities Table as follows:

NAME/DESIGNATION	NUMBER OF UNITS	DESCRIPTION

Fire Station	2	2-Story concrete frame w/ CMU infill/ concrete slab roof
Vehicle and Apparatus Bays	2	1-Story high bay concrete frame w/ CMU infill / corrugated metal roofing
Fire Fighter's Training Tower	2	3-Story concrete frame w/ CMU infill
Gate House	2	1-Story concrete frame w/ CMU infill
Guard Shack	2	1-Story concrete frame w/ CMU infill
Guard Tower	8	2-Story concrete frame
Communications Tower	2	30-meter (100-ft) height steel tower with micro-wave dish
Water Cistern	2	25,000 30,000 -gallon (94,500 liter) steel tank
Trash Collection Points	4	Three-sided enclosure with gate on concrete slab
Well House with Storage Tanks	2	1-Story concrete frame w/ CMU infill. Tank is 3000-gallon (11,340-liter) steel structure.
Generators, Fuel Storage and Canopy	2	Concrete slabs, containment dikes w/ canopy structure

4.9 Water System

Delete “Design and construct a Potable Water System (PWS), to include a well, protected in an enclosed water well house, water well pump(s), a 5,000-gallon (18,940-liter) elevated water storage tank with an accompanying 25,000-gallon (94,500-liter) cistern water storage tank and an underground pipe distribution network system for each project site. “

Replace with “Design and construct a Potable Water System (PWS) *in accordance with the plans and specifications*, to include a water well(s) to provide sufficient supply for the facilities, protected in an enclosed water well house, water well pump(s), a ~~5,000~~ **3,000**-gallon (18,940 **11,356-liter**) elevated water storage tank with an accompanying ~~25,000~~ **30,000**-gallon (94,500 **113,562-liter**) cistern water storage tank and an underground pipe distribution network system for each project site. “

4.11.4 GENERATOR FUEL STORAGE

The work shall include a factory fabricated tank(s) and installation of the entire fuel storage and distribution system for each project site. Tanks shall be as indicated on the drawings and be provided with a concrete dike, security fencing, and protective overhead canopy. Tanks shall be provided and installed in accordance with *Appendix A and* Section 01015: TECHNICAL REQUIREMENTS.

4.14 GENERATOR & FUEL STORAGE CANOPY (*SHED*) AND VEHICLE REFUEL POINT

The Contractor shall construct, in the location shown on the provided Concept plan drawing, a Generator and Fuel Storage Canopy (*Shed*) and Vehicle Refuel Point in accordance with the provided contract drawings.

4.19 COMMUNICATION TOWER

~~Construct one communication tower for each project in accordance with the contract drawings and located per the provided site plans. The contractor is not responsible for the communications dish and other equipment, to include cabling, as shown on the drawing; this will be government furnished and installed materials.~~

4.13 Road Network, Sidewalk, and Parking

The Contractor shall design and construct the entire road and parking network for each project site. The roads shall be **asphalt and** designed to carry traffic of a 40 metric-ton five-axle vehicle. A storm drainage system shall also be included. The road layout shall provide access to entry control points, parking lots, vehicle maintenance facilities, fuel points, generator yard, sewage septic tank, and the trash collection point. Provide parking areas inside the compound, for number of vehicles and size as indicated in the concept plan. Road design shall be designed per **Appendix A – Drawings and** Section 01015, Technical Requirements. Roadways and sidewalks are required as shown on attached drawings and shall be designed and constructed based upon recommendations from geotechnical analysis as required herein. A large paved vehicle turning area is required per the standard drawings provided.

Provide a network of sidewalks to connect the buildings as indicated on the Concept Plan drawing. Sidewalks shall be **aggregate and a** minimum 1.5 m in width.

SECTION 01015

3.3.4 Roads, 1st sentence, Delete: “Aggregate roads are required within the compounds.”

Add “**Asphalt roads are required within the compounds in accordance with the standard drawings.**”

3.4.1 Water

G - WATER STORAGE TANK

1st paragraph; 3rd Sentence - Delete “Volume of the water storage tank shall be 5000 gallons (26,500 liters).”

SECTION 01060

1.20 CONTRACTOR FURNISHED EQUIPMENT LISTS

Delete “The Contractor shall furnish a list of all items, other than integral construction type items, furnished under the contract.”

Add “The Contractor will NOT be responsible for providing the furnishings. However, the contractor shall provide a list of all furnishings and items, other than integral construction type items, to be provided by others.”

(End of Summary of Changes)