

|  |  |   |  |   |  |  |  |
|--|--|---|--|---|--|--|--|
| <b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>  |  |   |  | 1. CONTRACT ID CODE<br><div style="text-align: center;">J</div>   |  | PAGE OF PAGES<br><div style="text-align: center;">1   45</div> |  |
| 2. AMENDMENT/MODIFICATION NO.<br><div style="text-align: center;">0005</div>   |  | 3. EFFECTIVE DATE<br><div style="text-align: center;">20-Jul-2007</div> |  | 4. REQUISITION/PURCHASE REQ. NO.  |  | 5. PROJECT NO.(If applicable)                                  |  |
| 6. ISSUED BY<br>AFGHANISTAN ENGINEER DISTRICT<br>US ARMY CORPS OF ENGINEERS<br>KABUL<br>APO AE 09356   |  | CODE<br>W917PM  |  | 7. ADMINISTERED BY (If other than item 6)<br><div style="text-align: center; font-size: 1.2em;"><b>See Item 6</b></div> |  |  |  |
| 8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)  |  |   |  | X   |  | 9A. AMENDMENT OF SOLICITATION NO.<br>W917PM-07-R-0067          |  |
|  |  |   |  | X   |  | 9B. DATED (SEE ITEM 11)<br>21-May-2007                         |  |
|  |  |   |  |   |  | 10A. MOD. OF CONTRACT/ORDER NO.                                |  |
|  |  |   |  |   |  | 10B. DATED (SEE ITEM 13)                                       |  |
| CODE   |  | FACILITY CODE   |  |   |  |  |  |
| 11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS  |  |   |  |   |  |  |  |
| <input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended.<br><br>Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods:<br>(a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;<br>or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE<br>RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN<br>REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter,<br>provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified. |  |   |  |   |  |  |  |
| 12. ACCOUNTING AND APPROPRIATION DATA (If required)  |  |   |  |   |  |  |  |
| 13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.<br>IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.  |  |   |  |   |  |  |  |
| A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.   |  |   |  |   |  |  |  |
| B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).  |  |   |  |   |  |  |  |
| C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:   |  |   |  |   |  |  |  |
| D. OTHER (Specify type of modification and authority)  |  |   |  |   |  |  |  |
| E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.  |  |   |  |   |  |  |  |
| 14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)  |  |   |  |   |  |  |  |
| Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.   |  |   |  |   |  |  |  |
| 15A. NAME AND TITLE OF SIGNER (Type or print)  |  |   |  | 16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)  |  |  |  |
|  |  |   |  | TEL: _____ EMAIL: _____   |  |  |  |
| 15B. CONTRACTOR/OFFEROR<br><br>_____<br>(Signature of person authorized to sign)   |  | 15C. DATE SIGNED  |  | 16B. UNITED STATES OF AMERICA<br><br>BY _____<br>(Signature of Contracting Officer)                                     |  | 16C. DATE SIGNED<br><br>20-Jul-2007                            |  |

## SECTION SF 30 BLOCK 14 CONTINUATION PAGE

**The following items are applicable to this modification:**

The Government has made changes to the requirements of the RFP as well as corrections to the scope of work and clauses. Offerors are afforded the opportunity to submit a revised proposal addressing these changes. Submit only the parts of your proposal that are changed as a result of this amendment.

**REVISED PROPOSALS ARE DUE 28 JULY 2007, 5PM.**

This amendment is made to:

1. Provide a new section 01010 proposal schedule for the amended Government requirement. Note CLIN 0004, Economic Surveillance Reports is deleted, but the requirement to report is still required as stated in section 00800.
2. The liquidated damages amount is amended to \$2453.46 as referenced in section 00150, paragraph 4.0 Project Schedule and section 00800 FAR clause 52.211-12. Changes are in red print.
3. Provide scope changes for section 01010 as follows:
  - a. Paragraph 3.1 UXO REMOVAL AND CLEARANCE is removed in its entirety and replaced with the new paragraph 3.1 in red print.
  - b. The population table in paragraph 4.1.1 GENERAL REQUIREMENTS FOR FACILITIES is corrected for a population of 1376 as shown in red print.
  - c. Paragraph 4.10 (3) HVAC is removed in its entirety and replaced by the new paragraph 4.10 (3) in red print.
4. Provide scope of work changes for section 01015 as follows:
  - a. Paragraph 1.4.1.1 UXO/mine Discovery During Project Construction is deleted in its entirety and replaced by the new paragraph 1.4.1.1 in red print.
  - b. Paragraph 3.12.8.1 is amended as shown in red print to ceramic tile.
  - c. Paragraph 3.12.8.2 is amended as shown in red print to concrete floor with epoxy sealer.
  - d. Paragraph 6.5.1 Unitary (ductless split) DX Air Conditioning Units is deleted in its entirety and replaced with the new 6.5.1 in red print.
  - e. Paragraph 6.5.2 is deleted in its entirety and not replaced.
5. The solicitation is changed to “subject to availability of funds” by the addition of FAR clause 52.238-18 to section 00100.
6. Section 00100 INSTRUCTIONS TO BIDDERS is changed as follows:

“In accordance with FAR 36.204 -- Disclosure of the Magnitude of Construction Projects, the estimated cost range of this project including the base proposal and all options is greater than \$10,000,000.00.”

7. The following clauses were added:
  - a. Section 00700- FAR 52.203-6, FAR 52.232-38
  - b. Section 00800- EFARS 52.232-5000

**SUMMARY OF CHANGES****SECTION 00010 - SOLICITATION CONTRACT FORM****REVISED PROPOSAL SCHEDULE  
20 JULY 2007**

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|---|----------|------|------------|--------|
| 0001    | Design<br>FFP<br>The contractor shall perform all design for the construction (site development/foundations) as per the scope of work herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES                       | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0001AA  | Design Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|---|----------|------|------------|--------|
| 0002    | Construction<br>FFP<br>The contractor shall provide all equipment, labor, materials and supervision to complete the construction (site development and foundations) for the upgrading of Camp Cunningham as per the scope of work herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AA  | Road Grading and Surfacing<br>FFP<br>The contractor shall perform road grading and surfacing as per the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AB  | General rough site grading<br>FFP<br>The contractor shall perform rough site grading as per the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AC  | Building pad preparation<br>FFP<br>The contractor shall construct the building pad as per the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AD  | Electrical Power<br>FFP<br>The contractor shall tie into the existing power system in accordance with the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AE  | Communications<br>FFP<br>The contractor shall tie into existing communications on the compound in accordance with the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|--|----------|----------|------------|--------|
| 0002AF  | Foundations<br>FFP<br>The contractor shall provide all equipment, labor, material and supervision to construct the foundations for the buildings of the base proposal.<br>FOB: Destination | 1        | Lump Sum |            |        |
|         |  |          |          |            | <hr/>  |
| NET AMT |  |          |          |            |        |

| ITEM NO | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0002AG  | Underground Utility Corridor<br>FFP<br>The contractor shall provide all equipment, labor, material and supervision to construct the utility corridor as per the scope of work herein.<br>FOB: Destination | 1        | Lump Sum |            |        |
|         |   |          |          |            | <hr/>  |
| NET AMT |   |          |          |            |        |

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|--|----------|------|------------|--------|
| 0003    | Design Billeting Buildings<br>FFP<br>The contractor shall perform design of the billeting buildings as per the scope of work herein.<br>FOB: Destination |          |      |            |        |
|         |  |          |      |            | <hr/>  |
| NET AMT |  |          |      |            |        |

| ITEM NO | SUPPLIES/SERVICES                       | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|---|----------|----------|------------|--------|
| 0003AA  | Design Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|--|----------|------|------------|--------|
| 0004    | Economic Surveillance Reports<br>FFP<br>CLIN 004 IS DELETED from the proposal schedule but contractors still have the obligation to do this reporting as per section 00800 herein.<br>FOB: Destination |          |      |            |        |

---

(Deleted don propose)

NET AMT

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|--|----------|------|------------|--------|
| 0005    | Construction for Billeting Buildings<br>FFP<br>The contractor shall perform construction of the billeting buildings as per the scope of work herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT



| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|---------|--|----------|------|------------|--------|
| 0005AA  | Construct Billeting Building<br>FFP<br>The contractor shall provide all equipment, labor, materials and supervision to construct the billeting building as per the scope of work herein. Each building is a single two story 80 person double occupancy billeting building constructed from shipping containers or other modular prefabricated construction methods; includes all amenities within building; utilities shall include power, communications and preparation of capped stub-outs for connection of future plumbing fixtures and future installation of water and sanitary sewer lines.<br>FOB: Destination | 2        | Each |            |        |

---

 NET AMT

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|--|----------|----------|------------|--------|
| 0005AB  | Construct Billeting Building<br>FFP<br>The contractor shall provide all equipment, labor, materials and supervision to construct the billeting building as per the scope of work herein. (single two story 48 person double occupancy billeting building constructed from shipping containers or other type modular prefabricated construction methods; includes all utilities within building; utilities shall include power, communications and preparation of capped stub-outs for connection of future plumbing fixtures and future installation of water and sanitary sewer lines).<br>FOB: Destination | 3        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|--|----------|----------|------------|--------|
| 0005AC  | Construct Billeting Building<br>FFP<br>The contractor shall provide all equipment, labor, materials and supervision to construct the billeting building as per the scope of work herein. (single two story 48 person double occupancy billeting building constructed from shipping containers or other type modular prefabricated construction methods; includes all utilities within building; utilities shall include power, communications and preparation of capped stub-outs for connection of future plumbing fixtures and future installation of water and sanitary sewer lines).<br>FOB: Destination | 3        | Lump Sum |            |        |

---

NET AMT

**TOTAL BASE PRPOSAL (CLINS 0001-0005AC)**

---

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0006<br>OPTION | Option No.1<br>FFP<br>The contractor shall provide all equipment, labor, materials and supervision to design and construct the facilities as per the scope of work herein. Design and construction for two (2) each 80 person facilities within base proposal, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br><br>FOB: Destination |          |      |            |        |
| NET AMT        |  |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0006AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |
| NET AMT          |   |          |          |            |        |

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0006AB<br>OPTION | Building costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0007<br>OPTION | Option No. 2<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct three (3) each 48 person facilities within base proposal, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br><br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0007AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0007AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0008<br>OPTION | Option No. 3<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct three (3) each 48 person facilities within base proposal, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br><br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0008AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0008AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0009<br>OPTION | Option No. 4<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0009AA<br>OPTION | Construction Costs<br>FFP<br>Site & Foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0009AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0010<br>OPTION | Option No. 5<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no. 4, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0010AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0010AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0011<br>OPTION | Option No. 6<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT



| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0011AA<br>OPTION | Construction Costs<br>FFP<br>Site & Foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
| NET AMT          |   |          |          |            |        |

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0011AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
| NET AMT          |   |          |          |            |        |

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0012<br>OPTION | Option No. 7<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.6, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0012AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0012AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0013<br>OPTION | Option No. 8<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0013AA<br>OPTION | Construction Costs<br>FFP<br>Site & Foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0013AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0014<br>OPTION | Option No. 9<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no. 8, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0014AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0014AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination |          | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0015<br>OPTION | Option No. 10<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0015AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0015AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0016<br>OPTION | Option No. 11<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.10, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0016AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination |          | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0016AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0017<br>OPTION | Option No. 12<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0017AA<br>OPTION | Construction Costs<br>FFP<br>Site and Foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0017AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0018<br>OPTION | Option No. 13<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.12, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks<br>FOB: Destination |          |      |            |        |
|                |   |          |      |            | <hr/>  |
| NET AMT        |   |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0018AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
| NET AMT          |   |          |          |            |        |



| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0018AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0019<br>OPTION | Option No. 14<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0019AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0019AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0020<br>OPTION | Option No. 15<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.14, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0020AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0020AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0021<br>OPTION | Option No. 16<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0021AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0021AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
| NET AMT          |   |          |          |            |        |

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0022<br>OPTION | Option No. 17<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.16, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |
|                |  |          |      |            | <hr/>  |
| NET AMT        |  |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0022AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0022AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0023<br>OPTION | Option N0. 18<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0023AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0023AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0024<br>OPTION | Option No. 19<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.18, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0024AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0024AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0025<br>OPTION | Option No. 20<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0025AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
|                  |   |          |          | NET AMT    |        |

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0025AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |   |          |          |            | <hr/>  |
|                  |   |          |          | NET AMT    |        |



| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0026<br>OPTION | Option No. 21<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.20, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0026AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0026AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0027<br>OPTION | Option No. 22<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0027AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0027AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0028<br>OPTION | Option No. 23<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no.22, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0028AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0028AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0029<br>OPTION | Option No. 24<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 80 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0029AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0029AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |

---

 NET AMT

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0030<br>OPTION | Option No. 25<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no. 24, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |
| NET AMT        |   |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|--|----------|----------|------------|--------|
| 0030AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility work<br>FOB: Destination | 1        | Lump Sum |            |        |
| NET AMT          |  |          |          |            |        |

| ITEM NO          | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|--|----------|----------|------------|--------|
| 0030AB<br>OPTION | Building Costs<br>FFP<br>Interior utility work<br>FOB: Destination | 1        | Lump Sum |            |        |
| NET AMT          |  |          |          |            |        |

| ITEM NO        | SUPPLIES/SERVICES  | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|--|----------|------|------------|--------|
| 0031<br>OPTION | Option No. 26<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct one (1) additional 48 person billeting building as described in base proposal and elsewhere herein.<br>FOB: Destination |          |      |            |        |
| NET AMT        |  |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0031AA<br>OPTION | Construction Costs<br>FFP<br>Site and foundation.<br>FOB: Destination | 1        | Lump Sum |            |        |
| NET AMT          |   |          |          |            |        |

| ITEM NO          | SUPPLIES/SERVICES                                   | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|---|----------|----------|------------|--------|
| 0031AB<br>OPTION | Billeting Building Costs<br>FFP<br>FOB: Destination | 1        | Lump Sum |            |        |
| NET AMT          |   |          |          |            |        |

| ITEM NO        | SUPPLIES/SERVICES   | QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------------|---|----------|------|------------|--------|
| 0032<br>OPTION | Option NO. 27<br>FFP<br>Contractor shall provide all equipment, labor, materials and supervision to design and construct for all facilities within Option no. 26, add the following: complete lavatories/showers/toilets; connect new water lines to new potable water system; connect new sanitary sewer lines to new holding tanks.<br>FOB: Destination |          |      |            |        |
|                |   |          |      |            | <hr/>  |
| NET AMT        |   |          |      |            |        |

| ITEM NO          | SUPPLIES/SERVICES  | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|------------------|--|----------|----------|------------|--------|
| 0032AA<br>OPTION | Construction Costs<br>FFP<br>Exterior utility costs.<br>FOB: Destination | 1        | Lump Sum |            |        |
|                  |  |          |          |            | <hr/>  |
| NET AMT          |  |          |          |            |        |

| ITEM NO | SUPPLIES/SERVICES       | QUANTITY | UNIT     | UNIT PRICE | AMOUNT |
|---------|-------------------------|----------|----------|------------|--------|
| 0032AB  |                         | 1        | Lump Sum |            |        |
| OPTION  | Building Costs          |          |          |            |        |
|         | FFP                     |          |          |            |        |
|         | Interior utility costs. |          |          |            |        |
|         | FOB: Destination        |          |          |            |        |

NET AMT

TOTAL PRICE ALL OPTION ITEMS (CLINS 0006-0032AB)

TOTAL PRICE BASE PLUS ALL OPTION ITEMS



**CLAUSES INCORPORATED BY FULL TEXT****52.217-7 OPTION FOR INCREASED QUANTITY--SEPARATELY PRICED LINE ITEM (MAR 1989)**

The Government may require the delivery of the numbered line item, identified in the Schedule as an option item, in the quantity and at the price stated in the Schedule. The Contracting Officer may exercise the option by written notice to the Contractor within **120 calendar days**. Delivery of added items shall continue at the same rate that like items are called for under the contract, unless the parties otherwise agree.

(End of clause)

**PROPOSAL SCHEDULE NOTES****PROPOSAL SCHEDULE NOTES**

1. Offeror shall submit prices on all items.
2. Only one contract for the entire schedule will be awarded under this solicitation. This project will be awarded as a lump sum contract. This Proposal Schedule is an accounting tool for allocating funds to applicable budget.
3. Costs associated with this project shall include design and construction costs for site, facilities and utilities preparation but, no less than all items as shown in proposal schedule.
4. **DESIGN COSTS DEFINITION:** Design costs shall consist of preparation of planning and site designs, plans, drawings, and specifications.
5. **SEPARATION OF WORK:** All work for Design and Construction shall be included in all Proposal Items.
6. **EVALUATION OF OPTIONS:** The award will be made to the offeror whose proposal represents the best overall value to the Government. For pricing purposes, the Government will evaluate both the Base Proposals and Option Proposals. The Government is not obligated to exercise the options.
7. **EXERCISE OF OPTIONAL BID ITEMS:** Optional bid items (if any) may, at the option of the Government, be exercised at any time within 120 calendar days after award of Base Proposal.
8. In accordance with FAR 36.204 "Disclosure of the magnitude of construction projects", FAR 36.205 "Statutory Cost Limitations", and " DFARS 252.236-7006 "Cost Limitations", the magnitude cost limitation for the construction part of this contract (basic and with all options and any subsequent modifications) shall not exceed \$1,500,000. In addition, the twenty percent (20%) acquisition cost limitation as described in the Army Interim Relocatable Building Policy, paragraph 5-2 (b)(2), is binding upon the Contractor.

**52.217-7 OPTION FOR INCREASED QUANTITY--SEPARATELY PRICED LINE ITEM (MAR 1989)**

The Government may require the delivery of the numbered line item, identified in the Schedule as an option item, in the quantity and at the price stated in the Schedule. The Contracting Officer may exercise the option by written notice to the Contractor within **120 calendar days**. Delivery of added items shall continue at the same rate that like items are called for under the contract, unless the parties otherwise agree.

(End of clause)

**SECTION 00100 - BIDDING SCHEDULE/INSTRUCTIONS TO BIDDERS**

The following have been added by reference:

52.232-18                      Availability Of Funds                      APR 1984

The following have been modified:

**INSTRUCTIONS TO BIDDERS**

Section 00100 - Bidding Schedule/Instructions to Bidders

**INSTRUCTIONS TO BIDDERS**

**In accordance with FAR 36.204 -- Disclosure of the Magnitude of Construction Projects, the estimated cost range of this project including the base proposal and all options is greater than \$10,000,000.00.**

**SECTION 00150**

**SECTION 00150**

**THE DESIGN/BUILD PROCESS**

**PART 1 - GENERAL**

**PROJECT SCHEDULE:**

**Liquidated damages (see section 00800).**

**SECTION 00700 - CONTRACT CLAUSES**

The following have been added by reference:

|           |  |          |
|-----------|--|----------|
| 52.203-6  | Restrictions On Subcontractor Sales To The Government          | SEP 2006 |
| 52.232-38 | Submission of Electronic Funds Transfer Information with Offer | MAY 1999 |

**SECTION 00800 - SPECIAL CONTRACT REQUIREMENTS**

The following have been added by full text:

52.232-5000 PAYMENT FOR MATERIALS DELIVERED OFF-SITE (MAR 1995)--EFARS

(a) Pursuant to FAR clause 52.232-5, Payments Under Fixed Priced Construction Contracts, materials delivered to the contractor at locations other than the site of the work may be taken into consideration in making payments if included in payment estimates and if all the conditions of the General Provisions are fulfilled. Payment for items delivered to locations other than the work site will be limited to: (1) materials required by the technical provisions; or (3) materials that have been fabricated to the point where they are identifiable to an item of work required under this contract.

(b) Such payment will be made only after receipt of paid or receipted invoices or invoices with canceled check showing title to the items in the prime contractor and including the value of material and labor incorporated into the item. In addition to petroleum products, payment for materials delivered off-site is limited to the following items: \_\_\_\_\_

(End of clause)

The following have been modified:

SECTION: 01010

**SECTION 01010****SCOPE OF WORK****1.1 UXO REMOVAL AND CLEARANCE**

The contractor is not responsible for the clearance or removal of mines and unexploded ordnance (UXO) from the site prior to the commencement of construction.

It is the responsibility of the Contractor to be aware of the risk of encountering UXO/mines and to take all actions necessary to assure a safe work area to perform the requirements of this contract. The Contractor assumes the risk of any and all personal injury, property damage or other liability arising out of or resulting from any Contractor action taken hereunder. The Contractor and its subcontractors may not handle, work with, move, transport, render safe, or disarm any UXO/mine, unless they have appropriate accreditations from the MAC.

If a UXO/mine is encountered during project construction, UXO/mine disposal shall be handled in accordance with Section 01015, Technical Requirements.

#### 4.1.1 GENERAL REQUIREMENTS FOR FACILITIES

| Population for 1376 (total development) |      |     |          |       |
|---|------|-----|----------|-------|
| SENIOR                                  | HIGH | MID | ORDINARY | Total |
| n/a                                     | n/a  | n/a | n/a      | 1,376 |

#### 4.8 BILLETING FACILITIES

(3) HVAC: HVAC shall be provided by unitary (ductless split) DX system. Refer to Section 01015 for system description.

#### SECTION: 01015

#### SECTION 01015

#### TECHNICAL REQUIREMENTS

##### 1.4.1.1 UXO/mine Discovery During Project Construction

It is the responsibility of the Contractor to be aware of the risk of encountering UXO and to take all actions necessary to assure a safe work area to perform the requirements of this contract. If during construction, the contractor becomes aware of or encounters UXO or potential UXO, the contractor shall immediately stop work at the site of encounter, move to a safe location, notify the COR, and mitigate any delays to scheduled or unscheduled contract work. Once the contractor has informed the COR, the contractor will await further direction. The Contractor assumes the risk of any and all personal injury, property damage or other liability arising out of or resulting from any Contractor action taken hereunder.

Scrap metal shall be the property of the Host Government. The scrap metal on site shall be moved to an area away from the site perimeter as directed by the Contracting Officer's Representative and left for the Host Government to remove and/or salvage.

NOTE: For previous UXO/mine information, the following points of contact from the UN Mine Action Center of Afghanistan are provided:

Mohammad Sediq, Chief of Operations,  
Email: [sediq@unmaca.org](mailto:sediq@unmaca.org)  
Cell: +93 070 295207

Hansie Heymans, Chief Information Officer,  
Email: [hansie@unmaca.org](mailto:hansie@unmaca.org)  
Cell: +93 070 294286

3.12.8.1 Floors in wet areas shall be 300 mm x 300 mm **ceramic** tile with thin set mortar. Joints shall be 2-3 mm. Waterproof gray grout shall be applied the full depth of the tile. Floors shall slope, minimum 1/50, to floor drains. Slope shall be obtained with sloping mortar bed of minimum 20 mm thickness. Provide continuous waterproofing membrane beneath sloping mortar bed, turn up wall 300 mm behind wall base. Membrane shall be fully sealed at joints and shall shed water into body of floor drain. Color of tile shall be selected

by the Contracting Officer from samples provided by the Contractor.

3.12.8.2 Floors in administration areas, living quarters, corridors, and all rooms unless otherwise stated shall be **concrete flooring with epoxy sealer**. Joints shall be 2-3 mm. Waterproof gray grout shall be applied the full depth of the tile. Color of tile shall be selected by the Contracting Officer from samples provided by the Contractor.

#### 6.5.1 Unitary (ductless split) DX Air Conditioning Units

Ductless split units shall be unitary in design and factory manufactured ready for installation. System shall be designed such that several evaporators are serviced by one condensing unit. The number of evaporator units and, or square area serviced by the condensing unit will be based on the standard requirements of the manufacturer of the system. Evaporator unit shall consist of a DX evaporator cooling coil, blower, electric heater and washable filter all mounted in a housing finished for exposed installation. Cooling coil condensate piping shall route to and discharge to the sanitary sewer system. The condensing unit will contain compressor, condenser coil, and all internal controls/fittings complete to include a weatherized housing. The condensate drains shall be connected to the sanitary sewer or be drained to the outside in such a way that the condensate does not create an unsightly condition. Installation and, or mounting of outside condensing unit shall be as recommended by the manufacturer. Copper refrigerant suction and liquid piping shall be sized, insulated and installed in accordance to unit manufacture recommendations. Unit temperature control shall include wall mounted adjustable thermostat, blower on-off-auto switch and heating-cooling change over control. Provide a sloped cover at top of condensing unit to shed water and to prevent accumulation of snow. *Provision shall be made for the use of outside air through an automatically controlled damper for full economizer cycle or mix thereof.*

#### 6.5.2 Packaged Terminal Air Conditioners

[Not used]

### 52.211-12 LIQUIDATED DAMAGES--CONSTRUCTION (SEP 2000)

(a) If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of **\$2453.46** for each calendar day of delay until the work is completed or accepted.

(b) If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

(End of clause)

(End of Summary of Changes)